## **Brodart Contract Furniture** 2017 Price List and Specifications

# Table of Contents

## 2017 Price List and Specifications

General Specifications and Mo	difications	The Quorum 94T Collection	
General Specifications		Reading Tables	
Modifications & Up Charges	MOD 1 MOD 0	Café Tables	
• •	NOD 1 - MOD 8	Computer Tables	
Collections		Media Workstations & Carrels	
The Abridge Collection	ABR 1 - ABR 44	PAC Stations	
Circulation Desks	ABR 2 - ABR 15	Desk and Credenzas	
Reading Tables	ABR 16 - ABR 21	Dictionary / Atlas Stands	
Computer Tables	ABR 22 - ABR 26	Newspaper Rack & EOR Station	
Media Workstations & Carrels	ABR 27 - ABR 34	Picture Book Table	
PAC Stations	ABR 35	Shelving Continuous Tops & End Panels	
Dictionary / Atlas Stands	ABR 36	Lounge Furniture	QUO 31 - QUO 32
Shelving Continuous Tops	ABR 37 - ABR 39	Array Tables	ARY 1 - ARY 12
Lounge Furniture	ABR 40 - ABR 44		
The Chancellor's Collection	CHA 1 - CHA 36	mTables	
Circulation Desks		Reading Tables	
Reading Tables		Computer Tables	
Computer Tables		Mobile Tables	MOB 1 - MOB 4
Media Workstations & Carrels		Sync Tables (Collaborative Tables.)	CVN 1 CVN A
Dictionary / Atlas Stands	CHA 30		
Shelving Continuous Tops		Collection Accessories	ACC 1 - ACC 4
Lounge Furniture		Shelving	
TI T 16 II I	FD0.4 FD0.40	Classic Shelving	CI A 1 - CI A 49
The Epoch Collection		Shelving	
Circulation Desks		Shelving and Accessories	
Reading Tables			
Computer Tables  Conference Tables		Reprise Shelving	
Media Workstations & Carrels		Shelving	
PAC / OPAC Stations		Shelving and Accessories	REP 35 - REP 36
Dictionary / Atlas Stands		Seating	
CD/DVD Cabinets		Seating	Various
Shelving Continuous Tops & End Panels		Alpha Chairs	
Lounge Furniture		Banbury Chairs	
		B-Series Chairs	
Geometrix		Calyx Chairs & Stools	CAL 1 - CAL 5
General Specifications and Legend		Calyx Swivel and Swivel Tilt Chair	CAL 6 - CAL 7
Linear Shelving		Carver Chairs	
Arc (Curved) Shelving		D-Series Chairs	DSE 1 - DSE 3
3-Way Towers and Components		Entice Chairs	ENT 1 - ENT 2
Finishing Panels for Shelving		Essex Chairs	ESS 1 - ESS 2
Mobile Shelving (Linear and Arc)		Melis Chairs	MEL 1 - MEL 2
Back Panels (Linear, Arc, and Mobile)		Metro Chairs	MET 1
Seating (Linear and Arc)		Netta Chairs	NET 1
Tables	GEO 51 - GEO 52	Parallax Chairs	
The Horizons Collection	HOR 1 - HOR 32	Pellego Chairs	
Circulation Desks	HOR 2 - HOR 13	Parallax Chairs	PAR 1 - PAR 2
Reading Tables	HOR 14 - HOR 21	Lounge Furniture	
Media Stations	HOR 22 - HOR 26	Lounge	Various
Book Browsers	HOR 27 - HOR 28	L1 Series	
Shelving End Panels	HOR 29	L4 Series	
Seating	HOR 30 - HOR 31	L5 Series	
Cutout Designs	HOR 32	LX Series	LXS 1 - LXS 2
		Engage Series	ENG 1 - ENG 2
The Matrix Collection		Cirro Soft Seating	
Circulation Desks		Miscellaneous Furniture and	
Reading Tables			
Computer Tables		Cabinets (Base, Wall & Storage)	CAB 1 - CAB 8
Media Workstations & Carrels		Display Furniture	DIS 1 - DIS 16
PAC Stations			
Dictionary / Atlas Stands		Wood Book Trucks	vvBi 1 - WBI 4
Shelving Continuous Tops & End Panels	MAT 41 - MAT 44	Electrical	ELE 1 - ELE 16
The Maxim Collection	MAX 1 - MAX 16		
C: 11: D 1	14470 144746		

**-TOC 2 -** F11-1-19G-COV

## General Specifications

Materials and Finishes, Quality Standards, and Performance Tests and Results

### General Information Brodart Contract Furniture

### ORDERING INSTRUCTIONS

Your order can be entered and acknowledged promptly only if you supply us with certain essential information. A clean purchase order is needed to be entered into the manufacturing production process (Product Number, Quantity, Fabric, Finish, Species, Layouts, Photos, ect.). If any of these items are missing, your purchase order cannot be processed.

- a. Each item to be purchased must be identified by a complete catalog number.
- b. The quantity of each item to be purchased.
- c. If an item is modified in any way, the letters "MOD" must be used as a suffix on the catalog number.
- Unit price and extended price as determined from the Brodart price list, or a quotation from Brodart.
- e. If shop drawings are needed, note this requirement on your purchase order. You must supply architectural prints of pertinent building areas when requesting shop drawings.

Failure to supply essential order information may result in delays in the processing of your order.

### **TERMS AND CONDITIONS**

### Prices

These prices supersede all previously issued prices. All prices herein are list prices, unless otherwise noted, and are subject to change without notice. Prices stated are for our standard finishes, laminates, and materials. Any deviations from 'standard' are subject to an up charge. Up charges for specials will be quoted upon request.

### **Discounts**

Discounts can be obtained by contacting a Project Coordinator. When obtaining discounts, you must be prepared to provide total list price information, estimated delivery dates, as well as all other information located on the *Discount Request Form*.

### **Payment Terms**

Net 30 days from date of invoice, F.O.B. Factory

### Taxes

Any sales or excise tax, or any other tax or government charge now or hereafter levied upon the product, sale, use or shipment of goods shall, at the Company's option, be charged to the customer.

### Orders

All orders are subject to acceptance by Brodart Co., 280 North Road, Clinton County Industrial Park, McElhattan, PA 17748.

### **Acknowledgements**

Brodart will ship products as detailed on the acknowledgement. Please confirm that all items are ordered as intended. Brodart will not accept responsibility for products shipped as acknowledged.

### Cancellations

All orders are considered firm and cannot be cancelled without Brodart's approval. A cancellation charge will be required based on costs incurred. Minimum cancellation charge will be \$50.00

### **Order Changes**

Changes to orders already in process are subject to a charge covering the making of the change. You will be required to indicate your acceptance of the additional costs before Brodart can proceed with the change. Minimum charge is \$50.00, other charges are as follows: Within 8 weeks of ship date - minimum charge is \$150.00 plus any material costs incurred. Once the job is within 6 weeks and is in full production - minimum charge is \$350.00 for the change and any material and labor costs involved. Brodart reserves the right to deny change requests within 6 weeks of the ship date.

### All product ships from McElhattan, PA with the following exceptions:

### Gondola Display Shelving Units:

For units ordered in quantities of 5 or less (or the only products on the order); units are shipped from 280 North Road with all other Furniture. For units ordered in quantities of 6 or more; product will ship direct from Columbus, Ohio.

### Claims - Freight

All shipments are delivered to common carriers in good condition. Brodart's liability ceases once the order is delivered to the carrier. If your order is received short or damaged, you should note on your freight bill and file a claim immediately with the carrier.

### Claims - Product

Claims against Brodart for defects, errors or shortages must be made by the purchaser, in writing, within 30 days after delivery. Failure to make such claim shall constitute full acceptance of the merchandise.

#### Returns

No Merchandise may be returned for credit without our previous agreement. Unauthorized returns will not be accepted.

### Warranty

Brodart warrants that the Furniture designed and manufactured by it will be free of defects in material and workmanship for a period of twenty-five (25) years for furniture and five (5) years for seating. *Please refer to the official warranty documents for more information.* 

### **Product Specifications**

Product specifications are subject to change without notice.

### **Environmental**

Brodart focuses on implementing environmental management practices that ensure our operations are conducted in a manner that respects, protects, and sustains the natural environment. For the most up-to-date information on Brodart's environmental policy including CARB, and more, please visit <a href="http://www.brodartfurniture.com/about/environmental-efforts">http://www.brodartfurniture.com/about/environmental-efforts</a> or contact a Brodart Furniture representative.

### Modified/Custom Products

Modifications in dimension, wood species, and design are available for an additional fee. Completely customized products are available as well on a per-project and per-quote basis. The following part numbers will be used based on the type of product:

CUSTOM	Custom Furniture	TABLEMOD	Custom Table
SHELVMOD	Custom Shelving	COMPMOD	Custom Computer Furniture
LOUNGEMOD	Custom Lounge Furniture	CARRELMOD	Custom Carrels
HARDWAREMOD	Custom Hardware	CIRCMOD	Custom Circulation
DISPLAYMOD	Custom Display Units	CHAIRMOD	Custom Chair
REPRISEMOD	Custom Reprise	GEOMOD	Custom Geometrix

For any charges not listed in this Price List, please contact a Project Coordinator.

### Product Options Brodart Contract Furniture

### **Antimicrobial Finish:**

Brodart's finish now contains an antimicrobial agent formulated to resist mildew growth. This specially formulated finish prevents the growth and action of microbes from the degrading of Brodart Furniture and also helps to inhibit bacterial odors. There is no up-charge for this additive.

TABLE 1					
		WOOD FINISH OPTION	ONS		
		Oak Wood			
Clear On Oak	O33	Natural Oak	089	Antique on Oak	343
Porcelain on Oak	654	Solar on Oak	716	Victorian on Oak	790
Dark on Oak	801	Mocha on Oak	812	Champagne on Oak	837
		Maple Wood			
Clear on Maple	M33	Natural Maple	089	Antique on Maple	343
Porcelain on Maple	654	Solar on Maple	716	Victorian on Maple	790
Dark on Maple	801	Mocha on Maple	812	Champagne on Maple	837
		Cherry Wood			
Clear on Cherry	C33	Porcelain on Cherry	654		
Antique on Cherry	343	Victorian on Cherry	790		
Pigmente	Pigmented Stains (Formulated for Maple Wood, available on Oak Wood):				
Grasshopper	570	Pumpkin	515	Ginger	GNG
Storm	546	Fern	FRN	Mustard	MUS
Peaceful Blue	520	Cranberry	CRN	Sky	SKY
Dark Chocolate	580				

**Finish Note:** The wood finishes listed above are specifically formulated for the wood species listed. Color may vary significantly if the stain is used on a different species of wood. Color may vary on the same wood species due to grain and texture differences. Solid wood and matching veneer have distinct grain and color variations. Harmonious color variations will appear in each Brodart furniture piece.

**Custom Finish:** Custom finishes on orders over \$5,000.00 **NET** will not require a special finish fee. On orders under \$5,000.00 **NET**, one-step custom finishes are available at an up-charge of \$250.00 **NET** per color, per order. On orders where the finish is a multi-step or hand-wiped finish, a special up charge will be applied. Contact Brodart for a quotation.

**HIGH-PRESSURE LAMINATES:** WilsonArt laminates in finishes ending with "-60" and "-38" are preferred for Brodart Furniture. Up-charges for laminate that deviates from these are listed below. Please note that these selections may require a change in lead time as well. For an up-to-date listing of available WilsonArt Laminates, please visit: <a href="https://www.wilsonartcontract.com/">www.wilsonartcontract.com/</a>.

TABLE 2		
Laminate Manufacturer & Type	Grade	Up-Charge
Wilsonart		
-60 and -38 Finishes	G1	0%
-01, -07, -18, -52, -78 Finishes	G2	3%
-35, -45, -55, and DeepStar Finishes	G3	12%
All Indie Collection	G5	45%
Pionite		
General Purpose Laminates	G2	3%
Specials	G3	12%
Nevamar		
All Laminate	G3	12%
Formica		
Patterns, Woodgrains, Solids, Dust & Graphix, Formations and Prime Colors (Grade 12, and 20 Matte)	G2	3%
Patterns, Woodgrains, Solids, Dust & Graphix, Formations and Prime Colors (Grade 12 Textured/ Sparkle)	G3	12%
Etchings, Honed, Riverwash & Radiance (All Grades)	G3	12%
ColorCore and Chemtop	G5	45%
Marmoleum		
All	G4	20%

Alternatives to high-pressure laminate are available as well. If an alternative to high-pressure laminate (such as Corian) is desired, please refer to the "modifications" sections throughout this price list or contact your Project Coordinator for more information.

METAL OPTIONS (<u>Powder Paint Guidelines & Up-Charges</u>): Brodart's standard paint colors are available at no charge. Brodart "Select" colors are available at an up-charge of \$500.00 **NET** per color, per order. Custom powder paints are available as well; please call Brodart for pricing and availability.

TABLE 3						
		METAL O	PTIONS			
	"Standa	ard" Paint Options		"Select" Paint Op	"Select" Paint Options	
Sand	R3500051	Metallic Anthracite	R3500070	Yellow	R3500064	
Almond	R3500057	Metallic Beige	R3500071	F/T* Blue	R3500098	
Red	R3500052	Metallic Bengal Black	R3500095	F/T* Pale Yellow	R3500099	
Blue	R3500060	Metallic Bengal Silver	R3500096	F/T* Red	R3500100	
Gray	R3500053	Metallic Copper	R3500073			
Burgundy	R3500061			Metallic Sun Gold	R3500077	
Hunter Green	R3500063	Nu Black Hammertone	R3500078	Metallic Bronze	R3500072	
Brown	R3500055	Capri Blue Hammertone	R3500079	Metallic Gray	R3500074	
Mango	R3500066	Antique White	R3500093			
Lilac	R3500067	Antique Gold	R3500091	Sapphire Hammertone	R3500087	
Sapling	R3500068	Antique Silver	R3500092			
Olive	R3500069	Antique Copper	R3500090			
F/T* Black	R3500050					
F/T* Anthracite	R3500097			*FT = Fine Textured		
F/T* Bronze Mist	R3500065					

**REPRISE SHELVING COLOR OPTIONS:** Specify a color option for the body and base shelf of shelving unit (Base Colors Only). Specify color option for shelves (Base Colors or Accent Colors for shelves).

TABLE 4				
	BRODART STANDARD LAMINATES			
Accent Colors Base Colors				
Orange	158	Canadian Gray	168	
Red	201	Classic Maple	290	
Plum	262	Classic Black	631	
Island	375	White	143	
Lapis Blue	5265	Biltmore Cherry	615	
		Bannister Oak	519	
		Pewter Mesh	823	

**FABRIC OPTIONS:** Yardage requirements are listed under each product line. Yardages indicated in this price list are for non-directional 54" wide upholstery fabric. Additional yardage will be required if your upholstery fabric deviates in any way from "non-directional 54" wide".

TABLE 5		
FABRIC OPTIONS		
CFStinson or Douglass	www.brodartfurniture.com/products/custom-options/fabrics.asp	
Cirro Vinyls	Use Zander vinyl from spradlingvinyl.com	

Fabric Grade Information: Brodart offers fabrics in Grades 1-5 as listed in this price list. Fabrics can be selected from either CFStinson or Douglass via <a href="https://www.brodartfurniture.com/products/custom-options/fabrics.asp">www.brodartfurniture.com/products/custom-options/fabrics.asp</a>. Any fabrics listed on these sites as COM or coming from any other supplier must be handled as outlined in the "COM Fabrics" section of this price list.

California Technical Bulletin #133 treatment is available on all Crypton Upholstery at a charge of \$50.00/yard (list)

**COM Fabrics**: All fabrics sent to Brodart must be shipped PREPAID and tagged with the Project Name, Item Number, Sales Order Number (if available), and Project Manager's name. Ship to: *Brodart Co., 280 North Road, Clinton County Industrial Park, McElhattan, PA 17748 Attention: Furniture Marketing.* 

**Installation Hardware Kit:** Full installation hardware kits are available upon request and include shelf pins, bolts, screws, washers, bushings, and brackets. For a complete list, please contact your Project Coordinator.

**INSTHARDWARE** 

\$50.00 NET Per Kit

ACRYLICS: Standard Brodart Resin Offering. 1/4" thick, sandstone finish on both sides is the STANDARD. Variations may incurr an up-charge.

TABLE 6		
RESIN OPTIONS		
Product	Colors	
C3 (up to 3 layers)	Titanium, Sable, Marsh and Atlantic	
Cirque	Silver	
Linen	White	
Regency	Silver	
Struck	Cayenne, Jute and Kelp	

Contact your designated Project Coordinator for ordering instructions.



**-GEN 8 -** F11-1-19G-GEN

# Modifications & Up Charges

## Modificiations & Up Charges

Catalog No.	Description	Price
Replace End Panels	s with Knee Space Panels  To order, change S00 to M0D and insert "knee panel on (left or right)" to your description	\$109
Removal of Gromm	et and Bushing Holes from and End Panel Per Panel	\$147
Removal of Gromm	ets from Work Surface Per Work Surface	\$177
Cut Down in Dimen	sion of a Open Unit (example: XX-014-S00)  1 Dimension Cut Down 2 Dimension Cut Down 3 Dimension Cut Down	\$177 \$250 \$353
Cut Down in Dimen	sion of a Cupboard/Drawer Unit (example: XX-121-S00)  1 Dimension Cut Down  2 Dimension Cut Down  3 Dimension Cut Down	\$353 \$501 \$647
Change Work Surfa	nce Height (For Surface Between Panels Only)  Per Unit	\$177
Move A Box/File D	rawer Left or Right Per Unit, specify location	\$182
Factory Installed Ad	dd On Patron Ledge (Patron Ledge must be ordered separately) Single-Wide per Unit Double-Wide per Unit	\$324 \$401
Add A Lock To A Dra	awer or Door Per Lock	\$132
Key A Lock Differer	ntly from All Other Locks Per Lock	\$132
Replace Standard	Fops with Sup Tops Per Unit	\$177
Place Continuous T	Tops on A Circulation Desk Unit Per Unit, Must use Sub Tops	\$104
Change Standard T	op/Edge Band to Corian Please send a Special Pricing Form to your Project Coordinator	SPECIAL PRICING

Catalog No.	Description	Price
Casters for Tables LG-CST-S00 MTCASTER	Caster to Convert Table to be Mobile-Includes a Brake (Price is per leg) Caster to Convert M-Tables, Mobile Tables and Sync Tables Only (Price is per leg)	\$84 \$28
Cut Down in Dimer	nsion of Leg Base Tables*  1 Dimension Cut Down 2 Dimension Cut Down Note: Dimension Cut Down pricing listed is for cuts on square and rectangular table ONLY. All others will require special pricing.	\$177 \$251
Cut Down in Dimer	nsion of Apron/Panel Base Tables  1 Dimension Cut Down  2 Dimension Cut Down  Note: Dimension Cut Down pricing listed is for cuts on square and rectangular table ONLY.  All others will require special pricing.	\$324 \$472
Change 29"H Table	e to 32"H  Note: Not available for mTables/Sync Tables/Mobile Tables	\$153
Tapered Leg Option	n: <b>Up-Charge</b> Any Series Table.	\$196
Change Standard	Fop/Edge Band to Corian Please send a Special Pricing Form to your Project Coordinator.	SPECIAL PRICING
Add Grommets	Grommets can be added to all table sizes. Please specify the size of grommet (and location) and add the grommet list price to the table list price.	SPECIAL PRICING
Center Leg on 60"\	N to 72"W  Tables 60"W to 72"W will automatically receive a center leg for stability.  Please contact your Project Coordinator for up-charge.	SPECIAL PRICING

Catalog No.	Description	Price	
	Computer Furniture (example: Keyboard Trays & CPU Holders) can be for coessories Section page CIR 4.	ound in the	
Casters for Compu	ter Tables		
LG-CST-S00	Caster to Convert Table to be Mobile-Includes a Brake (Price is per leg)	\$84	
MTCASTER	Caster to Convert M-Tables Only (Price is per leg)	\$28	
Cut Down in Dimer	nsion of Computer Tables without Privacy Panel		
	1 Dimension Cut Down	\$177	
	2 Dimension Cut Down	\$251	
	<b>Note:</b> Dimension Cut Down pricing listed is for cuts on square and rectangular table ONLY. All others will require special pricing.		
Cut Down in Dimer	nsion of Computer Tables with Privacy Panel		
	1 Dimension Cut Down	\$324	
	2 Dimension Cut Down	\$472	
	Note: Dimension Cut Down pricing listed is for cuts on square and rectangular table ONLY.  All others will require special pricing.		
Cut Down in Dimer	nsion of any Workstations/Carrel Unit		
	Per Dimension, Per Unit	\$353	
Add an ADA Station to any Carrel Unit			
	Per Unit, Must Specify Location of Unit	\$279	
Change Standard	Top/Edge Band to Corian	SPECIAL PRICING	
3	Please send a Special Pricing Form to your Project Coordinator.		

## Continuous Tops and End Panels for Wood, Steel and Reprise

## Modificiations & Up Charges

Catalog No.	Description	Price
Add Edge Band	on back side of Single-Faced Continuous Tops	
	10% Per Continous Top	10%
	<b>Note:</b> Charge is for adding the same style band that is on the unit.	
Add Drop Edge	Band to Continuous Tops	
	2% Per Continous Top	2%
Add Mitered Co	rners to Butt-Joint Series	
MOD	Per Continous Top	\$266
Change in Size	of Continuous Tops	
3	0% - Add 0'' - 2''	0%
	10% - Add 2" - 4"	10%
	15% - Add 4'' - 6''	15%
	<b>Note:</b> 0% for Reduction in Top Size.	0%
Change Standa	rd Top/Edge Band to Corian	
3	Please send a Special Pricing Form to your Project Coordinator	SPECIAL PRICING
Change in Size	of End Panels	
3	0% - Add 0'' - 2''	0%
	10% - Add 2" - 4"	10%
	15% - Add 4" - 6"	15%
	<b>Note:</b> 0% for Reduction in Top Size.	0%

	Oak Catalog No.	Maple Catalog No.	Wt. Description (lbs.)	Oak Price	Maple Price
Dust Covers (for use on high shelving) 1/4" Plywood, Cleats & Screws	outding its.	outulog No.	Dust Covers (for use on high shelving) 1/4" Plywood, Cleats & Screws	11100	
174 Flywood, Cleats & Sciews	SHELVMOD		Dust Cover for 10"D Unit 5	\$187	\$199
	SHELVMOD		Dust Cover for 12"D Unit 7	\$193	\$205
	SHELVMOD		Dust Cover for 16"D Unit 9	\$198	\$210
	SHELVMOD		Dust Cover for 20"D Unit 10	\$209	\$222
	SHELVMOD		Dust Cover for 24"D Unit 14	\$214	\$227
	SHELVMOD		Dust Cover for 32"D Unit 18	\$240	\$254
Shelving Modifications			Shelving Modifications		
	BNE		Bullnose End Panels, Add to Unit Price	14%	14%
Bullnose Fascia on Shelving Top	BNS		Bullnose Shelves, Add to Unit Price	5%	5%
builtiose rascia of Shelving Top	BNT		Bullnose Fascia on Shelving Top, Single-Faced	\$65	\$68
	BNT		Bullnose Fascia on Shelving Top, Double-Faced	\$136	\$143
	FT		Florad Faceta on Chaldran Tan Chala Faced	<b>4/</b> 5	<b>*</b> /0
	FT FT		Fluted Fascia on Shelving Top, Single-Faced Fluted Fascia on Shelving Top, Double-Faced	\$65 \$124	\$68
Fluted Fascia on Shelving Top	r i		riulea rascia on sneiving rop, bouble-racea	\$136	\$143
	DT		Dentil Fascia on Shelving Top, Single-Faced	\$65	\$68
	DT		Dentil Fascia on Shelving Top, Double-Faced	\$136	\$143
Dentil Fascia on Shelving Top	AT		Arched Fascia on Shelving Top, Single-Faced	\$65	\$68
	AT		Arched Fascia on Shelving Top, Double-Faced	\$136	\$143
ArchedFascia on Shelving Top	SBS		Sloping Base Shelving Option (per shelf)  Note: Sloping Base Shelf Price includes deletion of Standard Base Shelf.	\$44	\$46
Undersizing (Cut-Down)			Undersizing (Cut-Down)		
	MOD		Undersized Backs and Partitions (Specify Dimensions of Unit)	\$25	N/A
	MOD		Cut-Down Height, Shelving Starter Unit Undersize Only	\$98	N/A
	MOD		Cut-Down Height, Shelving Adder Unit Undersize Only	\$60	N/A
	MOD		Cut-Down Width, Wood Shelving Unit, Undersize	\$219	N/A
	MOD		Cut-Down Width, Omega or Omega Book Stop Shelving Unit, Undersize	\$416	N/A
	MOD		Shelving Range Reducer Panel/Step Down Shelving (S/F or D/F, LAYOUT - SKETCH REQUIRED)	\$444	N/A
Oversizing			Oversizing		
	MOD		Oversized Backs and Partitions up to 42"W	\$132	\$139
	MOD		Oversized Width Shelving, Wood Only (Oversize to 42" MAX)	\$592	\$622
			Note: Omega Shelving cannot be supplied oversized.		

## Modificiations & Up Charges

	Maple	0ak Drigo	Wt.	Description	Maple Catalog No.	Oak Catalog No
Finish and Band Back Sid	Price	Price	(lbs.)	Description  Finish and Dand Dank Side of Shahing Unit /D	Catalog No.	Catalog No.
of Shelving Un			sacks Ordered Separately)	Finish and Band Back Side of Shelving Unit (B		
<b>3</b> ·	\$359	\$342	nit Starter	Finish and Band Back Side of S/F Shelving Ur		MOD
	\$266	\$253	nit Adder	Finish and Band Back Side of S/F Shelving Ur		MOD
Convert Unit to Mobil			acing, hardware and partition.)	Convert Unit to Mobile (Price includes base fa		
	\$1,300	\$1,300	ım of 20''D	Unit must be 60-1/2"H or less and a minimu		MOD
Filler Pan				Filler Panel		
	\$32	\$30	)	Plywood (per sq. ft Excluding Edge Banding)		SHELVMOD
	\$6	\$6	)	Edge Banding, 1" x 1/4" (per lineal ft.)		SHELVMOD
	\$143	\$136		Corner Filler Cap (per sq. ft.)		SHELVMOD
	\$164	\$156		Corner Filler Cap with HPL (per sq. ft.)		SHELVMOD
Deletion of Shelve				Deletion of Shelves		
	<b>*</b> 20	<b># 2</b> /		Dalation of 400 Ward Chalf (complete)		140D
	\$ -38 \$ -44	\$ -36 \$ -42		Deletion of 10" Wood Shelf (per shelf) Deletion of 12" Wood Shelf (per shelf)		MOD MOD
	\$-44 \$-92	\$ -42 \$ -85	١	Deletion of 12" Picture Book Shelf (per shelf)		MOD
	φ-72	<b>\$-03</b>	1	Deletion of 12 Ficture Book Shell (per Shell)		VIOD
	\$ -29	\$ -29		Deletion of 10" Omega Shelf (per shelf)		MOD
	\$-36	\$ -36		Deletion of 12" Omega Shelf (per shelf)		MOD
Clip & Strip Shelvin	elving prices	ver standard she	10% Upcharge o	Clip & Strip Shelving		
	hanging		Laminate Shelves ONLY and ca	All shelving (with the exception of Glass Door Clip & Strip shelving is available for Wood or L		
	0 0	er unit to S4.	anging the S2 prefix on the add	the S1 prefix on the starter unit to S3, and cha Example: S3 861 S00 or S4 861 S00.		
Sub Tops for Shelvin		er unit to S4.	HPL tops (sold separately)	Example: S3 861 S00 or S4 861 S00.  Sub Tops for Shelving (to accept continuous H		
Sub Tops for Shelvin		er unit to S4.	HPL tops (sold separately)	Example: S3 861 S00 or S4 861 S00.  Sub Tops for Shelving (to accept continuous Hare available and can be ordered by changing		
Sub Tops for Shelvin		er unit to S4.	HPL tops (sold separately)	Example: S3 861 S00 or S4 861 S00.  Sub Tops for Shelving (to accept continuous H		
Sub Tops for Shelvin	\$-34 \$-67	\$ -34 \$ -67	HPL tops (sold separately) y the S00 extension on the ops (list deduct per unit)	Example: \$3 861 \$00 or \$4 861 \$00.  Sub Tops for Shelving (to accept continuous Hare available and can be ordered by changing catalog number to \$02.		
	\$-34	\$-34	HPL tops (sold separately) y the S00 extension on the ops (list deduct per unit)	Sub Tops for Shelving (to accept continuous Hare available and can be ordered by changing catalog number to S02.  Example: S1 861 S02.  10", 12" and 16" Shelving Units with Sub To 20", 24" and 32" Shelving Units with Sub To		
Sub Tops for Shelvin	\$-34	\$-34	HPL tops (sold separately)  If the SOO extension on the open (list deduct per unit)  If the SOO extension on the open (list deduct per unit)	Sub Tops for Shelving (to accept continuous H are available and can be ordered by changing catalog number to S02.  Example: S1 861 S02.  10", 12" and 16" Shelving Units with Sub Tops		
	\$-34	\$-34	HPL tops (sold separately)  If the SOO extension on the open (list deduct per unit)  If the SOO extension on the open (list deduct per unit)	Sub Tops for Shelving (to accept continuous Hare available and can be ordered by changing catalog number to S02.  Example: S1 861 S02.  10", 12" and 16" Shelving Units with Sub To 20", 24" and 32" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" Shelv		
	\$-34	\$-34	HPL tops (sold separately) g the SOO extension on the ops (list deduct per unit) ops (list deduct per unit)	Sub Tops for Shelving (to accept continuous Hare available and can be ordered by changing catalog number to S02.  Example: S1 861 S02.  10", 12" and 16" Shelving Units with Sub To 20", 24" and 32" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 24" and 25" Shelving Units with Sub To 20", 2		

			0ak	Maple
		Description	Price	Price
Panel Style		Panel Styles Up-charge is to be added to the STARTER UNIT price of the unit receiving the design. Any additional species/modification up-charges should be added over and above this charge.		
	Chancellor Panel	Upcharge for Chancellor Sketch Face Design - No Top Cap (per panel)	62%	62%
	Foreit	Upcharge for Epoch with Painted Metal Inlay Design (per panel) Arched Top with 1/4" Painted Metal Inlay 4" from the bottom of the Panel.  Note: Due to the arch on the Epoch series panels, if continuous tops are used, they MUST be inset (not overhang).	9%	9%
	Epoch Panel	Upcharge for Epoch with Chrome Metal Inlay Design (per panel) Arched Top with 1/4" Chrome Metal Inlay 4" from the bottom of the Panel.  Note: Due to the arch on the Epoch series panels, if continuous tops are used, they MUST be inset (not overhang).	14%	14%
©:: ● ·	Horizon Panel	Upcharge for Horizon Cut-Out with Laminate Inlay Design (per panel) With specified Cut-Outs and Laminate Inlay (overall panel thickness will be 1-1/4").	81%	81%
	Matrix Panel	Upcharge for Matrix Panel with Black Matrix Design Stencil (per panel)	6%	6%

### **General Specifications**

#### **DESKTOP**

Standard desktop is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The desk top receives a solid Northern-grown Red Oak or maple flush edge band 5/8" x 1-3/16" thick, radiused 1/2" to form a waterfall shape on the patron side. A 1/4", solid Northern-grown Red Oak or maple edge band is applied to the remaining three sides of the desk top, with top and bottom edges have a 1/8" radius. All edges are applied to the desktop after the laminate and backer sheets are applied, constituting an external edge band. Desktop is positioned over the end panels of the desk module, flush with the outside edges of the end panels.

### **END PANEL**

Desk module end panel is 1" thick, 3-ply, 45# density particleboard core with select plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges are externally banded with a 1" x 1.6mm thick Northern-grown Red Oak or maple veneer edge band. The end panel and front panel are joined with 3/4" x 3/4" thick solid hardwood cleats screwed to the inside surface of the panel. Each end panel receives a 3" diameter egress grommet to provide for wire passage and two adjustable glides to allow leveling of the individual units.

### FRONT PANEL

The front panel is 3/4" thick; 45# density particleboard core comprised of select rift cut Northern-grown Red Oak veneers or maple plain sliced slip matched veneers. Exposed edges are externally banded with a 3/4" x 1.6mm thick, veneer edge band. A 6"H x 3/4"D recessed, ebonized, toe space is incorporated at the bottom of the panel. The front panel is positioned over the end panels of the desk module, flush with the outside edges of the end panels. Double wide units have two front panels to give the appearance of two individual units.

### **WORK SURFACE**

Work surface is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The exposed edge receives a 1/4" thick, Northern-grown Red Oak or maple solid internal edge band in straight design. The back edge of the work surface has a plastic black strip, 1-1/2"W, which projects above the work surface 1/4" to act as a retainer. The work surface is 24-1/2"D and is positioned 1-1/2" away from the front panel, creating a cord drop space. Adjustable work surfaces positioned at heights of 36", 32" or 27" are available in single wide standing height desks.


**Note:** See Brodart optional electrical accessories for electrical power-distribution system for desk modules.

#### **SHELVES**

Shelves are constructed of 7-ply, furniture-grade veneer-core hardwood plywood, with Northern-grown Red Oak plain sliced face veneer or maple plain sliced face veneer. Exposed edges receive a 1.6mm thick, solid-oak or maple edge band.

#### DRAWER

Drawer is constructed of solid Northern-grown Red Oak or maple with 1/4" thick wood bottom panel. Drawer has 3-ply particleboard fronts with select oak-face veneer or maple veneer. Box drawer has extension slides with 100# load capacity. File drawer has full-extension slides with 100# load capacity. Double Units: 32-3/16"H x 70"W x 30"D




Abridge Flush Edge Band

### **DESK DIMENSIONS**

Standing-Height Desk, overall: 39-3/16"Hx 70"Wx 30"D. or 39-3/16"Hx 70"Wx 30"D.

Sitting-Height Desk, overall: 32-3/16"Hx 70"Wx 30"D. or 32-3/16"Hx 70"Wx 30"D.



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
ABOCIRSW39PLS	ABMCIRSW39PLS	Standing Height Desk with Patron Service Ledge	39-3/16" x 35" x 30"	140	\$2,654	\$2,893	Single-Wide Desk with Patron Service Ledge
		Inside dimensions: 33"W x 26-3/7-7/8" patron ledge is at a heigh Note: Adjustable-height work su at heights of 36", 32" or 27".	t of 39-1/4"H.				
ABOCIRSW32PLS	ABMCIRSW32PLS	Sitting Height Desk with Patron Service Ledge	32-3/16" x 35" x 30"	125	\$2,522	\$2,748	
		Inside dimensions: 33"W x 26-3/7-7/8" patron ledge is at a heigh <b>Note</b> : Work surface is fixed at 27	t of 32-3/16"H.				
ABOCIRSW39S	ABMCIRSW39S	Standing Height Desk	39-3/16" x 35" x 30"	135	\$2,317	\$2,525	Single-Wide Desk
		without Patron Service Ledge Inside dimensions: 33"W x 26-3/		.00	<i>4=,0</i>	<del>+</del> =/0=0	without Patron Service Ledge
		work surface is at 39-3/16"H. Tw grommets are located in the work	o 3" diamenter				
ABOCIRSW32S	ABMCIRSW32S	Sitting Height Desk without Patron Service Ledge	32-3/16" x 35" x 30"	120	\$2,122	\$2,313	
		Inside dimensions: 33"W x 26-3/work surface is at 32-3/16"H. Tw grommets are located in the work	o 3" diamenter				
ABOCIRSW39BRS	ABMCIRSW39BRS	Standing Height Book Return Unit	39-3/16" x 35" x 30"	135	\$2,246	\$2,448	Book Return Unit
		Inside dimensions: 33"W x 26-3/work surface is at 39-3/16"H. Ur finished opening centered in the f of books and a book chute to diredepressible book truck. (Depressi Two 3" diameter grommets are lo	nit has a 5"H x 12"W ront panel for passage ct the books over a mobile ble book truck not include				
ABOCIRSW32BRS	ABMCIRSW32BRS	Sitting Height Book Return Unit Inside dimensions: 33"W x 26-3/ work surface is at 32-3/16"H. Ur		120	\$2,114	\$2,305	
		finished opening centered in the f of books and a book chute to dire depressible book truck. (Depressi Two 3" diameter grommets are lo	ront panel for passage ct the books over a mobile ble book truck not include				0

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Cupboard and Open S	Shelf	ABOCIRSW39COSS	ABMCIRSW39COSS	Standing Height Cupboard and Open Shelf	39-3/16" x 35" x 30"	175	\$4,415	\$4,813
0				This unit has one fixed and tw shelves. A hidden drawer is p the lockable storage compar grommets are located in the	ositioned above tment. Two 3" diameter			
	7	ABOCIRSW32COSS	ABMCIRSW32COSS	Sitting Height Cupboard	32-3/16" x 35" x 30"	160	\$4,127	\$4,498
	1			This unit has one fixed and or shelf. A hidden drawer is pos the lockable storage compar grommets are located in the	itioned above tment. Two 3" diameter			
Full Width Drawer, Cupboard and Drawe	ers	ABOCIRSW39FCDS	ABMCIRSW39FCDS	Standing Height Full Width Drawer, Cupboard and Draw	39-3/16" x 35" x 30" ers	225	\$6,048	\$6,593
				This unit has one full-width d two file drawers, and a lockal compartment. Two 3" diame are located in the work surfac <b>Note</b> : Available in 39"H on	ble storage eter grommets ce.			
Cupboard and Drawe	er Unit	ABOCIRSW39CDS	ABMCIRSW39CDS	Standing Height Cupboard	39-3/16" x 35" x 30"	225	\$5,355	\$5,837
	0 0 0 0			and Drawer Unit This unit has one locking box and two file drawers. Cupboa has two adjustable shelves a on hinges. Two 3" diameter of located in the work surface.	ard section nd locking door			
7	•	ABOCIRSW32CDS	ABMCIRSW32CDS	Sitting Height Cupboard and Drawer Unit	32-3/16" x 35" x 30"	205	\$4,878	\$5,316
0	0.00			This unit has one locking file and one file drawer. Cupboar has one adjustable shelf and on hinges. Two 3" diameter of located in the work surface.	rd section Hocking door			

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
ABOCIRSW390SDS	ABMCIRSW390SDS	Standing Height Open Shelf and Drawer Unit	39-3/16" x 35" x 30"	200	\$4,942	\$5,387	Open Shelf and Drawer Unit
		This unit has one lockable bo and two file drawers. Shelf se two adjustable shelves, and o Two 3" diameter grommets a	ection has one fixed base shelf.	face.			
ABOCIRSW320SDS	ABMCIRSW320SDS	Sitting Height Open Shelf and Drawer Unit	32-3/16" x 35" x 30"	180	\$4,510	\$4,916	
		This unit has one lockable bo and one file drawer. Shelf sec one adjustable shelf, and one Two 3" diameter grommets a	ction has e fixed base shelf.	face.			
ABOCIRSW39CSDS	ABMCIRSW39CSDS	Standing Height Cash Drawe	r Unit39-3/16" x 35" x 3	0''150	\$3,359	\$3,662	Cash Drawer Unit
		Inside dimensions: 33"W x 2 The work surface is at 39-3/ has locking drawer with a coi Two 3" diameter grommets a	16"H. Desk n and currency tray.	face.			0 0
ABOCIRSW32CSDS	ABMCIRSW32CSDS	Sitting Height Cash Drawer U	nit32-3/16" x 35" x 30"	135	\$3,216	\$3,505	
		Inside dimensions: 33"W x 2 The work surface is at 32-3/ has locking drawer with a coi Two 3" diameter grommets a	16"H. Desk n and currency tray.	face.			
ABOCIRSW32ADAS	ABMCIRSW32ADAS	Sitting Height ADA Station	32-3/16" x 35" x 30"	185	\$2,522	\$2,748	ADA Station
		The ADA transaction station i designed to provide wheelch on the patrons' side. The kne on the patrons' side is 22-1/ staff side is 16". Two 3" diar are located in the work surfac egress with sleeve is located	air access he space depth '4" and on the meter grommets he. One 3-1/2" diameter	passage.			

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Full Width Drawer Unit		ABOCIRSW39FS	ABMCIRSW39FS	Standing Height Full Width Drawer Unit	39-3/16" x 35" x 30"	160	\$3,455	\$3,765
				This drawer unit has a full-wi 10"H x 33"W x 18-3/4"D. grommets are located in the <b>Note</b> : Available in 39" H on	Two 3" diameter work surface.			

**Full Width Drawer and Cupboard Unit** 



ABOCIRSW39FCS ABMCIRSW39FCS Standing Height Full Width 39-3/16" x 35" x 30" Drawer and Cupboard Unit

\$3,841

\$4,187

This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Hinged doors have a catch, lock and door pulls. Two 3" diameter grommets are located in the work surface.

Discharge Unit ABOCIRSW39DS ABMCIRSW39DS Standing Height Discharge Unit 39-3/16" x 35" x 30" 165 \$3,612 \$3,937 These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 39-3/16"H. Note: Standing-height roll unders do not work with this unit. ABOCIRSW32DS ABMCIRSW32DS Sitting Height Discharge Unit 32-3/16" x 35" x 30" 145 \$3,725 \$3,418 These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 32-3/16"H.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
ABOCIRSW390SS	ABMCIRSW390SS	Standing Height Open Shelf Unit	39-3/16" x 35" x 30"	175	\$2,689	\$2,931		Open Shelf Unit
		This unit has a full-depth fixed bass shelf and two full-depth adjustable Two 3" diameter grommets are loot the work surface.	e shelves. cated in			c		
ABOCIRSW32OSS	ABMCIRSW32OSS	Sitting Height Open Shelf Unit This unit has a full-depth fixed bass shelf and two full-depth adjustable Two 3" diameter grommets are loo the work surface.	e shelves.	155	\$2,400	\$2,616		
ABOCIRSW39CS	ABMCIRSW39CS	Standing Height Cupboard Unit	39-3/16" x 35" x 30"	200	\$3,340	\$3,640		Cupboard Unit
		This unit has a full-depth fixed bass shelf and two full-depth adjustable Hinged doors have a catch, lock ar Two 3" diameter grommets are loc work surface.	e shelves. nd door pulls.			0		1
ABOCIRSW32CS	ABMCIRSW32CS	Sitting Height Cupboard Unit	32-3/16" x 35" x 30"	180	\$3,187	\$3,474		
		This unit has a full-depth fixed bass shelf and one full-depth adjustable Hinged doors have a catch, lock ar Two 3" diameter grommets are loc work surface.	e shelf. nd door pulls.				0	
ABOCIRSW39FOSS	ABMCIRSW39FOSS	Standing Height Full Width Drawer and Open Shelves	39-3/16" x 35" x 30"	180	\$3,264	\$3,558	Full	Width Drawer and Open Shelves
		This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable full-depth shelf. Two 3" diameter grommets are located in the work s						
ABOCIRSW32FOSS	ABMCIRSW32FOSS	Sitting Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable full-depth shelf. Two 3" diameter grommets are located in the works		165	\$3,072	\$3,349	0	199

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Media Storage Unit		ABOCIRSW39MSS	ABMCIRSW39MSS	Standing Height Media Storage Unit	39-3/16" x 35" x 30"	225	\$4,613	\$5,028
0	0			This unit has four full-width 8-1/2"H x 33"W x 24"D v containing five compartme	with each			
	<b>\</b>	ABOCIRSW32MSS	ABMCIRSW32MSS	Sitting Height Media Storage Unit	32-3/16" x 35" x 30"	205	\$4,240	\$4,621
0		5		This unit has three full-widt 8-1/2"H x 33"W x 24"D v containing five compartme	with each			

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
ABOCIRDW39PL35S	ABMCIRDW39PL35S	Standing Height Double-Wide Desk with Patron Service Ledge	39-3/16" x 70" x 30"	245	\$3,839	\$4,185		uble-Wide Desk Service Ledge
		Work Surface at 35"H Inside dimensions are 68"W x 2 The 7-7/8"D patron ledge is at Two 3" diameter grommets are <b>Note</b> : Standing-height roll und	a height of 39-3/16". located in the work surface		0			
ABOCIRDW32PLS	ABMCIRDW32PLS	Sitting Height Double-Wide Desk with Patron Service Ledge Work Surface at 28"H Inside dimensions are 68"W x 2 The 7-7/8"D patron ledge is at Two 3" diameter grommets are	26-3/4"D. a height of 32-3/16".	210 e.e.	\$3,621	\$3,947		
ABOCIRDW39PL28S	ABMCIRDW39PL28S	Standing Height Double-Wide Desk with Patron Service Ledge Work Surface at 28"H Inside dimensions are 68"W x 2 The 7-7/8"D patron ledge is at Two 3" diameter grommets are <b>Note</b> : Standing-height roll und	26-3/4"D. a height of 39-3/16". located in the work surfac		\$3,742	\$4,079		
ABOCIRDW39S	ABMCIRDW39S	Standing Height Double-Wide Desk without Patron Service Lec Inside dimensions are 68"W x 2 The work surface is at 39-3/16' diameter grommets are located	dge 26-3/4"D. " H. Two 3"	230	\$3,411	\$3,717		uble-Wide Desk n Service Ledge
ABOCIRDW32S	ABMCIRDW32S	Sitting Height Double-Wide Desk without Patron Service Lec	32-3/16" x 70" x 30" dge	195	\$3,240	\$3,532		0

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ High-Pressure\ Laminate\ (Table\ 2).\ Details\ can\ be\ found\ on\ page\ GEN\ 4.$ 


Inside dimensions are 68"W x 26-3/4"D.
The work surface is at 32-3/16" H. Two 3" diameter grommets are located in the work surface.

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Double Work Desk	Pedestal	ABOCIRDW32DPS	ABMCIRDW32DPS	Sitting Height Double-Wide Double Pedestal Work Desk	32-3/16" x 70" x 30"	260	\$7,872	\$8,580
		1 2 2		Inside dimensions are 68"W x This unit has two drawer pedes on each side consisting of one one file drawer with hanging fil Two center drawers are mounte Two 3" diameter grommets are Note: Available in 32-3/16"	stals, one mounted locking drawer at top; le rack at bottom. ed between the two pedesta e located in the work surfac			



Oak Catalog No	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
Catalog No. ABOCIR9039MCS	ABMCIR9039MCS	Standing Height 90 Degree	39-3/16" x 71-3/4" x		\$5,013	\$5,464		90 Degree ti-Purpose Corner
		Multi-Purpose Corner Unit has 29-5/16"W port arr angled areas to the left and ri grommet is located in the wo with sleeve is located in each	ight of the desk module. C rk-surface top. One 3-1/2	)ne 3" diame 2" diameter e	ter			)
ABOCIR9032MCS	ABMCIR9032MCS	Sitting Height 90 Degree Multi-Purpose Corner	32-3/16" x 71-3/4" x	30" 215	\$4,797	\$5,228		•
		Unit has 29-5/16"W port are angled areas to the left and rigrommet is located in the wo with sleeve is located in each	ight of the desk module. C rk-surface top. One 3-1/2	)ne 3" diame 2" diameter e	ter		0	0
ABOCIR9039MCPS	ABMCIR9039MCPS	Standing Height 90 Degree Multi-Purpose with Patron Se	39-3/16" x 71-3/4" x ervice Ledge	30" 245	\$6,513	\$7,099		ti-Purpose Corner on Service Ledge
		Unit has 29-5/16"W port arr of 39-3/16". Work surface i two angled areas to the left a is located in the work surface located in each end panel for	s at 35"H. Storage shelve and right of the module. O top. One 3-1/2"diamete	es are located ne 3" diamet	d in the er grommet			0
ABOCIR9032MCPS	ABMCIR9032MCPS	Sitting Height 90 Degree Multi-Purpose with Patron Se	32-3/16" x 71-3/4" x ervice Ledge	30" 210	\$6,239	\$6,801		•
		Unit has 29-5/16"W port are Work surface is at 28"H. Sto and right of the module. One 3-1/2" diameter egress with	rage shelves are located i 3" diameter grommet is	n the two and located in the	led areas to t work surface	he left top. One	0	0
ABOCIR9039CCS	ABMCIR9039CCS	Standing Height 90 Degree Closed Corner Unit	39-3/16"H	140	\$2,680	\$2,921	C	90 Degree
		This 90 degree unit is used to This is not available with patr in each end panel for wire pa	on ledge. One 3-1/2" dia	meter egress	•	0	0	
ABOCIR9032CCS	ABMCIR9032CCS	Sitting Height 90 Degree Closed Corner Unit	32-3/16"H	120	\$2,550	\$2,779		
		This 90 degree unit is used to This is not available with patr in each end panel for wire pa	on ledge. One 3-1/2" dia	meter egress	-		Ĺ	

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
45 Degree Closed	Corner Unit	ABOCIR4539CCS	ABMCIR4539CCS	Standing Height 45 Degree Closed Corner Unit	39-3/16" x 22-7/8" x 3	0" 130	\$2,490	\$2,715
				This corner unit is used to creat This unit is not available with		e circulatio	n desk.	
		ABOCIR4532CCS	ABMCIR4532CCS	Sitting Height 45 Degree Closed Corner Unit	32-3/16" x 22-7/8" x 3	0" 110	\$2,358	\$2,570
				This corner unit is used to creat This unit is not available with		e circulatio	n desk.	
90 Degree Open C with Patron Servic		ABOCIR90390CCPS	ABMCIR90390CCPS	Standing Height 90 Degree Open Curved Corner with Patr		0'' 245	\$8,125	\$8,856
0	0			The 7-7/8"D patron ledge is Unit has 26-5/8"W port area and right of the desk module. One 3-12" diameter egress v	a. Storage shelves are locat One 3" diameter grommet	ed in the tv is located	vo angled area in the work sur	s to the lef face top.
	-	ABOCIR90320CCPS	ABMCIR90320CCPS	Sitting Height 90 Degree Open Curved Corner with Patr	32-3/16" x 70-1/8" x 3 ron Service Ledge	0'' 210	\$7,829	\$8,533
0		0		The 7-7/8"D patron ledge is Unit has 26-5/8"W port area and right of the desk module. One 3-12" diameter egress v	a. Storage shelves are locat One 3" diameter grommet	ed in the tv is located	vo angled area in the work sur	s to the left face top.



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
ABOCIR6039CCPS	ABMCIR6039CCPS	Standing Height 60 Degree Curved Corner with Patron Se	39-3/16" x 80-3/4" x 30' ervice Ledge		\$9,785	\$10,665		gree Curved Corner tron Service Ledge
		35-7/16"H. Unit has 49-1/ two angled areas to the left a	at a height of 39-3/16". The 16" W port area. Storage she and right of the desk module. O rk surface top. One 3-1/2" o panel for wire passage.	lves are loca One 3'' dian	nted in the neter			0
ABOCIR6032CCPS	ABMCIR6032CCPS	Sitting Height 60 Degree Curved Corner with Patron Se	32-3/16" x 80-3/4" x 30' ervice Ledge	' 210	\$9,434	\$10,283		•
		Unit has 49-1/16" W port ar left and right of the desk mod	at a height of 32-3/16". The rea. Storage shelves are locat dule. One 3" diameter gromm gress with sleeve is located in	ed in the two et is located	angled areas in the work s	urface	0	
ABOCIR6039CCS	ABMCIR6039CCS	Standing Height 60 Degree Curved Corner	39-3/16" x 80-3/4" x 30'	' 245	\$8,843	\$9,638	60 De	gree Curved Corner
		Work surface is at 39-3/16" are located in the two angled 3" diameter grommet is located in the two angled are diameter grommet is located in the two angled are the two angled in the two angle	H. Unit has 49-1/16''W port I areas to the left and right of t ated in the work surface top. O in each end panel for wire pas	he desk mo ne 3-1/2''	dule. One			
ABOCIR6032CCS	ABMCIR6032CCS	located in the two angled are	32-3/16" x 80-3/4" x 30'  H. Unit has 49-1/16"W port eas to the left and right of the crk surface top. One 3-1/2" or wire passage.	area. Storaç desk module	e. One 3" dian		0	
ABOCIR9039CCCS	ABMCIR9039CCCS	Standing Height 90 Degree Closed Corner Unit	39-3/16"Hx30"D	140	\$3,464	\$3,776		90 Degree Curved
			o form a right-angle turn in a d urved front panel.	esk arrange	ment.			
ABOCIR9032CCCS	ABMCIR9032CCCS	Sitting Height 90 Degree Closed Corner Unit	32-3/16"Hx30"D	120	\$3,236	\$3,527		
		This 90 degree unit is used to	o form a right-angle turn in a d	esk arrange	ment.			

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
45 Degree Curved Closed Corner Unit		ABOCIR4539CCCS	ABMCIR4539CCCS	Standing Height 45 Degree Curved Closed Corner Unit	39-3/16" x 22-3/8" x 30"		\$3,167	\$3,452
				This unit is used to create a 49. It is not available with patron		on desk.		
		ABOCIR4532CCCS	ABMCIR4532CCCS	Sitting Height 45 Degree Curved Closed Corner Unit	32-3/16" x 22-3/8" x 30"	110	\$2,938	\$3,203
	0			This unit is used to create a 4! It is not available with patron		on desk.		
90 Degree Open Corr	ner Shelf	ABOCIR90390CSS	ABMCIR90390CSS	Standing Height 90 Degree Open Corner Shelf	39-3/16"H x 30"D	140	\$2,464	\$2,686
				This 90 degree unit is used to Has one fixed base shelf and Note: Units must be modified on open corner units.	two adjustable shelves.			ough
		ABOCIR90320CSS	ABMCIR90320CSS	Sitting Height 90 Degree Open Corner Shelf	32-3/16"H x 30"D	120	\$2,281	\$2,486
				This 90 degree unit is used to Has one fixed base shelf and Note: Units must be modified on open corner units.	two adjustable shelves.			ough
90 Degree Square Co	orner Unit	ABOCIR9039SCS	ABMCIR9039SCS	Standing Height 90 Degree Square Corner Unit	39-3/16" x 30" x 30"	160	\$2,667	\$2,906
0 0				This square corner unit is used One 3" diameter egress is loc a continuous ABS tube.				
		ABOCIR9032SCS	ABMCIR9032SCS	Sitting Height 90 Degree Square Corner Unit	32-3/16" x 30" x 30"	140	\$2,514	\$2,740
0	0			This square corner unit is used One 3" diameter egress is loc a continuous ABS tube.				

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
ABOCIREP39S	ABMCIREP39S	Detachable End Panels (Pair)	37-1/2" x 1" x 26-3/4"	52	\$1,027	\$1,119	Detachable End Panels (Pair)
		End panels are 1" thick, 3-ply, particleboard core with plain-s veneers. Exposed edges are ex with 1.6mm thick, solid Norths	liced oak or maple ternally banded	e band.			
ABOCIREP32S	ABMCIREP32S	Detachable End Panels (Pair)	30-1/2" x 1" x 26-3/4"	42	\$980	\$1,068	
		End panels are 1" thick, 3-ply, particleboard core with plain-s veneers. Exposed edges are ex with 1.6mm thick, solid Northe	liced oak or maple ternally banded	e band.			

ABOCIRSWPL7HS	ABMCIRSWPL7HS	Single-Wide Add On 7''H Patron Ledge	7" x 35" x 7-7/8"	10	\$510	\$556	Single-Wide Add On 7"H Patron Ledge
			Patron Ledge Assembly will at #8 x 2-1/2" screws inserted t		[		

ABOCIRDWPL7HS	ABMCIRDWPL7HS	Double-Wide Add On 7''H Patron Ledge	7" x70" x 7-7/8"	20	\$644	\$702	Double-Wide Add On 7"H Patron Ledge
		, ,	Patron Ledge Assembly will at #8 x 2-1/2" screws inserted t				

### **General Specifications**

#### **TABLETOP**

Tabletop is 1-3/16" thick, 9-ply solid hardwood plywood or 3-ply 45# density particleboard, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Edges are solid Northern-grown Red Oak or maple. Top receives an external solid drop edge Northern-grown Red Oak or maple band 5/8" x 1-5/8" thick, radiused 1/2" to form a waterfall shape.

**Note:** Tables with a depth exceeding 48" receive only 1-3/16" thick, 3-ply, 45# density particleboard core.

### APRON (OPTIONAL)

A 4"H x 1" thick solid Northern-grown Red Oak or maple apron is fitted between the legs and behind the extended tabletop edge band. Starting 1/2" in from each end, the apron receives a radius that peaks at 2" in the center. The ends of each apron receive a 1/2" radius. Aprons are attached to the table using wood cleats screwed to the underside of the tabletop. Aprons on round tables go straight between the legs

**Note:** Aprons are not available for trapezoid shaped tables or Pedestal Base tables.

### LEG

The leg is glued up 2-1/4" solid Northern-grown Red Oak or maple. The leg is molded into a triangle shape with the front face receiving a 2" radius and outside edges receiving a 1/2" radius that tapers to a 90° right angle. A 1/4" wide x 1/16" deep horizontal vein line is routed 2" up from the bottom of the leg. A 1/8" chamfer is placed at the bottom of the leg. Each leg receives a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut which is further recessed into the leg by means of a counter-sink boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The assembled leg is attached to the tabletop by five 5/16" x 1" machine bolts engaging internal and external threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended table edge band.


### **TABLETOP SUPPORT**

For maximum rigidity, rectangular tables 60" wide or more receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 90" or wider receive two extra legs located under the center of the table to provide added support.


Note: Center support legs will be glued up, 2-1/4" square solid Northern-grown Red Oak or maple. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are chamfered 1/8". Each leg has a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two-thirds of the glide.

#### **PEDESTAL**

Pedestal base will be solid Northern-grown Red Oak or maple. The base consists of four assembled leg components comprised of 6/4 solid material assembled using mortise and tenon construction. The upper horizontal part of the each base leg will receive borings for attaching the assembly to the tabletop. The lower horizontal piece will receive a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut which is further recessed into the leg by means of a counter-sink boring which accepts the upper two-thirds of the glide. All pedestal base edges will receive a 1/4" radius. The four assembled base components will connect to a 2-1/4" x 2-1/4" solid Northern-grown red oak or maple post using metal to metal hardware fasteners forming a one piece pedestal. Table tops are attached to base by bolting through the upper horizontal members of base into internal and external threaded bushings embedded in the under side of the table top.



Abridge Drop Edge Band



Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Round Oak Table							Round Table
ABOT36RD27BRTWS	ABOT36RD29ARTWS ABOT36RD27ARTWS ABOT36RD25ARTWS	Youth Table	29"H x 36" Diameter 27-1/2"H x 36" Diameter 25"H x 36" Diameter	100 100 100	\$1,480 \$1,480 \$1,480	\$1,371 \$1,371 \$1,371	
ABOT42RD27BRTWS	ABOT42RD29ARTWS ABOT42RD27ARTWS ABOT42RD25ARTWS	Youth Table	29"H x 42" Diameter 27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110 110	\$1,584 \$1,584 \$1,584	\$1,450 \$1,450 \$1,450	
ABOT48RD27BRTWS	ABOT48RD29ARTWS ABOT48RD27ARTWS ABOT48RD25ARTWS	Youth Table	29"H x 48" Diameter 27-1/2"H x 48" Diameter 25"H x 48" Diameter	120 120 120	\$1,642 \$1,642 \$1,642	\$1,488 \$1,488 \$1,488	n A e
N/A N/A N/A	ABOT6ORD29ARTWS ABOT6ORD27ARTWS ABOT6ORD25ARTWS	Youth Table	29"H x 60" Diameter 27-1/2"H x 60" Diameter 25"H x 60" Diameter	120 120 120	N/A N/A N/A	\$1,785 \$1,785 \$1,785	
Round Maple Table	<u>e</u>						
ABMT36RD27BRTWS	ABMT36RD29ARTWS ABMT36RD27ARTWS ABMT36RD25ARTWS	Youth Table	29"H x 36" Diameter 27-1/2"H x 36" Diameter 25"H x 36" Diameter	100 100 100	\$1,509 \$1,509 \$1,509	\$1,399 \$1,399 \$1,399	
ABMT42RD27BRTWS	ABMT42RD29ARTWS ABMT42RD27ARTWS ABMT42RD25ARTWS	Youth Table	29"H x 42" Diameter 27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110 110	\$1,626 \$1,626 \$1,626	\$1,491 \$1,491 \$1,491	
ABMT48RD27BRTWS	ABMT48RD29ARTWS ABMT48RD27ARTWS ABMT48RD25ARTWS	Youth Table	29"H x 48" Diameter 27-1/2"H x 48" Diameter 25"H x 48" Diameter	120 120 120	\$1,687 \$1,687 \$1,687	\$1,534 \$1,534 \$1,534	
N/A N/A	ABMT60RD29ARTWS ABMT60RD27ARTWS ABMT60RD25ARTWS	Adult Table Youth Table	29"H x 60" Diameter 27-1/2"H x 60" Diameter	120 120	N/A N/A	\$1,838 \$1,838	
N/A	ABIVITOURD25ARTW5	Juverille rable	25"H x 60" Diameter	120	N/A	\$1,838	
Square Oak Table							Square Table
ABOT303029BRTWS	ABOT303029ARTWS	Adult Table	29" x 30" x 30"	110	\$1,143	\$1,009	
ABOT303027BRTWS	ABOT303027ARTWS	Youth Table	27-1/2" x 30" x 30"	110	\$1,143	\$1,009	The state of
ABOT303025BRTWS	ABOT303025ARTWS		25" x 30" x 30"	110	\$1,143	\$1,009	
ABOT363629BRTWS ABOT363627BRTWS	ABOT363629ARTWS ABOT363627ARTWS	Adult Table Youth Table	29" x 36" x 36" 27-1/2" x 36" x 36"	110	\$1,258 \$1,258	\$1,110 \$1,110	
	ABOT363625ARTWS		27-172 x 36 x 3	110 110	\$1,258 \$1,258	\$1,110 \$1,110	f # 1
ABOT424229BRTWS	ABOT424229ARTWS	Adult Table	29" x 42" x 42"	110	\$1,275	\$1,142	9
	ABOT424227ARTWS		27-1/2" x 42" x 42"	110	\$1,275	\$1,142	
ABOT424225BRTWS	ABOT424225ARTWS	Juvenile Table	25" x 42" x 42"	110	\$1,275	\$1,142	
	ABOT484829ARTWS		29" x 48" x 48"	110	\$1,367	\$1,209	
	ABOT484827ARTWS ABOT484825ARTWS		27-1/2" x 48" x 48" 25" x 48" x 48"	110 110	\$1,367 \$1,367	\$1,209 \$1,209	
Square Maple Tab	<b>l</b> e						
	ABMT303029ARTWS	Adult Table	29" x 30" x 30"	110	\$1,157	\$1,022	
	ABMT303027ARTWS		27-1/2" x 30" x 30"	110	\$1,157 \$1,157	\$1,022	
ABMT303025BRTWS	ABMT303025ARTWS	Juvenile Table	25" x 30" x 30"	110	\$1,157	\$1,022	
ABMT363629BRTWS	ABMT363629ARTWS	Adult Table	29" x 36" x 36"	110	\$1,273	\$1,126	
	ABMT363627ARTWS		27-1/2" x 36" x 36"	110	\$1,273	\$1,126 \$1,126	
	ABMT363625ARTWS		25" x 36" x 36"	110	\$1,273	\$1,126	
	ABMT424229ARTWS		29" x 42" x 42"	110	\$1,296 \$1,206	\$1,161 \$1,161	
ABIVITATATATATRIRING	ABMT424227ARTWS		27-1/2" x 42" x 42" 25" x 42" x 42"	110 110	\$1,296 \$1,296	\$1,161 \$1,161	
			20 NIZ NTZ	110	Ψ:/2/0	ΨΙ,ΙΟΙ	
ABMT424225BRTWS			20" v 40" v 40"	110	¢1 202	¢1 220	
ABMT424225BRTWS ABMT484829BRTWS	ABMT484829ARTWS ABMT484827ARTWS	Adult Table	29" x 48" x 48" 27-1/2" x 48" x 48"	110 110	\$1,382 \$1,382	\$1,229 \$1,229	

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4. Note: Optional Wood Aprons for Tables are located on page ABR 21.

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Recta	ngular Oak Table					
Rectrangular Table	ABOT306029BRTWS	ABOT306029ARTWS	Adult Table	29" x 30" x 60"	120	\$1,532	\$1,198
	ABOT306027BRTWS	ABOT306027ARTWS	Youth Table	27-1/2" x 30" x 60"	120	\$1,532	\$1,198
III TY	ABOT306025BRTWS	ABOT306025ARTWS	Juvenile Table	25" x 30" x 60"	120	\$1,532	\$1,198
	ABOT307229BRTWS	ABOT307229ARTWS	Adult Table	29" x 30" x 72"	140	\$1,638	\$1,334
	ABOT307227BRTWS	ABOT307227ARTWS	Youth Table	27-1/2" x 30" x 72"	140	\$1,638	\$1,334
f # f	ABOT307225BRTWS	ABOT307225ARTWS	Juvenile Table	25" x 30" x 72"	140	\$1,638	\$1,334
	Four-Reader Recta	ngular Maple Table					
	ABMT306029BRTWS	ABMT306029ARTWS	Adult Table	29" x 30" x 60"	120	\$1,617	\$1,269
	ABMT306027BRTWS	ABMT306027ARTWS	Youth Table	27-1/2" x 30" x 60"	120	\$1,617	\$1,269
	ABMT306025BRTWS	ABMT306025ARTWS	Juvenile Table	25" x 30" x 60"	120	\$1,617	\$1,269
	ABMT307229BRTWS	ABMT307229ARTWS	Adult Table	29" x 30" x 72"	140	\$1,714	\$1,399
	ABMT307227BRTWS	ABMT307227ARTWS	Youth Table	27-1/2" x 30" x 72"	140	\$1,714	\$1,399
	ABMT307225BRTWS	ABMT307225ARTWS	Juvenile Table	25" x 30" x 72"	140	\$1,714	\$1,399

Six-Reader	Six-Reader Rectan	Six-Reader Rectangular Oak Table									
Rectrangular Table	ABOT366029BRTWS	ABOT366029ARTWS	Adult Table	29" x 36" x 60"	120	\$1,597	\$1,280				
	ABOT366027BRTWS	ABOT366027ARTWS	Youth Table	27-1/2" x 36" x 60"	120	\$1,597	\$1,280				
	ABOT366025BRTWS	ABOT366025ARTWS	Juvenile Table	25" x 36" x 60"	120	\$1,597	\$1,280				
	ABOT367229BRTWS	ABOT367229ARTWS	Adult Table	29" x 36" x 72"	140	\$1,692	\$1,471				
	ABOT367227BRTWS	ABOT367227ARTWS	Youth Table	27-1/2" x 36" x 72"	140	\$1,692	\$1,471				
ų.	ABOT367225BRTWS	ABOT367225ARTWS	Juvenile Table	25" x 36" x 72"	140	\$1,692	\$1,471				
	ABOT487229BRTWS	ABOT487229ARTWS	Adult Table	29" x 48" x 72"	170	\$1,849	\$1,621				
	ABOT487227BRTWS	ABOT487227ARTWS	Youth Table	27-1/2" x 48" x 72"	170	\$1,849	\$1,621				
	ABOT487225BRTWS	ABOT487225ARTWS	Juvenile Table	25" x 48" x 72"	170	\$1,849	\$1,621				
	Six-Reader Rectan	gular Maple Table									
	ABMT366029BRTWS	ABMT366029ARTWS	Adult Table	29" x 36" x 60"	120	\$1,617	\$1,299				
	ABMT366027BRTWS	ABMT366027ARTWS	Youth Table	27-1/2" x 36" x 60"	120	\$1,617	\$1,299				
	ABMT366025BRTWS	ABMT366025ARTWS	Juvenile Table	25" x 36" x 60"	120	\$1,617	\$1,299				
	ABMT367229BRTWS	ABMT367229ARTWS	Adult Table	29" x 36" x 72"	140	\$1,714	\$1,493				
	ABMT367227BRTWS	ABMT367227ARTWS	Youth Table	27-1/2" x 36" x 72"	140	\$1,714	\$1,493				
	ABMT367225BRTWS	ABMT367225ARTWS	Juvenile Table	25" x 36" x 72"	140	\$1,714	\$1,493				
	ABMT487229BRTWS	ABMT487229ARTWS	Adult Table	29" x 48" x 72"	170	\$1,872	\$1,645				
	ABMT487227BRTWS	ABMT487227ARTWS	Youth Table	27-1/2" x 48" x 72"	170	\$1,872	\$1,645				
	ABMT487225BRTWS	ABMT487225ARTWS	Juvenile Table	25" x 48" x 72"	170	\$1,872	\$1,645				

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

Note: Optional Wood Aprons for Tables are located on page ABR 21.

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Rectangular Oak Ta	able with Center Sup	port Legs					Rectangular Table with
ABOT309029BRTWS	ABOT309029ARTWS	Adult Table	29" x 30" x 90"	165	\$2,163	\$1,760	Center Support Legs
ABOT309027BRTWS	ABOT309027ARTWS	Youth Table 27	-1/2" x 30" x 90"	165	\$2,163	\$1,760	
ABOT309025BRTWS	ABOT309025ARTWS	Juvenile Table	25" x 30" x 90"	165	\$2,163	\$1,760	
ABOT369029BRTWS	ABOT369029ARTWS	Adult Table	29" x 36" x 90"	165	\$2,163	\$1,855	
ABOT369027BRTWS	ABOT369027ARTWS	Youth Table 27	-1/2" x 36" x 90"	165	\$2,163	\$1,855	
ABOT369025BRTWS	ABOT369025ARTWS	Juvenile Table	25" x 36" x 90"	165	\$2,163	\$1,855	g
ABOT489029BRTWS	ABOT489029ARTWS	Adult Table	29" x 48" x 90"	185	\$2,279	\$1,968	
ABOT489027BRTWS	ABOT489027ARTWS	Youth Table 27	-1/2" x 48" x 90"	185	\$2,279	\$1,968	
ABOT489025BRTWS	ABOT489025ARTWS	Juvenile Table	25" x 48" x 90"	185	\$2,279	\$1,968	
Rectangular Maple	Table with Center S	upport Legs					
ABMT309029BRTWS	ABMT309029ARTWS	Adult Table	29" x 30" x 90"	165	\$2,191	\$1,788	
ABMT309027BRTWS	ABMT309027ARTWS	Youth Table 27	-1/2" x 30" x 90"	165	\$2,191	\$1,788	
ABMT309025BRTWS	ABMT309025ARTWS	Juvenile Table	25" x 30" x 90"	165	\$2,191	\$1,788	
ABMT369029BRTWS	ABMT369029ARTWS	Adult Table	29" x 36" x 90"	165	\$2,191	\$1,881	
ABMT369027BRTWS	ABMT369027ARTWS	Youth Table 27	-1/2" x 36" x 90"	165	\$2,191	\$1,881	
ABMT369025BRTWS	ABMT369025ARTWS	Juvenile Table	25" x 36" x 90"	165	\$2,191	\$1,881	
ABMT489029BRTWS	ABMT489029ARTWS	Adult Table	29" x 48" x 90"	185	\$2,310	\$1,999	
ABMT489027BRTWS	ABMT489027ARTWS	Youth Table 27-	-1/2" x 48" x 90"	185	\$2,310	\$1,999	
ABMT489025BRTWS	ABMT489025ARTWS	Juvenile Table	25" x 48" x 90"	185	\$2,310	\$1,999	
<u>Trapezoid Oak Tabl</u>							Trapezoid Table
ABOT60TR29BRTWS	ABOT60TR29ARTWS	Adult Table	29" x 30" x 30" x 60"	120	\$1,766	\$1,439	10
ABOT60TR27BRTWS	ABOT60TR27ARTWS		-1/2" x 30" x 30" x 60"	120	\$1,766	\$1,439	
ABOT60TR25BRTWS	ABOT60TR25ARTWS	Juvenile Table	25" x 30" x 30" x 60"	120	\$1,766	\$1,439	
<u>Trapezoid Maple Ta</u>	able						F F
ABMT60TR29BRTWS	ABMT60TR29ARTWS	Adult Table	29" x 30" x 30" x 60"	120	\$1,844	\$1,449	6
ABMT60TR27BRTWS	ABMT60TR27ARTWS	Youth Table 27	-1/2" x 30" x 30" x 60"	120	\$1,844	\$1,449	
ABMT60TR25BRTWS	ABMT60TR25ARTWS	Juvenile Table	25" x 30" x 30" x 60"	120	\$1,844	\$1,449	

Note: Aprons are NOT available for Trapezoid Tables.

Catalog No.	Description	Price	
LG-CST-S00	Caster add-on to make any table mobile.  3-inch black nylon hooded twin-wheel caster with a brake.	\$84	Caster for Abridge Tables
	Add one caster per table leg (sold each).		

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

Note: Optional Wood Aprons for Tables are located on page ABR 21.

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Round Table	Round Oak Table						
with Pedestal Base		ABOT36RD29AWPDS	Adult Table	29"H x 36" Diameter	100	\$2,010	\$1,923
		ABOT36RD27AWPDS		27-1/2"H x 36" Diameter	100	\$2,010	\$1,923
	ABOT36RD25BWPDS	ABOT36RD25AWPDS	Juvenile Table	25"H x 36" Diameter	100	\$2,010	\$1,923
	ABOT42RD29WPDWS	ABOT42RD29AWPDS	Adult Table	29"H x 42" Diameter	110	\$2,096	\$1,988
		ABOT42RD27AWPDS		27-1/2"H x 42" Diameter	110	\$2,096	\$1,988
		ABOT42RD25AWPDS		25"H x 42" Diameter	110	\$2,096	\$1,988
	VBUTASDU30B/WDU2	ABOT48RD29AWPDS	Adult Table	29"H x 48" Diameter	120	\$2,138	\$2,017
		ABOT48RD27AWPDS		27-1/2"H x 48" Diameter	120	\$2,138 \$2,138	\$2,017 \$2,017
		ABOT48RD25AWPDS		25"H x 48" Diameter	120	\$2,138	\$2,017
						·	
	N/A N/A	ABOT60RD29AWPDS ABOT60RD27AWPDS		29"H x 60" Diameter 27-1/2"H x 60" Diameter	120 120	N/A N/A	\$2,462 \$2,462
	N/A	ABOT60RD25AWPDS		25"H x 60" Diameter	120	N/A	\$2,462 \$2,462
	10/11	ADOTOORDZSAWI DS	Javenine rabie	20 TIXOO DIGINICIO	120	14774	Ψ <b>2</b> /102
	Round Maple Tabl	<u>e</u>					
	ABMT36RD29BWPDS	ABMT36RD29AWPDS	Adult Table	29"H x 36" Diameter	100	\$2,039	\$1,951
	ABMT36RD27BWPDS	ABMT36RD27AWPDS	Youth Table	27-1/2"H x 36" Diameter	100	\$2,039	\$1,951
	ABMT36RD25BWPDS	ABMT36RD25AWPDS	Juvenile Table	25"H x 36" Diameter	100	\$2,039	\$1,951
	ABMT42RD29BWPDS	ABMT42RD29AWPDS	Adult Table	29"H x 42" Diameter	110	\$2,133	\$2,026
	ABMT42RD27BWPDS	ABMT42RD27AWPDS	Youth Table	27-1/2"H x 42" Diameter	110	\$2,133	\$2,026
	ABMT42RD25BWPDS	ABMT42RD25AWPDS	Juvenile Table	25"H x 42" Diameter	110	\$2,133	\$2,026
	ABMT48RD29BWPDS	ABMT48RD29AWPDS	Adult Table	29"H x 48" Diameter	120	\$2,183	\$2,059
		ABMT48RD27AWPDS		27-1/2"H x 48" Diameter	120	\$2,183	\$2,059
	ABMT48RD25BWPDS	ABMT48RD25AWPDS	Juvenile Table	25"H x 48" Diameter	120	\$2,183	\$2,059
	N/A	ABMT60RD29AWPDS	Δdult Table	29"H x 60" Diameter	120	N/A	\$2,473
	N/A	ABMT60RD27AWPDS		27-1/2"H x 60" Diameter	120	N/A	\$2,473
	N/A	ABMT60RD25AWPDS		25"H x 60" Diameter	120	N/A	\$2,473
	0 01711						
Square Table	Square Oak Table					44.500	****
with Pedestal Base		ABOT303029AWPDS		29" x 30" x 30"	110	\$1,739	\$1,631
		ABOT303027AWPDS ABOT303025AWPDS		27-1/2" x 30" x 30" 25" x 30" x 30"	110 110	\$1,739 \$1,739	\$1,631 \$1,631
THE TO						•	·
		ABOT363629AWPDS		29" x 36" x 36"	110	\$1,809	\$1,703
	ABOT363627BWPDS	ABOT363627AWPDS		27-1/2" x 36" x 36"	110	\$1,809	\$1,703
	ABU1363625BWPDS	ABOT363625AWPDS	Juvenile lable	25" x 36" x 36"	110	\$1,809	\$1,703
		ABOT424229AWPDS		29" x 42" x 42"	110	\$1,845	\$1,738
		ABOT424227AWPDS		27-1/2" x 42" x 42"	110	\$1,845	\$1,738
	AB01424225BWPDS	ABOT424225AWPDS	Juvenile lable	25" x 42" x 42"	110	\$1,845	\$1,738
	ABOT484829BWPDS	ABOT484829AWPDS	Adult Table	29" x 48" x 48"	110	\$1,917	\$1,805
		ABOT484827AWPDS		27-1/2" x 48" x 48"	110	\$1,917	\$1,805
	ABOT484825BWPDS	ABOT484825AWPDS	Juvenile Table	25" x 48" x 48"	110	\$1,917	\$1,805
	Causes Manla T-L	lo					
	Square Maple Tab		A al   L T - L L -	2011 11 2011 11 2011	110	44 7/0	44 / 50
		ABMT303029AWPDS ABMT303027AWPDS		29" x 30" x 30"	110	\$1,760 \$1,760	\$1,653 \$1,653
		ABMT303027AWPDS		27-1/2" x 30" x 30" 25" x 30" x 30"	110 110	\$1,760 \$1,760	\$1,653 \$1,653
							•
		ABMT363629AWPDS		29" x 36" x 36"	110	\$1,825	\$1,720 \$1,720
		ABMT363627AWPDS ABMT363625AWPDS		27-1/2" x 36" x 36" 25" x 36" x 36"	110 110	\$1,825 \$1,825	\$1,720 \$1,720
					110	\$1,825	·
	ADMIT 42 4220DW/DDC	ABMT424229AWPDS		29" x 42" x 42"	110	\$1,868	\$1,760
			Vouth Toble	27-1/2" x 42" x 42"	110	£4 O/O	\$1,760
	ABMT424227BWPDS	ABMT424227AWPDS			110	\$1,868	•
	ABMT424227BWPDS	ABMT424227AWPDS ABMT424225AWPDS		25" x 42" x 42"	110	\$1,868 \$1,868	\$1,760
	ABMT424227BWPDS ABMT424225BWPDS ABMT484829BWPDS	ABMT424225AWPDS ABMT484829AWPDS	Juvenile Table Adult Table	25" x 42" x 42" 29" x 48" x 48"	110 110	\$1,868 \$1,939	\$1,760 \$1,816
	ABMT424227BWPDS ABMT424225BWPDS ABMT484829BWPDS ABMT484827BWPDS	ABMT424225AWPDS	Juvenile Table Adult Table Youth Table	25" x 42" x 42"	110	\$1,868	\$1,760

#### **Optional Wood Curved Aprons for Tables**

An Apron is a 4"H x 1" thick, curved oak or maple piece of wood that is fitted between the legs of a table. The Apron is attached to the table using wood cleats that are screwed to the underside of the tabletop. These Aprons are optional and must be ordered separately.

Note: Aprons are not available for Trapezoid Shaped Tables or Pedestal Base Tables.

0ak	Maple		Wt.	Oak	Maple
Catalog No.	Catalog No.	Description	(lbs.)	Price	Price
ABOAK36RDCAS	ABMAK36RDCAS	For 36" Diameter Table	5	\$294	\$313
ABOAK42RDCAS	ABMAK42RDCAS	For 42" Diameter Table	5	\$346	\$365
ABOAK48RDCAS	ABMAK48RDCAS	For 48" Diameter Table	5	\$370	\$396
ABOAK60RDCAS	ABMAK60RDCAS	For 60" Diameter Table	8	\$408	\$438
ADOAKAAAAA	ADMANAGAGAG	For 2011 Courses Table	F	¢207	<b>¢224</b>
ABOAK3030CAS	ABMAK3030CAS	For 30" Square Table	5	\$307	\$321
ABOAK3636CAS	ABMAK3636CAS	For 36" Square Table	5	\$294	\$313
ABOAK4242CAS	ABMAK4242CAS	For 42" Square Table	5	\$346	\$365
ABOAK4848CAS	ABMAK4848CAS	For 48" Square Table	5	\$371	\$396
ABOAK3060CAS	ABMAK3060CAS	For 30" x 60" Table	5	\$358	\$379
ABOAK3072CAS	ABMAK3072CAS	For 30" x 72" Table	5	\$397	\$422
ABOAK3090CAS	ABMAK3090CAS	For 30" x 90" Table	5	\$433	\$463
ABOAK3660CAS	ABMAK3660CAS	For 36" x 60" Table	8	\$365	\$389
ABOAK3672CAS	ABMAK3672CAS	For 36" x 72" Table	8	\$404	\$433
ABOAK3690CAS	ABMAK3690CAS	For 36" x 90" Table	10	\$442	\$474
ABOAK4872CAS	ABMAK4872CAS	For 48" x 72" Table	10	\$506	\$458
ABOAK4890CAS	ABMAK4890CAS	For 48" x 90" Table	12	\$465	\$502
ADUAN409UCAS	ADIVIAN489UCAS	rui 40 x 90 Table	12	<b>Ф40</b> Э	\$302

#### **TABLETOP**

Tabletop is 1-3/16" thick, 3-ply 45# density particle board, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Edges are solid Northern-grown Red Oak or maple. The top receives a solid drop edge band of Northern-grown Red Oak or maple, 5/8" x 1-5/8" thick, radiused 1/2" to form a waterfall shape.

Note: Standing Height Tables are Apron construction.

#### **TABLETOP SUPPORT**

For maximum rigidity, rectangular tables 60" or more wide receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 72" or wider receive two extra legs located under the center of the table to provide added support.

Note: Center support legs will be glued up, 2-1/4" square solid Northern-grown Red Oak or maple. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are chamfered 1/8". Each leg has a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two thirds of the glide.

#### **PRIVACY PANEL**

The privacy panel consists of end panels and a back constructed of 3/4" thick veneered particleboard 6"H x 10-7/16"D. The front edges of the privacy panel end panels receive a 3" radius. Exposed panel edges are banded with 1.6mm solid oak or maple. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the privacy panel panels. The privacy panel is finished to match the table and designed to obscure wires exiting computer equipment, to eliminate incidental tampering and create defined patron space.

#### **LEG WITHOUT APRON**

The leg is glued up 2-1/4" solid Northern-grown Red Oak or maple. The leg is molded into a triangle shape with the front face receiving a 2" radius and outside edges receiving a 1/2" radius that tapers to a 90° right angle. A 1/4" wide x 1/16" deep vein line is routed 2" up from the bottom of the leg. A 1/8" chamfer is placed at the bottom of the leg. Each leg receives a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersink boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold rolled steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The assembled leg is attached to the tabletop by five 5/16" x 1" machine bolts engaging internal and external threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended table edge band.

#### LEG WITH APRON

Leg is glued up 2-1/4" solid Northern-grown Red Oak or maple. The leg is molded into a triangle shape with the front face receiving a 2" radius and outside edges receiving a 1/2" radius that tapers to a 90° right angle. A 1/4" wide x 1/16" deep vein line is routed 2" up from the bottom of the leg. A 1/8" chamfer is placed at the bottom of the leg. Each leg receives a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut which is further recessed into the leg by means of a countersink boring that accepts the upper two-thirds of the glide. Legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16" - 18 hex head bolts which pass through the bracket and engage threaded bushings, embedded into the leg and cross-pinned with a 3/16" diameter steel pin.

APRON (Standard for Standing Height, Optional for Sitting Height) A 4"H x 1" thick solid Northern-grown Red Oak or maple apron is fitted between the legs and behind the extended tabletop edge band. Starting 1/2" in from each end, the apron receives a radius that peaks at 2" in the center. The ends of each apron receive a 1/2" radius. Aprons are attached to the table by means of wood cleats and formed 14-gauge steel corner brackets. Aprons on round tables go straight between the legs.

#### LEG (CENTER)


Center support legs will be glued up, 2-1/4" square solid Northerngrown Red Oak or maple. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are chamfered 1/8". Each leg has a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The assembled leg is attached to the tabletop by five 5/16" x 1" machine bolts engaging internal and external threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended table edge band.


#### **ELECTRICAL**

Each position on an Information Access Table receives one 3" diameter grommet for wire passage and J-channel wire manager to hold excess wires. Grommets are ABS black plastic with notched removable cap. J-channel is 18-gauge steel with electrostatically applied black powder paint and is mounted to the underside of the tabletop.

#### **TABLETOP HEIGHT**

Standing Height: 39" (with Apron) Sitting Height: 27-1/2" (without Apron)





Abridge Drop Edge Band

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
One Position Computer Tables	ABOITG0243027RTWS	ABMITG0243027RTWS	Sitting Height	27-1/2" x 30" x 24"	80	\$1,156	\$1,201
	ABOITG0303027RTWS	ABMITG0303027RTWS	Sitting Height	27-1/2" x 30" x 30"	80	\$1,232	\$1,280
Two Position Computer Tables	ABOITG0246027RTWS	ABMITG0246027RTWS	Sitting Height	27-1/2" x 60" x 24"	80	\$1,642	\$1,708
	ABOITG0306027RTWS	ABMITG0306027RTWS	Sitting Height	27-1/2" x 60" x 30"	80	\$1,768	\$1,839
One Position Computer Table with 6"H Privacy Panel	ABOITGS243627RTWS	ABMITGS243627RTWS	Sitting Height	27-1/2" x 36" x 24"	70	\$1,431	\$1,546
	ABOITGS363627RTWS	ABMITGS363627RTWS	Sitting Height	27-1/2" x 36" x 36"	80	\$1,556	\$1,680
Two Position Computer Table with 6"H Privacy Panel	ABOITGS247227RTWS ABOITGS367227RTWS	ABMITGS247227RTWS ABMITGS367227RTWS	Sitting Height Sitting Height	27-1/2" x 72" x 24" 27-1/2" x 72" x 36"	150 150	\$1,909 \$2,075	\$2,073 \$2,241
Three Position Computer Table with 6"H Privacy Panel	ABOITGS249027RTWS	ABMITGS249027RTWS	Sitting Height	27-1/2" x 90" x 24"	180	\$2,560	\$2,778
	ABOITGS369027RTWS	ABMITGS369027RTWS	Sitting Height	27-1/2" x 90" x 36"	170	\$2,781	\$3,003

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

Note: Optional Wood Aprons for Computer Tables are located on page ABR 26.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
ABOITG0303039RTAS	ABMITG0303039RTAS	Standing Height	39" x 30" x 30"	85	\$1,344	\$1,404	One Position Computer Tables
ABOITGO306039RTAS	ABMITG0306039RTAS	Standing Height	39" x 60" x 30"	115	\$1,860	\$1,927	Two Position Computer Tables
ABOITGS363639RTAS	ABMITGS363639RTAS	Standing Height	39" x 36" x 36"	85	\$1,619	\$1,745	One Position Computer Table with 6"H Privacy Panel
ABOITGS367239RTAS	ABMITGS367239RTAS	Standing Height	39" x 72" x 36"	150	\$2,161	\$2,332	Two Position Computer Table with 6"H Privacy Panel
ABOITGS369039RTAS	ABMITGS369039RTAS	Standing Height	39" x 90" x 36"	180	\$2,896	\$3,127	Three Position Computer Table with 6"H Privacy Panel

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

Note: Optional Wood Aprons for Computer Tables are located on page ABR 26.

# The Abridge Collection

#### **Optional Wood Curved Aprons for Sitting Height Computer Tables**

An Apron is a 4"H x 1" thick, curved oak or maple piece of wood that is fitted between the legs of a table. The Apron is attached to the table using wood cleats that are screwed to the underside of the tabletop. These Aprons are optional and must be ordered separately.

Note: Curved Apron is Standard on Standing Height Tables.

0ak	Maple		Wt.	Oak	Maple
Catalog No.	Catalog No.	Description	(lbs.)	Price	Price
ABOAK2430CAS	ABMAK2430CAS	For 24" x 30" Table	5	\$290	\$302
ABOAK2436CAS	ABMAK2436CAS	For 24" x 36" Table	5	\$278	\$290
ABOAK2460CAS	ABMAK2460CAS	For 24" x 60" Table	5	\$340	\$356
ABOAK2472CAS	ABMAK2472CAS	For 24" x 72" Table	5	\$379	\$397
ABOAK2490CAS	ABMAK2490CAS	For 24" x 90" Table	8	\$415	\$435
ABOAK3030CAS	ABMAK3030CAS	For 30" Square Table	5	\$307	\$321
ABOAK3636CAS	ABMAK3636CAS	For 36" Square Table	5	\$358	\$379
ABOAK3060CAS	ABMAK3060CAS	For 30" x 60" Table	5	\$294	\$313
ABOAK3672CAS	ABMAK3672CAS	For 36" x 72" Table	8	\$404	\$433
ABOAK3690CAS	ABMAK3690CAS	For 36" x 90" Table	10	\$442	\$474

#### WORK SURFACE

Work surface is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The front edge of the work surface receives a drop edge band of Northern-grown Red Oak or maple, 5/8" x 1-5/8" thick with a 1/2" radius to form a waterfall shape. The back edge of the work surface has a black plastic strip, 1-1/2"W, which projects above the work surface 1/4" to act as a retainer.

Work surface is 27-1/2"D with an additional 1-1/2"W cord drop available in two widths: 48" and 36", and adjustable in heights to 27", 32" and 39". Workstation is of modular starter and adder design. Work surface is attached to end and intermediate panels by means of two metal 23" long "Z" brackets with 5/16" x #18 hex-head bolts engaging embedded internal and external threaded bushings. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end, intermediate and back panels with 3/4" x 3/4" steel, black painted angle brackets and black #8 screws.

#### **END PANEL**

End panel consists of a framed panel and plinth base assembly. The framed panel assembly consists of Northern-grown Red Oak or maple hardwood rails and stiles with a veneered panel. The panel is 3/4" thick plain-sliced slip-matched Northern-grown Red Oak or maple. The top rail is 2"H x 1" thick and side stiles are 1" x 1" with a 1" radius. The plinth base is composed of one piece of 5/4 solid Northern-grown Red Oak or maple 2-1/4"H x 1" thick. The plinth base receives a molded shape at the top which consists of a 1" radius ending in a 1/4"W reveal and is attached to the bottom of the frame panel assembly by means of three #8 x 3" long flat-head screws and wood glue. The bottom of the plinth receives two 7/8" diameter chrome adjustable glides located 1-1/4" from the plinth ends. End panel attaches to back panels by means of recessed metal fasteners and shoulder screws.

#### INTERMEDIATE PANEL

Intermediate panels are 1" thick, 3-ply 45# density particleboard core, with select plain-sliced slip-matched Northern-grown Red Oak or maple veneers. The panel will receive a 1.6mm solid oak or maple band on all four (4) sides. Each panel receives a 3" diameter egress grommet to provide for wire passage and two 7/8" diameter chrome adjustable glides located 1-1/4" from the ends. Intermediate panel attaches to back panels by means of recessed metal fasteners and shoulder screws.

#### **BACK PANEL**

Back panel is 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or maple face veneers. The top and bottom edge of the back panel receives 1.6mm solid oak or maple band. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The back panel on double-faced units receives a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### **SHELF**


A 12"D storage shelf, located under the work surface, extends the full width of the station.

#### **ELECTRICAL**

To hide excess wires, a 1-1/2" separation between the work surface and back panel is provided.

#### WORKING SPACE HEIGHTS

Adjustable at 27", 32" and 39"



**Abridge Drop Edge Band** 

Adder

Adder

		Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced Infor	mation Access	36" Wide Adju	ıstable Height V	Vorking Space	<u>ce</u>			
Workstations/Car	rels	ABOICSFS36S	ABMICSFS36S	S/F Starter	47-3/4" x 38" x 34-1/2"	85	\$2,098	\$2,408
		ABOICSFA36S	ABMICSFA36S	S/F Adder	47-3/4" x 37" x 34-1/2"	75	\$1,628	\$1,803
		48" Wide Adju	ıstable Height V	Vorking Space	<u>ce</u>			
2		ABOICSFS48S	ABMICSFS48S	S/F Starter	47-3/4" x 49-3/4" x 34-1/2"	90	\$2,230	\$2,537
		ABOICSFA48S	ABMICSFA48S	S/F Adder	47-3/4" x 49" x 34-1/2"	80	\$1,732	\$1,912
Starter								

Double-Faced Information Access	<u>36" Wide Adju</u>	<i>ıstable Height V</i> I	orking Spac	<u>e</u>			
Workstations/Carrels	ABOICDFS36S	ABMICDFS36S	D/F Starter	47-3/4" x 38" x 68"	140	\$3,808	\$4,270
	ABOICDFA36S	ABMICDFA36S	D/F Adder	47-3/4" x 37" x 68"	126	\$2,912	\$3,356
	48" Wide Adju	ıstable Height VI	orking Spac	<u>e</u>			
	ABOICDFS48S	ABMICDFS48S	D/F Starter	47-3/4" x 49-3/4" x 68"	150	\$4,133	\$4,727
	ABOICDFA48S	ABMICDFA48S	D/F Adder	47-3/4" x 49" x 68"	136	\$3,249	\$3,596
Starter	2						

Pinwheel Design	36" Wide Adjustable Height Working Space							
Information Access Workstations/Carrels	ABOICPIN36S	ABMICPIN36S	Pinwheel	47-3/4" x 75" x 75"	375	\$6,445	\$7,390	
	48" Wide Adju	ustable Height V	Vorking Space	2				
	ABOICPIN48S	ABMICPIN48S	Pinwheel	47-3/4" x 99" x 99"	425	\$6,979	\$7,927	

#### WORKSTATION

Workstation is of modular starter and adder design, with an overall height 35-1/4". Work surfaces are available in 36", 48", 73", 97", and 110" widths. A knee-space panel, located below the work surface, supports all work surfaces greater than 48"W. Work surface height is at 27-1/2" and depth is 22-1/2" with a 1-1/2"W cord drop. The work surface is attached to end and intermediate panels by means of two metal 16" long "Z" brackets with 5/16" x #18 hex-head bolts engaging embedded internal and external threaded bushings. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end, intermediate, and back panels with 1" x 1" steel, black painted angle brackets and black #8 screws.

#### **WORK SURFACE**

Work surface is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The front edge of the work surface receives a drop edge band of Northern-grown Red Oak or Maple, 5/8" x 1-5/8" thick with a 1/2" radius to form a waterfall shape. The back edge of the work surface has a plastic black strip, 1-1/2"W, which projects above the work surface 1/4" to act as a retainer.

#### **END PANEL**

End panel consists of a framed panel assembly. The framed panel assembly consists of Northern-grown Red Oak or Maple hardwood rails and stiles with a veneered panel. The panel is 3/4" thick plain-sliced slip-matched Northern-grown Red Oak or Maple routed on two (2) edges. The top and bottom rails are 2"H x 1" thick and side bands are 1" x 1" with a 1" radius. The bottom rail is screwed on using #8 x 3" long flat-head screws and wood glue. The side bands receive a 1/4" x 1/16" vein line 2" up from the bottom of the panel. The bottom of the end panel receives two 7/8" diameter chrome adjustable glides located 1-1/2" from the ends. End panel attaches to back panels by means of recessed metal fasteners and shoulder screws.

#### INTERMEDIATE PANEL

Intermediate panel is 1" thick, 3-ply 45# density particleboard core, with select plain sliced slip matched Northern-grown Red Oak or Maple veneers. The panel receives a 1" x 1.6mm solid oak or maple band. Each panel receives a 3" diameter egress grommet to provide for wire passage and two 7/8" diameter chrome adjustable glides located 1-1/2" from the ends. Intermediate panel attaches to back panels by means of recessed metal fasteners and shoulder screws.

#### **BACK PANEL/PARTITION**

Back panel is 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or Maple face veneers. The top and bottom edge of the back panel receives 1.6mm solid oak or maple band. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The partition on double-faced units receives a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### **SHELF**


Shelf is 3/4" thick x 5"D 45# density particleboard core with face veneers of select Northern-grown Red Oak or Maple. Shelf is banded on the front edge with a 1.6mm solid oak or maple band. The shelf is attached to end and intermediate panels with 1" x 1" steel, black painted angle brackets and black #8 screws. Back corners of shelf have a 3" x 3" cutout to allow for the passage of electrical cords. The shelf is positioned 11-13/16" below the bottom of the work surface.

#### WIRE MANAGEMENT DOOR

The wire management door is positioned between the bottom of the work surface and the shelf and is designed to form a concealed wire management channel 5"D x 11-5/16"H. The door is 1/4" thick with select oak or maple face veneers. The door slides in two aluminum tracks, one that is attached to the bottom of the work surface while the other is attached to the top of the shelf.

#### **KNEE-SPACE PANEL**

All 72" and 96"W workstations, as well as functional corner units, have a knee-space panel positioned under the work surface for additional work-surface support. Units 110"W have two knee-space panels. The knee-space panel is 1" thick, 3 ply 45# density particleboard core with select Northern-grown Red Oak or Maple face veneers. The panel is banded on exposed edges with a 1.6mm solid oak or maple band. The knee-space panel is attached to the back panel using a 1" square, solid oak or maple post. Panels attach to the post using recessed metal fasteners and shoulder screws. The knee-space panel is angled in the back to create a space to allow passage of electrical and data cords. The knee-space panel receives one 7/8" diameter chrome adjustable glide.



**Abridge Drop Edge Band** 


# The Abridge Collection


	Oak Maple Catalog No. Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced One-Position	36" Wide Working Space					
	ABOMMSSF1S36S ABMMMSSF1S3 ABOMMSSF1A36S ABMMMSSF1A3		35-1/4" x 38" x 26" 35-1/4" x 37" x 26"	130 100	\$2,128 \$1,456	\$2,282 \$1,585
Starter	48" Wide Working Space					
	ABOMMSSF1S48S ABMMMSSF1S4	48S One-Position S/F Starter	35-1/4" x 50" x 26"	155	\$2,288	\$2,461
	ABOMMSSF1A48S ABMMMSSF1A4	48S One-Position S/F Adder	35-1/4" x 49" x 26"	125	\$1,568	\$1,709
Adder						
D II 5 10 D "						
Double-Faced One-Position	36" Wide Working Space	0. D. III. D./EQL.	05.4 /411. 0011. 5411	045	40.050	40.500
	ABOMMSDF1S36S ABMMMSDF1S3 ABOMMSDF1A36S ABMMMSDF1A3		35-1/4" x38" x51" 35-1/4" x37" x51"	215 155	\$3,352 \$2,464	\$3,588 \$2,730
	48" Wide Working Space					
	ABOMMSDF1S48S ABMMMSDF1S4		35-1/4" x 50" x 51"	255	\$3,564	\$3,842
Starter	ABOMMSDF1A48S ABMMMSDF1A4	48S One-Position D/F Adder	35-1/4" x 49" x 51"	195	\$2,688	\$2,924
Adder						
Single-Faced Two-Position	36" Wide Working Space					
	ABOMMSSF2S36S ABMMMSSF2S3 ABOMMSSF2A36S ABMMMSSF2A3		35-1/4" x 75" x 26" 35-1/4" x 74" x 26"	195 165	\$2,980 \$2,296	\$3,226 \$2,516
	48" Wide Working Space					
Charles	ABOMMSSF2S48S ABMMMSSF2S4	18S Two-Position S/F Starter	35-1/4" x 99" x 26"	235	\$3,308	\$3,592
Starter	ABOMMSSF2A48S ABMMMSSF2A4	18S Two-Position S/F Adder	35-1/4" x 98" x 26"	205	\$2,464	\$2,703
Adder						
Double-Faced Two-Position	36" Wide Working Space					
	ABOMMSDF2S36S ABMMMSDF2S3	36S Two-Position D/F Starter	35-1/4" x 75" x 51"	330	\$4,770	\$5,118
	ABOMMSDF2A36S ABMMMSDF2A3		35-1/4" x 74" x 51"	270	\$3,883	\$4,212
	48" Wide Working Space					
	ABOMMSDF2S48S ABMMMSDF2S4	48S Two-Position D/F Starter	35-1/4" x 99" x 51"	410	\$5,186	\$5,612
Starter	ABOMMSDF2A48S ABMMMSDF2A4		35-1/4" x 98" x 51"	155	\$4,305	\$4,675
Adder		sh (Table 1) and High-Pressure La ils can be found on page GEN 4.	minate (Table 2).			

# The Abridge Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Wol	rking Space						Single-Faced Three-Position
	S ABMIMMSSF3S36S	Three-Position S/F Starter	35-1/4" x 112" x 26"	260	\$3,862	\$4,197	
ABOMMSSF3A36S	S ABMIMMSSF3A36S	Three-Position S/F Adder	35-1/4" x 111" x 26"	230	\$3,024	\$3,327	Starter

<u>36" Wide Working Space</u>						Double-Faced Three-Position
ABOMMSDF3S36S ABMMMSDF3S36S ABOMMSDF3A36S ABMMMSDF3A36S	Three-Position D/F Starter Three-Position D/F Adder	35-1/4" x112" x51" 35-1/4" x111" x51"	445 385	\$6,151 \$5,489	\$6,612 \$6,184	
						Starter
						Adder
		r 35-1/4"x62"x26"	225	\$4,019	\$4,358	90° Functional Corner Uni





#### **TABLETOP**

Tabletop is 1-3/16" thick, 3-ply 45# density particle board, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Edges are solid Northern-grown Red Oak or maple. Top receives a Northern-grown Red Oak or maple external solid flush edge band 5/8" x 1-3/16" thick, radiused 1/2" to form a waterfall shape.

#### **PRIVACY PANEL**


Privacy panels consist of two panels constructed of 3/4" thick Northern-grown Red oak or maple veneered particleboard. The two panels are 6"H x 45"W and intersect in the middle of the tabletop to form an "X". Privacy panels receive keyways and shoulder screws for assembly. The front edge of the privacy panel end panel receives a 3" radius. Exposed panel edges are banded with 1.6mm solid oak or maple. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the privacy panel. Panels are finished to match the table edge band. Privacy panel is designed to obscure wires exiting computer equipment, to eliminate incidental tampering and create defined patron space.

#### **TABLE BASE**

Table base is panel and post construction. Posts are 1-3/4" square, with a 3/4"W x 1/8"D groove to receive panels. Each post has a 1-1/4" diameter, adjustable glide. Base back and vertical panels are 3/4" 3-ply 45# Northern-grown Red Oak or Maple veneered particleboard. Back panels are 23-1/2"H with a 4" base clearance for wire management access. Vertical panels are 26-5/16"H and receive two rubber cushioned chrome glides per panel. Base is assembled using metal to metal hardware fasteners and is attached to tabletop using 12" x 3/4" x 3/4" wood cleats.

#### **WORKING SPACE HEIGHT**


Fixed at 27" with a grommet in each position for wire passage.



Abridge Flush Edge Band

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Square Working Space	ABOPAC4PS27GSS	ABMPAC4PS27GSS	Square with Privacy Panel	33-1/2" x 48-1/4" x 48-1/4"	360	\$2,678	\$3,065
	ABOPAC4PS27GOS	S ABMPAC4PS27GOS	Square without Privacy Panel	27-1/2" x 48-1/4" x 48-1/4"	350	\$2,342	\$2,729





#### WORK SURFACE

Work surface are 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The desk top receives a solid Northern-grown Red Oak or maple flush edge band 5/8" x 1-3/16" thick, radiused 1/2" to form a waterfall shape on the patron side. Edge band is applied to the desktop after the laminate and backer sheets are applied, constituting an external edge band.

#### **VERTICAL PANEL**

Vertical panel is 1" thick, with select plain-sliced slip-matched Northern-grown Red Oak or maple veneers. The panel receives a 1" x 1.6mm solid oak or maple band. Each panel receives a 3" diameter egress grommet to provide for wire passage and two 7/8" diameter chrome adjustable glides located 1-1/4" from the ends. The intermediate panel attaches to back panels by means of recessed metal fasteners and shoulder screws.

#### **BACK PANEL**

Back panel is 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or maple face veneers. The top and bottom edges of the back panel receive 1.6mm solid oak or maple bands. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The back panel receives a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### ELECTRICAL ACCESS DOOR

Access door is 3/4" thick and comprised of select face veneers of Northern-grown Red Oak or maple over a particleboard core. Panel is externally banded on all four sides with a 1.6mm solid oak or maple edge band. Access door has a full-length hinge and lock and can be located in any one of the back panels on the station.

#### CPU/UTILITY SHELF

Shelf is 3/4" thick x 15"D, 7-ply veneer-core oak or maple plywood construction. Front edge receives a 1/2" solid oak or maple band.

#### **CENTER CAP**

Cap is constructed of 3/4" particleboard core with plastic and backer. Available in full-hexagon, half-hexagon, or square configuration; the cap closes the center opening by mounting at the top rear edge of end panels on systems arranged in full- or half-hexagon configuration.


#### **AVAILABLE WORKING SPACE**

Depth of monitor and keyboard combined cannot exceed 29".

#### **WORKING SPACE HEIGHTS**

Working space is adjustable to: Standing Height: 39"

ADA Height: 32" Sitting Height: 27"



Abridge Flush Edge Band

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
ABOPAC6PAHS	ABMPAC6PAHS	Six position with angular tops.	42-1/4" x 99-1/4" x 99-1/4"	629	\$9,622	\$10,963	Six Position PAC Station
ABOPAC4PAHS	ABMPAC4PAHS	Four position with angular tops.	42-1/4" x 75-1/2" x 75-1/2"	510	\$8,200	\$8,764	Four Position PAC Station
ABOPAC3PAHS	ABMPAC3PAHS	Three position with angular tops. Composed of one sta	42-1/4" x 99-1/2" x 47-1/2" rter unit and two adder units.	401	\$6,002	\$6,941	Three Position PAC Station

#### **WORK SURFACE**

Work surface is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The exposed work surface edge receives a Northern-grown Red Oak or maple drop edge band 5/8" x 1-3/16" thick with a 1/2" radius to form a waterfall shape. The back edge of the work surface has a metal black strip, 1-1/2"W, which projects above the work surface 1/4" to act as a retainer.

#### **END PANEL**

End panel consists of a framed panel and plinth base assembly. The framed panel assembly consists of solid Northern-grown Red Oak or maple hardwood rails and stiles with a veneered panel. The panel is 3/4" thick plain sliced slip matched Northern grown Red Oak or maple routed on three sides. The top rail is 2"H x 1" thick and side stiles are 1" x 1" with a 1" radius. The plinth base is composed of one piece of 5/4 solid Northern-grown Red Oak or maple 2-1/4"H x 1" thick. The plinth base receives a molded shape at the top which consists of a 1" radius ending in a 1/4"W reveal and is attached to the bottom of the frame panel assembly by means of three #8 x 3" long flat-head screws and wood glue. The bottom of the plinth receives two 7/8" diameter chrome adjustable glides located 1-1/4" from the plinth ends. End panel attaches to back panels by means of recessed metal fasteners and shoulder screws.

#### **BACK PANEL**

Back panel is select Northern-grown Red Oak or maple face veneer 3/4" thick, 3–ply 45# density particleboard core of. The top and bottom edge of the back panel receives 1.6mm solid oak or maple band. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The back panel on double-face units receives a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### SHELF (MONITOR)


Monitor shelf is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Laminate has a lo-glare finish resistant to scratches, fading and staining that meets or exceeds NEMA standards. The exposed work surface edge receives a Northern-grown Red Oak or maple flush edge band 5/8" x 1-3/16" thick with a 1/2" radius to form a waterfall shape. Shelf receives one 3" diameter grommet for wire passage.

#### SHELF (PRINTER)

Printer shelf shall have a fascia, 1-3/4"H x 3/4" thick of solid oak banded to a 3/4" 3-ply 45# density particleboard core of specified depth. The top front corner shall have a 1/8" radius. Glue blocks will also be provided at the intersection of the fascia and top panel. Printer shelf is mounted as pull out shelf on 100# capacity nylon glides.

#### SHELF (FIXED)

Shelf is constructed of 3-ply 45# density particleboard core, with Northern-grown Red Oak plain sliced face veneer or maple plain sliced face veneer. Exposed edges receive a 1.6mm thick, solid-oak or maple edge band.



Abridge Drop Edge Band

	0ak	Maple			Wt.	0ak	Maple
	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
Self Check Out Station	ABOSCS3236433	S ABMSCS323643S	Self Check Out Station	43-1/2" x 36" x 32"	220	\$1.930	\$2.397



#### **END OF RANGE PAC STATION - Free Standing**


Unit is designed to fit at the end of a double-faced shelving range. Standard tops are 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The desk top receives a solid Northern-grown Red Oak or maple flush edge band 5/8" x 1-3/16" thick, radiused 1/2" to form a waterfall shape. Edge band is applied to the top after the laminate and backer sheets are applied, constituting an external edge band.

End panel consists of a framed panel and plinth base assembly. The framed panel assembly consists of Northern-grown Red Oak or maple hardwood rails and stiles with a veneered panel. The panel is 34" thick plain-sliced slip-matched Northern-grown Red Oak or maple routed on two sides and splined. The top rail is 2"H x 1" thick and side stiles are 1" x 1" with a 1" radius. The plinth base is composed of one piece of 5/4 solid Northern-grown Red Oak or maple 2-1/4" H x 1" thick. The plinth base receives a molded shape at the top which consists of a 1" radius ending in a 1/4" W reveal and is attached to the bottom of the frame panel assembly by means of three #8 x 3" long flat-head screws and wood glue. The bottom of the plinth receives two 7/8" diameter chrome adjustable glides located 1-1/4" from the plinth ends. End panel attaches to back panels by means of recessed metal fasteners and shoulder screws. Inside faces of end panels allow for shelf adjustment on 32mm center. Back panel is 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or maple face veneers. The top and bottom edge of the back panel receives 1.6mm solid oak or maple band. Unit has two full-depth fixed shelves with 3" diameter grommets and one pullout shelf for the keyboard. Space above the fixed shelves is 11".

#### **END OF RANGE PAC STATION - Panel Mounted**

This unit is designed to be attached to a double-faced end panel. Standard top is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The top receives a solid Northern-grown Red Oak or maple flush edge band 58" x 1-3/16" thick, radiused 1/2" to form a waterfall shape on the front and two sides with a 1/4" band on the back edge. Edge band is applied to the top after the laminate and backer sheets are applied, constituting an external edge band.

All panels are 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or maple face veneers. The base of the unit consists of tapered end panels, a back panel, an access panel for wire management and a removable front cover panel that provides access to the wire management. The back and access panel are 9-7/8" wide. The back panel receives a grommet at the base and the access panel receives a 6"wide opening. The front cover is solid and attaches to the access panel.




Abridge Flush Edge Band

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
ABOPACEOR39S	ABMPACEOR39S	Free-Standing End-of-Range	39" x 23-1/2" x 20"	110	\$1,893	\$2,117	End-Of-Range Station
ABOPACEOR32S	ABMPACEOR32S	Free-Standing End-of-Range	32" x 23-1/2" x 20"	100	\$1,725	\$1,968	
ABOPACEPM39S	ABMPACEPM39S	Panel Mounted End-of-Range	39" x 22-1/2" x 18-1/8"	80	\$1,053	\$1,143	
ABOPACEPM32S	ABMPACEPM32S	Panel Mounted End-of-Range	32" x 22-1/2" x 18-1/8"	70	\$930	\$1,011	
		End Panel Mounted PAC Station	for Wood or Steel Shelving End Pa	anels.	6		
		Note: Shelving End Panels are o	ordered separately and units MUS	T be attached		THE	

#### **DICTIONARY STAND**

Standard tops are 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The desk top receives a solid Northern-grown Red Oak or maple flush external edge band 5/8" x 1-3/16" thick, radiused 1/2" to form a waterfall shape on the front and back. A 5/8" x 5/8" book retainer is positioned along the bottom edge of sloped top. End panel consists of a framed panel and plinth base assembly similar to all other Abridge end panels. Inside faces of end panels allow for shelf adjustment on 32mm center. Back panel is 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or maple face veneers. The top and bottom edge of the back panel receives 1.6mm solid oak or maple band. Bottom shelf is stationary.



Abridge Flush Edge Band

#### ATLAS STAND

Standard tops are 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction and receives a solid Northern-grown Red Oak or maple flush external edge band 5/8" x 1-3/16" thick, radiused 1/2" to form a waterfall shape on the front and back. A 5/8" x 5/8" book retainer is positioned along the bottom edge of sloped top. End panel consists of a framed panel and plinth base assembly similar to all other Abridge end panels. The bottom of the plinth receives two 7/8" diameter chrome adjustable glides located 1-1/4" from the plinth ends. Back panel is 3/4" thick, 45# density particleboard core of select Northern-grown Red Oak or maple face veneers. The top and bottom edge of the back panel receives 1.6mm solid oak or maple band. Each unit has five pullout shelves on nylon rollers. Stops on shelves prevent accidental removal. Shelves are 25-3/4"W x 23-7/8"D, with 3" between shelves. Children's height unit contains four pull-out shelves with 2-1/2" between shelves.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Dictionary Stand	ABODCS162545S	ABMDCS162545S	Adult Dictionary Stand	45-1/2" x 24-3/8" x 16-1/2"	210	\$1,811	\$1,974
	ABODCS162538S	ABMDCS162538S	Youth Dictionary Stand	38-1/2" x 24-3/8" x 16-1/2"	200	\$1,811	\$1,974
Atlas Stand	ABOATS293045S	ABMATS293045S	Adult Atlas Stand	45-1/2" x 28-3/8" x 29"	250	\$3,223	\$3,513
	ABOATS293038S	ABMATS293038S	Youth Atlas Stand	38-1/2" x 28-3/8" x 29"	240	\$3,223	\$3,513

0ak	Maple			Oak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE UN	IIT				
ABOCTW10SFC1S	ABMCTW10SFC1S	10"D, Single-Faced	11	\$277	\$291
ABOCTW12SFC1S	ABMCTW12SFC1S	12"D, Single-Faced	14	\$281	\$295
ABOCTW20DFC1S	ABMCTW20DFC1S	20"D, Double-Faced	23	\$393	\$413
ABOCTW24DFC1S	ABMCTW24DFC1S	24"D, Double-Faced	27	\$438	\$460
To Cover TWO UN	<i>IITS</i>				
ABOCTW10SFC2S	ABMCTW10SFC2S	10"D, Single-Faced	22	\$366	\$384
ABOCTW12SFC2S	ABMCTW12SFC2S	12"D, Single-Faced	28	\$389	\$408
ABOCTW20DFC2S	ABMCTW20DFC2S	20"D, Double-Faced	46	\$551	\$578
ABOCTW24SFC2S	ABMCTW24SFC2S	24"D, Double-Faced	54	\$693	\$727
To Cover THREE I	<u>UNITS</u>				
ABOCTW10SFC3S	ABMCTW10SFC3S	10"D, Single-Faced	33	\$478	\$502
ABOCTW12SFC3S	ABMCTW12SFC3S	12"D, Single-Faced	42	\$510	\$536
ABOCTW20DFC3S	ABMCTW20DFC3S	20"D, Double-Faced	69	\$695	\$729
ABOCTW24DFC2S	ABMCTW24DFC2S	24"D, Double-Faced	81	\$733	\$770
To Cover FOUR U	<u>NITS</u>				
ABOCTW10SFC4S	ABMCTW10SFC4S	10"D, Single-Faced	44	\$730	\$767
ABOCTW12SFC4S	ABMCTW12SFC4S	12"D, Single-Faced	56	\$775	\$814
ABOCTW20DFC4S	ABMCTW20DFC4S	20"D, Double-Faced	92	\$1,087	\$1,142
ABOCTW24SFC4S	ABMCTW24SFC4S	24"D, Double-Faced	108	\$1,170	\$1,228
To Cover FIVE UN	<u>IITS</u>				
ABOCTW10SFC5S	ABMCTW10SFC5S	10"D, Single-Faced	55	\$843	\$886
ABOCTW12SFC5S	ABMCTW12SFC5S	12"D, Single-Faced	70	\$899	\$944
ABOCTW20DFC5S	ABMCTW20DFC5S	20"D, Double-Faced	115	\$1,245	\$1,307
ABOCTW24DFC5S	ABMCTW24DFC5S	24"D, Double-Faced	135	\$1,426	\$1,497
To Cover SIX UNI	<u>TS</u>				
ABOCTW10SFC6S	ABMCTW10SFC6S	10"D, Single-Faced	66	\$953	\$1,001
ABOCTW12SFC6S	ABMCTW12SFC6S	12"D, Single-Faced	84	\$1,020	\$1,071
ABOCTW20DFC6S	ABMCTW20DFC6S	20"D, Double-Faced	138	\$1,389	\$1,458
ABOCTW24DFC6S	ABMCTW24DFC6S	24"D, Double-Faced	162	\$1,464	\$1,538
To Cover SEVEN	<u>UNITS</u>				
ABOCTW10SFC7S	ABMCTW10SFC7S	10"D, Single-Faced	77	\$1,229	\$1,291
ABOCTW12SFC7S	ABMCTW12SFC7S	12"D, Single-Faced	98	\$1,303	\$1,368
ABOCTW20DFC7S	ABMCTW20DFC7S	20"D, Double-Faced	161	\$1,780	\$1,869
ABOCTW24DFC7S	ABMCTW24DFC7S	24"D, Double-Faced	189	\$1,902	\$1,997
To Cover EIGHT U	<u>INITS</u>				
ABOCTW10SFC8S	ABMCTW10SFC8S	10"D, Single-Faced	88	\$1,319	\$1,385
ABOCTW12SFC8S	ABMCTW12SFC8S	12"D, Single-Faced	112	\$1,409	\$1,479
ABOCTW20DFC8S	ABMCTW20DFC8S	20"D, Double-Faced	184	\$1,941	\$2,038
ABOCTW24DFC8S	ABMCTW24DFC8S	24"D, Double-Faced	216	\$2,156	\$2,264
To Cover NINE UI	<u>VITS</u>				
ABOCTW10SFC9S	ABMCTW10SFC9S	10"D, Single-Faced	99	\$1,432	\$1,503
ABOCTW12SFC8S	ABMCTW12SFC9S	12"D, Single-Faced	126	\$1,530	\$1,606
ABOCTW20DFC8S	ABMCTW20DFC9S	20"D, Double-Faced	207	\$2,085	\$2,189
ABOCTW24DFC8S	ABMCTW24DFC9S	24"D, Double-Faced	243	\$2,196	\$2,306

**Note:** Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

# The Abridge Collection

Oak	Maple			Oak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE UI					
ABOCTS10SFC1S	ABMCTS10SFC1S	10"D, Single-Faced	11	\$302	\$317
ABOCTS12SFC1S	ABMCTS12SFC1S	12"D, Single-Faced	14	\$304	\$319
ABOCTS20DFC1S	ABMCTS20DFC1S	20"D, Double-Faced	23	\$425	\$446
ABOCTS24DFC1S	ABMCTS24DFC1S	24"D, Double-Faced	27	\$478	\$502
To Cover TWO U	<u>NITS</u>				
ABOCTS10SFC2S	ABMCTS10SFC2S	10"D, Single-Faced	22	\$396	\$416
ABOCTS12SFC2S	ABMCTS12SFC2S	12"D, Single-Faced	28	\$421	\$442
ABOCTS20DFC2S	ABMCTS20DFC2S	20"D, Double-Faced	46	\$599	\$629
ABOCTS24SFC2S	ABMCTS24SFC2S	24"D, Double-Faced	54	\$751	\$788
To Cover THREE	UNITS				
ABOCTS10SFC3S	ABMCTS10SFC3S	10"D, Single-Faced	33	\$517	\$543
ABOCTS12SFC3S	ABMCTS12SFC3S	12"D, Single-Faced	42	\$554	\$582
ABOCTS20DFC3S	ABMCTS20DFC3S	20"D, Double-Faced	69	\$755	\$793
ABOCTS24DFC3S	ABMCTS24DFC2S	24"D, Double-Faced	81	\$794	\$832
ADUC1324DFC23	ADIVICT324DFG23	24 D, Double-Faceu	01	\$174	\$03Z
To Cover FOUR L					
ABOCTS10SFC4S	ABMCTS10SFC4S	10"D, Single-Faced	44	\$796	\$836
ABOCTS12SFC4S	ABMCTS12SFC4S	12"D, Single-Faced	56	\$843	\$886
ABOCTS20DFC4S	ABMCTS20DFC4S	20"D, Double-Faced	92	\$1,125	\$1,181
ABOCTS24SFC4S	ABMCTS24SFC4S	24"D, Double-Faced	108	\$1,271	\$1,335
To Cover FIVE U	<u>VITS</u>				
ABOCTS10SFC5S	ABMCTS10SFC5S	10"D, Single-Faced	55	\$911	\$957
BOCTS12SFC5S	ABMCTS12SFC5S	12"D, Single-Faced	70	\$972	\$1,026
ABOCTS20DFC5S	ABMCTS20DFC5S	20"D, Double-Faced	115	\$1,353	\$1,421
BOCTS24DFC5S	ABMCTS24DFC5S	24"D, Double-Faced	135	\$1,548	\$1,625
o Cover SIX UN	ITS				
BOCTS10SFC6S	ABMCTS10SFC6S	10"D, Single-Faced	66	\$1,033	\$1,085
BOCTS12SFC6S	ABMCTS12SFC6S	12"D, Single-Faced	84	\$1,033 \$1,112	\$1,063
BOCTS 23FC6S	ABMCTS20DFC6S	20"D, Double-Faced	138	\$1,112 \$1,509	\$1,100 \$1,585
BOCTS24DFC6S		24"D, Double-Faced	162		
DOC1324DFC03	ABMCTS24DFC6S	24 D, DOUNIE-FACEU	102	\$1,590	\$1,669
To Cover SEVEN		10110 01 1		40	
ABOCTS10SFC7S	ABMCTS10SFC7S	10"D, Single-Faced	77	\$1,311	\$1,376
ABOCTS12SFC7S	ABMCTS12SFC7S	12"D, Single-Faced	98	\$1,401	\$1,470
ABOCTS20DFC7S	ABMCTS20DFC7S	20"D, Double-Faced	161	\$1,949	\$2,046
ABOCTS24DFC7S	ABMCTS24DFC7S	24"D, Double-Faced	189	\$2,068	\$2,171
o Cover EIGHT	<u>UNITS</u>				
ABOCTS10SFC8S	ABMCTS10SFC8S	10"D, Single-Faced	88	\$1,432	\$1,503
ABOCTS12SFC8S	ABMCTS12SFC8S	12"D, Single-Faced	112	\$1,530	\$1,607
ABOCTS20DFC8S	ABMCTS20DFC8S	20"D, Double-Faced	184	\$2,107	\$2,213
ABOCTS24DFC8S	ABMCTS24DFC8S	24"D, Double-Faced	216	\$2,343	\$2,460
To Cover NINE U	NITS				
ABOCTS10SFC9S	ABMCTS10SFC9S	10"D, Single-Faced	99	\$1,553	\$1,630
ABOCTS12SFC8S	ABMCTS12SFC9S	12"D, Single-Faced	126	\$1,667	\$1,749
ABOCTS20DFC8S	ABMCTS20DFC9S	20"D, Double-Faced	207	\$2,264	\$2,377
ABOCTS24DFC8S	ABMCTS24DFC9S	24"D, Double-Faced	243	\$2,385	\$2,504
	.15.110102751073	= 1 D <sub>1</sub> Double 1 docu	2.10	ψ <u>2</u> ,000	Ψ2,007

**Note:** Edge Band on long side only. Tops are designed to be inset betweend end panels. If edge bands are desired on short edges, please enter the part as a modification and specify which bands to be included.


To ensure that tops for steel shelving work with each manufacturer and top method, please specify the exact width and depth of tops. Add 15% for HPL on top and bottom (Steel Shelving ONLY).

#### **END PANELS**

End panel consists of a framed panel and plinth base assembly. The framed panel assembly consists of Northern-grown Red Oak or Maple hardwood rails and stiles with a veneered panel. The panel is 3/4" thick plain sliced slip matched Northern-grown Red Oak or maple routed on two sides. The top rail is 2"H x 1" thick and side stiles are 1" x 1" with a 1" radius. The plinth base is composed of one piece of 5/4 solid Northern grown Red Oak or maple 2-1/4"H x 1" thick. The plinth base receives a molded shape at the top which consists of a 1" radius ending in a 1/4"W reveal and is attached to the bottom of the frame panel assembly by means of three #8 x 3" long flat-head screws and wood glue. End panels are not machined. No fastening hardware is provided with end panels.

End panels for steel shelving with continuous tops or canopy top inset are designed to have the canopy top "inset" between the end panels.

Note: Exact height and depth of panel must be specified when ordering.



**End Panel with Canopy Top Inset** 

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price	
AB0EPSSFP4313S	ABMEPSSFP4313S	43-3/4" x 13-7/8"	14	\$434	\$456	Single-Faced End Panels
ABOEPSSFP4315S	ABMEPSSFP4315S	43-3/4" x 15-7/8"	16	\$445	\$467	950
ABOEPSSFP6713S	ABMEPSSFP6713S	67-3/4" x 13-7/8"	21	\$496	\$521	
ABOEPSSFP6715S	ABMEPSSFP6715S	67-3/4" x 15-7/8"	26	\$513	\$539	
AB0EPSSFP7913S	ABMEPSSFP7913S	79-3/4" x 13-7/8"	25	\$556	\$584	
ABOEPSSFP7915S	ABMEPSSFP7915S	79-3/4" x 15-7/8"	30	\$575	\$603	
ABOEPSSFP8513S	ABMEPSSFP8513S	85-3/4" x 13-7/8"	28	\$589	\$618	
ABOEPSSFP8515S	ABMEPSSFP8515S	85-3/4" x 15-7/8"	33	\$607	\$638	
AB0EPSSFP9113S	ABMEPSSFP9113S	91-3/4" x 13-7/8"	29	\$625	\$657	
ABOEPSSFP9115S	ABMEPSSFP9115S	91-3/4" x 15-7/8"	35	\$654	\$687	
						Double-Faced End Panels
ABOEPSDFP4324S	ABMEPSDFP4324S	43-3/4" x 24-3/8"	27	\$488	\$513	
ABOEPSDFP4328S	ABMEPSDFP4328S	43-3/4" x 28-3/8"	33	\$510	\$536	
ABOEPSDFP6724S	ABMEPSDFP6724S	67-3/4" x 24-3/8"	43	\$586	\$615	
ABOEPSDFP6728S	ABMEPSDFP6728S	67-3/4" x 28-3/8"	52	\$621	\$652	
ABOEPSDFP7924S	ABMEPSDFP7924S	79-3/4" x 24-3/8"	51	\$647	\$680	
AB0EPSDFP7928S	ABMEPSDFP7928S	79-3/4" x 28-3/8"	61	\$683	\$716	
ABOEPSDFP8524S	ABMEPSDFP8524S	85-3/4" x 24-3/8"	55	\$680	\$714	
ABOEPSDFP8528S	ABMEPSDFP8528S	85-3/4" x 28-3/8"	66	\$716	\$751	
ABOEPSDFP9124S	ABMEPSDFP9124S	91-3/4" x 24-3/8"	59	\$718	\$754	
ABOEPSDFP9128S	ABMEPSDFP9128S	91-3/4" x 28-3/8"	60	\$756	\$794	
		Please specify Wood Finish (Tal	ole 1). Details can be fou	nd on page GEN 4.		

#### **CHAIR FRAME**

The end frames are constructed of a framed panel and plinth base assembly. The framed panel assembly consists of solid Northern-grown Red Oak or maple hardwood rails and stiles with a veneered panel. The panel is 3/4" thick plain sliced slip matched Northern grown Red Oak or Maple routed on three sides. The top rail is 2"H x 1" thick and side stiles are 1" x 1" with a 1" radius. The plinth base is composed of one piece of 5/4 solid Northern-grown Red Oak or maple 2-1/4"H x 1" thick. The plinth base receives a molded shape at the top which consists of a 1" radius ending in a 1/4"W reveal and is attached to the bottom of the frame panel assembly by means of three #8 x 3" long flat-head screws and wood glue. The bottom of the plinth receives two 7/8" diameter chrome adjustable glides located 1-1/4" from the plinth ends.

The front stretcher and front seat rail are 3"W x 1" thick Northern-grown Red Oak or maple. The back seat rail is 2-3/4"W x 1" thick solid red oak or maple. The cross stretcher and seat rails are mortised, tenoned, and glued into the side frames.

#### UPHOLSTERED SEAT AND BACK

The seat and back frame are a single piece of 3/4" bent plywood. The seat portion is fitted with a Dimatrol Webbing and then covered with black cambric fabric for comfort. This is then covered with 3-1/2" foam, which is also used on the chair back. The entire seat and back assembly is covered with the specified upholstery fabric except for the underside of the seat which is covered with a black cambric fabric. Brodart upholstery materials meet requirements of the following fire codes:

Calif. Technical Bulletin #117 (sec. E part 1); CS-191-53 class 1.

Catalog No.	Description	Overall H x W x D	Wt. (lbs.)	COM Price		Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
One Seat Lou	inge, Oak Wood									One Sea
ABOLNG1SS	Lounge	31" x 27" x 29-1/2'	65	\$2,887	\$2,783	\$3,506	\$3,752	\$4,014	\$4,295	
ABOLNG1SRTS	Lounge w/Right Table Arm	31" x 27" x 29-1/2'	70	\$3,112	\$3,010	\$3,780	\$4,044	\$4,326	\$4,630	
ABOLNG1SLTS	Lounge w/Left Table Arm	31" x 27" x 29-1/2'	70	\$3,112	\$3,010	\$3,780	\$4,044	\$4,326	\$4,630	
One Seat Lou	ınge, Maple Wood									
ABMLNG1SS	Lounge	31" x 27" x 29-1/2'	65	\$3,015	\$2,905	\$3,660	\$3,918	\$4,190	\$4,485	
ABMLNG1SRTS	Lounge w/Right Table Arm	31" x 27" x 29-1/2'	70	\$3,248	\$3,130	\$3,944	\$4,219	\$4,516	\$4,831	400
ABMLNG1SLTS	Lounge w/Left Table Arm	31" x 27" x 29-1/2'	70	\$3,248	\$3,130	\$3,944	\$4,219	\$4,516	\$4,831	
Fahric Require	ments: 3 yards per ch	air Non-direction	al 54"	wide						

Two Seat Lou	nge, Oak Wood									Two Sea
ABOLNG2SS	Lounge	31" x 51" x 29-1/2"	110	\$4,185	\$3,986	\$5,022	\$5,374	\$5,750	\$6,153	
ABOLNG2SRTS	Lounge w/Right Table Arm	31" x 51" x 29-1/2"	115	\$4,417	\$4,206	\$5,301	\$5,672	\$6,067	\$6,493	
ABOLNG2SLTS	Lounge w/Left Table Arm	31" x 51" x 29-1/2"	115	\$4,417	\$4,206	\$5,301	\$5,672	\$6,067	\$6,493	
Two Seat Lou	nge, Maple Wood									
ABMLNG2SS	Lounge	31" x 51" x 29-1/2"	110	\$4,333	\$4,127	\$5,201	\$5,564	\$5,954	\$6,371	
ABMLNG2SRTS	Lounge w/Right Table Arm	31" x 51" x 29-1/2"	115	\$4,567	\$4,350	\$5,481	\$5,865	\$6,276	\$6,714	
ABMLNG2SLTS	Lounge w/Left Table Arm	31" x 51" x 29-1/2"	115	\$4,567	\$4,350	\$5,481	\$5,865	\$6,276	\$6,714	
Fabric Requirer	ments: 6 yards per ch	air, Non-directiona	l, 54"	wide.						

<u>ariatric Loun</u>	ige, Oak Wood									Bariatric Lounge
BOLNGBAS I	Lounge	31" x 42" x 29-1/2"	110	\$4,374	\$4,166	\$5,249	\$5,617	\$6,009	\$6,431	
BOLNGBARTS	Lounge w/Right Table Arm	31" x 42" x 29-1/2"	115	\$4,605	\$4,387	\$5,528	\$5,916	\$6,328	\$6,772	
BOLNGBALTS	Lounge w/Left Table Arm	31" x 42" x 29-1/2"	115	\$4,605	\$4,387	\$5,528	\$5,916	\$6,328	\$6,772	
ariatric Loun	nge, Maple Wood									
BMLNGBAS I	Lounge	31" x 42" x 29-1/2"	110	\$4,522	\$4,307	\$5,427	\$5,807	\$6,212	\$6,649	
3MLNGBARTS	Lounge w/Right Table Arm	31" x 42" x 29-1/2"	115	\$4,755	\$4,528	\$5,706	\$6,104	\$6,532	\$6,989	
3MLNGBALTS	Lounge w/Left Table Arm	31" x 42" x 29-1/2"	115	\$4,755	\$4,528	\$5,706	\$6,104	\$6,532	\$6,989	
abric Requirem	nents: 5 yards per ch	air, Non-directiona	l, 54"	wide.						

Please specify Wood Finish (Table 1), High-Pressure Laminate; if applicable (Table 2) and Upholstery (Table 5). Details can be found on pages GEN 4 and GEN 5.

#### **TABLETOP**

Tabletop is 1-3/16" thick, 3-ply 45# density particleboard, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Edges are solid Northern-grown Red Oak or maple. Top receives an external solid drop edge Northern-grown Red Oak or maple band 5/8" x 1-5/8" thick, radiused 1/2" to form a waterfall shape.


#### APRON (OPTIONAL)

A 4"H x 1" thick solid Northern-grown Red Oak or maple apron is fitted between the legs and behind the extended tabletop edge band. Starting 1/2" in from each end, the apron receives a radius that peaks at 2" in the center. The ends of each apron receive a 1/2" radius. Aprons are attached to the table using wood cleats screwed to the underside of the tabletop. Aprons on round tables are fitted between the legs and follow the curvature of the edge band.

**Note:** Aprons are not available for trapezoid shaped tables or Pedestal Base tables.

#### **LEG**

The leg is glued up 2-1/4" solid Northern-grown Red Oak or maple. The leg is molded into a triangle shape with the front face receiving a 2" radius and outside edges receiving a 1/2" radius that tapers to a 90° right angle. A 1/4" wide x 1/16" deep horizontal vein line is routed 2" up from the bottom of the leg. A 1/8" chamfer is placed at the bottom of the leg. Each leg receives a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut which is further recessed into the leg by means of a counter-sink boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The assembled leg is attached to the tabletop by five 5/16" x 1" machine bolts engaging internal and external threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended table edge band.



Abridge Drop Edge Band

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
ABOT30RD16ARTWS	ABMT30RD16ARTWS	Round Table	16"H x 30" Diameter	60	\$1,507	\$1,688	Round Table
ABOT36RD16ARTWS	ABMT36RD16ARTWS	Round Table	16"H x 36" Diameter	60	\$1,557	\$1,743	
ABOT242422ARTWS	ABMT242422ARTWS	Square End Table	22" x 24" x 24"	45	\$1,111	\$1,242	Square Table
ABOT303016ARTWS	ABMT303016ARTWS	Square Lounge Table	16" x 30" x 30"	51	\$1,378	\$1,545	
ABOT243022ARTWS	ABMT243022ARTWS	Rectangular End Table	22" x 30" x 24"	48	\$1,160	\$1,299	Rectangular Table
ABOT244816ARTWS	ABMT244816ARTWS	Rectangular Lounge Table	16" x 48" x 24"	46	\$1,564	\$1,750	

**-ABR 44-** F11-1-19G-ABR

# The Chancellor's Collection

#### **DESKTOP**

Standard desk top is 1-3/16" thick, 3-ply, 45# density particleboard core with a top surface of high-pressure laminate .050" thick. A backing sheet not less than .020" thick is also applied for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tops receive a 1" W x 1-3/16" thick solid-oak undercut chamfered edge band; applied to top core after lamination of the face plastic. The edge band is beveled at a 39° angle with a 3/8" radius bullnose at the leading edge. A 1/4" thick, solid Northern-grown red oak edge band is applied to the remaining three sides, with top and bottom edges radiused to 1/8". All edges are applied to the desk top after the top and bottom laminate sheets are applied, constituting an external edge band. Desk tops are positioned over the end panels of the desk module, flush with the outside edges of the end panels.

#### **DESK END PANELS**

Desk module end panels are 1" thick, 3-ply 45# density particleboard core with select plain-sliced oak veneer on both sides. Exposed edges are externally banded with a 1" x 1/16" thick, Northern-grown oak edge band. The end panels and front panel are joined and secured with 3/4" x 3/4" thick solid hardwood cleats screwed to the inside surfaces of the panels. The bottom of each end panel receives two adjustable glides to allow leveling of the individual units. Each end panel receives a 3" diameter egress and grommet to provide for wire passage.

#### FRONT PANEL

The front panel is 3/4" thick, 45# density particleboard core comprised of select plain-sliced, slip-matched oak veneer on the inside face. Veneer on outside face is a combination of plain-sliced ash veneer surrounded by rift-cut oak veneer to form a framed appearance. The "frame" is composed of 3-1/4"W rift-cut, oak veneer strips along both vertical edges and the bottom edge, and a 3-1/4"W rift cut oak veneer strip at the top edge shaped to form an internal arc. Panels are externally banded with 1.6mm solid oak on all vertical and horizontal edges, and all edges are eased. The front incorporates a 6"H x 3/4"D recessed and ebonized toe space at the bottom of the panel. The front panel is positioned over the end panels of the desk module, flush with the outside edges of the end panels. Double wide units have two front panels to give the appearance of two individual units.

#### ADJUSTABLE WORK SURFACE


Work surfaces are 1-3/16" thick, 3-ply particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. The exposed edge receives a 1/4" thick, solid Northern-grown red oak internal edge band in straight design. The back edge of the work surface has a black strip, 1-1/2"W, which projects above the work surface 1/4" to act as a retainer. The work surface is 24-1/2"D and is positioned 1-1/2" away from the front panel, creating a cord drop space. Adjustable work surfaces are available in single-wide standing-height desks. Work surfaces in standing-height desks (catalog numbers 73-012-S00) may be positioned at heights of 36", 32" or 27".

#### **SHELVES**

Shelves are constructed of 7-ply, furniture-grade hardwood, and veneer-core plywood with plain-sliced solid-oak face veneer. Fronts are banded with solid oak. Exposed edges receive a 1.6mm thick solid-oak edge band.

#### **DRAWERS**

Drawers are constructed of solid hardwood with 1/4" thick wood bottom panel. Drawers have 3-ply particleboard fronts with select oak face veneers. Box drawers have extension slides with 100# load capacity. File drawers have full-extension slides with 100# load capacity.



Chancellor's Series Edge Band


#### **DESK DIMENSIONS**

Standing-Height Desk, overall:

39-1/4"Hx35"Wx30-3/8"D or 39-1/4"Hx70"Wx30-3/8"D.

Sitting-Height Desk, overall:


32-1/4"Hx35"Wx30-3/8"D or 32-1/4"Hx70"Wx30-3/8"D.



# The Chancellor's Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
CH2-012-S00 OAK	CH2-012-S00 MAP	Standing Height Desk with Patron Service Ledge	39-3/16" x 35" x 30"	140	\$3,254	\$3,547	Single-Wide Desk with Patron Service Ledge
		Inside dimensions: 33"W x 26-3 7-7/8" patron ledge is at a heigl <b>Note:</b> Adjustable-height work so at heights of 36", 32" or 27".	ht of 39-3/16"H.				
CH2-E12-S00 OAK	CH2-E12-S00 MAP	Sitting Height Desk with Patron Service Ledge	32-3/16" x 35" x 30"	125	\$3,097	\$3,376	
		Inside dimensions: 33"W x 26-3 7-7/8" patron ledge is at a heigl <b>Note:</b> Work surface is fixed at 2	ht of 32-3/16"H.				
CH2-014-S00 OAK	CH2-014-S00 MAP	Standing Height Desk without Patron Service Ledge	39-3/16" x 35" x 30"	135	\$2,896	\$3,157	Single-Wide Desk without Patron Service Ledge
		Inside dimensions: 33"W x 26-3 work surface is at 39-3/16"H. To grommets are located in the work	wo 3" diamenter				0
CH2-E14-S00 OAK	CH2-E14-S00 MAP	Sitting Height Desk without Patron Service Ledge	32-3/16" x 35" x 30"	120	\$2,680	\$2,922	
		Inside dimensions: 33"W x 26-3 work surface is at 32-3/16"H. To grommets are located in the worl	wo 3" diamenter				0
CH2-015-S00 OAK	CH2-015-S00 MAP	Standing Height Book Return Un	it 39-3/16" x 35" x 30"	135	\$2,819	\$3,073	Book Return Unit
		Inside dimensions: 33"W x 26-3 work surface is at 39-3/16"H. U finished opening centered in the of books and a book chute to dire depressible book truck. (Depress Two 3" diameter grommets are le	nit has a 5''H x 12''W front panel for passage ect the books over a mobile sible book truck not included).				0
CH2-E15-S00 OAK	CH2-E15-S00 MAP	Sitting Height Book Return Unit	32-3/16" x 35" x 30"	120	\$2,671	\$2,911	
		Inside dimensions: 33"W x 26-3 work surface is at 32-3/16"H. U finished opening centered in the of books and a book chute to dire depressible book truck. (Depress Two 3" diameter grommets are left.	nit has a 5''H x 12''W front panel for passage ect the books over a mobile sible book truck not included).				0

Standing Sitting	Oak	Maple			Wt.	0ak	Maple
	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
Cupboard and Open Shelf	CH2-121-S00 OAK	CH2-121-S00 MAP	Standing Height Cupboard and Open Shelf	39-3/16" x 35" x 30"	175	\$5,132	\$5,595
0			This unit has one fixed and two ac shelves. A hidden drawer is posit the lockable storage compartme grommets are located in the work	ioned above nt. Two 3'' diameter			
	CH2-E21-S00 OAK	CH2-E21-S00 MAP	Sitting Height Cupboard	32-3/16" x 35" x 30"	160	\$4,806	\$5,239
			This unit has one fixed and one ashelf. A hidden drawer is position the lockable storage compartme grommets are located in the work	ned above nt. Two 3'' diameter			
Full Width Drawer, Cupboard and Drawers	CH2-122-S00 OAK	CH2-122-S00 MAP	Standing Height Full Width Drawer, Cupboard and Drawers	39-3/16" x 35" x 30"	225	\$6,872	\$7,490
			This unit has one full-width drawe two file drawers, and a lockable s compartment. Two 3" diameter of are located in the work surface. <b>Note:</b> Available in 39"H only.	storage			



# The Chancellor's Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
CH2-124-S00 OAK	CH2-124-S00 MAP	Standing Height Open Shelf and Drawer Unit	39-3/16" x 35" x 30"	200	\$5,692	\$6,204	Open Shelf and Drawer Unit
		This unit has one lockable box drav and two file drawers. Shelf section two adjustable shelves, and one fix Two 3" diameter grommets are loc	has red base shelf.				0
CH2-E24-S00 OAK	CH2-E24-S00 MAP	Sitting Height Open Shelf and Drawer Unit	32-3/16" x 35" x 30"	125	\$5,217	\$5,687	
		This unit has one lockable box drav and one file drawer. Shelf section I one adjustable shelf, and one fixed Two 3" diameter grommets are loc	nas I base shelf.				
CH2-131-S00 OAK	CH2-131-S00 MAP	Standing Height Cash Drawer Unit	39-3/16" x 35" x 30"	150	\$4,014	\$4,375	Cash Drawer Unit
		Inside dimensions: 33"W x 26-3/4 The work surface is at 39-3/16"H. has locking drawer with a coin and Two 3" diameter grommets are loc	Desk currency tray.			-	0 0
CH2-E31-S00 OAK	CH2-E31-S00 MAP	Sitting Height Cash Drawer Unit	32-3/16" x 35" x 30"	135	\$3,844	\$4,190	
		Inside dimensions: 33"W x 26-3/4 The work surface is at 32-3/16"H. has locking drawer with a coin and Two 3" diameter grommets are loc	Desk currency tray.				
CH2-E32-S00 OAK	CH2-E32-S00 MAP	Sitting Height ADA Station	32-3/16" x 35" x 40-1/2	" 185	\$3,016	\$3,288	ADA Station
		The ADA transaction station is designed to provide wheelchair acc on the patrons' side. The knee spa on the patrons' side is 22-1/4" ar staff side is 16". Two 3" diameter are located in the work surface. On egress with sleeve is located in each	ce depth nd on the grommets e 3-1/2" diameter	<b>j</b> e.			0

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	0ak Price	Maple Price
Full Width Drawer Unit	t	CH2-133-S00 OAK	CH2-133-S00 MAP	Standing Height Full Width Drawer Unit	39-3/16" x 35" x 30"	160	\$4,115	\$4,486
				This drawer unit has a full-width 10"H x 33"W x 18-3/4"D. Tw grommets are located in the wo Note: Available in 39-3/16"H	o 3" diameter ork surface.			

**Full Width Drawer and Cupboard Unit** 



CH2-135-S00 OAK CH2-135-S00 MAP

Standing Height Full Width **Drawer and Cupboard Unit** 

39-3/16" x 35" x 30"

220 \$4,527

\$4,934

This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Hinged doors have a catch, lock and door pulls. Two 3" diameter grommets are located in the work surface. Note: Available in 39-3/16"H only.

Discharge Unit CH2-172-S00 OAK Standing Height Discharge Unit 39-3/16" x 35" x 30" CH2-172-S00 MAP 165 \$4,278 \$4,663 These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 39-3/16"H. Note: Standing-height roll unders do not work with this unit. CH2-E72-S00 OAK CH2-E72-S00 MAP Sitting Height Discharge Unit 32-3/16" x 35" x 30" \$4,061 \$4,426 These units have a full-width well with seven removable wood trays for 5 "H x 3 "W cards. The 7-7/8" patron ledge is at a height of 32-3/16"H.

# The Chancellor's Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
CH2-174-S00 OAK	CH2-174-S00 MAP	Standing Height Open Shelf Unit	39-3/16" x 35" x 30"	175	\$3,301	\$3,598	Open Shelf Unit
		This unit has a full-depth fixed base shelf and two full-depth adjustable Two 3" diameter grommets are locathe work surface.	shelves.				
CH2-E74-S00 OAK	CH2-E74-S00 MAP	Sitting Height Open Shelf Unit	32-3/16" x 35" x 30"	155	\$2,974	\$3,241	
		This unit has a full-depth fixed base shelf and two full-depth adjustable Two 3" diameter grommets are locathe work surface.	shelves.				
CH2-176-S00 OAK	CH2-176-S00 MAP	Standing Height Cupboard Unit	39-3/16" x 35" x 30"	200	\$3,993	\$4,352	Cupboard Unit
		This unit has a full-depth fixed base shelf and two full-depth adjustable Hinged doors have a catch, lock and Two 3" diameter grommets are loca work surface.	shelves. d door pulls.				
CH2-E76-S00 OAK	CH2-E76-S00 MAP	Sitting Height Cupboard Unit	32-3/16" x 35" x 30"	180	\$3,813	\$4,156	
		This unit has a full-depth fixed base shelf and one full-depth adjustable Hinged doors have a catch, lock and Two 3" diameter grommets are located work surface.	shelf. d door pulls.				
CH2-234-S00 OAK	CH2-234-S00 MAP	Standing Height Full Width Drawer and Open Shelves	39-3/16" x 35" x 30"	180	\$3,914	\$4,267	Full Width Drawer and Open Shelves
		This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work so	urface.				
CH2-E34-S00 OAK	CH2-E34-S00 MAP	Sitting Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work so	32-3/16" x 35" x 30" urface.	165	\$3,690	\$4,022	

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Media Storage Unit	ĀŦ	CH2-236-S00 OAK	CH2-236-S00 MAP	Standing Height Media Storage Unit	39-3/16" x 35" x 30"	225	\$5,437	\$5,926
				This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me	edia storage.			
		CH2-E36-S00 OAK	CH2-E36-S00 MAP	Sitting Height Media Storage Unit	32-3/16" x 35" x 30"	205	\$5,040	\$5,494
0				This unit has three full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me				


## The Chancellor's Collection

CH2-011-S00 OAK	CH2-011-S00 MAP		HxWxD	(lbs.)	Price	Price	Standing	Sitting
		Standing Height Double-Wide Desk with Patron Service Ledge	39-3/16" x 70" x 30"	245	\$4,695	\$5,117	Double with Patron Se	e-Wide Desk rvice Ledge,
		Work Surface at 35"H Inside dimensions are 68"W x 26-3 The 7-7/8"D patron ledge is at a he Two 3" diameter grommets are loca Note: Standing-height roll unders	eight of 39-3/16". ated in the work surface.		0			
CH2-E11-S00 OAK	CH2-E11-S00 MAP	Sitting Height Double-Wide Desk with Patron Service Ledge	32-3/16" x 70" x 30"	210	\$4,698	\$5,122		
		Work Surface at 28"H Inside dimensions are 68"W x 26-3 The 7-7/8"D patron ledge is at a he Two 3" diameter grommets are local	eight of 32-3/16".					
CH2-011-SEA OAK	CH2-011-SEA MAP	Standing Height Double-Wide Desk with Patron Service Ledge	39-3/16" x 70" x 30"	245	\$4,967	\$5,414		
		Work Surface at 28"H Inside dimensions are 68"W x 26-3 The 7-7/8"D patron ledge is at a he Two 3" diameter grommets are loca Note: Standing-height roll unders	eight of 39-3/16". ated in the work surface.		0			
CH2-013-S00 OAK	CH2-013-S00 MAP	Standing Height Double-Wide	39-3/16" x 70" x 30"	230	\$4,499	\$4,905	Double without Patron Se	e-Wide Desk
		Desk without Patron Service Ledge Inside dimensions are 68"W x 26-3 The work surface is at 39-3/16" H. diameter grommets are located in t	Two 3''		0	0	0 0	i vice Leage
CH2-E13-S00 OAK	CH2-E13-S00 MAP	Sitting Height Double-Wide Desk without Patron Service Ledge	32-3/16" x 70" x 30"	195	\$4,287	\$4,673		

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ High-Pressure\ Laminate\ (Table\ 2).\ Details\ can\ be\ found\ on\ page\ GEN\ 4.$ 

The work surface is at 32-3/16" H. Two 3" diameter grommets are located in the work surface.

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Double Work Desk	Pedestal	CH2-E37-S00 OAK	CH2-E37-S00 MAP	Sitting Height Double-Wide Double Pedestal Work Desk	32-3/16" x 70" x 30"	260	\$9,461	\$10,313
				Inside dimensions are 68"W x 2. This unit has two drawer pedest on each side consisting of one I one file drawer with hanging file Two center drawers are mounte Two 3" diameter grommets are Note: Available in 32-3/16" H	als, one mounted ocking drawer at top; rack at bottom. d between the two pedestals. located in the work surface.			



## The Chancellor's Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
CH2-010-S00 OAK	CH2-010-S00 MAP	Standing Height 90 Degree Multi-Purpose Corner	39-3/16" x 71-3/4" x 30"	250	\$7,812	\$8,514	Mı	90 Degree ulti-Purpose Corner
		Unit has 29-5/16"W port are angled areas to the left and rig	a. Storage shelves are located ght of the desk module. One 3' k-surface top. One 3-1/2" dia end panel for wire passage.	diameter		0		0
CH2-E10-S00 OAK	CH2-E10-S00 MAP	Sitting Height 90 Degree Multi-Purpose Corner	32-3/16" x 71-3/4" x 30"	215	\$7,415	\$8,083		
		angled areas to the left and rig	a. Storage shelves are located pht of the desk module. One 3' k-surface top. One 3-1/2" dia end panel for wire passage.	diameter			0	0
CH2-017-S00 OAK	CH2-017-S00 MAP	Standing Height 90 Degree Multi-Purpose with Patron Ser	39-3/16" x 71-3/4" x 30" vice Ledge	245	\$10,196	\$11,113		ulti-Purpose Corner tron Service Ledge
		Work surface is at 35"H. Stor and right of the module. One 3	a. The 7-7/8"D patron ledge i age shelves are located in the "diameter grommet is locate vith sleeve is located in each e	two angled	l areas to the rk surface to	e left op.		0
CH2-E17-S00 OAK	CH2-E17-S00 MAP	Sitting Height 90 Degree Multi-Purpose with Patron Ser	32-3/16" x 71-3/4" x 30" vice Ledge	210	\$9,684	\$10,556		•
		Work surface is at 28"H. Stor and right of the module. One	a. The 7-7/8"D patron ledge i age shelves are located in the 3" diameter grommet is locate with sleeve is located in each e	two angled	l areas to the ork surface t	e left op.	0	0
CH2-016-S00 OAK	CH2-016-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"H	140	\$3,556	\$3,875		90 Degree Closed Corner Unit
		This is not available with patro	form a right angle turn in a des on ledge. One 3-1/2'' diamete sage through a continuous AB:	egress is				
CH2-E16-S00 OAK	CH2-E16-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"H	120	\$3,432	\$3,741		
		This is not available with patro	form a right angle turn in a des on ledge. One 3-1/2'' diamete sage through a continuous AB	egress is				

		0ak	Monlo			\ <i>\</i> /4	Ook	Monlo			
Standing	Sitting	Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price			
45 Degree Closed Corn	er Unit	CH2-018-S00 OAK	CH2-018-S00 MAP	Standing Height 45 Degree Closed Corner Unit	39-3/16" x 22-7/8" x 30"	130	\$3,556	\$3,875			
				This corner unit is used to create a 45 degree angle in the circulation desk.  This unit is not available with a patron ledge.							
		CH2-E18-S00 OAK	CH2-E18-S00 MAP	Sitting Height 45 Degree Closed Corner Unit	32-3/16" x 22-7/8" x 30"	110	\$3,432	\$3,741			
				This corner unit is used to creat This unit is not available with a	e a 45 degree angle in the circul patron ledge.	ation des	sk.				
90 Degree Open Curved with Patron Service Lec		CH2-040-S00 OAK	CH2-040-S00 MAP	Standing Height 90 Degree Open Curved Corner with Patro	39-3/16" x 70-1/8" x 30" n Service Ledge	245	\$12,610	\$13,744			
0	0			Unit has 26-5/8"W port area. and right of the desk module. C	t a height of 39-3/16". The work Storage shelves are located in the One 3" diameter grommet is loca th sleeve is located in each end p	ne two an Ited in the	igled areas e work surf	to the left ace top.			
		CH2-E40-S00 OAK	CH2-E40-S00 MAP	Sitting Height 90 Degree Open Curved Corner with Patro	32-3/16" x 70-1/8" x 30" n Service Ledge	210	\$11,888	\$12,958			
0		0		Unit has 26-5/8"W port area. and right of the desk module. C	t a height of 32-3/16". The work Storage shelves are located in the One 3" diameter grommet is loca th sleeve is located in each end p	ne two an Ited in th	igled areas e work surf	to the left ace top.			
90 Degree Open Curved	d Corner	CH2-041-S00 OAK	CH2-041-S00 MAP	Standing Height 90 Degree Open Curved Corner	39-3/16" x 70-1/8" x 30"	245	\$11,165	\$12,170			
	0			Work surface is at 39-3/16"H. in the two angled areas to the le	. Unit has 26-5/8"W port area. S eft and right of the desk module. op. One 3-1/2" diameter egres: age.	One 3"	diameter g	rommet			
	•	CH2-E41-S00 OAK	CH2-E41-S00 MAP	Sitting Height 90 Degree Open Curved Corner	32-3/16" x 70-1/8" x 30"	210	\$10,522	\$11,469			
0		0		in the two angled areas to the le	. Unit has 26-5/8"W port area. Seft and right of the desk module. op. One 3-1/2" diameter egres: age.	One 3"	diameter g	rommet			

## The Chancellor's Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
CH2-047-S00 OAK	CH2-047-S00 MAP	Standing Height 60 Degree Curved Corner with Patron Se	39-3/16" x 80-3/4" x 30" ervice Ledge	245	\$14,675	\$15,996	60 Degree Curved Corner with Patron Service Ledge
		Unit has 49-1/16" W port ar left and right of the desk mod	at a height of 39-3/16". The vea. Storage shelves are locatedule. One 3" diameter gromme gress with sleeve is located in e	d in the tw t is locate	o angled are d in the work	eas to the surface	
CH2-E47-S00 OAK	CH2-E47-S00 MAP	Sitting Height 60 Degree Curved Corner with Patron Se	32-3/16" x 80-3/4" x 30" rvice Ledge	210	\$13,899	\$15,150	
		Unit has 49-1/16" W port ar left and right of the desk mod	at a height of 32-3/16". The vea. Storage shelves are located ule. One 3" diameter gromme gress with sleeve is located in a	d in the tw t is locate	o angled are d in the work	eas to the c surface	
CH2-048-S00 OAK	CH2-048-S00 MAP	Standing Height 60 Degree Curved Corner	39-3/16" x 80-3/4" x 30"	245	\$13,238	\$14,430	60 Degree Curved Corner
		located in the two angled are	H. Unit has 49-1/16"W port a as to the left and right of the de rk surface top. One 3-1/2" dia wire passage.	esk modul	e. One 3'' di	ameter eve is	
CH2-E48-S00 OAK	CH2-E48-S00 MAP	Sitting Height 60 Degree Curved Corner	32-3/16" x 80-3/4" x 30"	210	\$12,557	\$13,687	
		located in the two angled are	H. Unit has 49-1/16"W port a as to the left and right of the de rk surface top. One 3-1/2" dia wire passage.	esk modul	e. One 3'' di	ameter	
CH2-055-S00 OAK	CH2-055-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"H x 30"D	140	\$5,708	\$6,221	90 Degree Curved Closed Corner Unit
		This 90 degree unit is used to This unit is provided with a cu	form a right-angle turn in a de rved front panel.	sk arrange	ement.		
CH2-E55-S00 OAK	CH2-E55-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"H x 30"D	120	\$5,311	\$5,789	
		This 90 degree unit is used to This unit is provided with a cu	form a right-angle turn in a derved front panel.	sk arrange	ement.		

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price		
45 Degree Curved Closed Corner Unit		CH2-058-S00 0AK	CH2-058-S00 MAP	Standing Height 45 Degree Curved Closed Corner Unit	39-3/16" x 22-3/8" x 30"	130	\$5,708	\$6,221		
				This unit is used to create a 45 degree angle in the circulation desk. It is not available with patron ledge.						
		CH2-E58-S00 0AK	CH2-E58-S00 MAP	Sitting Height 45 Degree Curved Closed Corner Unit	32-3/16" x 22-3/8" x 30"	110	\$5,311	\$5,789		
				This unit is used to create a 45 It is not available with patron le		desk.				
90 Degree Open Co	rner Shelf	CH2-143-S00 OAK	CH2-143-S00 MAP	Standing Height 90 Degree Open Corner Shelf	39-3/16"H x 30"D	140	\$3,571	\$3,893		
				This 90 degree unit is used to form a right-angle turn in a desk arrangement. Has one fixed base shelf and two adjustable shelves.  Note: Units must be modified on a project by project basis for electrical pass-thm on open corner units.						
		CH2-E43-S00 OAK	CH2-E43-S00 MAP	Sitting Height 90 Degree Open Corner Shelf	32-3/16"H x 30"D	120	\$3,417	\$3,725		
				This 90 degree unit is used to f Has one fixed base shelf and to <b>Note:</b> Units must be modified on open corner units.	vo adjustable shelves.	_		ugh		
90 Degree Square C	Corner Unit	CH2-150-S00 0AK	CH2-150-S00 MAP	Standing Height 90 Degree Square Corner Unit	39-3/16" x 30" x 30"	160	\$4,139	\$4,511		
0 0				This square corner unit is used	to form a right angle in a desk a ated in each end panel for wire p					
		CH2-E50-S00 0AK	CH2-E50-S00 MAP	Sitting Height 90 Degree Square Corner Unit	32-3/16" x 30" x 30"	140	\$3,937	\$4,291		
0	0			This square corner unit is used	to form a right angle in a desk a sted in each end panel for wire p	_				

## The Chancellor's Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
CH2-178-S00 OAK	CH2-178-S00 MAP	Detachable End Panels (Pair)	39" x 1" x 26-3/4"	52	\$2,150	\$2,344	Detachable End Panels (Pair)
		End panels are 1" thick, 3-ply, particleboard core with plain-sli veneers. Exposed edges are extrement 1.6mm thick, solid Norther	iced oak or maple ernally banded	e band.	•		
CH2-E78-S00 OAK	CH2-E78-S00 MAP	Detachable End Panels (Pair)	32" x 1" x 26-3/4"	42	\$1,902	\$2,073	
		End panels are 1" thick, 3-ply, particleboard core with plain-sli veneers. Exposed edges are extrement 1.6mm thick, solid Norther	iced oak or maple ernally banded	e band.			

CH2-196-S00 OAK CH2-196-S00 MAP Single-Wide Add On 7" x 35" x 7-7/8" 10 \$612 \$667 Single-Wide Add On 7"H Patron Ledge

Unit is designed to be added onto a single wide desk without a patron ledge. The Patron Ledge Assembly will attach to the desktop by means of #8 x 2-1/2" screws inserted through the work surface into the ledge assembly.

CH2-197-S00 OAK CH2-197-S00 MAP Double-Wide Add On 7" x70" x7-7/8" 20 \$815 \$888 Double-Wide Add On 7"H Patron Ledge

Unit is designed to be added onto a double wide desk without a patron ledge. The Patron Ledge Assembly will attach to the desktop by means of #8 x 2-1/2" screws inserted through the work surface into the ledge assembly.

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core with a .050" high-pressure laminate face and a .020" thick backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled at a 39° angle with a 3/8" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered at all four corners with corners radiused 1/8".

#### TABLE LEGS - SQUARE WITH APRON


Legs are 2-1/2"W square and glued-up face to face from three solid-oak blanks. All glue joints are tight and smooth. All vertical edges receive a 1/4" radius. Legs receive a horizontal vein line 5/32"W x 3/32"D on the two outside faces of the leg positioned 3-11/32" below the top of the legs. This vein line matches the horizontal vein line on the apron. An identical vein line is positioned 3-1/4" above the bottom of the leg. At the bottom of this vein line the two back sides of the leg taper to a dimension of 1-7/8" x 1-7/8" at the bottom of the leg. Legs receive a 1-1/2" diameter adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersunk boring which accepts the upper two-thirds of the glide. Tables are of apron design with a 3-1/2" x 1" thick apron screwed to the underside of the tabletop. A 5/32"W x 3/32"D vein line is positioned at the bottom front surface of the apron to mirror the top horizontal vein line on the table leg. The legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16" - 18 hex-head bolts which pass through the bracket and engage threaded bushings embedded into the leg and cross-pinned with a 3/16" diameter steel pin.

#### TABLE LEGS - SQUARE WITHOUT APRON


Legs are 2-1/2"W, square shape, and glued-up face to face from three solid-oak blanks. All glue joints are tight and smooth. All vertical edges receive a 1/4" radius. Legs receive a horizontal vein line 5/32"W x 3/32"D on the two outside faces of the leg positioned 3-11/32" below the top of the legs. An identical vein line is positioned 3-1/4" above the bottom of the leg. At the bottom of this vein line the two back sides of the leg taper to a dimension of 1-7/8" x 1-7/8" at the bottom of the leg. Table is designed without an apron, with legs attaching to the tabletop by means of a 5" square x 5/16" thick steel plate. Plates are painted flat black and have no sharp edges. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted in the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended edge band. Edge bands extend 1/2" below the tabletop. Each leg has a 1-1/2" diameter adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersunk boring which accepts the upper two-thirds of the glide.


#### TABLE LEGS - ROUND WITH APRON


Legs are solid, glued-up oak, face-to-face glued from three to four oak blanks. All glue joints are tight and smooth. Table is of apron design with a 3-1/2"W x 1" thick apron screwed to the underside of the tabletop. A 1/4"D "V" groove is positioned 1/2" from the bottom edge of the apron. The bottom edge is radiused 1/4" to mirror the decorative raised rings on the cylindrical portion of the leg. The top of the leg is 2-7/8" square, radiused 1/4" on the vertical edges. The leg then transitions to a 2-1/2" diameter. A 5/8"W x 2-3/4" diameter ring is positioned 3/16" below squared portion of the leg and is radiused 3/8" to accent the transition from square to round. A second ring is positioned 2" from the bottom of the leg. Each leg has a 2" diameter adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersunk boring which accepts the upper two-thirds of the glide. The legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16" - 18 hex head bolts which pass through the bracket and engage threaded bushings, embedded into the leg and cross-pinned with a 3/16" diameter steel pin.



Chancellor's Series Drop Edge







Chancellor's Series Leg Without Apron

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Without Apron	With Apron
	fered Square Legs и	vithout Apron						Round Table
CH2-109-S00 OAK	CH2-109-S00 MAP	Round Table	29"H x 38" Diameter	100	\$2,329	\$2,539		
CH2-129-S00 OAK	CH2-129-S00 MAP	Round Table	29"H x 44" Diameter	90	\$2,476	\$2,699		$\prod$
CH2-141-S00 OAK	CH2-141-S00 MAP	Round Table	29"H x 50" Diameter	100	\$2,476	\$2,699		
CH2-130-S00 OAK	CH2-130-S00 MAP	Round Table	29"H x 62" Diameter	110	\$3,156	\$3,440	# []	$\forall$
Table with Chami	fered Square Legs и	vith Apron						
CH2-A09-S00 OAK	CH2-A09-S00 MAP	Round Table	29"H x 38" Diameter	100	\$2,444	\$2,664		
CH2-A29-S00 OAK	CH2-A29-S00 MAP	Round Table	29"H x 44" Diameter	90	\$2,593	\$2,826		
CH2-A41-S00 OAK	CH2-A41-S00 MAP	Round Table	29"H x 50" Diameter	100	\$2,593	\$2,826	$\forall$	
CH2-A30-S00 OAK	CH2-A30-S00 MAP	Round Table	29"H x 62" Diameter	110	\$3,317	\$3,616		$\forall$
Table with Cham	fered Square Legs и	vithout Aprop						Square Table
CH2-191-S00 OAK		-	20" v 22 2 /4" v 22 2 /4"	100	¢2 010	¢2 201		>qua. 0 10010
CH2-191-S00 OAK	CH2-191-S00 MAP CH2-137-S00 MAP	Square Table Square Table	29" x 32-3/4" x 32-3/4" 29" x 44-3/4" x 44-3/4"	100 100	\$2,019 \$2,166	\$2,201 \$2,361		1
CH2-154-S00 OAK	CH2-157-300 MAP	Square Table Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,100 \$2,314	\$2,501 \$2,523		
		•	29 100-3/4 100-3/4	100	\$Z,314	\$Z,3Z3		4
	fered Square Legs и	-		400	40.400			
CH2-A91-S00 OAK	CH2-A91-S00 MAP	Square Table	29" x 32-3/4" x 32-3/4"	100	\$2,128	\$2,320	<b>"</b>	
CH2-A37-S00 OAK	CH2-A37-S00 MAP	Square Table	29" x 44-3/4" x 44-3/4"	100	\$2,275	\$2,480	y	W
CH2-A54-S00 OAK	CH2-A54-S00 MAP	Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,423	\$2,641	·	₩
Table with Chami	fered Square Legs и	vithout Apron					Rec	tangular Table
CH2-194-S00 OAK	CH2-194-S00 MAP	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,205	\$2,404		
CH2-195-S00 OAK	CH2-195-S00 MAP	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$2,314	\$2,523		
CH2-144-S00 OAK	CH2-144-S00 MAP	=	29" x 62-3/4" x 38-3/4"	110	\$2,251	\$2,453		
CH2-138-S00 OAK	CH2-144-300 MAP	Rectangular Table Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$2,251	\$2,453 \$2,572		
		-					$\Psi$	Ψ
CH2-145-S00 OAK	CH2-145-S00 MAP	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$2,671	\$2,911	$\coprod$	
Table with Chami	<u>fered Square Legs и</u>	<u>vith Apron</u>						
CH2-A94-S00 OAK	CH2-A94-S00 MAP	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,314	\$2,523		
CH2-A95-S00 OAK	CH2-A95-S00 MAP	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$2,423	\$2,641		
CH2-A44-S00 OAK	CH2-A44-S00 MAP	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$2,360	\$2,572		#
CH2-A38-S00 OAK	CH2-A38-S00 MAP	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$2,476	\$2,699	Ψ	
CH2-A45-S00 OAK	CH2-A45-S00 MAP	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$2,811	\$3,064	Д	1
	fered Square Legs и	-						ular Table with
CH2-198-S00 OAK	CH2-198-S00 MAP	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$2,785	\$3,036	Cente	er Support Legs
CH2-146-S00 OAK	CH2-146-S00 MAP	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$2,834	\$3,089		
CH2-134-S00 OAK	CH2-134-S00 MAP	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$3,254	\$3,547		
Table with Chami	<u>fered Square Legs и</u>	<u>vith Apron</u>						Щ
CH2-A98-S00 OAK	CH2-A98-S00 MAP	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$2,894	\$3,155	-	
CH2-A46-S00 OAK	CH2-A46-S00 MAP	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$2,982	\$3,250	$\forall$	
CH2-A34-S00 OAK	CH2-A34-S00 MAP	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$3,432	\$3,741		
	Please specify	Wood Finish (Table 1)	and High-Pressure Laminate (	Table 2). D	etails can be f	ound on page	GEN 4.	]

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Round Table	Table with Tradition	onal Round Legs with	Apron				
	CH2-R09-S00 0AK	CH2-R09-S00 MAP	Round Table	29"H x 38" Diameter	100	\$2,444	\$2,664
	CH2-R29-S00 0AK	CH2-R29-S00 MAP	Round Table	29"H x 44" Diameter	90	\$2,593	\$2,826
	CH2-R41-S00 0AK	CH2-R41-S00 MAP	Round Table	29"H x 50" Diameter	100	\$2,593	\$2,826
	CH2-R30-S00 0AK	CH2-R30-S00 MAP	Round Table	29"H x 62" Diameter	110	\$3,317	\$3,616

Square Table

### Table with Traditional Round Legs with Apron

	•	•				
CH2-R91-S00 OAK	CH2-R91-S00 MAP	Square Table	29" x 32-3/4" x 32-3/4"	100	\$2,128	\$2,320
CH2-R37-S00 OAK	CH2-R37-S00 MAP	Square Table	29" x 44-3/4" x 44-3/4"	100	\$2,275	\$2,480
CH2-R54-S00 OAK	CH2-R54-S00 MAP	Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,423	\$2,641

Rectangular Table

#### Table with Traditional Round Legs with Apron

	3					
CH2-R94-S00 0AK	CH2-R94-S00 MAP	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,314	\$2,523
CH2-R95-S00 0AK	CH2-R95-S00 MAP	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$2,423	\$2,641
CH2-R44-S00 0AK	CH2-R44-S00 MAP	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$2,360	\$2,572
CH2-R38-S00 0AK	CH2-R38-S00 MAP	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$2,476	\$2,699
CH2-R45-S00 0AK	CH2-R45-S00 MAP	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$2,811	\$3,064

Rectangular Table with Center Support Legs



#### Table with Traditional Round Legs with Apron

CH2-R98-S00 0AK	CH2-R98-S00 MAP	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$2,894	\$3,155
CH2-R46-S00 0AK	CH2-R46-S00 MAP	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$2,982	\$3,250
CH2-R34-S00 0AK	CH2-R34-S00 MAP	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$3,432	\$3.741


#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core with a .050" high-pressure laminate face and a .020" thick backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled at a 39° angle with a 3/8" radius bullnose at the leading edge. The edge band extends 1-3/4" beyond the vertical ends of the panel base and is notched at each end at a 45° angle.

#### **TABLE END PANELS**

Table end panels are 1-3/16" thick, 3-ply 45# density particleboard core with select plain-sliced, slip-matched oak veneer on the inside face. Veneer on outside face is sketched to form a "framed" appearance. The frame is composed of 3-1/4" rift-cut, oak-veneer strips along both vertical edges and a 3-1/4" solid wood plinth at the bottom edge. At the top edge is a 3-1/4" rift cut oak veneer strip shaped to form a 1-1/2"H

internal arc. Within the frame is select plain-sliced, slip-matched ash veneer. Panels are externally banded with 1.6mm thick solid oak on the two vertical and top edges. All panel edges are eased. Each panel has two 1-1/4" diameter chrome, adjustable glides. End panels extend 1/4" above tabletop work surface.



Chancellor's Series Drop Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
CH2-P44-S00 OAK	CH2-P44-S00 MAP	Panel Base Table	29" x 62-3/4" x 38-3/4"	130	\$2,866	\$3,124	Table with Panel Base
CH2-P38-S00 OAK	CH2-P38-S00 MAP	Panel Base Table	29" x 74-3/4" x 38-3/4"	150	\$3,137	\$3,419	
CH2-P46-S00 OAK	CH2-P46-S00 MAP	Panel Base Table	29" x 92-3/4" x 38-3/4"	170	\$3,246	\$3,538	
CH2-P45-S00 OAK CH2-P34-S00 OAK	CH2-P45-S00 MAP CH2-P34-S00 MAP	Panel Base Table Panel Base Table	29" x 74-3/4" x 50-3/4" 29" x 92-3/4" x 50-3/4"	180 200	\$3,455 \$4,046	\$3,766 \$4,410	

#### **TABLETOP**

Standard tabletops are 1-3/16" thick, 3-ply particleboard core including a top surface of .050" thick high-pressure laminate, and a backing sheet .020" thick for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading, and stainingin accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled at a 39° angle with 3/8" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered at all four corners with corners radiused 1/8". Note: All Standing-Height Tables are made with an apron to allow adequate leg clearance.

#### TABLE LEGS - SQUARE WITH APRON

Legs are 2-1/2"W, square shape, glued-up face to face from three solid-oak blanks. All glue joints are tight and smooth. All vertical edges receive a 1/4" radius. Legs receive a horizontal vein line 5/32"W x 3/32"D on the two outside faces of the leg positioned 3-11/32" below the top of the legs. This vein line matches the horizontal vein line on the apron. An identical vein line is positioned 3-1/4" above the bottom of the leg. At the bottom of this vein line the two back sides of the leg taper to a dimension of 1-7/8" x 1-7/8" at the bottom of the leg. Legs receive a 1-1/2" diameter adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersunk boring which accepts the upper two-thirds of the glide. Tables are of apron design with a 3-1/2" x 1" thick apron screwed to the underside of the tabletop. A 5/32"W x 3/32"D vein line is positioned at the bottom front surface of the apron to mirror the top horizontal vein line on the table leg. The legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16" - 18 hex-head bolts which pass through the bracket and engage threaded bushings embedded into the leg and cross-pinned with a 3/16" diameter steel pin.

#### TABLE LEGS - SQUARE WITHOUT APRON

Legs are 2-1/2"W, square shape, glued-up face to face from three solid-oak blanks. All glue joints are tight and smooth. All vertical edges receive a 1/4" radius. Legs receive a horizontal vein line 5/32"W x 3/32"D on the two outside faces of the leg positioned 3-11/32" below the top of the legs. An identical vein line is positioned 3-1/4" above the bottom of the leg. At the bottom of this vein line the two back sides of the leg taper to a dimension of 1-7/8" x 1-7/8" at the bottom of the leg. Tables are without an apron, with legs attaching to the tabletop by means of a 5" square x 5/16" thick steel plate. Plates are painted flat black and have no sharp edges. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted in the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended edge band. Edge bands extend 1/2" below the tabletop. Each leg has a 1-1/2" diameter adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersunk boring which accepts the upper two-thirds of the glide. Additional leg(s) added to the center of the table for extra support are 2-1/4"square with a 1/2" radius on vertical edges.

#### **EQUIPMENT SHIELD PRIVACY PANEL**


Privacy panels are 10"H, constructed of 1" thick veneer-core plywood. Exposed panel edges are banded with 1.6mm solid oak. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the privacy panels. Privacy panels are finished to match the table edge band. Privacy panels are designed to obscure wires exiting computer equipment and to eliminate incidental tampering.

#### **ELECTRICAL**

Tables receive 3" grommets in the tabletop for wire passage, and J-channel wire managers are mounted under the tabletop to hold excess wires. Grommets are ABS, black plastic with notched removable cap. J-channel is 18-gauge steel with electrostatically applied black powder paint.

#### **TABLETOP HEIGHT**

Standing Height: 39" (with Apron) Sitting Height: 27-1/2" (without Apron)



Chancellor's Series Drop Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing with Apron	Sitting without Apron
CH2-645-S00 OAK CH2-665-S00 OAK	CH2-645-S00 MAP CH2-665-S00 MAP	Sitting Height Sitting Height	27-1/2" x 32-3/4" x 26-3/4" 27-1/2" x 32-3/4" x 32-3/4"	80 80	\$1,784 \$2,128	\$1,945 \$2,320		One Position Computer Tables
CH2-649-S00 OAK CH2-669-S00 OAK	CH2-649-S00 MAP CH2-669-S00 MAP	Sitting Height Sitting Height	27-1/2" x 62-3/4" x 26-3/4" 27-1/2" x 62-3/4" x 32-3/4"	110 110	\$2,765 \$2,880	\$3,014 \$3,140		Two Position Computer Tables
	CH2-643-S00 MAP	Sitting Height	27-1/2" x 38-3/4" x 26-3/4"	70	\$2,174	\$2,369	One Posit	ion Computer Table
CH2-663-S00 OAK	CH2-663-S00 MAP	Sitting Height	27-1/2" x 38-3/4" x 38-3/4"	70	\$2,283	\$2,488		10"H Privacy Panel
CH2-643-S05 OAK CH2-663-S05 OAK	CH2-643-S05 MAP CH2-663-S05 MAP	Standing Height Standing Height	39" x 38-3/4" x 26-3/4" 39" x 38-3/4" x 38-3/4"	75 75	\$2,360 \$2,469	\$2,572 \$2,691		
CH2-642-S00 OAK CH2-662-S00 OAK	CH2-642-S00 MAP CH2-662-S00 MAP	Sitting Height Sitting Height	27-1/2" x 74-3/4" x 26-3/4" 27-1/2" x 74-3/4" x 38-3/4"	150 150	\$3,114 \$3,269	\$3,395 \$3,563		ion Computer Table 10"H Privacy Panel
CH2-642-S05 OAK CH2-662-S05 OAK	CH2-642-S05 MAP CH2-662-S05 MAP	Standing Height Standing Height	39" x 74-3/4" x 26-3/4" 39" x 74-3/4" x 38-3/4"	155 155	\$3,393 \$3,549	\$3,698 \$3,869		
CH2-644-S00 OAK CH2-664-S00 OAK	CH2-644-S00 MAP CH2-664-S00 MAP	Sitting Height Sitting Height	27-1/2" x 92-3/4" x 26-3/4" 27-1/2" x 92-3/4" x 38-3/4"	180 180	\$3,735 \$3,967	\$4,072 \$4,324		ion Computer Table 10"H Privacy Panel
CH2-644-S05 OAK CH2-664-S05 OAK	CH2-644-S05 MAP CH2-664-S05 MAP	Standing Height Standing Height	39" x 92-3/4" x 26-3/4" 39" x 92-3/4" x 38-3/4"	185 185	\$4,123 \$4,356	\$4,494 \$4,748		
							#	

#### **CARRELS**

Carrels are designed in a modular starter and adder system. The carrel top is 36"W x 28-1/2"D. A 1-1/2"W cord drop runs the width of the carrel between work surface and back panel to allow passage of electrical cords. The carrel shelf is 36"W x 8"D. End panels and intermediate panels are 48"H and 30"D. The carrel top is attached to end panels and intermediate panels by means of a steel, angled "Z" bracket inserted into a route on the underside of the carrel top and screwed. The opposing leg of the "Z" bracket bolts to end panels or intermediate panels with 5/16"-18 hex-head bolts into metal bushings. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end and intermediate panels with 3/4" x 3/4" aluminum or steel angle brackets painted black, with black #8 screws.

#### **CARREL TOP**

The carrel top is 1-3/16" thick, 45# density particleboard core including a top surface of .050" thick, high-pressure laminate and a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. The exposed edge is banded with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band laminated to the work surface core after lamination of the face plastic. The edge band is beveled to a 3/8" radius bullnose at the leading edge. Bevel is at a 39° angle. The edge band extends 1-3/4" beyond the vertical end and intermediate panels and is notched at each end at a 45° angle. The back edge of the top has a black plastic strip 1-1/2"W which projects above the work surface 1/4" to act as a retainer. All work surfaces are adjustable in height to 29" (Sitting) and 32" (Wheelchair).

#### **END AND INTERMEDIATE PANELS**


End and intermediate panels are 1-3/16" thick, 3-ply 45# particleboard core. The inside face of end panels and both faces of intermediate panels are select plain-sliced, slip-matched oak veneer. Veneer on the outside face of end panels is sketched to form a "framed" appearance. The "frame" is composed of 3-1/4" rift-cut, oak-veneer strips along both vertical edges and a 3-1/4" solid wood plinth at the bottom edge. At the top edge is a 3-1/4" rift cut oak veneer strip shaped to form a 1-1/2"H internal arc. Within the frame is select plain-sliced, slip-matched ash veneer. On the double-faced end panel a 3"W rift-cut, oak veneer strip is positioned between the top and bottom oak veneer strips and located at the center of the end panel. The vertical edges of the end panel receive a 1.6mm solid oak external edge band. The top edge of the panel receives a 2-1/4"W x 1-1/4"H solid oak top cap. Top cap is 1-3/16"W at the bottom sloping outward on both sides at a 60° angle. Both the front and back edges of the top cap receive a 3/8" radius. Each panel has two 1-1/4" diameter chrome adjustable glides.

#### **BACK PANEL**

The back panel is 1-3/16" thick, 3-ply 45# density particleboard core with select plain-sliced, slip-matched oak veneer on both faces. Top edge of the back panel is shaped to form an arc. Panels extend to within 1" of the bottom of end panels. Panels are banded externally with 1.6mm thick solid oak on top and bottom edges. Banded edges are eased.


#### CARREL SHELF

The carrel shelf is 3/4" thick x 8"D, 45# density particleboard core with select AA slip-matched oak veneer. The shelf has a 1-3/4"W x 3/4" thick solid-oak external band on the exposed edge.



Chancellor's Series Drop Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Work	ing Space						Single-Faced
CH2-160-S00 OAK	CH2-160-S00 MAP	S/F Starter	49" x 39-1/2" x 32-1/2"	165	\$3,711	\$4,045	Modular Study Carrel
CH2-159-S00 OAK	CH2-159-S00 MAP	S/F Adder	49" x 37-3/4" x 32-1/2"	115	\$2,796	\$3,047	



36" Wide Working Space CH2-161-S00 OAK CH2-161-S00 MAP D/F Starter 49" x 39-1/2" x 61-1/4" 305 \$5,334 \$5,814 CH2-162-S00 OAK CH2-162-S00 MAP D/F Adder 49" x 37-3/4" x 61-1/4" 205 \$3,914 \$4,267

**Double-Faced Modular Study Carrel** 





#### WORKSTATIONS

Workstations are designed in a modular starter and adder system. The workstation tops are 36" or 48"W x 28-1/2"D. A 1-1/2"W cord drop runs the width of the carrel between work surface and back panel to allow passage of electrical cords. The workstation shelf is 36" or 48"W x 8"D. End panels and intermediate panels are 48"H and 30"D. The workstation top is attached to end and intermediate panels by means of a steel, angled "Z" bracket inserted into a route on the underside of the workstation top and screwed. The opposing leg of the "Z" bracket bolts to end panels or intermediate panels with 5/16"-18 hex-head bolts into metal bushings. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end, intermediate, and back panels with 3/4" x 3/4" aluminum or steel angle brackets painted black with black #8 screws.

#### **WORKSTATION TOP**

The workstation top is 1-3/16" thick, 45# density particleboard core including a top surface of .050" thick, high-pressure laminate and a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading, and staining in accordance with NEMA standards. The exposed edge is banded with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band laminated to the work surface core after lamination of the face plastic. The edge band is beveled to a 3/8" radius bullnose at the leading edge. Bevel is at a 39° angle. The edge band extends 1-3/4" beyond the vertical end and intermediate panels and is notched at each end at a 45° angle. The back edge of the top has a black metal band 1-1/2"W which projects above the work surface 1/4" to act as a retainer. All work surfaces are adjustable in heights to 27" (Sitting), 32" (Wheelchair), and 39" (Standing).

#### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-3/16" thick, 3-ply 45# particleboard core. The inside face of end panels and both faces of intermediate panels are select plain-sliced, slip-matched oak veneer. Veneer on the outside face of end panels is sketched to form a "framed" appearance. The "frame" is composed of 3-1/4" rift-cut, oak-veneer strips along both vertical edges and a 3-1/4" solid wood plinth at the bottom edge. At the top edge is a 3-1/4" rift-cut oak veneer strip shaped to form a 1-1/2"H internal arc. Within the frame is select plain-sliced, slip-matched ash veneer. On the double-faced end panel a 3"W rift-cut, oak veneer strip is positioned between the top and bottom oak veneer strips and located at the center of the end panel. The vertical edges of the end panels receive a 1.6mm solid oak external edge band. The top edge of the panel receives a 2-1/4"W x 1-1/4"H solid oak top cap. The top cap is 1-3/16"W at the bottom sloping outward on both sides at a 60° angle. Both front and back edges of the top cap receive a 3/8" radius. Each panel has two 1-1/4" diameter chrome adjustable glides.

#### **BACK PANEL**


The back panel is 1-3/16" thick, 3-ply 45# density particleboard core with select plain-sliced, slip-matched oak veneer on both faces. Top edge of the back panel is shaped to form an arc. Panels extend to within 1" of the bottom of end panels. Panels are banded externally with 1.6mm thick solid oak on all edges. Banded edges are eased.

#### WORKSTATION SHELF

The workstation shelf is 3/4" thick x 8"D, 45# density particleboard core with select AA slip-matched oak veneer. The shelf has a 3/4" thick solid oak external band on the exposed edge. The shelf is located under the work surface and extends the full width of the workstation.

#### WORK SURFACE HEIGHTS

Adjustable at 27", 32" and 39".



Chancellor's Series Drop Edge

36" Wide Working Space CH2-673-S00 OAK	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Starter	Adder
36" Wide Working Space CH2-673-S00 OAK									
CH2-673-S00 OAK	<u>36" Wide Workir</u>	<u>ng Space</u>						onigio i do	
48" Wide Working Space CH2-460-S00 OAK	CH2-673-S00 OAK	CH2-673-S00 MAP	S/F Starter	49" x 39-1/2" x 32-1/2"	165	\$3,711	\$4,045		
CH2-460-S00 OAK	CH2-672-S00 OAK	CH2-672-S00 MAP	S/F Adder	49" x 37-3/4" x 32-1/2"	115	\$2,796	\$3,047		
CH2-460-S00 OAK									
CH2-459-S00 OAK CH2-459-S00 MAP S/F Adder 49" x 49-3/4" x 32-1/2" 145 \$3,214 \$3,503  Starter	48" Wide Workir	ng Space							
Starter	CH2-460-S00 OAK	CH2-460-S00 MAP	S/F Starter	49" x 51-1/2" x 32-1/2"	195	\$4,021	\$4,383		
	CH2-459-S00 OAK	CH2-459-S00 MAP	S/F Adder	49" x 49-3/4" x 32-1/2"	145	\$3,214	\$3,503		
Addor #/								Starter	Adder

36" Wide Worki	ng Space						Double-Faced Information Access
CH2-674-S00 OAK	CH2-674-S00 MAP	D/F Starter	49" x 39-1/2" x 61-1/4"	306	\$5,334	\$5,814	Workstations/Carrels
CH2-675-S00 OAK	CH2-675-S00 MAP	D/F Adder	49" x 37-3/4" x 61-1/4"	205	\$3,914	\$4,267	
48" Wide Worki	ng Space						
CH2-461-S00 OAK	CH2-461-S00 MAP	D/F Starter	49" x 51-1/2" x 61-1/4"	366	\$6,002	\$6,542	
CH2-462-S00 OAK	CH2-462-S00 MAP	D/F Adder	49" x 49-3/4" x 61-1/4"	265	\$4,597	\$5,011	Starter
							Nation 1

#### WORKSTATIONS

Workstations are of modular starter and adder design, with an overall height 33". Workstations are available in 36", 48", 72", 96", and 108" widths. A knee-space panel located below the work surface supports all work surfaces greater than 48"W. Work surface height is at 27-1/2". Work surface depth is 27-1/2" with an additional 1-1/2"W cord drop between the work surface and back panel to allow passage of electrical cords. Work surface is attached to end and intermediate panels by means of two metal 22-1/2" long "Z" brackets with 5/16" – 18 hex-head bolts engaging internally and externally threaded bushings embedded into panels. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end and intermediate panels and back panels with 1" x 1" steel, black painted angle brackets and black #8 screws.

#### **WORK SURFACE**

Standard work surface is 1-3/16" thick, 3-ply, 45# density particleboard including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Front edges of work surfaces have a 1-3/4" thick x 2"W solid oak external undercut chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled at a 39° angle with 3/8" radius bullnosed at the leading edge. The back edge of the top has a black plastic strip 1-1/2"W which projects above the work surface 1/4" to act as a retainer.

#### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-1/8" thick, 45# density particleboard core with select face veneers of Northern-grown red oak. The end panels on starer units receive the Chancellor's Collection veneer sketch face pattern on the outside face surface. These end panels also have the Chancellor's Collection solid red oak top edge cap. This wood cap measures 2-5/16"W x 1-1/4" thick and has a 3/8" radius on all four of the top edges. These edges also bevel downward at a 60° angle. All other edges are banded with a 1.6mm oak veneer band. Intermediate panels receive a 3" diameter grommet below the work surface to allow passage of electrical and data wires. Each panel receives two 1-1/4" adjustable glides.

#### **BACK PANEL**

Back panel is 3/4" thick, 45# density particleboard core with face veneers of select Northern-grown red oak. The top and bottom edges of the back panel receives 1.66mm veneer solid oak edge bands. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The back panel on double-faced units receive a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### **SHELF**


Shelf is 3/4" thick x 8"D 45# density particleboard core with face veneers of select Northern-grown red oak. Shelf is banded on the front edge with a 1.6mm solid oak band. Shelf attaches to end and intermediate panels by means of a pair of metal "L" brackets. Back corners of shelf have a 3" x 3" cutout to allow for the passage of electrical cords. The shelf is positioned 10" below the bottom of the work surface.

#### WIRE MANAGEMENT DOOR

The wire management door is positioned between the bottom of the work surface and the shelf and is designed to form a concealed wire management channel 8-1/2"H x 9-1/2"D. The door is 1/4" thick with select oak face veneers. The door slides in two aluminum tracks, one that is attached to the bottom of the work surface while the other is attached to the top of the shelf.

#### **KNEE-SPACE PANEL**

All 72" and 96"W workstations, as well as functional corner units, have a knee-space panel positioned under the work surface for additional work-surface support. Units 108"W have two knee-space panels. The knee-space panel is 1-1/8" thick, 45# density particleboard core with select face veneers of Northern-grown red oak. The panel is banded on exposed edges with a 1.6mm solid oak band. The knee-space panel is attached to the back panel using a 1-3/4" square, solid-oak post, grooved to receive the knee space panel and back panels. Panels attach to the post using recessed metal fasteners and shoulder screws. The knee-space panel is angled in the back to create a space to allow passage of electrical and data cords. The knee-space panel receives two 1-1/4" diameter black adjustable glides.



Chancellor's Series Edge Band

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Worki	ng Space						Single-Faced One-Position
CH2-S31-SS0 OAK	CH2-S31-SS0 MAP	One-Position S/F Starter	36" x 37-1/2" x 31"	130	\$3,592	\$3,915	Starter
CH2-S31-SAO OAK	CH2-S31-SA0 MAP	One-Position S/F Adder	39" x 36-1/2" x 31"	100	\$2,383	\$2,598	Starter
48" Wide Worki	ng Space						
CH2-S41-SSO OAK	CH2-S41-SS0 MAP	One-Position S/F Starter	36" x 49-1/4" x 31"	155	\$3,759	\$4,097	Adder
CH2-S41-SAO OAK	CH2-S41-SA0 MAP	One-Position S/F Adder	39" x 48" x 31"	125	\$2,444	\$2,664	
	na Space						Double-Faced One-Position
CH2-D31-SS0 OAK	CH2-D31-SS0 MAP	One-Position D/F Starter	33-1/2" x 37-1/2" x 59-1/2"	215	\$5,380	\$5,864	
CH2-D31-SAO OAK	CH2-D31-SA0 MAP	One-Position D/F Adder	33-1/2" x 36-1/2" x 59-1/2"	155	\$3,817	\$4,160	
48" Wide Worki	ng Space						Starter
CH2-D41-SSO OAK	CH2-D41-SS0 MAP	One-Position D/F Starter	33-1/2" x 49-1/4" x 59-1/2"	255	\$5,662	\$6,172	
CH2-D41-SAO OAK	CH2-D41-SA0 MAP	One-Position D/F Adder	33-1/2" x 48" x 59-1/2"	195	\$4,010	\$4,370	Adder
	ing Snace						Single-Faced Two-Position
CH2-S32-SS0 OAK	CH2-S32-SS0 MAP	Two-Position	33-1/2" x 74" x 31"	195	\$4,763	\$5,192	
CH2-S32-SAO OAK	CH2-S32-SA0 MAP	S/F Starter Two-Position S/F Adder	33-1/2" x 73" x 31"	165	\$3,566	\$3,887	Starter
48" Wide Worki	ng Space						Starter
CH2-S42-SSO OAK	CH2-S42-SS0 MAP	Two-Position S/F Starter	33-1/2" x 97-1/4" x 31"	235	\$5,075	\$5,532	
CH2-S42-SA0 OAK	CH2-S42-SA0 MAP	Two-Position S/F Adder	33-1/2" x 96" x 31"	205	\$3,759	\$4,097	
							Adder
36" Wide Worki	ng Space						Double-Faced Two-Position
CH2-D32-SSO OAK	CH2-D32-SS0 MAP	Two-Position D/F Starter	33-1/2" x 74" x 59-1/2"	330	\$7,180	\$7,826	
CH2-D32-SA0 OAK	CH2-D32-SA0 MAP	Two-Position D/F Adder	33-1/2" x 73" x 59-1/2"	270	\$5,695	\$6,208	Starter
48" Wide Workii	• .	T D	00.4/01107.4/41150.4 (5.11)	110	<b>4/22</b>	h	
CH2-D42-SS0 OAK	CH2-D42-SS0 MAP	Two-Position D/F Starter	33-1/2" x 97-1/4" x 59-1/2"	410	\$6,081	\$6,629	
CH2-D42-SAO OAK	CH2-D42-SA0 MAP	Two-Position D/F Adder	33-1/2" x 96" x 59-1/2"	155	\$7,673	\$8,364	Adder

Starter	Adder	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced Th	ree-Position	CH2-S33-SS0 OAK	CH2-S33-SS0 MAP	Three-Position S/F Starter	36" x 110-1/2" x 31"	260	\$6,025	\$6,568
7	Starter	CH2-S33-SAO OAK	CH2-S33-SA0 MAP	Three-Position S/F Adder	36" x 109-1/4" x 31"	230	\$4,699	\$5,122
Double-Faced Th		CH2-D33-SSO OAK	CH2-D33-SS0 MAP	Three-Position D/F Starter	36" x 110-1/2" x 59-1/2"	445	\$7,778	\$8,478
	Starter	CH2-D33-SA0 OAK	CH2-D33-SA0 MAP	Three Position D/F Adder	36" x 109-1/4" x 59-1/2"	385	\$9,267	\$10,101
90° Functional of Start		CH2-SCR-SSO OAK	CH2-SCR-SS0 MAP	90-Degree Functional Corner Starter	36" x 62" x 31"	225	\$7,701	\$8,394
Adde		CH2-SCR-SAO OAK	CH2-SCR-SA0 MAP	90-Degree Functional Corner Adder	36" x 62" x 31"	195	\$6,348	\$6,919

#### STATION TOP

Each top is 46-3/4"W at the front, tapering to 21-3/16" at the rear. Tops are 28-3/4"D. A 1-1/2"W cord drop runs the width of the station between the top and back panel to allow passage of electrical and data cords. Station tops are 1-3/16" thick, 45# density particleboard core including a top surface of .050" thick, high-pressure laminate and a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading, and staining in accordance with NEMA standards. The front edge of the top is banded with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band laminated to the work surface core after lamination of the face plastic. The edge band is beveled to a 3/8" radius bullnose at the leading edge. Bevel is at a 39° angle.

#### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-3/16" thick, 45# density particleboard core. Veneer on both faces of the panels is sketched to form a framed appearance. The "frame" is composed of 3-1/4" rift-cut, oak-veneer strips along both vertical edges and a 3-1/4" solid wood plinth at the bottom edge. At the top edge is a 3-1/4" rift-cut oak veneer strip shaped to form a 1-1/2"H internal arc. Within the frame is select plain-sliced, slip-matched ash veneer. The vertical edges of the end panel receives a 1.6mm solid-oak external edge band. The top edge of the panel receives a 2-1/4"W x 1-1/4"H solid-oak top cap. The top cap is 1-3/16"W at the bot-tom sloping outward on both sides at a 30° angle. Both the front and back edges of the top cap receive a 3/8" radius. Each panel has two 1-1/4" diameter chrome adjustable glides with solid plinth.

ELECTRICAL ACCESS DOOR (One for each 3- or 6- station unit)
Access door is 3/4" thick, comprised of select face veneers of Northerngrown red oak over a particleboard core. Panel is externally banded
on all four sides with a 1.6mm thick solid-oak edge band. Door has a
full-length hinge and a lock. Access door is located on one back panel,
which can be located anywhere in the PAC station.

#### **BACK PANEL**

The back panel is 1-3/16" thick, 3-ply 45# density particleboard core with select plain-sliced, slip-matched oak veneer on both faces. The panel is internally banded with 1.6mm thick solid oak on both the bottom edge and the top edge. Back panels are attached to end and intermediate panels using hidden metal keyways and shoulder screws. Back panels have a 3" diameter grommeted egress for electrical cords to pass to the center hub of half-hexagon or full-hexagon station configuration.

#### **SHELVES**


Shelves are 3/4" thick, select oak-veneered 45# density particleboard with a 5/8" thick x 1-3/4"H solid-oak front edge band.

#### **CENTER CAP**

The center cap is 3/4" thick, 45# density particleboard, with high-pressure laminate to match the tops, and shaped to enclose half-hexagon and full-hexagon station configurations.

#### **WORKING SPACE**


The working space is adjustable to: Standing Height 39", ADA Height 32" and Sitting Height 27".



Chancellor's Series Drop Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
CH2-682-S00 OAK	CH2-682-S00 MAP	Six position with	43-1/2" x 98-1/2" x 98-1/2"	500	\$18,830	\$20,524	S

Six Position PAC Station



CH2-685-S00 OAK CH2-685-S00 MAP

Three position with 43-1/2" x 9 angular tops. Composed of one starter

unit and two adder units.


43-1/2" x 98-1/2" x 47-1/2"

265

\$10,172

\$11,088

**Three Position PAC Station** 



#### **TOPS**

Tops are 1-3/16" thick, 3-ply 45# density particleboard including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick. Front edges are externally banded with a 1-3/16" thick x 1"W solid-oak undercut chamfered edge band applied to top core after lamination of the face plastic. The edge band is beveled at a 39° angle with a 3/8" radius bullnose at the leading edge. The back and side edges of top are straight and externally banded with a 1/4" thick oak band. Tops slope at an 8° angle. A 5/8" x 5/8" solid-oak book retainer strip is fastened to the top surface at the front of the sloped top.

#### **END PANELS**

End panels are 1-3/16" thick select, plain-sliced, oak-veneered 45# density particleboard. The inside face of end panels is select plain-sliced, slip-matched oak veneer. Veneer on the outside face of end panels is sketched to form a "framed" appearance. The "frame" is composed of 3-1/4" rift-cut, oak veneer strips along both vertical edges and a 3-1/4" solid wood plinth at the bottom edge. At the top edge is a 3-1/4" rift-cut oak veneer strip shaped to form a 1-1/2"W internal arc. Within the frame is select plain-sliced, slip-matched ash veneer. The vertical edges of the end panel receive a 1.6mm solid oak external edge band. Each panel has two 1-1/4" diameter chrome adjustable glides.

#### **BACK PANEL**


The back panel is 3/4" thick select, plain-sliced, oak-veneered 45# density particleboard banded on the bottom.

#### **DICTIONARY STAND SHELVES**

Dictionary stands have one adjustable and one fixed base shelf. Shelves are 3/4" thick, oak-veneered plywood having a 1.6mm veneer edge band.

#### ATLAS STAND SHELVES

Atlas stands have five pullout shelves. Pullout shelves are 3/4" thick, oak-veneered plywood. Front edges of each shelf have a 2-1/4" x 3/4" solid-oak hardwood fascia. Shelves operate on metal slides with nylon rollers. Each shelf has an automatic shelf stop to prevent accidental removal.



	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Dictionary Stand	CH2-869-S00 OAK	CH2-869-S00 MAP	Dictionary Stand	45" x 25-7/8" x 15-3/4"	200	\$2,826	\$3,080



Atlas Stand	CH2-871-S00 OAK	CH2-871-S00 MAP	Atlas Stand	45" x 29-1/4" x 29- 3/4"	250	\$4,581	\$4,994



0ak	Maple			0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE UN	VIT				
CH2-W10-S01 OAK	CH2-W10-S01 MAP	10"D, Single-Faced	11	\$376	\$395
CH2-W12-S01 OAK	CH2-W12-S01 MAP	12"D, Single-Faced	14	\$398	\$418
CH2-W20-S01 OAK	CH2-W20-S01 MAP	20"D, Double-Faced	23	\$653	\$685
CH2-W24-S01 OAK	CH2-W24-S01 MAP	24"D, Double-Faced	27	\$697	\$732
To Cover TWO UI	VITS				
CH2-W10-S02 OAK	CH2-W10-S02 MAP	10"D, Single-Faced	22	\$515	\$541
CH2-W12-S02 OAK	CH2-W12-S02 MAP	12"D, Single-Faced	28	\$558	\$585
CH2-W20-S02 OAK	CH2-W20-S02 MAP	20"D, Double-Faced	46	\$920	\$966
CH2-W24-S02 OAK	CH2-W24-S02 MAP	24"D, Double-Faced	54	\$1,019	\$1,070
To Cover THREE	UNITS				
CH2-W10-S03 OAK	CH2-W10-S03 MAP	10"D, Single-Faced	33	\$642	\$674
CH2-W12-S03 OAK	CH2-W12-S03 MAP	12"D, Single-Faced	42	\$714	\$750
CH2-W20-S03 OAK	CH2-W20-S03 MAP	20"D, Double-Faced	69	\$1,244	\$1,306
CH2-W24-S03 OAK	CH2-W24-S03 MAP	24"D, Double-Faced	81	\$1,291	\$1,355
To Cover FOUR U	INITC				
CH2-W10-S04 OAK	CH2-W10-S04 MAP	10"D, Single-Faced	44	\$867	\$910
CH2-W10-304 OAK CH2-W12-S04 OAK	CH2-W10-304 MAP	12"D, Single-Faced	56	\$956	\$1,004
CH2-W12-S04 OAK CH2-W20-S04 OAK	CH2-W20-S04 MAP	20"D, Double-Faced	92	\$1,551	\$1,00 <del>4</del> \$1,628
CH2-W20-304 OAK CH2-W24-S04 OAK	CH2-W20-S04 MAP	24"D. Double-Faced	108	\$1,748	\$1,026 \$1,835
		24 D, Double-1 decu	100	Ψ1,740	Ψ1,033
To Cover FIVE UN					
CH2-W10-S05 OAK	CH2-W10-S05 MAP	10"D, Single-Faced	55	\$983	\$1,032
CH2-W12-S05 OAK	CH2-W12-S05 MAP	12"D, Single-Faced	70	\$1,114	\$1,170
CH2-W20-S05 OAK	CH2-W20-S05 MAP	20"D, Double-Faced	115	\$1,875	\$1,969
CH2-W24-S05 OAK	CH2-W24-S05 MAP	24"D, Double-Faced	135	\$2,019	\$2,120
To Cover SIX UNI	<u>ITS</u>				
CH2-W10-S06 OAK	CH2-W10-S06 MAP	10"D, Single-Faced	66	\$1,125	\$1,181
CH2-W12-S06 OAK	CH2-W12-S06 MAP	12"D, Single-Faced	84	\$1,269	\$1,332
CH2-W20-S06 OAK	CH2-W20-S06 MAP	20"D, Double-Faced	138	\$2,202	\$2,313
CH2-W24-S06 OAK	CH2-W24-S06 MAP	24"D, Double-Faced	162	\$2,292	\$2,406
To Cover SEVEN	<u>UNITS</u>				
CH2-W10-S07 OAK	CH2-W10-S07 MAP	10"D, Single-Faced	77	\$1,348	\$1,416
CH2-W12-S07 OAK	CH2-W12-S07 MAP	12"D, Single-Faced	98	\$1,511	\$1,586
CH2-W20-S07 OAK	CH2-W20-S07 MAP	20"D, Double-Faced	161	\$2,505	\$2,630
CH2-W24-S07 OAK	CH2-W24-S07 MAP	24"D, Double-Faced	189	\$2,749	\$2,886
To Cover EIGHT L	<u>UNITS</u>				
CH2-W10-S08 OAK	CH2-W10-S08 MAP	10"D, Single-Faced	88	\$1,478	\$1,552
CH2-W12-S08 OAK	CH2-W12-S08 MAP	12"D, Single-Faced	112	\$1,668	\$1,751
CH2-W20-S08 OAK	CH2-W20-S08 MAP	20"D, Double-Faced	184	\$2,831	\$2,973
CH2-W24-S08 OAK	CH2-W24-S08 MAP	24"D, Double-Faced	216	\$3,005	\$3,155
To Cover NINE U	<u>NITS</u>				
CH2-W10-S09 OAK	CH2-W10-S09 MAP	10"D, Single-Faced	99	\$1,650	\$1,732
CH2-W12-S09 OAK	CH2-W12-S09 MAP	12"D, Single-Faced	126	\$1,868	\$1,961
CH2-W20-S09 OAK	CH2-W20-S09 MAP	20"D, Double-Faced	207	\$3,201	\$3,361
CH2-W24-S09 OAK	CH2-W24-S09 MAP	24"D, Double-Faced	243	\$3,336	\$3,503

**Note:** Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

0ak	Maple			Oak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE UI	VIT				
CH2-S10-S01 OAK	CH2-S10-S01 MAP	10"D, Single-Faced	11	\$376	\$395
CH2-S12-S01 OAK	CH2-S12-S01 MAP	12"D, Single-Faced	14	\$398	\$418
CH2-S20-S01 OAK	CH2-S20-S01 MAP	20"D, Double-Faced	23	\$653	\$685
CH2-S24-S01 OAK	CH2-S24-S01 MAP	24"D, Double-Faced	27	\$697	\$732
To Cover TWO U	NITS				
CH2-S10-S02 OAK	CH2-S10-S02 MAP	10"D, Single-Faced	22	\$515	\$541
CH2-S12-S02 OAK	CH2-S12-S02 MAP	12"D, Single-Faced	28	\$558	\$585
CH2-S20-S02 OAK	CH2-S20-S02 MAP	20"D, Double-Faced	46	\$920	\$966
CH2-S24-S02 OAK	CH2-S24-S02 MAP	24"D, Double-Faced	54	\$1,019	\$1,070
To Cover THREE	IINITS				
CH2-S10-S03 OAK	CH2-S10-S03 MAP	10"D, Single-Faced	33	\$642	\$674
CH2-S10-S03 OAK	CH2-S12-S03 MAP	12"D, Single-Faced	42	\$714	\$074 \$750
CH2-S12-S03 OAK CH2-S20-S03 OAK	CH2-S20-S03 MAP	20"D, Double-Faced	69	\$714 \$1,244	\$750 \$1,306
CH2-S24-S03 OAK	CH2-S24-S03 MAP	24"D, Double-Faced	81	\$1,291	\$1,355 \$1,355
		·			
<u>To Cover FOUR L</u>	<i>JNITS</i> CH2-S10-S04 MAP	10"D Cinals Food	4.4	¢0/7	\$910
CH2-S10-S04 OAK CH2-S12-S04 OAK		10"D, Single-Faced	44 56	\$867 \$956	\$910 \$1,004
	CH2-S12-S04 MAP	12"D, Single-Faced 20"D, Double-Faced	92		\$1,004 \$1,628
CH2-S20-S04 OAK	CH2-S20-S04 MAP	24"D, Double-Faced		\$1,551 \$1,740	-
CH2-S24-S04 OAK	CH2-S24-S04 MAP	24 D, Double-Faced	108	\$1,748	\$1,835
To Cover FIVE UI					
CH2-S10-S05 OAK	CH2-S10-S05 MAP	10"D, Single-Faced	55	\$983	\$1,032
CH2-S12-S05 OAK	CH2-S12-S05 MAP	12"D, Single-Faced	70	\$1,114	\$1,170
CH2-S20-S05 OAK	CH2-S20-S05 MAP	20"D, Double-Faced	115	\$1,875	\$1,969
CH2-S24-S05 OAK	CH2-S24-S05 MAP	24"D, Double-Faced	135	\$2,019	\$2,120
To Cover SIX UN	<u>ITS</u>				
CH2-S10-S06 OAK	CH2-S10-S06 MAP	10"D, Single-Faced	66	\$1,125	\$1,181
CH2-S12-S06 OAK	CH2-S12-S06 MAP	12"D, Single-Faced	84	\$1,269	\$1,332
CH2-S20-S06 OAK	CH2-S20-S06 MAP	20"D, Double-Faced	138	\$2,202	\$2,313
CH2-S24-S06 OAK	CH2-S24-S06 MAP	24"D, Double-Faced	162	\$2,292	\$2,406
To Cover SEVEN	<u>UNITS</u>				
CH2-S10-S07 OAK	CH2-S10-S07 MAP	10"D, Single-Faced	77	\$1,348	\$1,416
CH2-S12-S07 OAK	CH2-S12-S07 MAP	12"D, Single-Faced	98	\$1,511	\$1,586
CH2-S20-S07 OAK	CH2-S20-S07 MAP	20"D, Double-Faced	161	\$2,505	\$2,630
CH2-S24-S07 OAK	CH2-S24-S07 MAP	24"D, Double-Faced	189	\$2,749	\$2,886
To Cover EIGHT	<u>UNITS</u>				
CH2-S10-S08 OAK	CH2-S10-S08 MAP	10"D, Single-Faced	88	\$1,478	\$1,552
CH2-S12-S08 OAK	CH2-S12-S08 MAP	12"D, Single-Faced	112	\$1,668	\$1,751
CH2-S20-S08 OAK	CH2-S20-S08 MAP	20"D, Double-Faced	184	\$2,831	\$2,973
CH2-S24-S08 OAK	CH2-S24-S08 MAP	24"D, Double-Faced	216	\$3,005	\$3,155
To Cover NINE U	<u>NITS</u>				
CH2-S10-S09 OAK	CH2-S10-S09 MAP	10"D, Single-Faced	99	\$1,650	\$1,732
0110 040 000 041/	CH2-S12-S09 MAP	12"D, Single-Faced	126	\$1,868	\$1,961
CH2-S12-S09 OAK					
CH2-S12-S09 OAK CH2-S20-S09 OAK	CH2-S20-S09 MAP	20"D, Double-Faced	207	\$3,201	\$3,361

**Note:** Edge Band on long side only. Tops are designed to be inset betweend end panels. If edge bands are desired on short edges, please enter the part as a modification and specify which bands to be included.

To ensure that tops for steel shelving work with each manufacturer and top method, please specify the exact width and depth of tops. Add 15% for HPL on top and bottom (Steel Shelving ONLY).

#### **END PANELS: STEEL SHELVING**

End panels are 1-3/16" thick, 3-ply 45# density particleboard core with select plain-sliced, slip-matched oak veneer on the inside face. Oak veneer on outside face of end panels is sketched to form a "framed" appearance. The "frame" is composed of 3-1/4" rift-cut, oak-veneer strips along both vertical edges and a 3-1/4" solid wood plinth at the bottom edge. At the top edge is a 3-1/4" rift-cut oak veneer strip shaped to form a 1-1/2"H internal arc. Within the frame is select plain-sliced, slip-matched ash veneer. The vertical edges of the end panel receives a 1.6mm solid oak external edge band. The top edge of the panel receives

a 1-3/4"W x 1-1/4"H solid oak top cap. The top cap is 1-3/16"W at the bottom sloping outward at a 30° angle. Both ends of the top cap receive a 3/8" radius. The vertical edges of the end panel receive a 1.6mm solid-oak external edge band. All panel edges are eased. Exact height and depth of panel must be specified when ordering. End panels are not machined. No fastening hardware is provided with end panels.

**Note:** Please use the part number below and specify exact sizes of end panels and whether continuous tops are to be "inset" (between the panels) or overhung out over the panels.

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price	With Without Top Caps	
CH2-702-MOD OAK	CH2-702-MOD MAP	43-3/4" x 13-7/8"	10	\$634	\$667	Single-Faced End P	anels
CH2-703-MOD OAK	CH2-703-MOD MAP	43-3/4" x 15-7/8"	12	\$655	\$688		
CH2-705-MOD OAK	CH2-705-MOD MAP	67-3/4" x 13-7/8"	16	\$725	\$761		
CH2-706-MOD OAK	CH2-706-MOD MAP	67-3/4" x 15-7/8"	19	\$757	\$795		
CH2-708-MOD OAK	CH2-708-MOD MAP	79-3/4" x 13-7/8"	15	\$786	\$825		
CH2-709-MOD OAK	CH2-709-MOD MAP	79-3/4" x 15-7/8"	24	\$822	\$864		
CH2-711-MOD OAK	CH2-711-MOD MAP	85-3/4" x 13-7/8"	18	\$815	\$856		
CH2-712-MOD OAK	CH2-712-MOD MAP	85-3/4" x 15-7/8"	27	\$866	\$909		
CH2-714-MOD OAK	CH2-714-MOD MAP	91-3/4" x 13-7/8"	20	\$852	\$895		
CH2-715-MOD OAK	CH2-715-MOD MAP	91-3/4" x 15-7/8"	29	\$901	\$945		
CH2-722-MOD OAK	CH2-722-MOD MAP	43-3/4" x 24-3/8"	20	\$794	\$833	Double-Faced End P	anels
CH2-723-MOD OAK	CH2-723-MOD MAP	43-3/4" x 28-3/8"	24	\$825	\$867		A
CH2-725-MOD OAK	CH2-725-MOD MAP	67-3/4" x 24-3/8"	32	\$946	\$994		
CH2-726-MOD OAK	CH2-726-MOD MAP	67-3/4" x 28-3/8"	38	\$1,019	\$1,070		
CH2-728-MOD OAK	CH2-728-MOD MAP	79-3/4" x 24-3/8"	30	\$1,042	\$1,094		
CH2-729-MOD OAK	CH2-729-MOD MAP	79-3/4" x 28-3/8"	48	\$1,128	\$1,184		
CH2-731-MOD OAK	CH2-731-MOD MAP	85-3/4" x 24-3/8"	36	\$1,087	\$1,142		
CH2-732-MOD OAK	CH2-732-MOD MAP	85-3/4" x 28-3/8"	54	\$1,188	\$1,247		
CH2-734-MOD OAK	CH2-734-MOD MAP	91-3/4" x 24-3/8"	40	\$1,142	\$1,199		
CH2-735-MOD OAK	CH2-735-MOD MAP	91-3/4" x 28-3/8"	58	\$1,241	\$1,303		
Note: Heights note overhung will NOT	d do NOT include the topreceive a top cap.	p cap. End panels that	t are to have c	ontinuous top	os		<b>\</b>

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

#### CHAIR FRAME

The end frames are constructed of legs that are 1-1/4" thick x 2-1/2"W, and a top arm rail that is 1" thick by 2-1/2"W. All parts are constructed from solid oak. All joints are mortised, tenoned, and glued to form a solid unit. Within the end frame is a 1" thick, 45# density particleboard core, veneered panel. The panel is flush to the inside of the end frame leaving a 1/4" inset reveal on the outside face of the frame. The inside face of the end panel receives select plain-sliced, slip-matched oak veneer. The veneer on the outside face of the panel is sketched to form a "framed" appearance. The frame is composed of a horizontal 2-1/2" rift-cut, oak-veneer strip along the bottom edge of the panel, and a horizontal 3-1/4"W rift-cut oak-veneer strip along the top edge, shaped to form a 1-1/2"H internal arc. The solid oak legs of the end frames form the vertical sides of the "frame". Within the frame is select plain-sliced, slip-matched ash veneer. The front stretcher and front seat rail are 3"W x 1" thick solid red oak. The back seat rail is 2-3/4"W x 1" thick solid red oak. The cross stretcher and seat rails are mortised, tenoned, and glued into the side frames.

#### UPHOLSTERED SEAT AND BACK


The seat and back frame are a single piece of 3/4" bent plywood. The seat portion is fitted with a Dimatrol Webbing and then covered with black cambric fabric for comfort. This is then covered with 3-1/2" foam, which is also used on the chair back. The entire seat and back assembly is covered with the specified upholstery fabric except for the underside of the seat which is covered with a black cambric fabric. Brodart upholstery materials meet requirements of the following fire codes: Calif. Technical Bulletin #117 (sec. E part 1); CS-191-53 class 1. Fabrics which meet Calif. Technical Bulletin #133 are available.

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply, 45# density particleboard core with a .050" high-pressure laminate face and a .020" thick backing sheet on the underside. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2"W solid-oak external undercut chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled at a 39° angle with a 3/8" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered at all four corners and corners radiused 1/8".

#### **TABLE LEGS**

Table legs are 2-1/2"W, square shape, glued up face to face from three solid-oak blanks. All glue joints are tight and smooth. All vertical edges receive a 1/4" radius. Legs receive a horizontal vein line 5/32"W x 3/32"D on the two outside faces of the leg positioned 3-11/32" below the top of the legs. This vein line matches the horizontal vein line on the apron. An identical vein line is positioned 3-1/4" above the bottom of the leg. At the bottom of this vein line the two back sides of the leg taper to a dimension of 1-7/8" x 1-7/8" at the bottom of the leg. Legs receive a 1-1/2" diameter adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a countersunk boring which accepts the upper two-thirds of the glide. Table is an apron design with a 3-1/2" x 1" thick apron screwed to the underside of the tabletop. A 5/32"W x 3/32"D vein line is positioned at the bottom front surface of the apron to mirror the top horizontal vein line on the table leg. The legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16" - 18 hex-head bolts which pass through the bracket and engage threaded bushings embedded into the leg and cross-pinned with a 3/16" diameter steel pin.



Chancellor's Series Edge

## The Chancellor's Collections

Catalog No.	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
One Seat Lounge,	Oak Wood								One Sea
CH2-101-S00 OAK	31" x 29-1/2" x 29-3/8"	65	\$2,463	\$2,375	\$2,994	\$3,181	\$3,466	\$3,665	
One Seat Lounge,	Maple Wood								
CH2-101-S00 MAP	31" x 29-1/2" x 29-3/8"	65	\$2,759	\$2,660	\$3,353	\$3,563	\$3,882	\$4,105	
Fabric Requirements	s: 2 yards per chair, Non	-direction	al, 54" wia	le.					

<u>Two Seat Lounge, Oak Wood</u>												
CH2-201-S00 OAK	31" x 53-1/2" x 29-3/8"	110	\$3,488	\$3,310	\$4,553	\$4,875	\$4,832	\$5,110				
Tora Contil norman Marila Wand												
Two Seat Lounge, N	парте илова											
CH2-201-S00 MAP	31" x 53-1/2" x 29-3/8"	110	\$3,907	\$3,706	\$5,099	\$5,460	\$5,413	\$5,723				

Two Seat

Fabric Requirements: 4 yards per chair, Non-directional, 54" wide.

Three Seat Lounge, Oak Wood												
CH2-301-S00 OAK	31" x 77-7/8" x 29-3/8"	162	\$4,401	\$4,133	\$5,998	\$6,480	\$6,035	\$6,382				
Three Seat Lounge, CH2-301-S00 MAP	. <i>Maple Wood</i> 31" x77-7/8" x 29-3/8"	162	\$4,928	\$4,630	\$6,718	\$7,258	\$6,759	\$7,148				



Fabric Requirements: 6 yards per chair, Non-directional, 54" wide.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Round Table	Table with Chamfere	ed Square Legs with	Apron .				
	CH2-610-S00 OAK	CH2-610-S00 MAP	Round Table	16"H x 38" Diameter	70	\$1,854	\$2,076
Square Table	Table with Chamfere		•				
	CH2-621-S00 OAK	CH2-621-S00 MAP	Square Table	16" x 32" x 32"	47	\$1,554	\$1,740
 Rectangular Table	Table with Chamfere	ed Sauare Leas with	Apron				
	CH2-611-S00 OAK	CH2-611-S00 MAP	Rectangular Table	16" x 50" x 26"	60	\$1,450	\$1,624

#### **DESKTOP**

Standard desktops are 1-3/16" thick 3-ply, 45# density, particleboard core, with a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Tops receive a 2"W x 1-3/4" T solid Northern-grown hard maple edge band on the patron side, and edges beveled down at a 20° angle with a 1/2" radius at the leading edge forming a bullnose shape. A 1/4" thick, solid Northern-grown hard maple edge band is applied to the remaining three sides, with top and bottom edges radiused to 1/8". All edges are applied to the desktop after the top and bottom laminate sheets are applied, constituting an external edge band. Desktops are positioned over the end panels of the desk module, flush with the outside edges of the end panels.

#### **UPRIGHT UNIT PANELS**

Desk module end panels are 1" thick, 3-ply, 45# density particleboard core with select plain-sliced maple veneers on both sides. Exposed edges are externally banded with a 1" x 1/16" thick, solid Northern-grown maple edge band. The end panels and front panel are joined and secured with 3/4" x 3/4" thick solid hardwood cleats screwed to the inside surfaces of the panels. The bottom of each end panel receives two adjustable glides to allow leveling of the individual units. Each end panel receives a 3" diameter egress and grommet to provide for wire passage.

#### FRONT PANELS

The front panel is 3/4" thick, comprised of the select plain-sliced face veneers of Northern-grown maple over a 45# density particleboard core. Exposed edges are externally banded with a 3/4" x 1.6 mm thick, solid Northern-grown maple edge band. The front incorporates a 6"H x 3/4"D recessed, ebonized, toe space at the bottom of the panel. The front panel is positioned over the end panels of the desk module, flush with the outside edges of the end panels. Doublewide units have two front panels to give the appearance of two individual units, for a uniform look.

#### OFFSET RESIN PANEL FRONT DESIGN

A tinted, 1/4" thick resin panel accent is attached to the front panels 12"H. Single units have one resin panel accent, while double and square corner units have two. The resin panel is held back 1" from each end of the unit. A 2-1/2" diameter x 1/2" thick metal cap nut is used to bolt the resin panel to the front panel, a felt or rubber washer is used against both surfaces of the resin panel, and loc-tite is used on the bolt to keep the cap nut from turning after positioned. The cap nuts are centered in 3-1/2" from the end of the resin panel and down 3" and 4-1/2". There are four cap nuts on each piece of resin panel (Also see tinted resin panel specifications). The cap nuts are chrome plated or powder-coated as specified (see chrome specifications).

#### CHROME/POWDER COAT DESIGN

A steel bar 1/4" thick x 1-1/4"W is recessed 3/16"D down 3-5/16" from the top of the front panel and run from the left edge to the right edge, and 1-1/2" down from the bottom of this bar a second bar is recessed 3/16"D into the front panel. This second bar is like the first bar except it has a 6" x 1-1/4" x 1/4" protrusion, centered and welded in place and pointing down when placed on the front. Each bar is glued in place so it cannot be removed. The bars are either chrome plated or power-coated as specified. (See chrome specifications).

#### ADJUSTABLE WORK SURFACE

Work surfaces are 1-3/16" thick, 3-ply particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards.

The exposed edge receives a 5/8" thick solid Northern-grown red oak internal edge band in a straight design. The back of the work surface has a black plastic band 1-1/2"W, which projects above the work surface 1/4" to act as a retainer. The work surface is 24-1/2"D and is positioned 1-1/2" away from the front panel, creating a cord drop space. Adjustable work surfaces are available in single wide standing height desks. Work surfaces in standing-height desks (catalog number 73-012) may be positioned at heights of 36", 32", or 27".

#### CHROME PLATING SPECIFICATION


Where "chrome plated" is specified, Brodart uses a decorative chromium electro-plated finish, which protects against tarnish and minimizes scratching.

Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.

#### OFFSET RESIN PANEL SPECIFICATIONS

Unless otherwise specified all offset resin panels are 1/4" thick. The customer must specify the tint color that they require from those offered by Brodart.

The offset resin panel is held in place by 1/4" thick solid wood maple molding on both sides of the resin which is sanded flush with the panel surfaces.



**Epoch Series Edge** 

#### **SHELVES**

Shelves are constructed of 7-ply, furniture grade hardwood veneer-core plywood, with plain-sliced maple face veneer. Exposed edges receive a 1/4" thick, solid maple edge band.


#### **DRAWERS**


Drawers are constructed of solid hardwood with a 1/4" thick wood bottom panel. Drawers have 3-ply particleboard fronts with select maple face veneer. Box drawers have extension slides with 100# load capacity. File drawers have full-extension slides with 100# load capacity.

#### **DESK DIMENSIONS**


Standing-height Desk, overall: 39-3/16"H x 35"W x 31-3/8"D or 39-3/16"H x 70"W x 31-3/8"D.

Sitting-Height Desk, overall: 32-3/16"H x 35"W x 31-3/8"D or 32-3/16"H x 70"W x 31-3/8"D.





Offset Resin Panel Design



Metal "T" Front Design

# Circulation Desks with Offset Resin Panel Fronts, Single-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Wide Des with Patron Serv		59-012-S02 OAK 59-012-S00 OAK	59-012-S02 MAP 59-012-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	140 140	\$3,544 \$3,827	\$3,862 \$4,171
				Inside dimensions: 33"W x 26-3/4"I 7-7/8" patron ledge is at a standing <b>Note</b> : Adjustable-height work surfac at heights of 36", 32" or 27".	height of 39-3/16"H.			
		59-E12-S02 OAK 59-E12-S00 OAK	59-E12-S02 MAP 59-E12-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	125 125	\$3,293 \$3,558	\$3,589 \$3,878
0	0			Inside dimensions: 33"W x 26-3/4"I 7-7/8" patron ledge is at a sitting he <b>Note</b> : Work surface is fixed at 27"H.	ight of 32-3/16"H.			
Single-Wide Des		59-014-S02 OAK 59-014-S00 OAK	59-014-S02 MAP 59-014-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	135 135	\$3,421 \$3,693	\$3,729 \$4,025
0	0			Inside dimensions: 33"W x 26-3/4"I work surface is at a standing height of grommets are located in the work surf	f 39-3/16"H. Two 3" diament	er		
0		59-E14-S02 OAK 59-E14-S00 OAK	59-E14-S02 MAP 59-E14-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front Inside dimensions: 33"W x 26-3/4"I work surface is at a sitting height of 3: grommets are located in the work surf	2-3/16"H. Two 3" diamenter	120 120	\$3,251 \$3,510	\$3,544 \$3,825
Book Return Un	it O O O	59-015-S02 OAK 59-015-S00 OAK	59-015-S02 MAP 59-015-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front Inside dimensions: 33"W x 26-3/4"I work surface is at a standing height 3 finished opening centered in the front of books and a book chute to direct th depressible book truck. (Depressible Two 3" diameter grommets are locate	9-3/16"H. Unit has a 5"H x 12 panel for passage he books over a mobile book truck not included).	135	\$3,944 \$4,259	\$4,298 \$4,642
		59-E15-S02 OAK 59-E15-S00 OAK	59-E15-S02 MAP 59-E15-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front Inside dimensions: 33"W x 26-3/4"I work surface is at a sitting height 32-3 finished opening centered in the front of books and a book chute to direct th depressible book truck. (Depressible Two 3" diameter grommets are located	3/16"H. Unit has a 5"H x 12" panel for passage he books over a mobile book truck not included).	120	\$3,727 \$4,026	\$4,062 \$4,388

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
		Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	140 140	\$3,232 \$3,877	\$3,523 \$4,226	Single-Wide Desk with Patron Service Ledge
		Inside dimensions: 33"W x 26-3/7-7/8" patron ledge is at a standi <b>Note:</b> Adjustable-height work sur at heights of 36", 32" or 27".	ng height of 39-3/16"H.				0
		Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	125 125	\$2,980 \$3,577	\$3,249 \$3,898	
		Inside dimensions: 33"W x 26-3/7-7/8" patron ledge is at a sitting Note: Work surface is fixed at 27	height of 32-3/16"H.				
59C-014-S02 OAK	59C-014-S02 MAP	Desk w/Painted Metal "T" Front	39-3/16" x 35" x 31-3/8"	135	\$3,106	\$3,385	Single-Wide Desk
59C-014-S00 OAK	59C-014-S00 MAP	Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8"	135	\$3,727	\$4,062	without Patron Service Ledge

59C-E14-S02 OAK 59C-E14-S02 MAP Desk w/Painted Metal "T" Front 32-3/16" x 35" x 31-3/8" 120 \$2,939 \$3,203


Inside dimensions: 33"W x 26-3/4"D. The

grommets are located in the work surface.

**59C-E14-S00 OAK 59C-E14-S00 MAP** Desk w/Chrome Metal "T" Front 32-3/16" x 35" x 31-3/8"

Inside dimensions: 33"W x 26-3/4"D. The work surface is at a sitting height of 32-3/16"H. Two 3" diamenter grommets are located in the work surface.

work surface is at a standing height of 39-3/16"H. Two 3" diamenter



\$3,527 \$3,844

 59C-015-S02 OAK
 59C-015-S02 MAP
 Desk w/Painted Metal "T" Front
 39-3/16" x 35" x 31-3/8"
 135
 \$3,631
 \$3,958

 59C-015-S00 OAK
 59C-015-S00 MAP
 Desk w/Chrome Metal "T" Front
 39-3/16" x 35" x 31-3/8"
 135
 \$4,357
 \$4,749

Inside dimensions: 33"W x 26-3/4"D. The work surface is at a standing height 39-3/16"H. Unit has a 5"H x 12"W finished opening centered in the front panel for passage of books and a book chute to direct the books over a mobile depressible book truck. (Depressible book truck not included). Two 3" diameter grommets are located in the work surface.

 59C-E15-S02 OAK
 59C-E15-S02 MAP
 Desk w/Painted Metal "T" Front
 32-3/16" x 35" x 31-3/8"
 120
 \$3,414
 \$3,722

 59C-E15-S00 OAK
 59C-E15-S00 MAP
 Desk w/Chrome Metal "T" Front
 32-3/16" x 35" x 31-3/8"
 120
 \$4,099
 \$4,468

Inside dimensions: 33"W x 26-3/4"D. The work surface is at a sitting height 32-3/16"H. Unit has a 5"H x 12"W finished opening centered in the front panel for passage of books and a book chute to direct the books over a mobile depressible book truck. (Depressible book truck not included). Two 3" diameter grommets are located in the work surface.






Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

# Circulation Desks with Offset Resin Panel Fronts, Single-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Cupboard and Ope	n Shelf	59-121-S02 OAK 59-121-S00 OAK	59-121-S02 MAP 59-121-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	175 175	\$4,975 \$5,371	\$5,422 \$5,854
0				This standing height unit has one fixed shelves. A hidden drawer is positioned the lockable storage compartment. To grommets are located in the work sur	d above wo 3" diameter			
		59-E21-S02 OAK 59-E21-S00 OAK	59-E21-S02 MAP 59-E21-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	160 160	\$4,453 \$4,809	\$4,854 \$5,241
0	This sitting height unit has one fixed and one adjustable shelf. A hidden drawer is positioned above the lockable storage compartment. Two 3" diameter grommets are located in the work surface.							
Full Width Drawer,		59-122-S02 OAK	59-122-S02 MAP	Desk w/Painted Resin Panel Front	39-3/16" x 35" x 31-3/8"	225	\$7,098	\$7,737
Cupboard and Drav	wers	59-122-S00 OAK	59-122-S00 MAP	Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8"	225	\$7,664	\$8,353
				This standing height unit has one full- two file drawers, and a lockable stora compartment. Two 3" diameter grom are located in the work surface. Note: Available in 39-3/16"H only.				



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
	59C-121-S02 MAP 59C-121-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	175 175	\$4,661 \$5,593	\$5,080 \$6,096	Cupboard and Open Shelf
		This standing height unit has one fix shelves. A hidden drawer is position the lockable storage compartment. grommets are located in the work s	ned above Two 3'' diameter				0
	59C-E21-S02 MAP 59C-E21-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	160 160	\$4,141 \$4,968	\$4,513 \$5,415	
		This sitting height unit has one fixe shelf. A hidden drawer is positioned the lockable storage compartment. grommets are located in the work s	d above Two 3'' diameter				
	59C-122-S02 MAP 59C-122-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	225 225	\$6,740 \$8,091	\$7,347 \$8,819	Full Width Drawer, Cupboard and Drawers
		This standing height unit has one fu	ıll-width drawer,				

two file drawers, and a lockable storage compartment. Two 3" diameter grommets are located in the work surface.

Note: Available in 39-3/16"H only.

located in the work surface.

**Cupboard and Drawer Unit** 59C-123-S02 OAK 59C-123-S02 MAP Desk w/Painted Metal "T" Front 39-3/16" x 35" x 31-3/8" 225 \$5,970 \$6,507 59C-123-S00 OAK 59C-123-S00 MAP Desk w/Chrome Metal "T" Front 39-3/16" x 35" x 31-3/8" 225 \$7,165 \$7,810 This standing height unit has one locking box drawer and two file drawers. Cupboard section has two adjustable shelves and locking door on hinges. Two 3" diameter grommets are located in the work surface. 59C-E23-S02 OAK 59C-E23-S02 MAP Desk w/Painted Metal "T" Front 32-3/16" x 35" x 31-3/8" 205 **\$5,141** 59C-E23-S00 OAK 59C-E23-S00 MAP Desk w/Chrome Metal "T" Front 32-3/16" x 35" x 31-3/8" 205 **\$6,169** \$6,724 This sitting height unit has one locking file drawer and one file drawer. Cupboard section has one adjustable shelf and locking door on hinges. Two 3" diameter grommets are

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

# Circulation Desks with Offset Resin Panel Fronts, Single-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Open Shelf and I	Orawer Unit	59-124-S02 OAK 59-124-S00 OAK	59-124-S02 MAP 59-124-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	200 200	\$5,711 \$6,168	\$6,225 \$6,723
0				This standing height unit has one lock and two file drawers. Shelf section has two adjustable shelves, and one fixed Two 3" diameter grommets are locate	s base shelf.			
		59-E24-S02 OAK 59-E24-S00 OAK	59-E24-S02 MAP 59-E24-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	180 180	\$5,041 \$5,444	\$5,494 \$5,934
0				This sitting height unit has one lockab and one file drawer. Shelf section has one adjustable shelf, and one fixed ba Two 3" diameter grommets are locate	ise shelf.			
Cash Drawer Un	it	59-131-S02 OAK 59-131-S00 OAK	59-131-S02 MAP 59-131-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	150 150	\$3,844 \$4,150	\$4,189 \$4,524
0				Inside dimensions: 33"W x 26-3/4"E The work surface is at a standing heigh has locking drawer with a coin and cur Two 3" diameter grommets are locate	nt 39-3/16"H. Desk rency tray.			
		59-E31-S02 OAK 59-E31-S00 OAK	59-E31-S02 MAP 59-E31-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	135 135	\$3,652 \$3,945	\$3,981 \$4,301
0	0			Inside dimensions: 33"W x 26-3/4"I The work surface is at a sitting height is has locking drawer with a coin and cur Two 3" diameter grommets are located	32-3/16"H. Desk rency tray.			
ADA Station		59-E32-S00 OAK	59-E32-S00 MAP	Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 42-1/8"	185	\$2,771	\$3,020
0				The sitting height ADA transaction stated designed to provide wheelchair access on the patrons' side. The knee space on the patrons' side is 22-1/4" and of staff side is 16". Two 3" diameter groare located in the work surface. One 3 egress with sleeve is located in each et Note: Available in 32-3/16"H only.	s depth on the mmets -1/2" diameter			

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sit	tting
	59C-124-S02 MAP 59C-124-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	200 200	\$5,398 \$6,477	\$5,884 \$7,060	Open Shelf and Drawer	r Unit
		This standing height unit has one lot and two file drawers. Shelf section two adjustable shelves, and one fix Two 3" diameter grommets are loc	has ed base shelf.					
59C-E24-S02 OAK	59C-E24-S02 MAP	Desk w/Painted Metal "T" Front	32-3/16" x 35" x 31-3/8"	180	\$4,728	\$5,153		
59C-E24-S00 OAK	59C-E24-S00 MAP	Desk w/Chrome Metal "T" Front	32-3/16" x 35" x 31-3/8"	180	\$5,673	\$6,183		
		This sitting height unit has one lock and one file drawer. Shelf section h one adjustable shelf, and one fixed Two 3" diameter grommets are loc	as base shelf.				0	
	59C-131-S02 MAP 59C-131-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	150 150	\$3,530 \$4,235	\$3,848 \$4,616	Cash Drawer	r Unit
370-131-300 OAK	370-131-300 WIAI	Inside dimensions: 33"W x 26-3/4 The work surface is at a standing he has locking drawer with a coin and Two 3" diameter grommets are loc	H"D. eight 39-3/16"H. Desk currency tray.	130	Ψ4, <b>2</b> 33	\$4,010	0	
	59C-E31-S02 MAP 59C-E31-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	135 135	\$3,340 \$4,009	\$3,640 \$4,369		
		Inside dimensions: 33"W x 26-3/4 The work surface is at a sitting heighas locking drawer with a coin and Two 3" diameter grommets are loc	ht 32-3/16"H. Desk currency tray.				0	

59C-E32-S00 OAK 59C-E32-S00 MAP Desk w/Chrome Metal "T" Front

32-3/16" x 35" x 42-1/8" 185 \$2,771 \$3,020

**ADA Station** 

The sitting height ADA transaction station is designed to provide wheelchair access on the patrons' side. The knee space depth on the patrons' side is 22-1/4" and on the staff side is 16". Two 3" diameter grommets are located in the work surface. One 3-1/2" diameter egress with sleeve is located in each end panel for wire passage. Note: Available in 32-3/16"H only.



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

# Circulation Desks with Offset Resin Panel Fronts, Single-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Full Width Draw	wer Unit	59-133-S02 OAK 59-133-S00 OAK	59-133-S02 MAP 59-133-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	160 160	\$4,092 \$4,420	\$4,460 \$4,818
0				This standing height drawer unit has a 10"H x 32-7/8"W x 18-1/4"D. Two grommets are located in the work surf Note: Available in 39-3/16"H only.	3" diameter			

Full Width Drawer and Cupboard Unit



59-135-S02 OAK 59-135-S02 MAP Desk w/Painted Resin Panel Front 39-3/16" x 35" x 31-3/8" 220 \$5,199 \$5,667 59-135-S00 OAK 59-135-S00 MAP Desk w/Chrome Resin Panel Front 39-3/16" x 35" x 31-3/8" 220 \$5,615 \$6,121

This standing height unit has a full-width drawer 10"H x 32-7/8"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Hinged doors have a catch, lock and door pulls. Two 3" diameter grommets are located in the work surface.

Note: Available in 39-3/16"H only.

Discharge Unit



**59-172-S02 OAK 59-172-S02 MAP** Desk w/Painted Resin Panel Front 39-3/16" x 35" x 31-3/8" 165 \$5,275 \$5,749 \$59-172-S00 OAK 59-172-S00 MAP Desk w/Chrome Resin Panel Front 39-3/16" x 35" x 31-3/8" 165 \$5,696 \$6,209

These standing height units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 39-3/16"H.

Note: Standing-height roll unders do not work with this unit.

59-E72-S02 OAK 59-E72-S00 OAK 59-E72-S02 MAP 59-E72-S00 MAP Desk w/Painted Resin Panel Front
Desk w/Chrome Resin Panel Front
32-3/16" 3

32-3/16" x 35" x 31-3/8" 145 \$5,028 \$5,480 32-3/16" x 35" x 31-3/8" 145 \$5,431 \$5,920

These sitting height units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 32-3/16"H.

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
59C-133-S02 OAK	59C-133-S02 MAP	Desk w/Painted Metal "T" Front	39-3/16" x 35" x 31-3/8"	160	\$3,778	\$4,119	Full Width Dra	wer Unit
59C-133-S00 OAK	59C-133-S00 MAP	Desk w/Chrome Metal "T" Front	39-3/16" x 35" x 31-3/8"	160	\$4,533	\$4,941		
		This standing height drawer unit ha 10"H x 32-7/8"W x 18-1/4"D. To grommets are located in the work s <b>Note</b> : Available in 39-3/16"H onl	wo 3" diameter urface.					

59C-135-S02 OAK 59C-135-S02 MAP 59C-135-S00 OAK 59C-135-S00 MAP

 Desk w/Painted Metal "T" Front
 39-3/16" x 35" x 31-3/8"
 220
 \$4,886
 \$5,326

 Desk w/Chrome Metal "T" Front
 39-3/16" x 35" x 31-3/8"
 220
 \$5,865
 \$6,393

 This standing height unit has a full-width drawer

10"H x 32-7/8"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Hinged doors have a catch, lock and door pulls. Two 3" diameter grommets are located in the work surface.

Note: Available in 39-3/16"H only.

Full Width Drawer and Cupboard Unit



59C-172-S02 OAK 59C-172-S02 MAP Desk w/Painted Metal "T" Front 59C-172-S00 OAK 59C-172-S00 MAP Desk w/Chrome Metal "T" Front

39-3/16" x 35" x 31-3/8" 165 \$4,959 \$5,405 39-3/16" x 35" x 31-3/8" 165 \$5,951 \$6,487

These standing height units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 39-3/16"H.

Discharge Unit

**Note:** Standing-height roll unders do not work with this unit.

59C-E72-S02 OAK 59C-E72-S02 MAP 59C-E72-S00 OAK 59C-E72-S00 MAP

 Desk w/Painted Metal "T" Front
 32-3/16" x 35" x 31-3/8"
 145
 \$4,714
 \$5,139

 Desk w/Chrome Metal "T" Front
 32-3/16" x 35" x 31-3/8"
 145
 \$5,659
 \$6,168

These sitting height units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 32-3/16"H.



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

# Circulation Desks with Offset Resin Panel Fronts, Single-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Open Shelf Unit		59-174-S02 OAK 59-174-S00 OAK	59-174-S02 MAP 59-174-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	175 175	\$4,130 \$4,460	\$4,502 \$4,861
0				This standing height unit has a full-dep shelf and two full-depth adjustable sho Two 3" diameter grommets are locate the work surface.	elves.			
		59-E74-S02 OAK 59-E74-S00 OAK	59-E74-S02 MAP 59-E74-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	155 155	\$3,767 \$4,069	\$4,106 \$4,435
0				This sitting height unit has a full-depth shelf and two full-depth adjustable sh. Two 3" diameter grommets are locate the work surface.	elves.			
Cupboard Unit		59-176-S02 OAK 59-176-S00 OAK	59-176-S02 MAP 59-176-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	200 200	\$4,812 \$5,198	\$5,246 \$5,665
				This standing height unit has a full-dep shelf and two full-depth adjustable she have a catch, lock and door pulls. Two are located in the work surface.	elves. Hinged doors			
		59-E76-S02 OAK 59-E76-S00 OAK	59-E76-S02 MAP 59-E76-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"	180 180	\$4,431 \$4,785	\$4,830 \$5,216
0	0			This sitting height unit has a full-depth shelf and one full-depth adjustable sh ave a catch, lock and door pulls. Two 3 are located in the work surface.	elf. Hinged doors h			
Full Width Drawe Open Shelves	r and	59-234-S02 OAK 59-234-S00 OAK	59-234-S02 MAP 59-234-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8" 39-3/16" x 35" x 31-3/8"	180 180	\$4,668 \$5,042	\$5,088 \$5,495
				This standing height unit has a full-wid 10"H x 32-7/8"W x 18-3/4"D. Also and one adjustable, full-depth shelf. 1 grommets are located in the work surfa	, one fixed Two 3'' diameter			
		59-E34-S02 OAK 59-E34-S00 OAK	59-E34-S02 MAP 59-E34-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"		\$4,342 \$4,691	\$4,732 \$5,113
0				This sitting height unit has a full-width 10"H x 32-7/8"W x 18-3/4"D. Also, and one adjustable, full-depth shelf. I grommets are located in the work surface.	, one fixed Two 3'' diameter			

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
59C-174-S02 OAK 59C-174-S00 OAK	59C-174-S02 MAP 59C-174-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front			\$3,818 \$4,580	\$4,162 \$4,993	Open Shelf Unit
		This standing height unit has a full shelf and two full-depth adjustable Two 3" diameter grommets are loo the work surface.	e shelves.				
59C-E74-S02 OAK 59C-E74-S00 OAK	59C-E74-S02 MAP 59C-E74-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front		155 155	\$3,454 \$4,143	\$3,765 \$4,516	
		This sitting height unit has a full-de shelf and two full-depth adjustable. Two 3" diameter grommets are loot the work surface.	e shelves.				
59C-176-S02 OAK 59C-176-S00 OAK	59C-176-S02 MAP 59C-176-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front		200 200	\$4,501 \$5,399	\$4,905 \$5,885	Cupboard Unit
		This standing height unit has a full shelf and two full-depth adjustable have a catch, lock and door pulls. are located in the work surface.	e shelves. Hinged doors				
59C-E76-S02 OAK 59C-E76-S00 OAK	59C-E76-S02 MAP 59C-E76-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front		180 180	\$4,118 \$4,942	\$4,489 \$5,387	
		This sitting height unit has a full-de shelf and one full-depth adjustabl ave a catch, lock and door pulls. To are located in the work surface.	e shelf. Hinged doors h				
59C-234-S02 OAK 59C-234-S00 OAK		Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front			\$4,356 \$5,226	\$4,748 \$5,696	Full Width Drawer and Open Shelves
		This standing height unit has a full 10"H x 32-7/8"W x 18-3/4"D. A full-depth shelf. Two 3" diameter	also, one fixed and one adjusta		ce.		
59C-E34-S02 OAK 59C-E34-S00 OAK	59C-E34-S02 MAP 59C-E34-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front			\$4,030 \$4,837	\$4,393 \$5,272	
		This sitting height unit has a full-w 10"H x 32-7/8"W x 18-3/4"D. A full-depth shelf. Two 3" diameter	also, one fixed and one adjusta		ce.		

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

# Circulation Desks with Offset Resin Panel Fronts, Single-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Media Storag	je Unit	59-236-S02 OAK	59-236-S02 MAP	Desk w/Painted Resin Panel Front	39-3/16" x 35" x 31-3/8"	225	\$6,485	\$7,069
que la		59-236-S00 OAK	59-236-S00 MAP	Desk w/Chrome Resin Panel Front	39-3/16" x 35" x 31-3/8"	225	\$7,004	\$7,634
				This standing height unit has four full- 8-1/2"H x 33"W x 24"D with each containing five compartments for med				
	_	59-E36-S02 OAK	59-E36-S02 MAP	Desk w/Painted Resin Panel Front	32-3/16" x 35" x 31-3/8"	205	\$6,034	\$6,577
	-	59-E36-S00 OAK	59-E36-S00 MAP	Desk w/Chrome Resin Panel Front	32-3/16" x 35" x 31-3/8"	205	\$6,517	\$7,104
0	3/3/3	1		This sitting height unit has three full-w 8-1/2"H x 33"W x 24"D with each containing five compartments for med				

 $Please\ specify\ Wood\ Finish\ (Table\ 1),\ High-Pressure\ Laminate\ (Table\ 2),\ Metal\ Color\ (Table\ 3)\ and\ Resin\ Option\ (Table\ 6).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4,\ GEN\ 5\ and\ GEN\ 6.$ 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
59C-236-S02 OAK 59C-236-S00 OAK	59C-236-S02 MAP 59C-236-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front			\$6,051 \$7,260	\$6,596 \$7,913	Media S	torage Unit
		This standing height unit has four f 8-1/2"H x 33"W x 24"D with eac containing five compartments for r	:h				18/8/8/8	0
59C-E36-S02 OAK 59C-E36-S00 OAK	59C-E36-S02 MAP 59C-E36-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 35" x 31-3/8" 32-3/16" x 35" x 31-3/8"		\$5,599 \$6,719	\$6,103 \$7,324		
		This sitting height unit has three fu 8-1/2"H x 33"W x 24"D with eac containing five compartments for r	h				8/8/8	•

# Circulation Desks with Offset Resin Panel Fronts, Double-Wide

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Des with Patron Servi		59-011-S02 OAK	59-011-S02 MAP 59-011-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 70" x 31-3/8" 39-3/16" x 70" x 31-3/8"	245 245	\$6,120 \$6,609	\$6,671 \$7,204
				Work Surface at 35-1/2"H Inside dimensions are 68"W x 26-3, The 7-7/8"D patron ledge is at a sta Two 3" diameter grommets are local <b>Note</b> : Standing-height roll unders d	nding height of 39-3/16". ted in the work surface.			
		59-E11-S02 OAK 59-E11-S00 OAK	59-E11-S02 MAP 59-E11-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 70" x 31-3/8" 32-3/16" x 70" x 31-3/8"	210 210	\$5,747 \$6,206	\$6,265 \$6,765
0				Desk with Patron Service Ledge Work Surface at 28-1/2"H Inside dimensions are 68"W x 26-3. The 7-7/8"D patron ledge is at a sitt Two 3" diameter grommets are local	ing height of 32-3/16".			
		ll .	59-011-SE2 MAP 59-011-SEA MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 70" x 31-3/8" 39-3/16" x 70" x 31-3/8"	245 245	\$6,132 \$6,623	\$6,684 \$7,219
0	V			Desk with Patron Service Ledge Work Surface at 28-1/2"H Inside dimensions are 68"W x 26-3/ The 7-7/8"D patron ledge is at a sta Two 3" diameter grommets are local <b>Note</b> : Standing-height roll unders d	/4"D. Inding height of 39-3/16". Ited in the work surface.	_ 10	<b>V</b> 0/4-0	*/ <u>-</u> /-/-
Double-Wide Des			59-013-S02 MAP 59-013-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 70" x 31-3/8" 39-3/16" x 70" x 31-3/8"	230 230	\$6,015 \$6,498	\$6,557 \$7,083
0	0			Inside dimensions are 68"W x 26-3, The work surface is at 39-3/16" H.1 diameter grommets are located in th	wo 3"			
			59-E13-S02 MAP 59-E13-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 70" x 31-3/8" 32-3/16" x 70" x 31-3/8"	195 195	\$5,726 \$6,184	\$6,241 \$6,741
0	0			Inside dimensions are 68"W x 26-3/ The work surface is at 32-3/16" H. T diameter grommets are located in th	wo 3''			

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.


Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
59C-011-S02 OAK 59C-011-S00 OAK	59C-011-S02 MAP 59C-011-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front Work Surface at 35-1/2"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a s Two 3" diameter grommets are loo Note: Standing-height roll unders	39-3/16" x 70" x 31-3/8" 39-3/16" x 70" x 31-3/8" 3/4"D. standing height of 39-3/16". cated in the work surface.	245	\$5,494 \$6,593	\$5,988 \$7,186	Double-Wide Desk with Patron Service Ledge
59C-E11-S02 OAK 59C-E11-S00 OAK	59C-E11-S02 MAP 59C-E11-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front Desk with Patron Service Ledge Work Surface at 28-1/2"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a s Two 3" diameter grommets are loc	32-3/16" x 70" x 31-3/8" 3/4"D. sitting height of 32-3/16".	210 210	\$5,121 \$6,145	\$5,582 \$6,698	
59C-011-SE2 OAK 59C-011-SEA OAK	59C-011-SE2 MAP 59C-011-SEA MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front Desk with Patron Service Ledge Work Surface at 28-1/2"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a s Two 3" diameter grommets are loc Note: Standing-height roll unders	.3/4"D. standing height of 39-3/16". cated in the work surface.	245 245	\$5,504 \$6,605	\$5,999 \$7,199	
59C-013-S02 OAK 59C-013-S00 OAK	59C-013-S02 MAP 59C-013-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front Inside dimensions are 68"W x 26-	39-3/16" x 70" x 31-3/8"		\$5,391 \$6,470	\$5,876 \$7,052	Double-Wide Desk without Patron Service Ledge

The work surface is at 39-3/16" H. Two 3" diameter grommets are located in the work surface.

 59C-E13-S02 OAK
 59C-E13-S02 MAP
 Desk w/Painted Metal "T" Front 32-3/16" x 70" x 31-3/8"
 195
 \$5,101
 \$5,559

 59C-E13-S00 OAK
 59C-E13-S00 MAP
 Desk w/Chrome Metal "T" Front 32-3/16" x 70" x 31-3/8"
 195
 \$6,119
 \$6,670


Inside dimensions are 68"W x 26-3/4"D. The work surface is at 32-3/16" H. Two 3" diameter grommets are located in the work surface.



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

# Circulation Desks with Offset Resin Panel Fronts, Double-Wide

Standing Sittin	Oak 9 Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Double Pedesta Work Desk	59-E37-S02 OAK 59-E37-S00 OAK	59-E37-S02 MAP 59-E37-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front Inside dimensions are 68"W x 26-3. This sitting height unit has two drawe on each side consisting of one lockir one file drawer with hanging file rack Two center drawers are mounted bet Two 3" diameter grommets are loca Note: Available in 32-3/16" H only	/4"D. er pedestals, one mounted ng drawer at top; at bottom. ween the two pedestals. ted in the work surface.	260 260	\$9,163 \$9,896	\$9,987 \$10,786



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
59C-E37-S02 OAK 59C-E37-S00 OAK	59C-E37-S02 MAP 59C-E37-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front		260 260	\$8,855 \$10,625	\$9,652 \$11,581	Double-Wide Do	work Desk
		Inside dimensions are 68"W x 26- This sitting height unit has two drawn each side consisting of one lock one file drawer with hanging file ra Two center drawers are mounted b Two 3" diameter grommets are lock Note: Available in 32-3/16" Hor	wer pedestals, one mounted king drawer at top; ck at bottom. etween the two pedestals. cated in the work surface.					

**Double-Wide Single Pedestal** \$8,239 59C-238-S02 OAK 59C-238-S02 MAP Desk w/Painted Metal "T" Front 39-3/16" x 70" x 31-3/8" 230 \$7,559 **59C-238-S00 OAK 59C-238-S00 MAP** Desk w/Chrome Metal "T" Front 39-3/16" x 70" x 31-3/8" 230 \$9,068 \$9,885 Work Desk Inside dimensions are 68"W x 26-3/4"D. This standing height unit has one drawer pedestal mounted on the left side consisting of one locking drawer at top; two file drawers with Pendaflex hangers at the bottom. Two 3" diameter grommets are located in the work surface. **59C-E38-S02 OAK 59C-E38-S02 MAP** Desk w/Painted Metal "T" Front 32-3/16" x 70" x 31-3/8" 195 \$6,990 \$7,619 **59C-E38-S00 OAK 59C-E38-S00 MAP** Desk w/Chrome Metal "T" Front 32-3/16" x 70" x 31-3/8" 195 \$8,386 \$9,141 Inside dimensions are 68"W x 26-3/4"D.

This sitting height unit has one drawer pedestal mounted on the left side consisting of one locking file drawer at top; one file drawer at the bottom, both with hanging file racks. Two 3" diameter grommets are located in the work surface.

# Circulation Desks with Offset Resin Panel Fronts, Corner

Standing Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price			
90 Degree Multi-Purpose Corner	59-010-S02 OAK 59-010-S00 OAK	59-010-S02 MAP 59-010-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 71-3/4" x 30" 39-3/16" x 71-3/4" x 30"		\$10,065 \$10,868				
			This unit is a standing height unit and has a 29-5/16"W port area. Storage shelves in the two angled areas to the left and right of the desk module. One 3" diameter gr is located in the work-surface top. One 3-1/2" diameter egress with sleeve is locate end panel for wire passage.							
	59-E10-S02 OAK 59-E10-S00 OAK	59-E10-S02 MAP 59-E10-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 71-3/4" x 30" 32-3/16" x 71-3/4" x 30"	215 215	\$9,953 \$10,750	\$10,849 \$11,717			
	0		This unit is a sitting height unit and h in the two angled areas to the left an is located in the work-surface top. O end panel for wire passage.	d right of the desk module. One	3" dian	neter gromr	net			
90 Degree Multi-Purpose Corne with Patron Service Ledge		59-017-S02 MAP 59-017-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 71-3/4" x 30" 39-3/16" x 71-3/4" x 30"		\$11,693 \$12,412	-			
			This unit is a standing height unit and is at a height of 39-3/16". Work su areas to the left and right of the mod top. One 3-1/2"diameter egress with the standard or the standard of the sta	rface is at 35"H. Storage shelvule. One 3" diameter grommet	es are lo is locate	cated in the d in the wo	two angled rk surface			
	59-E17-S02 OAK 59-E17-S00 OAK	59-E17-S02 MAP 59-E17-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 71-3/4" x 30" 32-3/16" x 71-3/4" x 30"		\$11,564 \$12,254				
	0		This unit is a sitting height unit and height of 32-3/16". Work surface is to the left and right of the module. One 3-1/2" diameter egress with si	at 28"H. Storage shelves are one 3" diameter grommet is loc	located in ated in th	n the two ar ne work sur	ngled areas face top.			
90 Degree Open Curved Corner with Patron Service Ledge	59-040-S02 OAK 59-040-S00 OAK	59-040-S02 MAP 59-040-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 70-1/8" x 30" 39-3/16" x 70-1/8" x 30"		\$12,998 \$14,037				
0 0			The 7-7/8"D patron ledge is at a he This unit is a sitting height unit and h two angled areas to the left and right the work surface top. One 3-12" dia passage.	as a 26-5/8"W port area. Sto t of the desk module. One 3" di	rage shel ameter g	ves are locarommet is	ocated in			
		59-E40-S02 MAP 59-E40-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 70-1/8" x 30" 32-3/16" x 70-1/8" x 30"		\$12,855 \$13,882	-			
	0		The 7-7/8"D patron ledge is at a he This unit is a sitting height unit and h two angled areas to the left and right the work surface top. One 3-12" dia passage.	as a 26-5/8"W port area. Sto t of the desk module. One 3" di	rage shel ameter g	ves are loca rommet is	ocated in			
			ressure Laminate (Table 2), Metal Co be found on pages GEN 4, GEN 5 and							

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
59C-010-S02 OAK 59C-010-S00 OAK	59C-010-S02 MAP 59C-010-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 71-3/4" x 30" 39-3/16" x 71-3/4" x 30"	250 250	\$9,296 \$11,155	\$10,132 \$12,159	90 Degree Multi-Purpose Corner
		This unit is a standing height unit a located in the two angled areas to grommetis located in the work-sur located in each end panel for wire	the left and right of the desk m face top. One 3-1/2" diamete	odule. C	ne 3'' dia	neter	
59C-E10-S02 OAK 59C-E10-S00 OAK	59C-E10-S02 MAP 59C-E10-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 71-3/4" x 30" 32-3/16" x 71-3/4" x 30"	215 215	\$9,179 \$11,017	\$10,005 \$12,008	
		This unit is a sitting height unit and in the two angled areas to the left is located in the work-surface top. end panel for wire passage.	and right of the desk module. C	ne 3'' d	iameter gr	ommet	
59C-017-S02 OAK 59C-017-S00 OAK	59C-017-S02 MAP 59C-017-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 71-3/4" x 30" 39-3/16" x 71-3/4" x 30"		\$10,365 \$12,199		90 Degree Multi-Purpose Corner with Patron Service Ledge
		This unit is a standing height unit a is at a height of 39-3/16". Work angled areas to the left and right o work surface top. One 3-1/2"dia wire passage.	surface is at 35"H. Storage sh f the module. One 3" diameter	elves are gromm	e located ir et is locate	the two ed in the	
59C-E17-S02 OAK 59C-E17-S00 OAK	59C-E17-S02 MAP 59C-E17-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 71-3/4" x 30" 32-3/16" x 71-3/4" x 30"		-	\$11,102 \$13,010	
		This unit is a sitting height unit and a height of 32-3/16". Work sur areas to the left and right of the m top. One 3-1/2" diameter egress	face is at 28"H. Storage shelve odule. One 3" diameter gromr	es are lo net is lo	cated in th	e two angle e work surfa	d 0
59C-040-S02 OAK 59C-040-S00 OAK	59C-040-S02 MAP 59C-040-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front			\$11,550 \$13,860	-	90 Degree Open Curved Corner with Patron Service Ledge
		The 7-7/8"D patron ledge is at a late of the two angled areas to the left located in the work surface top. Or panel for wire passage.	I has a 26-5/8"W port area. S and right of the desk module. C	torage s ne 3'' d	helves are iameter gr	located ommet is	
59C-E40-S02 OAK 59C-E40-S00 OAK	59C-E40-S02 MAP 59C-E40-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 70-1/8" x 30" 32-3/16" x 70-1/8" x 30"			\$12,433 \$14,921	
		The 7-7/8"D patron ledge is at a lath this unit is a sitting height unit and angled areas to the left and right of surface top. One 3-12" diameter	I has a 26-5/8"W port area. S If the desk module. One 3" dia egress with sleeve is located in	torage s meter gr each er	shelves are commet is l and panel fo	ocated in th r wire passa	ne work 0 0 gge.
	Ple	ease specify Wood Finish (Table 1), Details can	High-Pressure Laminate (Table found on pages GEN 4 and		nd Metal C	olor (Table	3).

# Circulation Desks with Offset Resin Panel Fronts, Corner

Standing Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
90 Degree Open Curved Corner	59-041-S02 OAK 59-041-S00 OAK	59-041-S02 MAP 59-041-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 70-1/8" x 30" 39-3/16" x 70-1/8" x 30"		\$12,696 \$13,710	-
0 0			Standing height unit with work surfact shelves are located in the two angled diameter grommet is located in the valued in each end panel for wire particular.	ce is at 39-3/16"H. Unit has 2 d areas to the left and right of th work-surface top. One 3-1/2"	6-5/8''V e desk m	V port area. nodule. One	Storage
		59-E41-S02 MAP 59-E41-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 70-1/8" x 30" 32-3/16" x 70-1/8" x 30"		\$12,509 \$13,511	•
			Sitting height unit with work surface shelves are located in the two angled diameter grommet is located in the vis located in each end panel for wire	d areas to the left and right of the vork-surface top. One 3-1/2"	e desk m	nodule. One	e 3"
60 Degree Curved Corner with Patron Service Ledge		59-047-S02 MAP 59-047-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 80-3/4" x 30" 39-3/16" x 80-3/4" x 30"		\$14,984 \$16,182	•
			The 7-7/8"D patron ledge is at a hei 35-7/16"H. Unit has 49-1/16" W p to the left and right of the desk modu top. One 3-1/2" diameter egress with the desk modulation of the desk modulation.	oort area. Storage shelves are loud. One 3" diameter grommet	ocated in	the two and in the wor	gled areas k surface
	59-E47-S02 OAK 59-E47-S00 OAK	59-E47-S02 MAP 59-E47-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 80-3/4" x 30" 32-3/16" x 80-3/4" x 30"		\$14,818 \$16,002	-
			The 7-7/8"D patron ledge is at a here 35-7/16"H. Unit has 49-1/16" Wight to the left and right of the desk modutop. One 3-1/2" diameter egress with	oort area. Storage shelves are loue. One 3" diameter grommet	ocated in	the two and in the wor	gled areas k surface
60 Degree Curved Corner		59-048-S02 MAP 59-048-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 80-3/4" x 30" 39-3/16" x 80-3/4" x 30"		\$14,447 \$15,601	
0 0			Standing height unit with work surfact shelves are located in the two angled diameter grommet is located in the v located in each end panel for wire pa	l areas to the left and right of th vork surface top. One 3-1/2" o	ie desk m	nodule. One	3"
		59-E48-S02 MAP 59-E48-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	32-3/16" x 80-3/4" x 30" 32-3/16" x 80-3/4" x 30"		\$14,279 \$15,421	•
	Plaasa specify Wood F	inich (Tahlo 1) Lliak De	Standing height unit with work surfar shelves are located in the two angled diameter grommet is located in the v located in each end panel for wire pa essure Laminate (Table 2), Metal Co	d areas to the left and right of th work surface top. One 3-1/2" o issage.	ie desk n	nodule. One	3"

and Resin Option (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD		Oak Maple Price Price	Ctonding Citting
59C-041-S02 OAK 59C-041-S00 OAK	59C-041-S02 MAP 59C-041-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front			,247 \$12,259 ,496 \$14,711	• •
		Standing height unit with work sur Storage shelves are located in the One 3" diameter grommet is loca with sleeve is located in each end	two angled areas to the left and ted in the work-surface top. On	d right of the	desk module.	0 0
59C-E41-S02 OAK 59C-E41-S00 OAK	59C-E41-S02 MAP 59C-E41-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 70-1/8" x 30" 32-3/16" x 70-1/8" x 30"		,077 \$12,074 ,294 \$14,490	
		Sitting height unit with work surfact shelves are located in the two ang diameter grommet is located in the sleeve is located in each end pane	led areas to the left and right of e work-surface top. One 3-1/2	the desk mo	dule. One 3"	
59C-047-S02 OAK 59C-047-S00 OAK	59C-047-S02 MAP 59C-047-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	39-3/16" x 80-3/4" x 30" 39-3/16" x 80-3/4" x 30"		,795 \$15,037 ,553 \$18,042	
370-047-300 OAK	370-047-300 IVIAF	The 7-7/8"D patron ledge is at a is at 35-7/16"H. Unit has 49-1/2 angled areas to the left and right to the work surfacetop. One 3-1/2" for wire passage.	height of 39-3/16". Standing I 16" W port area. Storage shelve of the desk module. One 3" dia	height unit wi es are located meter gromm	ith work surface d in the two net is located in	
59C-E47-S02 OAK 59C-E47-S00 OAK	59C-E47-S02 MAP 59C-E47-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front	32-3/16" x 80-3/4" x 30" 32-3/16" x 80-3/4" x 30"		,627 \$14,854 ,353 \$17,824	
		The 7-7/8"D patron ledge is at a 35-7/16"H. Unit has 49-1/16" to the left and right of the desk motop. One 3-1/2" diameter egress	N port area. Storage shelves are odule. One 3" diameter gromm	e located in the et is located i	he two angled a in the work surfa	reas
59C-048-S02 OAK 59C-048-S00 OAK	59C-048-S02 MAP 59C-048-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front				3
		Standing height unit with work sur Storage shelves are located in the One 3" diameter grommet is loca with sleeve is located in each end	two angled areas to the left an ited in the work surface top. On panel for wire passage.	d right of the e 3-1/2'' dia	desk module. ameter egress	
59C-E48-S02 OAK 59C-E48-S00 OAK	59C-E48-S02 MAP 59C-E48-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front				
		Standing height unit with work sur shelves are located in the two ang diameter grommet is located in the located in each end panel for wire	pled areas to the left and right one work surface top. One 3-1/2 passage.	f the desk mo !'' diameter e	odule. One 3'' egress with sleev	e is 0 0
	Ple	ase specify Wood Finish (Table 1), Details can b	High-Pressure Laminate (Tab be found on pages GEN 4 and 0		etal Color (Table	23).

# Circulation Desks with Offset Resin Panel Fronts, Corner

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
90 Degree Square Cor	ner Unit	59-150-S02 OAK 59-150-S00 OAK	59-150-S02 MAP 59-150-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front	39-3/16" x 30" x 30" 39-3/16" x 30" x 30"	160 160	\$6,959 \$7,513	\$7,585 \$8,189
0 0				This square corner unit is used to form One 3" diameter egress is located in a continuous ABS tube.		•	h	
	0	59-E50-S02 OAK 59-E50-S00 OAK	59-E50-S02 MAP 59-E50-S00 MAP	Desk w/Painted Resin Panel Front Desk w/Chrome Resin Panel Front This square corner unit is used to form One 3" diameter egress is located in a a continuous ABS tube.	0 0	,	\$5,744 \$6,205 h	\$6,261 \$6,763

 $Please\ specify\ Wood\ Finish\ (Table\ 1),\ High-Pressure\ Laminate\ (Table\ 2),\ Metal\ Color\ (Table\ 3)\ and\ Resin\ Option\ (Table\ 6).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4,\ GEN\ 5\ and\ GEN\ 6.$ 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
59C-150-S02 OAK	59C-150-S02 MAP	Desk w/Painted Metal "T" Front	39-3/16" x 30" x 30"	160	\$6,333	\$6,903	90 Degree Square (	Corner Unit
59C-150-S00 OAK	59C-150-S00 MAP	Desk w/Chrome Metal "T" Front	39-3/16" x 30" x 30"	160	\$7,599	\$8,284		
		This square corner unit is used to fo One 3" diameter egress is located i a continuous ABS tube.		•			0 0	
59C-E50-S02 OAK 59C-E50-S00 OAK	59C-E50-S02 MAP 59C-E50-S00 MAP	Desk w/Painted Metal "T" Front Desk w/Chrome Metal "T" Front This square corner unit is used to fo One 3" diameter egress is located in a continuous ABS tube.	0 0	•		\$5,581 \$6,696	0	0

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Detachable End Panels (Pair)	59-178-S00 OAK	59-178-S00 MAP	Detachable End Panels (Pair) End panels are 1" thick, 3-ply, 45# particleboard core with plain-sliced veneers. Exposed edges are external with 1.6mm thick, Northern-grown C	oak or maple ly banded	52	\$1,804	\$1,966
	59-E78-S00 OAK	59-E78-S00 MAP	Detachable End Panels (Pair) End panels are 1" thick, 3-ply, 45# ( particleboard core with plain-sliced veneers. Exposed edges are external  with 1.6mm thick, Northern-grown C	oak or maple Ily banded	42	\$1,532	\$1,670
Single-Wide Add On 7"H Patron Ledge	59-196-S00 OAK	59-196-S00 MAP	Single-Wide Add On 7"H Patron Ledge Unit is designed to be added onto a without a patron ledge. The Patron Leto the desktop by means of #8 x 2-1. the work surface into the ledge asser	edge Assembly will attach /2" screws inserted through	10	\$974	\$1,061
Double-Wide Add On 7"H Patron Ledge	59-197-S00 OAK	59-197-S00 MAP	Double-Wide Add On 7"H Patron Ledge Unit is designed to be added onto a without a patron ledge. The Patron L		20	\$1,099	\$1,198

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

to the desktop by means of #8 x 2-1/2" screws inserted through

the work surface into the ledge assembly.

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core or with a .050" high-pressure laminate with a .020" thick phenolic backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2" wide solid maple external chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled down at a  $20^{\circ}$  angle with a 1/2" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered at all four corners and corners radiused 1/8".

#### LEGS (CHROME)


Legs are 2-1/2" round, 16-gauge steel tubing. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Leg and plate are painted or plated to match the leg (see chrome specifications) and have no sharp edges. The plate is attached to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The bracket is attached to the leg plate and leg using metal to metal fasteners. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

#### LEG (WIRE MANAGEMENT)


A 1/2" wide slot is located in the back of the leg underneath the angle support bracket, 5/8" down from the top of the leg to within 3-3/8" of the bottom of the leg. To insert cords, a snap on slot cover of 1/8" bent metal and finished to match the leg is supplied to snap on after the cord is put into the slot. The snap on cover allows for a 1" egress at the top and bottom of the slot for cords.


#### CHROME PLATING SPECIFICATION


Where chrome plated is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.



Epoch Edge Detail







	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Round Table	Round Oak Table	e with Chrome Leg	<u>IS</u>				
	59C-109-S00 OAK	59C-109-S02 OAK	Round Table	29"H x 38" Diameter	100	\$2,925	\$2,768
	59C-129-S00 OAK	59C-129-S02 OAK	Round Table	29"H x 44" Diameter	110	\$3,039	\$2,880
	59C-141-S00 OAK	59C-141-S02 OAK	Round Table	29"H x 50" Diameter	120	\$3,227	\$3,002
	N/A	59C-130-S02 OAK	Round Table	29"H x 62" Diameter	140	N/A	\$3,628
	Round Maple Tal	ble with Chrome L	<u>egs</u>				
	59C-109-S00 MAP	59C-109-S02 MAP	Round Table	29"H x 38" Diameter	100	\$3,188	\$3,017
	59C-129-S00 MAP	59C-129-S02 MAP	Round Table	29"H x 44" Diameter	110	\$3,312	\$3,140
	59C-141-S00 MAP	59C-141-S02 MAP	Round Table	29"H x 50" Diameter	120	\$3,517	\$3,272
	N/A	59C-130-S02 MAP	Round Table	29"H x 62" Diameter	140	N/A	\$3,955
Square Table	Square Oak Tabl	e with Chrome Le	<u>gs</u>				
	59C-191-S00 OAK	59C-191-S02 OAK	Square Table	29" x 32-3/4" x 32-3/4"	100	\$3,025	\$2,698
	59C-137-S00 OAK	59C-137-S02 OAK	Square Table	29" x 44-3/4" x 44-3/4"	100	\$3,139	\$2,812
	59C-154-S00 OAK	59C-154-S02 OAK	Square Table	29" x 50-3/4" x 50-3/4"	100	\$3,265	\$2,939
	Square Maple Ta	able with Chrome I	<u>Legs</u>				
	59C-191-S00 MAP	59C-191-S02 MAP	Square Table	29" x 32-3/4" x 32-3/4"	100	\$3,297	\$2,941
	59C-137-S00 MAP	59C-137-S02 MAP	Square Table	29" x 44-3/4" x 44-3/4"	100	\$3,421	\$3,066
	59C-154-S00 MAP	59C-154-S02 MAP	Square Table	29" x 50-3/4" x 50-3/4"	100	\$3,559	\$3,203
Four Reader	Rectangular Oak	Table with Chron	ne Legs				
Rectangular Table	59C-194-S00 OAK	59C-194-S02 OAK	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$3,309	\$3,111
	59C-195-S00 OAK	59C-195-S02 OAK	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$3,429	\$3,239
NY .	59C-144-S00 OAK	59C-144-S02 OAK	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$3,385	\$3,187
1 0	59C-138-S00 OAK	59C-138-S02 OAK	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$3,504	\$3,314
	59C-145-S00 OAK	59C-145-S02 OAK	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$3,788	\$3,551
[	Rectangular Ma	ole Table with Chr	ome Legs				
	59C-194-S00 MAP	59C-194-S02 MAP	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$3,606	\$3,390
	59C-195-S00 MAP	59C-195-S02 MAP	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$3,738	\$3,530
	59C-144-S00 MAP	59C-144-S02 MAP	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$3,690	\$3,474
	59C-138-S00 MAP	59C-138-S02 MAP	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$3,819	\$3,613
	59C-145-S00 MAP	59C-145-S02 MAP	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$4,129	\$3,871
Six Reader Rectangular Table	Rectangular Oak	Table with Chron	ne Leas				
with Center Support Legs	59C-198-S00 OAK	59C-198-S02 OAK	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$4,844	\$4,563
0	59C-146-S00 OAK	59C-146-S02 OAK	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$4,920	\$4,638
	59C-134-S00 OAK	59C-134-S02 OAK	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$5,368	\$4,902
	Rectangular Maj	ole Table with Chr	ome Legs				
	59C-198-S00 MAP	59C-198-S02 MAP	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$5,280	\$4,974
	59C-146-S00 MAP	59C-146-S02 MAP	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$5,363	\$5,055
	59C-134-S00 MAP	59C-134-S02 MAP	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$5,851	\$5,343
arm file 22							
Chrome Wire Management Leg	59C-945-S00		Optional Leg	29"Н	12		\$639
Ple	ease specify Wood Finish	(Table 1) and High-Press	ure Laminate (Table 2	2). Details can be found on pa	age GEN	14.	

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core or with a .050" high-pressure laminate face a .020" thick phenolic backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 2" wide x 1-3/4" thick solid maple external chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled down at a  $20^{\circ}$  angle with a 1/2" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered and receive 1/8" radius on all corners.

#### LEGS (POWDER-COATED)


Legs are 2-1/2" round, 16-gauge steel tubing. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Legs and plates are electrostatic powder-coat painted and have no sharp edges. The plate attaches to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The steel bracket is attached to the leg plate and leg using metal to metal fasteners. The strap may be electrostatic powder-coat painted or chrome plated. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

#### **LEG (WIRE MANAGEMENT)**


A 1/2" wide slot is located in the back of the leg underneath the angle support bracket, 5/8" down from the top of the leg to within 3-3/8" of the bottom of the leg. To insert cords, a snap on slot cover of 1/8" bent metal and finished to match the leg is supplied to snap on after the cord is put into the slot. The snap on cover allows for a 1" egress at the top and bottom of the slot for cords.


#### CHROME PLATING SPECIFICATION


Where chrome plated is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.



**Epoch Series Edge** 







	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	•	Particleboard Core Price
Round Table	Round Oak Tabl	e with Powder-Coa	ated Legs				
	59-109-S00 OAK	59-109-S02 OAK	Round Table	29"H x 38" Diameter	100	\$2,366	\$2,208
	59-129-S00 OAK	59-129-S02 OAK	Round Table	29"H x 44" Diameter	110	\$2,479	\$2,323
	59-141-S00 OAK	59-141-S02 OAK	Round Table	29"H x 50" Diameter	120	\$2,667	\$2,442
11 11	N/A	59-130-S02 OAK	Round Table	29"H x 62" Diameter	140	N/A	\$3,067
11 11	Round Maple Ta	ble with Powder-C	Coated Legs				
	59-109-S00 MAP	59-109-S02 MAP	Round Table	29"H x 38" Diameter	100	\$2,579	\$2,406
	59-129-S00 MAP	59-129-S02 MAP	Round Table	29"H x 44" Diameter	110	\$2,702	\$2,532
	59-141-S00 MAP	59-141-S02 MAP	Round Table	29"H x 50" Diameter	120	\$2,907	\$2,661
	N/A	59-130-S02 MAP	Round Table	29"H x 62" Diameter	140	N/A	\$3,343
Square Table	Square Oak Tab	le with Powder-Co	ated Legs				
	59-191-S00 OAK	59-191-S02 OAK	Square Table	29" x 32-3/4" x 32-3/4"	100	\$2,295	\$2,137
	59-137-S00 OAK	59-137-S02 OAK	Square Table	29" x 44-3/4" x 44-3/4"	100	\$2,408	\$2,252
	59-154-S00 OAK	59-154-S02 OAK	Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,536	\$2,378
1 11 1	Square Maple Ta	able with Powder-	Coated Legs				
1 "1 1	59-191-S00 MAP	59-191-S02 MAP	Square Table	29" x 32-3/4" x 32-3/4"	100	\$2,502	\$2,329
	59-137-S00 MAP	59-137-S02 MAP	Square Table	29" x 44-3/4" x 44-3/4"	100	\$2,624	\$2,455
	59-154-S00 MAP	59-154-S02 MAP	Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,764	\$2,592
Four Reader	Rectangular Oal	k Table with Powd	er-Coated Legs				
Rectangular Table	59-194-S00 OAK	59-194-S02 OAK	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,722	\$2,525
3	59-195-S00 OAK	59-195-S02 OAK	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$2,835	\$2,646
	59-144-S00 OAK	59-144-S02 OAK	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$2,799	\$2,602
	59-138-S00 OAK	59-138-S02 OAK	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$2,913	\$2,725
	59-145-S00 OAK	59-145-S02 OAK	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$3,231	\$2,931
1 ,	Rectangular Ma	ple Table with Pou	vder-Coated Leg	<u> </u>			
	59-194-S00 MAP	59-194-S02 MAP	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,967	\$2,752
	59-195-S00 MAP	59-195-S02 MAP	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$3,090	\$2,885
	59-144-S00 MAP	59-144-S02 MAP	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$3,051	\$2,836
	59-138-S00 MAP	59-138-S02 MAP	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$3,176	\$2,970
	59-145-S00 MAP	59-145-S02 MAP	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$3,522	\$3,195
Six Reader Rectangular Table	Rectangular Oal	k Table with Powd	er-Coated Leas				
with Center Support Legs	59-198-S00 OAK	59-198-S02 OAK	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$3,958	\$3,674
•	59-146-S00 OAK	59-146-S02 OAK	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$4,033	\$3,750
Ny Y	59-134-S00 OAK	59-134-S02 OAK	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$4,478	\$4,054
	Rectangular Ma	ple Table with Pou	vder-Coated Leg	<u>75</u>			
	59-198-S00 MAP	59-198-S02 MAP	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$4,314	\$4,004
	59-146-S00 MAP	59-146-S02 MAP	Rectangular Table	29" x 92-3/4" x 38-3/4"	150	\$4,396	\$4,088
	59-134-S00 MAP	59-134-S02 MAP	Rectangular Table	29" x 92-3/4" x 50-3/4"	200	\$4,881	\$4,419
-							
Powder-Coated Wire Management Leg	59-945-S00		Optional Leg	29"H	12		\$323
PI	ease specify Wood Finish	_	e Laminate (Table 2) a d on pages GEN 4 and	and Metal Color; if applicable	(Table	3).	

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core or lumbercore with a .050" high-pressure laminate face a .020" thick phenolic backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 2" wide x 1-3/4" thick solid maple external chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled down at a 20° angle with a 1/2" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered and receive 1/8" radius on all corners.

#### LEGS (WOOD)


Legs are 2-1/2" round wood. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Plates are electrostatic powder coat painted and have no sharp edges. The plate attaches to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a  $45\,^\circ$  angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The steel bracket is attached to the leg plate and leg using metal to metal fasteners. The strap may be electrostatic powder-coat painted or chrome plated. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

#### LEG (WIRE MANAGEMENT)

A 1/2" wide slot is located in the back of the leg underneath the angle support bracket, 5/8" down from the top of the leg to within 3-3/8" of the bottom of the leg. To insert cords, a snap on slot cover of 1/8" bent metal and finished to match the leg is supplied to snap on after the cord is put into the slot. The snap on cover allows for a 1" egress at the top and bottom of the slot for cords.


#### CHROME PLATING SPECIFICATION


Where chrome plated is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.



**Epoch Series Edge** 







	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Round Table	Round Oak Table	e with Wood Legs					
	59W-109-S00 OAK	59W-109-S02 OAK	Round Table	29"H x 38" Diameter	100	\$2,366	\$2,208
	59W-129-S00 OAK	59W-129-S02 OAK	Round Table	29"H x 44" Diameter	110	\$2,479	\$2,323
PI TO	59W-141-S00 OAK	59W-141-S02 OAK	Round Table	29"H x 50" Diameter	120	\$2,667	\$2,442
	N/A	59W-130-S02 OAK	Round Table	29"H x 62" Diameter	140	N/A	\$3,067
	Round Maple Tal	ble with Wood Leg	<u>s</u>				
	59W-109-S00 MAP	59W-109-S02 MAP	Round Table	29"H x 38" Diameter	100	\$2,579	\$2,406
	59W-129-S00 MAP	59W-129-S02 MAP	Round Table	29"H x 44" Diameter	110	\$2,702	\$2,532
	59W-141-S00 MAP	59W-141-S02 MAP	Round Table	29"H x 50" Diameter	120	\$2,907	\$2,661
	N/A	59W-130-S02 MAP	Round Table	29"H x 62" Diameter	140	N/A	\$3,343
Square Table	Square Oak Tabl	e with Wood Legs					
	59W-191-S00 OAK	59W-191-S02 OAK	Square Table	29" x 32-3/4" x 32-3/4"	100	\$2,295	\$2,137
	59W-137-S00 OAK	59W-137-S02 OAK	Square Table	29" x 44-3/4" x 44-3/4"	100	\$2,408	\$2,252
P	59W-154-S00 OAK	59W-154-S02 OAK	Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,536	\$2,378
	Square Maple Ta	ble with Wood Leg	<u> 15</u>				
	59W-191-S00 MAP	59W-191-S02 MAP	Square Table	29" x 32-3/4" x 32-3/4"	100	\$2,502	\$2,329
	59W-137-S00 MAP	59W-137-S02 MAP	Square Table	29" x 44-3/4" x 44-3/4"	100	\$2,624	\$2,455
	59W-154-S00 MAP	59W-154-S02 MAP	Square Table	29" x 50-3/4" x 50-3/4"	100	\$2,764	\$2,592
Four Reader	Rectangular Oak	Table with Wood	<u>Legs</u>				
Rectangular Table	59W-194-S00 OAK	59W-194-S02 OAK	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,722	\$2,525
3	59W-195-S00 OAK	59W-195-S02 OAK	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$2,835	\$2,648
CYV	59W-144-S00 OAK	59W-144-S02 OAK	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$2,799	\$2,602
1 0	59W-138-S00 OAK	59W-138-S02 OAK	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$2,913	\$2,725
	59W-145-S00 OAK	59W-145-S02 OAK	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$3,231	\$2,931
	Rectangular Ma	ole Table with Woo	od Legs				
U	59W-194-S00 MAP	59W-194-S02 MAP	Rectangular Table	29" x 62-3/4" x 32-3/4"	110	\$2,967	\$2,752
	59W-195-S00 MAP	59W-195-S02 MAP	Rectangular Table	29" x 74-3/4" x 32-3/4"	130	\$3,090	\$2,887
	59W-144-S00 MAP	59W-144-S02 MAP	Rectangular Table	29" x 62-3/4" x 38-3/4"	110	\$3,051	\$2,836
	59W-138-S00 MAP	59W-138-S02 MAP	Rectangular Table	29" x 74-3/4" x 38-3/4"	130	\$3,176	\$2,970
	59W-145-S00 MAP	59W-145-S02 MAP	Rectangular Table	29" x 74-3/4" x 50-3/4"	160	\$3,522	\$3,195
Six Reader Rectangular Table	Rectangular Oak	Table with Wood	l eas				
with Center Support Legs	59W-198-S00 OAK		•	20" v 02 2 /4" v 22 2 /4"	150	\$3,958	\$3,674
como: capport 2095	59W-146-S00 OAK	59W-198-S02 OAK 59W-146-S02 OAK	Rectangular Table Rectangular Table	29" x 92-3/4" x 32-3/4" 29" x 92-3/4" x 38-3/4"	150 150	\$3,958 \$4,033	\$3,674 \$3,750
TV	59W-140-300 OAK	59W-134-S02 OAK	-	29" x 92-3/4" x 50-3/4"	200	\$4,478	\$3,750 \$4,054
	Rectangular Mai	ole Table with Woo	nd Leas				
	59W-198-S00 MAP	59W-198-S02 MAP	Rectangular Table	29" x 92-3/4" x 32-3/4"	150	\$4,314	\$4,004
	59W-146-S00 MAP	59W-146-S02 MAP	-	29" x 92-3/4" x 38-3/4"	150	\$4,396	\$4,088
	59W-134-S00 MAP	59W-134-S02 MAP	-	29" x 92-3/4" x 50-3/4"	200	\$4,881	\$4,419
Wood Wire Management Leg	59W-945-S00 OAK		Optional Oak Leg	29"H	12		\$378
management Log	59W-945-S00 MAP		Optional Maple Leg	29"H	12		\$378
U PI	ease specify Wood Finish	(Table 1), High-Pressure	Laminate (Table 2) ar	nd Metal Color; if applicable	(Table:	3).	

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core with a .050" high-pressure laminate face and a .020" thick backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2"W solid-maple external undercut chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled down at a 20° angle with a 1/2" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered on all corners and receive a 1/8" radius.

#### LEGS (CHROME)

Legs are 2-1/2" round, 16-gauge steel tubing. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Leg and plate are painted or plated to match the leg (see chrome specifications) and have no sharp edges. The plate is attached to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The bracket is attached to the leg plate and leg using metal to metal fasteners. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

#### LEGS (POWDER-COATED)


Legs are 2-1/2" round, 16-gauge steel tubing. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Legs and plates are electrostatic powder-coat painted and have no sharp edges. The plate attaches to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The steel bracket is attached to the leg plate and leg using metal to metal fasteners. The strap may be electrostatic powder-coat painted or chrome plated. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

#### PRIVACY PANEL


Privacy panels are 10"H, constructed of 1" thick, 9-ply hardwood veneer-core plywood. Exposed panel edges are banded with 1.6mm solid maple. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the privacy panels. Privacy panel is finished to match the table edge band. Privacy panel is designed to hide computer wires and to eliminate incidental tampering.

#### **ELECTRICAL**

Tables have 3" grommets for wire passage and J-channel wire managers mounted under the table to hold excess wires. Grommets are ABS, black plastic, with notched removable cap. J-channel wire managers are 18-gauge steel with electrostatic applied black powder-coat paint.



**Epoch Series Edge** 



	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
One Position Computer Tables	Table with Chro	ome Legs					
	59C-645-S00 OAK 59C-665-S00 OAK	59C-645-S00 MAP 59C-665-S00 MAP	Sitting Height Sitting Height	27-1/2" x 32-3/4" x 26-3/4" 27-1/2" x 32-3/4" x 32-3/4"	80 80	\$3,567 \$3,611	\$3,888 \$3,937
		der-Coated Legs					
	59-645-S00 OAK 59-665-S00 OAK	59-645-S00 MAP 59-665-S00 MAP	Sitting Height Sitting Height	27-1/2" x 32-3/4" x 26-3/4" 27-1/2" x 32-3/4" x 32-3/4"	80 80	\$2,540 \$2,604	\$2,768 \$2,838
Two Position Computer Tables	Table with Chro	ome Legs					
	59C-649-S00 OAK 59C-669-S00 OAK	59C-649-S00 MAP 59C-669-S00 MAP	Sitting Height Sitting Height	27-1/2" x 62-3/4" x 26-3/4" 27-1/2" x 62-3/4" x 32-3/4"	110 110	\$4,205 \$4,269	\$4,583 \$4,653
P. VI	Table with Pow	der-Coated Legs					
	59-649-S00 OAK 59-669-S00 OAK	59-649-S00 MAP 59-669-S00 MAP	Sitting Height Sitting Height	27-1/2" x 62-3/4" x 26-3/4" 27-1/2" x 62-3/4" x 32-3/4"	110 110	\$3,445 \$3,509	\$3,756 \$3,824
One Position Computer Table	Table with Chro	ome Legs					
with 10"H Privacy Panel	59C-643-S00 OAK 59C-663-S00 OAK	59C-643-S00 MAP 59C-663-S00 MAP	Sitting Height Sitting Height	27-1/2" x 38-3/4" x 26-3/4" 27-1/2" x 38-3/4" x 38-3/4"	70 70	\$3,899 \$3,854	\$4,251 \$4,201
	Table with Pow	der-Coated Legs					
	59-643-S00 OAK 59-663-S00 OAK	59-643-S00 MAP 59-663-S00 MAP	Sitting Height Sitting Height	27-1/2" x 38-3/4" x 26-3/4" 27-1/2" x 38-3/4" x 38-3/4"	70 70	\$2,879 \$2,971	\$3,138 \$3,238
Two Position Computer Table	Table with Chro	ome Legs					
with 10"H Privacy Panel	59C-642-S00 OAK 59C-662-S00 OAK	59C-642-S00 MAP 59C-662-S00 MAP	Sitting Height Sitting Height	27-1/2" x 74-3/4" x 26-3/4" 27-1/2" x 74-3/4" x 38-3/4"	150 150	\$4,830 \$5,007	\$5,265 \$5,457
	Table with Pow	der-Coated Legs					
	59-642-S00 OAK 59-662-S00 OAK	59-642-S00 MAP 59-662-S00 MAP	Sitting Height Sitting Height	27-1/2" x 74-3/4" x 26-3/4" 27-1/2" x 74-3/4" x 38-3/4"	150 150	\$3,673 \$3,854	\$4,003 \$4,202
Three Position Computer Table with 10"H Privacy Panel	Table with Chro	•					
with 10 fi Privacy Patier	59C-644-S00 OAK 59C-664-S00 OAK	59C-644-S00 MAP 59C-664-S00 MAP	Sitting Height Sitting Height	27-1/2" x 92-3/4" x 26-3/4" 27-1/2" x 92-3/4" x 38-3/4"	180 180	\$5,844 \$6,068	\$6,370 \$6,614
	Table with Pow	der-Coated Legs					
	59-644-S00 OAK 59-664-S00 OAK	59-644-S00 MAP 59-664-S00 MAP	Sitting Height Sitting Height	27-1/2" x 92-3/4" x 26-3/4" 27-1/2" x 92-3/4" x 38-3/4"	180 180	\$4,553 \$4,774	\$4,963 \$5,203

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color; if applicable (Table 3). Details can be found on pages GEN 4 and GEN 5.

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard, with a.050" thick high-pressure laminate top surface and a.020" thick backing sheet for balanced construction. Top receives a 2" x 1-3/4" thick external solid drop edge band of Northern-grown Red Oak or maple. Edge band is beveled down at a  $20^{\circ}$  angle with a 1/2" bullnose leading edge. Square and rectangular tabletop edge bands are mitered at all four corners and radius 1/8".

#### LEG (METAL)

Legs are 2-1/2" round 16-gauge cold-rolled steel tubing. Legs receive a 9" x 3" x 1/2" cold-rolled steel angle bracket placed at a 45° angle that is attached to a 5" square x 5/16" thick cold-rolled steel plate for connection to the tabletop. Legs are attached to the leg plate and bracket using metal to metal fasteners. The steel angle bracket receives two cutout designs replicating the edge band profile. The leg plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internal and external threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the drop edge band. Edge band extends 1/2" below the tabletop. Each leg receives a 2-1/2"D x 1"H adjustable glide mounted in a recessed threaded insert. Leg and plate are painted or plated to match (see chrome specifications) and have no sharp edges.

#### LEG (WOOD)

Legs are 2-1/2" round, glued up solid Northern-grown Red Oak or maple. Legs receive a 9" x 3" x 1/2" cold-rolled steel angle bracket placed at a  $45^{\circ}$  angle that is attached to a 5" square x 5/16" thick cold-rolled steel plate for connection to the tabletop. Legs are attached to the leg plate and bracket using metal to metal fasteners. The steel angle bracket receives two cutout designs replicating the edge band profile. The leg plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internal and external threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the drop edge band. Edge band extends 1/2" below the tabletop. Each leg receives a 2-1/2"D x 1"H adjustable glide mounted in a recessed threaded insert. Leg and plate are painted or plated to match (see chrome specifications) and have no sharp edges.


**Note:** Angle Bracket and Glide can be individually chrome plated (see chrome specifications) or painted any of Brodart's powder-coat paints as specified

#### LEG (WIRE MANAGEMENT)


When specified, a wire management leg will be provided. This leg has a 1/2" wide slot located in the back of the leg underneath the angle support bracket, 3/8" down from the top of the leg and 3-3/8" from the bottom of the leg. A spring loaded cover of 1/8" bent metal and finished to match the leg is \_\_\_\_\_. The cover allows for a 1" egress at the top and bottom of the slot for cords.

#### CHROME PLATING SPECIFICATION

Where chrome plating is specified, Brodart provides a decorative chrome electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture-grade finish.



**Epoch Series Edge** 



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price		
Table with Powe	der-Coat Painted l	Metal Legs						ISO Tables
590CIGS29AEPMS	59MCIGS29AEPMS	Standing Height Starter	29" x 42-11/16" x 30-1/2"	80	\$5,169	\$5,531		
590CIGA29AEPMS 590CIGS27AEPMS	59MCIGA29AEPMS 59MCIGS27AEPMS	Standing Height Adder Sitting Height Starter	29" x 42-11/16" x 30-1/2" 27-1/2" x 42-11/16" x 30-1/2"	70 80	\$3,503 \$5,169	\$3,748 \$5,531		Starter
590CIGA27AEPMS	59MCIGA27AEPMS	Sitting Height Adder	27-1/2" x 42-11/16" x 30-1/2"	70	\$3,503	\$3,748	1 , 1	
Table with Woo	<u>d Legs</u>						~	
590CIGS29AEWMS	59MCIGS29AEWMS	Standing Height Starter	29" x 42-11/16" x 30-1/2"	80	\$4,910	\$5,254		Adder
590CIGA29AEWMS	59MCIGA29AEWMS	Standing Height Adder	29" x 42-11/16" x 30-1/2"	70	\$3,374	\$3,610		
590CIGS27AEWMS 590CIGA27AEWMS	59MCIGS27AEWMS 59MCIGA27AEWMS	Sitting Height Starter Sitting Height Adder	27-1/2" x 42-11/16" x 30-1/2" 27-1/2" x 42-11/16" x 30-1/2"	80 70	\$4,910 \$3,374	\$5,254 \$3,610		

Note: For electrical and wire management options for the products listed above, please refer to the Electrical Accessories section of this price list...

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color; if applicable (Table 3). Details can be found on pages GEN 4 and GEN 5.

#### **TABLETOPS**

Table tops are 1-3/16" thick, 3-ply 45# density particleboard, with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Top receives a 2" x 1-3/4" thick external drop edge band of solid Northern-grown Red Oak or Maple. The band is beveled down at a 20° angle with a 1/2" bullnose leading edge. Square and rectangular tabletop edge bands are mitered at all four corners and radius 1/8".

**Note:** Tops for tables 96" and smaller will receive the grain of the veneer running in the "long" direction. Tops for tables 96" and longer will receive the grain running in the "short" direction.


#### BASE - WOOD

The base consists of a top and bottom horizontal stretcher connected by a vertical panel. The top and bottom horizontal pieces will be solid Northern-grown Red Oak or Maple. The vertical panel will be 1-3/16" thick, 3-ply 45# density particleboard, with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. The upper horizontal part of the each base will receive borings for attaching the assembly to the table top. The lower horizontal piece will receive a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut which is further recessed into the leg by means of a counter-sink boring which accepts the upper two-thirds of the glide. Table tops are attached to base by bolting through the upper horizontal members of base into internal and external threaded bushings embedded in the underside of the table top.

The assembled base components will connect to each other via two horizontal rails. Rails will be constructed of 1-3/16" thick, 3-ply 45# density particleboard, with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides and attach to base and also provide support for the tabletop.


#### **BASE - WOOD & METAL**

The wood and metal base construction is the same as the standard wood base with the addition of two 2-1/2" round 16-gauge cold-rolled steel tubing fitted between the pedestal top and bottom rails. Tubing will be Legs will be finished with electrostatic applied epoxy powder-coat paint.




**Epoch Series Edge** 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
590C0N367229WPDS	59MC0N367229WPDS	Two Pedestal Base	29" x 72" x 36"	125	\$7,360	\$7,968	Two Pedestal Base
590C0N489629WPDS	59MCON489629WPDS	Two Pedestal Base	29" x 96" x 48"	190	\$12,942	\$14,116	



590C0N5414429WPDS	59MC0N5414429WPDS	Three Pedestal Base	29" x 144" x 54"	350	\$22,074	\$24,063	Three Pedestal Base
590C0N5418029WPDS	59MC0N5418029WPDS	Three Pedestal Base	29" x 180" x 54"	410	\$23,434	\$25,556	
						_	




Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.


	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Two Pedestal Base	590C0N367229WMPS	59MCON367229WMPS	Two Pedestal Base	29" x 72" x 36"	125	\$7,905	\$8,513
	590C0N489629WMPS	59MCON489629WMPS	Two Pedestal Base	29" x 96" x 48"	190	\$13,492	\$14,661

 Three Pedestal Base
 590C0N5414429WMPS
 59MC0N5414429WMPS
 Three Pedestal Base
 29" x 144" x 54"
 350
 \$22,889
 \$24,878

 590C0N5418029WMPS
 59MC0N5418029WMPS
 Three Pedestal Base
 29" x 180" x 54"
 410
 \$24,254
 \$26,381



Four Pedestal Base 590C0N5424029WMPS 59MC0N5424029WMPS Four Pedestal Base 29" x 240" x 54" 550 \$31,005 \$33,704



#### WORKSTATIONS

Workstations are designed in a modular starter/adder configuration and available in single or double-face system. The workstation top is 36" or 47-5/8"W x 28-1/2"D. A 1-1/2"W cord drop runs the width of the carrel between work surface and back panel to allow passage of electrical cords. The workstation support shelf is 8"D. End and intermediate panels are 47-1/2"H and 33-1/8"D. The work surface attaches to end and intermediate panel by (2) metal "Z" brackets with 5/16" - 18 hex-head bolts engaging internally and externally threaded bushings embedded into panels. The back panel is attached to end and intermediate panel using hidden metal keyway attachments. The workstation support shelf is attached to end, intermediate and back panels with 3/4" x 3/4" black steel angle brackets and black #8 screws.

#### WORKSTATION TOP

The workstation top is 1-3/16" thick, 45# density particleboard core with a top surface of .050" thick high-pressure laminate and .020" thick phenolic backing sheet for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. The exposed edge is banded with a 2"W x 1-3/4" thick solid hard maple external chamfered edge band laminated to the work surface core after lamination of the face plastic. The edge band is beveled at a 20° angle with a 1/2" radius bullnose at the leading edge. The back edge of the top has a black plastic strap 1-1/2"W that projects above the work surface 1/4" to act as a retainer. All work surfaces are 29"H.

#### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-3/16" thick, 3-ply 45# particleboard core select plain-sliced, slip-matched maple veneer. Vertical and top edges of the end and intermediate panel have 1.6mm thick maple edge band. Each panel has two 1-1/4" diameter chrome adjustable glides. Starter end panels have an arched window inserted 3-1/4" down from the center of the top edge of the panel. The 3-form is 4"H x 16"W and is held in place with 1/4" thick maple molding on both sides of the window (see window specifications). The molding is sanded flush with the panel surfaces. End panels have a 1/4" x 1/4" x 3/16" square rod embedded 4" up from the bottom edge. The square rod can be chrome plated or powder coated as ordered (see chrome specs).

#### **BACK PANEL**

The back panel is 3/4" thick 3-ply 45# density particleboard core with plain-sliced slip matched maple veneer on both faces. The top and bottom edges have 1.6mm maple edge banding. The back panel is attached the end or intermediate panel using metal keyway attachments.

#### WORKSTATION SUPPORT SHELF


The workstation support is 3/4" thick, 45# density particleboard core with select AA slip-matched maple veneer. The support has a 3/4" thick solid maple external band on the exposed edge. The support is located under the work surface and extends the full width of the workstation.

#### CHROME PLATING SPECIFICATION

Where "chrome plated" is specified, Brodart provides a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.

#### WINDOW SPECIFICATIONS

Unless otherwise specified all resin window panels are 1/4" thick. Customers must specify the color they require from those offered by Brodart. The resin window is held in place by 1/4" thick solid wood maple molding, on both sides of the window. The molding is sanded flush with the panel surfaces.



**Epoch Series Edge** 

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Information Access Workstations with Resin Window and Painted	JO WIGE WOIK	• .	S/F Starter S/F Adder	47-1/2" x 38-1/4" x 33" 47-1/2" x 37-1/4" x 33"	165 115	\$5,050 \$2,311	\$5,505 \$2,519
	48" Wide Work 59GP-460-S00 OAK 59-459-S00 OAK	• .	S/F Starter S/F Adder	47-1/2" x 50" x 33" 47-1/2" x 48-3/4" x 33"	195 145	\$5,230 \$2,491	\$5,701 \$2,715
Starter Ad	lder						
Information Access Workstations with Resin Window and Chrome	Accent 59GC-673-S00 OAK 59-672-S00 OAK  48" Wide Work	59GC-673-S00 MAP 59-672-S00 MAP	S/F Starter S/F Adder S/F Starter S/F Adder	47-1/2" x 38-1/4" x 33" 47-1/2" x 37-1/4" x 33" 47-1/2" x 50" x 33" 47-1/2" x 48-3/4" x 33"	165 115 195 145	\$5,878 \$2,311 \$6,089 \$2,491	\$6,407 \$2,519 \$6,637 \$2,715
Starter Ac	dder	C7 107 000 11111	o, i riddol	77 77 2 8 10 67 7 8 00	. 10	Ψ2,171	ψ2,710
otano.							
Information Access Workstations with Painted Metal "T" Accent	59TP-673-S00 OAK 59-672-S00 OAK	59TP-673-S00 MAP 59-672-S00 MAP	S/F Starter S/F Adder	47-1/2" x 38-1/4" x 33" 47-1/2" x 37-1/4" x 33"	165 115	\$4,292 \$2,311	\$4,678 \$2,519
	<b>48" Wide Work</b> 59TP-460-S00 OAK 59-459-S00 OAK	• .	S/F Starter S/F Adder	47-1/2" x 50" x 33" 47-1/2" x 48-3/4" x 33"	195 145	\$4,444 \$2,491	\$4,844 \$2,715
Starter Ad	lder						
Information Access Workstations with Chrome Metal "T" Accent	s/Carrels <u>36" Wide Work</u>	ing Space					
Will Official Tracelle	59TC-673-S00 OAK 59-672-S00 OAK <b>48" Wide Work</b>	59-672-S00 MAP	S/F Starter S/F Adder	47-1/2" x 38-1/4" x 33" 47-1/2" x 37-1/4" x 33"	165 115	\$5,171 \$2,311	\$5,636 \$2,519
	59TC-460-S00 OAK 59-459-S00 OAK		S/F Starter S/F Adder	47-1/2" x 50" x 33" 47-1/2" x 48-3/4" x 33"	195 145	\$5,355 \$2,491	\$5,837 \$2,715
Starter Ac	lder						

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option; if applicable (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Worki	ing Space						Information Access Workstations/Carrels
59GP-674-S00 OAK	59GP-674-S00 MAP	D/F Starter	47-1/2" x 38-1/4" x 66-1/4"	306	\$9,781	\$10,661	with Resin Window and Painted Accent
59-675-S00 OAK	59-675-S00 MAP	D/F Adder	47-1/2" x 37-1/4" x 66-1/4"	205	\$4,809	\$5,241	9
48" Wide Worki	ing Space						
59GP-461-S00 OAK	59GP-461-S00 MAP	D/F Starter	47-1/2" x 50" x 66-1/4"	366	\$10,333	\$11,262	
59-462-S00 OAK	59-462-S00 MAP	D/F Adder	47-1/2" x 48-3/4" x 66-1/4"	265	\$4,724	\$5,149	Starter
36" Wide Worki	ing Space						Information Access Workstations/Carrels
59GC-674-S00 OAK	59GC-674-S00 MAP	D/F Starter	47-1/2" x 38-1/4" x 66-1/4"	165	\$11,389	\$12,414	with Resin Window and Chrome Accent
59-675-S00 OAK	59-675-S00 MAP	D/F Adder	47-1/2" x 37-1/4" x 66-1/4"	205	\$4,809	\$5,241	
48" Wide Worki	ing Space						
59GC-461-S00 OAK	59GC-461-S00 MAP	D/F Starter	47-1/2" x 50" x 66-1/4"	195	\$12,030	\$13,113	
59-462-S00 OAK	59-462-S00 MAP	D/F Adder	47-1/2" x 48-3/4" x 66-1/4"	265	\$4,724	\$5,149	Starter
36" Wide Worki	ing Space						Information Access Workstations/Carrels
59TP-674-S00 OAK	59TP-674-S00 MAP	D/F Starter	47-1/2" x 38-1/4" x 66-1/4"	165	\$8,312	\$9,060	with Painted Metal "T" Accent
59-675-S00 OAK	59-675-S00 MAP	D/F Adder	47-1/2" x 37-1/4" x 66-1/4"	205	\$4,809	\$5,241	
48" Wide Worki	ing Space						
59TP-461-S00 OAK 59-462-S00 OAK	59TP-461-S00 MAP	D/F Starter	47-1/2" x 50" x 66-1/4"	195	\$8,782	\$9,572	
59-462-500 UAK	59-462-S00 MAP	D/F Adder	47-1/2" x 48-3/4" x 66-1/4"	265	\$4,724	\$5,149	
							Starter
36" Wide Worki	ing Space						Information Access Workstations/Carrels
59TC-674-S00 OAK	59TC-674-S00 MAP	D/F Starter	47-1/2" x 38-1/4" x 66-1/4"	165	\$10,015	\$10,916	with Chrome Metal "T" Accent
59-675-S00 OAK	59-675-S00 MAP	D/F Adder	47-1/2" x 37-1/4" x 66-1/4"	205	\$4,809	\$5,241	
48" Wide Worki	ing Space						
59TC-461-S00 OAK 59-462-S00 OAK	59TC-461-S00 MAP 59-462-S00 MAP	D/F Starter D/F Adder	47-1/2" x 50" x 66-1/4" 47-1/2" x 48-3/4" x 66-1/4"	195 265	\$10,581 \$4,724	\$11,533 \$5,149	
						. ,	Starter

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option; if applicable (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

#### WORKSTATIONS

Workstations are of modular starter and adder design, with overall height 37". Workstations are available in 36", 48", 72", 96" and 108" width. A knee-space panel located below the work surface supports all work surfaces greater than 48"W. Work surface height is 27-1/2". Work surface depth is 27-3/16" with an additional 1-1/2"W cord drop between the work surface and back panel to allow passage of electrical cords. Work surface is attached to end and intermediate panels by means of two metal 22-1/2" long "Z" brackets with 5/16" - 18 hex-head bolts engaging internally and externally threaded bushings embedded in the panels. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end and intermediate panels and back panels with 3/4" x 3/4" steel, black-painted angle brackets and black #8 screws.

#### WORK SURFACE

Standard work surface is 1-3/16" thick, 3-ply, 45# density particleboard, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thickness for balanced construction. High-pressure laminate has a low-glare finish resistant to scratches, fading, staining, etc. High-pressure laminate meets or exceeds NEMA standards. Front edge of work surface has a 2" x 1- 3/4" solid maple edge band in a beveled bullnose shape, the same as the reading tables. The back edge of the top has a black plastic strap 1-1/2"W that projects above the work surface 1/4" to act as a retainer.

#### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-3/16" thick, 45# density particleboard core with select face veneers of maple. All edges are banded with a 1.6mm edge band. The end panels have an accent window 8-1/2"W x 3-3/4"H (see window specs). They have a 1/4" x 1/4" square rod embedded 3/16"D up 4" from the bottom edge and chrome plated or powder coated as ordered (see chrome specs). Intermediate panels have a 3" diameter grommet below the work surface to allow passage of electrical and data wires. Each panel has two 1-1/4" adjustable glides.

#### **BACK PANEL**

Back panel is 3/4" thick, 45# density particleboard core with face veneers of select maple. The top and bottom edges of the back panel have 1.6mm thick solid maple edge bands. Back panels attach to end and intermediate panels by recessed metal fasteners and shoulder screws. The back panel on double-faced units has a 3" diameter grommet below the work surface to allow passage of electrical and data wires.

#### SHFLE

Shelf is 3/4" thick x 8" D 45# density particleboard core with face veneers of select maple. Shelf is banded on the front edge with a 1.6 mm solid maple band. It attaches to end and intermediate panels by a pair of metal "L" brackets. Back corners of shelf have a 3" x 3" cutout to allow for the passage of electrical cords. The shelf is positioned 10" below the bottom of the work surface.

#### WIRE MANAGEMENT DOOR

The wire management door, positioned between the bottom of the work surface and the shelf, is designed to form a concealed wire management channel 8-1/2" H x 9-1/2" D. The door is 1/4" thick with select maple face veneers. The door slides in two aluminum tracks, one attaches to the bottom of the work surface while the other attaches to the top of the shelf.

#### **KNEE-SPACE PANEL**


All 72" and 96" W workstations, as well as functional corner units, have a knee-space panel under the work surface for additional work surface support. Units 108" W have two knee-space panels. The knee-space panel is 1-3/16" thick, 45# density particleboard core with select face veneers of maple. It is banded on exposed edges with a 1.6 mm solid maple band. The knee-space panel attaches to the back panel using a 1-3/4" square, solid maple post, grooved to receive the knee-space panel and back panels. Panels attach to the post using recessed metal fasteners and shoulder screws. The knee-space panel is angled in the back to create a space to allow passage of electrical and data cords. The knee-space panel has two 1-1/4" diameter black adjustable glides.

#### CHROME PLATING SPECIFICATION

Where "chrome plated" is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.

#### WINDOW SPECIFICATIONS

Unless otherwise specified, all resin window panels are 1/4" thick resin material. Customers must specify the color they require from those offered by Brodart. The resin window is held in place by 1/4" thick solid wood maple molding, on both sides of the resin. The molding is sanded flush with the panel surfaces.



**Epoch Series Edge** 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Worki	ina Space	-					Single-Faced One-Position
59GP-S31-SS0 OAK	59GP-S31-SS0 MAP	One-Position S/F Starter with Resin Window and Painted Accent	37" x 37-1/2" x 33-1/4"	130	\$3,451	\$3,762	
59GC-S31-SS0 OAK	59GC-S31-SS0 MAP		37" x 37-1/2" x 33-1/4"	130	\$4,002	\$4,362	
59-S31-SA0 OAK	59-S31-SA0 MAP		37" x 36-1/2" x 33-1/4"	100	\$2,312	\$2,520	Starter
48" Wide Worki	ing Space						
59GP-S41-SS0 OAK	59GP-S41-SS0 MAP	One-Position S/F Starter with Resin Window and Painted Accent	37" x 49-1/4" x 33-1/4"	155	\$3,635	\$3,962	Adder
59GC-S41-SS0 OAK	59GC-S41-SS0 MAP	One-Position S/F Starter with Resin Window and Chrome Accent	37" x 49-1/4" x 33-1/4"	155	\$4,217	\$4,597	
59-S41-SA0 OAK	59-S41-SA0 MAP	One-Position S/F Adder	37" x 48" x 33-1/4"	125	\$2,378	\$2,592	
36" Wide Worki	ing Space						Double-Faced One-Position
59GP-D31-SS0 OAK	59GP-D31-SS0 MAP	One-Position D/F Starter 33 with Resin Window and Painted Accent	37" x 37-1/2" x 63-1/2"	155	\$5,166	\$5,631	
59GC-D31-SS0 OAK	59GC-D31-SS0 MAP	One-Position D/F Starter 33 with Resin Window and Chrome Accent	37" x 37-1/2" x 63-1/2"	155	\$5,993	\$6,532	
59-D31-SA0 OAK	59-D31-SA0 MAP	One-Position D/F Adder	37" x 37-1/2" x 63-1/2"	155	\$3,705	\$4,038	Starter
48" Wide Worki	• •						
59GP-D41-SS0 OAK	59GP-D41-SS0 MAP	with Resin Window and Painted Accent	37" x 49-1/4" x 63-1/2"	195	\$5,474	\$5,966	
59GC-D41-SS0 OAK	59GC-D41-SS0 MAP	One-Position D/F Starter 3 with Resin Window and Chrome Accent	37" x 49-1/4" x 63-1/2"	195	\$6,350	\$6,922	Adder
59-D41-SA0 OAK	59-D41-SA0 MAP	One-Position D/F Adder	37" x 48" x 63-1/2"	195	\$3,568	\$3,889	
36" Wide Worki	ina Space						Single-Faced Two-Position
59GP-S32-SS0 OAK	59GP-S32-SS0 MAP	Two-Position S/F Starter with Resin Window and Painted Accent	37" x 74" x 33-1/4"	195	\$4,557	\$4,967	
59GC-S32-SS0 OAK	59GC-S32-SS0 MAP	Two-Position S/F Starter with Resin Window and Chrome Accent	37" x 74" x 33-1/4"	195	\$5,285	\$5,761	
59-S32-SA0 OAK	59-S32-SA0 MAP	Two-Position S/F Adder	37" x 73" x 33-1/4"	165	\$3,435	\$3,744	Starter
48" Wide Work	ing Space						
59GP-S42-SS0 OAK	59GP-S42-SS0 MAP	Two-Position S/F Starter sith Resin Window and Painted Accent	37" x 97-1/4" x 33-1/4"	235	\$4,864	\$5,302	Adder
59GC-S42-SS0 OAK	59GC-S42-SS0 MAP	Two-Position S/F Starter sith Resin Window and Chrome Accent	37" x 97-1/4" x 33-1/4"	235	\$5,641	\$6,148	Audi
59-S42-SA0 OAK	59-S42-SA0 MAP	Two-Position S/F Adder	37" x 96" x 33-1/4"	205	\$3,614	\$3,940	7
36" Wide Worki	ing Space						Double-Faced Two-Position
	59GP-D32-SS0 MAP	Two-Position D/F Starter with Resin Window and Painted Accent	37"x74"x63-1/2"	330	\$6,867	\$7,485	
59GC-D32-SS0 OAK	59GC-D32-SS0 MAP	Two-Position D/F Starter with Resin Window and Painted Accent	37"x74"x63-1/2"	330	\$7,966	\$8,683	
59-D32-SA0 OAK	59-D32-SA0 MAP	Two-Position D/F Adder	37" x 73" x 63-1/2"	270	\$5,487	\$5,981	Starter
48" Wide Worki	ing Space						
59GP-D42-SS0 OAK	59GP-D42-SS0 MAP	Two-Position D/F Starter 33 with Resin Window and Painted Accent	37" x 97-1/4" x 63-1/2"	355	\$7,087	\$7,725	
59GC-D42-SS0 OAK	59GC-D42-SS0 MAP		37" x 97-1/4" x 63-1/2"	355	\$8,222	\$8,962	
59-D42-SA0 OAK	59-D42-SA0 MAP	Two-Position D/F Adder	37" x 96" x 63-1/2"	355	\$5,424	\$5,912	Adder

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option; if applicable (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced One-Position	36" Wide Workii	na Space					
	59TP-S31-SS0 OAK	59TP-S31-SS0 MAP	One-Position S/F Starter with Painted Metal "T" Accent	37" x 37-1/2" x 33-1/4"	130	\$2,932	\$3,196
	59TC-S31-SS0 OAK	59TC-S31-SS0 MAP	One-Position S/F Starter with Chrome "T" Accent	37" x 37-1/2" x 33-1/4"	130	\$3,555	\$3,875
Starter	59-S31-SA0 OAK	59-S31-SA0 MAP	One-Position S/F Adder	37" x 36-1/2" x 33-1/4"	100	\$2,312	\$2,520
	48" Wide Workii	ng Space					
Adder	59TP-S41-SS0 OAK	59TP-S41-SS0 MAP	One-Position S/F Starter with Painted Metal "T" Accent	37" x 49-1/4" x 33-1/4"	155	\$3,089	\$3,367
	59TC-S41-SS0 OAK	59TC-S41-SS0 MAP	One-Position S/F Starter with Chrome "T" Accent	37" x 49-1/4" x 33-1/4"	155	\$3,744	\$4,080
	59-S41-SA0 OAK	59-S41-SA0 MAP	One-Position S/F Adder	37" x 48" x 33-1/4"	125	\$2,378	\$2,592
Double-Faced One-Position	36" Wide Workii	ng Space					
	59TP-D31-SS0 OAK	59TP-D31-SS0 MAP	One-Position D/F Starter with Painted Metal "T" Accent	37" x 37-1/2" x 63-1/2"	155	\$4,391	\$4,786
	59TC-D31-SS0 OAK	59TC-D31-SS0 MAP	One-Position D/F Starter with Chrome "T" Accent	37" x 37-1/2" x 63-1/2"	155	\$5,321	\$5,801
Starter	59-D31-SA0 OAK	59-D31-SA0 MAP	One-Position D/F Adder	37" x 37-1/2" x 63-1/2"	155	\$3,705	\$4,038
_	48" Wide Workii	ng Space					
	59TP-D41-SS0 OAK	59TP-D41-SS0 MAP	One-Position D/F Starter with Painted Metal "T" Accent	37" x 49-1/4" x 63-1/2"	195	\$4,654	\$5,073
Adder	59TC-D41-SS0 OAK	59TC-D41-SS0 MAP	One-Position D/F Starter with Chrome "T" Accent	37" x 49-1/4" x 63-1/2"	195	\$5,638	\$6,145
	59-D41-SA0 OAK	59-D41-SA0 MAP	One-Position D/F Adder	37" x 48" x 63-1/2"	195	\$3,568	\$3,889
Single-Faced Two-Position	36" Wide Workii	ng Space					
	59TP-S32-SS0 OAK	59TP-S32-SS0 MAP	Two-Position S/F Starter with Painted Metal "T" Accent	37" x 74" x 33-1/4"	195	\$3,874	\$4,222
	59TC-S32-SS0 OAK	59TC-S32-SS0 MAP	Two-Position S/F Starter with Chrome "T" Accent	37" x 74" x 33-1/4"	195	\$4,694	\$5,116
Starter	59-S32-SA0 OAK	59-S32-SA0 MAP	Two-Position S/F Adder	37" x 73" x 33-1/4"	165	\$3,435	\$3,744
	48" Wide Workii	ng Space					
Adder	59TP-S42-SS0 OAK	59TP-S42-SS0 MAP	Two-Position S/F Starter with Painted Metal "T" Accent	37" x 97-1/4" x 33-1/4"	235	\$4,133	\$4,505
	59TC-S42-SS0 OAK	59TC-S42-SS0 MAP	Two-Position S/F Starter with Chrome "T" Accent	37" x 97-1/4" x 33-1/4"	235	\$5,008	\$5,459
	59-S42-SA0 OAK	59-S42-SA0 MAP	Two-Position S/F Adder	37" x 96" x 33-1/4"	205	\$3,614	\$3,940
Double-Faced Two-Position	36" Wide Workii	ng Space					
	59TP-D32-SS0 OAK	59TP-D32-SS0 MAP	Two-Position D/F Starter with Painted Metal "T" Accent	37" x 74" x 63-1/2"	330	\$5,837	\$6,362
	59TC-D32-SS0 OAK	59TC-D32-SS0 MAP	Two-Position D/F Starter with Chrome "T" Accent	37" x 74" x 63-1/2"	330	\$7,072	\$7,709
Starter	59-D32-SA0 OAK	59-D32-SA0 MAP	Two-Position D/F Adder	37" x 73" x 63-1/2"	270	\$5,487	\$5,981
	48" Wide Workii	ng Space					
	59TP-D42-SS0 OAK	59TP-D42-SS0 MAP	Two-Position D/F Starter with Painted Metal "T" Accent	37" x 97-1/4" x 63-1/2"	355	\$6,024	\$6,566
	59TC-D42-SS0 OAK	59TC-D42-SS0 MAP	Two-Position D/F Starter with Chrome "T" Accent	37" x 97-1/4" x 63-1/2"	355	\$7,299	\$7,957
Adder	59-D42-SA0 OAK	59-D42-SA0 MAP	Two-Position D/F Adder	37" x 96" x 63-1/2"	355	\$5,424	\$5,912

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

### Modular Media Stations with Resin Window

## The Epoch Collection


Starter

Adder


Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Worki	ng Space						Single-Faced Three-Position
59GP-S33-SS0 OAK	59GP-S33-SS0 MAP	Three-Position S/F Starter with Resin Window and Painted	37" x 110-1/2" x 33-1/4" Accent	260	\$5,759	\$6,277	
59GC-S33-SS0 OAK	59GC-S33-SS0 MAP	Three-Position S/F Starter with Resin Window and Chrome	37" x 110-1/2" x 33-1/4" Accent	260	\$6,680	\$7,281	
59-S33-SA0 OAK	59-S33-SA0 MAP	Three-Position S/F Adder	37" x 109-1/4" x 33-1/4"	230	\$4,503	\$4,908	Starter
							F
							Adder
36" Wide Worki	ng Space						Double-Faced Three-Position
59GP-D33-SS0 OAK	59GP-D33-SS0 MAP	Three-Position D/F Starter with Resin Window and Painted	37" x 110-1/2" x 33-1/4" Accent	445	\$7,432	\$8,101	9 5
59GC-D33-SS0 OAK	59GC-D33-SS0 MAP	Three-Position D/F Starter with Resin Window and Chrome	37" x 110-1/2" x 33-1/4" Accent	445	\$8,623	\$9,399	
59-D33-SA0 OAK	59-D33-SA0 MAP	Three Position D/F Adder	37" x 109-1/4" x 33-1/4"	385	\$8,232	\$8,972	
							Starter
							Adder
							90° Functional Corner Unit
59GP-SCR-SS0 OAK	59GP-SCR-SS0 MAP	90-Degree Functional Corner Starter with Resin Windo	37" x 62" x 33-1/4" w and Painted Accent	225	\$7,337	\$7,997	70 I Unctional Comer Utilit
59GC-SCR-SS0 OAK	59GC-SCR-SS0 MAP	90-Degree Functional Corner Starter with Resin Windo	37" x 62" x 33-1/4" w and Chrome Accent	225	\$8,511	\$9,277	
59-SCR-SAO OAK	59-SCR-SAO MAP	90-Degree Functional Corner Adder	37" x 62" x 33-1/4"	195	\$6,077	\$6,624	

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2), Metal Color (Table 3) and Resin Option; if applicable (Table 6). Details can be found on pages GEN 4, GEN 5 and GEN 6.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced Three-Position	36" Wide Work S	<i>Surface</i>					
	59TP-S33-SS0 OAK	59TP-S33-SS0 MAP	Three-Position S/F Starter with Painted Metal "T" Accent	37" x 110-1/2" x 33-1/4"	260	\$4,895	\$5,335
Starter	59TC-S33-SS0 OAK	59TC-S33-SS0 MAP	Three-Position S/F Starter with Chrome "T" Accent	37" x 110-1/2" x 33-1/4"	260	\$5,932	\$6,466
Starter	59-S33-SA0 OAK	59-S33-SA0 MAP	Three-Position S/F Adder	37" x 109-1/4" x 33-1/4"	230	\$4,503	\$4,908
Adder							
Double-Faced Three-Position	<i>36" Wide Work S</i> 59TP-D33-SS0 OAK	<i>Furface</i> 59TP-D33-SS0 MAP	Three-Position D/F Starter	37" x 110-1/2" x 33-1/4"	445	\$6,319	\$6,888



36" Wide Work Surface											
59TP-D33-SS0 MAP	Three-Position D/F Starter with Painted Metal "T" Accent	37" x 110-1/2" x 33-1/4"	445	\$6,319	\$6,888						
59TC-D33-SS0 MAP	Three-Position D/F Starter with Chrome "T" Accent	37" x 110-1/2" x 33-1/4"	445	\$7,657	\$8,346						
59-D33-SA0 MAP	Three Position D/F Adder	37" x 109-1/4" x 33-1/4"	385	\$8,232	\$8,972						
	59TP-D33-SS0 MAP 59TC-D33-SS0 MAP	59TP-D33-SSO MAP Three-Position D/F Starter with Painted Metal "T" Accent Three-Position D/F Starter with Chrome "T" Accent	59TP-D33-SS0 MAP Three-Position D/F Starter with Painted Metal "T" Accent vith Painted Metal "T" Accent vith Chrome "T" Accent vith Chrom	59TP-D33-SS0 MAP         Three-Position D/F Starter with Painted Metal "T" Accent         37" x 110-1/2" x 33-1/4"         445           59TC-D33-SS0 MAP         Three-Position D/F Starter with Chrome "T" Accent         37" x 110-1/2" x 33-1/4"         445	59TP-D33-SS0 MAP         Three-Position D/F Starter with Painted Metal "T" Accent         37" x 110-1/2" x 33-1/4"         445         \$6,319           59TC-D33-SS0 MAP         Three-Position D/F Starter with Chrome "T" Accent         37" x 110-1/2" x 33-1/4"         445         \$7,657						



90° Functional Corner Unit

59TP-SCR-SS0 OAK	59TP-SCR-SS0 MAP	90-Degree Functional	37" x 62" x 33-1/4"	225	\$6,236	\$6,797
		Corner Starter with Painted Metal '	"T" Accent			
59TC-SCR-SS0 OAK	59TC-SCR-SS0 MAP	90-Degree Functional	37" x 62" x 33-1/4"	225	\$7,557	\$8,237
		with Chrome "T" Accent				
59-SCR-SAO OAK	59-SCR-SA0 MAP	90-Degree Functional	37" x 62" x 33-1/4"	195	\$6,077	\$6,624
		Corner Adder				

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

### **WORK SURFACE**

Each work surface is constructed of durable particleboard, and has a high-pressure laminate face that creates a protective, low-glare finish resistant to scratches, fading, and staining. All work surfaces measure a spacious 62"W x 44-1/2"D with a 62" radius, and are 29"H. Two-position units have one top, and four-position units have two.

### WORK SURFACE DIVIDER PANEL

Workstation divider panels are designed to provide semi-privacy and workspace definition. In a contemporary twist, all workstation divider panels feature an eye-catching window. Divider panels are made of sturdy, maple-veneered particleboard and measure 17-1/2"H x 42"W x 1-3/4" thick. Four-position units have two work surface divider panels.

#### WORK SURFACE BASE

All work surface bases measure 27-5/16"H and are made of two pieces of 3/4" maple-veneered particleboard with spacer, which brings the total thickness to 1-3/4". A 3" grommet hole is positioned in the upper rear corner of each panel, creating a convenient wire passage. Four-position units have two work surface bases.

### **END PANELS**

End panels are made of durable, maple-veneered particleboard measuring 47"H. The veneer grain runs vertical on the end panels and all edges receive a 1.6mm thick maple band. In the four-position unit, 3" grommets in the panels are located under the work surface for a convenient wire passage.

### **CENTER POST**

Workstation center posts measure 47-1/4"H x 2-1/4"W x 1-3/4" thick on two-position stations. Four-position center posts measure 47-1/4"H x 1-3/4"W x 1-3/4" thick. All posts are made of solid hard maple and have a 1/2" adjustable floor glide.

### **ELECTRICAL COMPONENTS**

As standard equipment, two-position units have two Brodart model #73-200-S00 lift-up black electrical grommets, which include duplex outlets and data jack ports. Each component measures 6" x 4-1/2" and is located in the corner of each work surface. Four-position units have four lift-up grommets.


As standard equipment, the two- and four-position units have one #73-210-S00 2-1/4" diameter black flexible wire manager, which allows wires to be kept together and out of sight. The wire manager is easily movable, but is weighted at the bottom for secure positioning.

### CHROME PLATING SPECIFICATION

Where "chrome plated" is specified, Brodart provides a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. The brilliance of the chrome plating enhances the overall look of the piece and creates a high-quality furniture grade finish


### WINDOW SPECIFICATIONS

Unless otherwise specified, all resin window panels are 1/4" thick, resin material. Customers may specify the preferred tint color from those offered by Brodart. Window panels are securely held in place by 1/4" thick solid wood maple molding on both sides.



**Epoch Series Edge** 

	Maple Price	Oak Price	Wt. (lbs.)	HxWxD	Description	Maple Catalog No.	Oak Catalog No.
Two Posi Computer Worksta	\$7,171	\$6,579	290	47-1/2" x 60" x 46-3/4"	S/F Two Position Computer Workstation	59-822-S00 MAP	59-822-S00 OAK
Four Posi Computer Worksta	\$12,950	\$11,881	480	47-1/2" x 60" x 90-3/16"	D/F Four Position Computer Workstation	59-824-S00 MAP	59-824-S00 OAK



### STATION TOP

Each top is 47"W at the front, tapering to 21-3/16" at the rear. Tops are 28-1/2"D plus a 1-1/2"W cord drop runs the width of the station between the top and back panel to allow passage of electrical and data cords. Station tops are 1-3/16" thick, 45# density particleboard core including a top surface of .050" thick, high-pressure laminate and a backing sheet .020" thick, for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. The front edge of the top is banded with a 2" x 1-3/4"W solid maple external edge band glued to the work surface core after lamination of the face plastic. The edge band is beveled at 20° to a 1/2" radius bullnose at the leading edge.

### **VERTICAL PANELS**

End and intermediate panels are 1-3/16" thick, 45# density particleboard core. Veneer on both faces of the panels are plain-sliced maple and slip matched. The vertical edges of the panel and top edge receive a 1.6mm edge band.

### **ELECTRICAL ACCESS DOOR**

(One for each 3- or 6-station unit) Access door is 3/4" thick, comprised of select face veneers of maple over a particleboard core. Panel is externally banded on all four sides with a 1/4" thick solid maple edge band. Door have a full-length hinge and have a lock. Access door is located on one back panel, which can be located anywhere in the PAC station.

### **BACK PANEL**

The back panel is 1-3/16" thick, 3-ply 45# density particle-board core with select plain-sliced, slip-matched maple veneer on both faces. The panel is externally banded with 1.6mm thick solid maple on both the bottom edge and the top edge.

Back panels are attached to end and intermediate panels using hidden metal keyways and shoulder screws. Back panels have a 3" diameter grommeted egress for electrical cords to pass to the center hub of half-hexagon station configurations.

### **SHELVES**


Shelves are 3/4" thick, select maple veneered 45# density particleboard having a 5/8" thick 1-3/4"H solid maple front edge band.

#### **CENTER CAP**

The center caps are 3/4" thick, 45# density particleboard, with high-pressure laminate to match the tops and shaped to enclose half-hexagon and full-hexagon station configurations.

#### WORKING SPACE

The working space is adjustable to: Standing Height 39", ADA Height 32" and Sitting Height 27".



Epoch Series Edge

265

\$7,835

\$8,540

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Six Position PAC Station	59-682-S00 OAK	59-682-S00 MAP	Six position with	45-1/4" x 101-1/2" x 101-1/2"	500	\$12,552	\$13,681
			angular tops.				





59-685-S00 OAK 59-685-S00 MAP

Three position with 45-1/4" x 101-1/2" x 50-3/4" angular tops. Composed of one starter unit and two adder units.

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

This unit consists of a C.P.U. cabinet, a work surface, end panels and monitor shield.

### C.P.U. STORAGE CABINET

The C.P.U. storage cabinet is constructed of 3/4" maple veneer plywood, that matches the end panels. The cabinet is 22-1/4"  $\times 24$ "  $\times 23-1/2$ " D. Inside cabinet dimensions are 20"  $\times 22-1/2$ "  $\times 22$ " D. The front has two doors, that can be locked. The cabinet is attached to the underside of the work surface. The bottom of the cabinet has a 3" grommet in each rear corner for wire passage.

#### WORK SURFACE

The work surface is 1-3/16" thick, 3-ply 45# density particleboard core with .050" high-pressure laminate face and a .020" thick phenolic backing sheet on the underside. The high-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining in accordance with NEMA standards.

The front edge of the work surface an external maple edge band 2"W x 1-3/4" T to match the shape of the edge on the tables. The rear edge has an external 5/8"W x 1-5/8" T bullnose solid maple band. A 3" grommet centered 6" from the back edge allows wires and heat to escape the cabinet.

#### **END PANELS**

The end panels measure 48-5/32"H x 33-1/8"W x 1-3/16" thick and include 1/2"H leveling glides. The end panels are plain sliced, slip matched maple veneers on a particleboard core of 45# density. The edges receive 1.6mm thick maple bands with top and vertical edges bullnosed. The vertical edges are also tapered down 2° from top to bottom. The top edge is arched with a 47-3/8" radius. A resin panel window 3-3/4"H x 8-1/2"W is inserted 3-1/4" down from the center of the top edge (see Window Specifications). The resin is held in place with

1/4" thick maple molding on both sides of the window. The molding is sanded flush on both panel surfaces. A 1/4" x 1/4" x 3/16" chrome plated or powder-coat painted square steel rod is embedded 4" from the bottom edge of the panel.

### MONITOR SHIELD


A monitor shield is bolted to the work surface 1-5/8" from the rear edge. It is 9"H x 18"W with a 9" radius shape. The material is 1/8" thick steel, black textured powder-coated.

### CHROME PLATING SPECIFICATION

Where "chrome plated" is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.

### WINDOW SPECIFICATIONS

Unless otherwise specified, all resin window panels are 1/4" thick. Customers must specify the tint color they require from those offered by Brodart. Resin is held in place by 1/4" thick solid wood maple molding, on both sides of the window. The molding is sanded flush with the panel surfaces.



**Epoch Series Edge** 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	0ak Price	Maple Price	
59GP-039-S00 OAK	59GP-039-S00 MAP	OPAC Station with	48-1/8" x 26-1/4" x 33"	296	\$3,715	\$4,050	OPAC Station
		Resin Window and Painted A	ccent				
59GC-039-S00 OAK	59GC-039-S00 MAP	OPAC Station with	48-1/8" x 26-1/4" x 33"	296	\$4,375	\$4,768	
		Resin Window and Chrome A	ccent				
59TP-039-S00 OAK	59TP-039-S00 MAP	OPAC Station with	48-1/8" x 26-1/4" x 33"	296	\$2,784	\$3,035	
		Painted Metal "T"Accent					
59TC-039-S00 OAK	59TC-039-S00 MAP	OPAC Station with	48-1/8" x 26-1/4" x 33"	296	\$3,788	\$4,129	
		Painted Chrome "T" Accent					
							1

### TOP

The sloped top is 1-3/16" thick, 3-ply particleboard including a top surface of .050" thick high-pressure laminate, with a backing sheet not less than .020" thick. The back edge band is solid wood 1/4" thick and the front edge is 2" wide x 1-3/4" thick with the Epoch shape.

### **STAND**

The back edge is internal and the front edge is external. A  $5/8" \times 5/8"$  solid wood book retainer strip is positioned at the front edge of the sloped top. The back, bottom, and shelf are 3/4" thick furniture grade plywood. The ends are 1-3/16" thick furniture-grade plywood with a bullnosed 5/8" thick edge on the top and vertical edges and 5/8" thick flat edge on the bottom edge. The bottom has adjustable floor glides. The vertical edges of the end panels angle out from the bottom at 92° the top edge has a 17-5/8" radius.


Toward the top center of each end panel is a resin window 9" x 3". The type of window is specified on the order, as many patterns and colors are available. A metal strip 1/4" x 1/4" is embedded 3/16" deep into the panel on the ouside 4" up from the bottom edge. This strip is chrome or powder-coat as specified.

### METAL "T" ACCENT

A 1-1/4" x 1/4" metal strip with a 6" center leg is embedded 3/16" deep across the panel towards the top and is chromed or powder-coated as specified.

#### **SHELVES**

There is one adjustable shelf that rests on 5/15-18 x 1" pins.



**Epoch Series Edge** 

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Dictionary Stand	59GP-869-S00 OAK	59GP-869-S00 MAP	Dictionary Stand with Resin Window	47-1/2" x 24-3/8" x 18-11/16" and Painted Accent	200	\$4,059	\$4,424
	59GC-869-S00 OAK	59GC-869-S00 MAP	Dictionary Stand with Resin Window	47-1/2" x 24-3/8" x 18-11/16" and Chrome Accent	200	\$4,719	\$5,144
	59TP-869-S00 OAK	59TP-869-S00 MAP	Dictionary Stand with Painted Metal	47-1/2" x 24-3/8" x 18-11/16" "T" Accent	200	\$3,472	\$3,784
S	59TC-869-S00 OAK	59TC-869-S00 MAP	Dictionary Stand with Painted Chrom	47-1/2" x 24-3/8" x 18-11/16" e "T" Accent	200	\$4,181	\$4,558

#### TOF

The sloped top is 1-316" thick, 3-ply particleboard including a top surface of .050" thick high-pressure laminate, with a backing sheet not less than .020" thick. The back edge band is solid wood 1/4" thick and the front edge is 2" wide x 1-3/4" thick with the Epoch shape.

#### **STAND**

The back edge is internal and the front edge is external. A  $5/8" \times 5/8" \times 5/8"$  solid wood book retainer strip is positioned at the front edge of the sloped top. The back, bottom, and shelf are 3/4" thick furniture grade plywood. The ends are 1-3/16" thick furniture grade plywood with a bullnosed 5/8" thick edge on the top and vertical edges and 5/8" thick flat edge on the bottom edge. The bottom has adjustable floor glides. The vertical edges of the end panels angle out from the bottom at 92° the top edge has a 17-5/8" radius.


Toward the top center of each end panel is a resin window 9" x 3". The type of window is specified on the order, as many patterns and colors are available. A metal strip 1/4" x 1/4" is embedded 3/16" deep into the panel on the ouside 4" up from the bottom edge. This strip is chrome or powder-coat as specified.

#### METAL "T" ACCENT

A 1-1/4" x 1/4" metal strip with a 6" center leg is embedded 3/16" deep across the panel towards the top and is chromed or powder-coated as specified.

### **SHELVES**

There is one adjustable shelf that rests on 5/15-18 x 1" pins.



**Epoch Series Edge** 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
59GP-871-S00 OAK	59GP-871-S00 MAP	Atlas Stand with Resin Window and I	47-9/16" x 28-3/8" x 33-1/8" Painted Accent	225	\$4,984	\$5,433	Atlas Stand
59GC-871-S00 OAK	59GC-871-S00 MAP	Atlas Stand with Resin Window and	47-9/16" x 28-3/8" x 33-1/8" Chrome Accent	225	\$5,643	\$6,151	
59TP-871-S00 OAK	59TP-871-S00 MAP	Atlas Stand with Painted Metal "T"	47-9/16" x 28-3/8" x 33-1/8" Accent	225	\$4,381	\$4,776	
59TC-871-S00 OAK	59TC-871-S00 MAP	Atlas Stand with Painted Chrome "T	47-9/16" x 28-3/8" x 33-1/8" " Accent	225	\$5,065	\$5,521	

This spacious unit consists of a cabinet of 3/4" thick maple veneer plywood 51-3/16"H x 36-7/8"W x 28-7/16"D. It has a 3/4" thick maple veneer plywood back with five drawers for storage or display of DVD or CD cases. This unit has design end panels to match other pieces in the Epoch Series. Approximate capacity for CD's is 624 for 525 for DVD's.

### **DRAWERS**

The drawers are constructed of 1/2" solid maple with a maple plywood bottom and front banded on all edges with 1.6mm solid maple. The grain direction runs vertically and the five drawer fronts are cut out of one sheet so that the grain all matches each other on each drawer front. The drawer bottom is cut to allow for five metal tracks with a metal follower block in each track to run from front to back of the drawer. This follower block is adjustable and holds the CD's and DVD's in an upright position. Each drawer to receive 100# load capacity full extension drawer slides. Each drawer receives two chrome drawer pulls for easy opening and closing. The unit has a mechanism that allows only one drawer to be open at a time so that the unit does not tip over.

### **END PANELS**


End panels measure 51-3/16"H x 28-7/16"W x 1-3/16" thick with plain sliced slip matched hard maple veneers and 45# density particleboard core. The edges are banded with 1.6mm solid maple. The front and rear vertical edges taper down 2° from the top edge. The top edge is arched at a 52" radius. Down 3-3/4" from the top edge a window of resin is centered on the panel. The size of the window with molding is 29-1/4" vertically x 2-1/2"W. (See Window Specifications) a square 1/4" x 1/4" rod is inserted into the surface of the end panel 3/16"D and is chrome plated or powder-coated as specified by the owner. (See Chrome Plating Specifications).

### CHROME PLATING SPECIFICATION

Where "chrome plated" is specified, Brodart uses a decorative chromium electro-plated finish, which protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.

### WINDOW SPECIFICATIONS

Unless otherwise specified all resin window panels are 1/4" thick. The customer must specify the resin color that they require from those offered by Brodart. The resin is held in place by 1/4" thick solid wood maple molding on both sides of the resin. The molding is sanded flush with the panel surfaces.



**Epoch Series Edge** 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Starter	Adder
59GP-771-S03 OAK	59GP-771-S03 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$8,838	\$9,634	5.000	Display Unit
		Resin Window and	Painted Accent					)
59GC-771-S03 OAK	59GC-771-S03 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$9,722	\$10,597		
		Resin Window and	Chrome Accent					
59TP-771-S03 OAK	59TP-771-S03 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$8,767	\$9,556		
		Painted Metal "T"	Accent				Service ,	
59TC-771-S03 OAK	59TC-771-S03 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$10,521	\$11,468	- Carrie	
		Painted Chrome "1	" Accent					
59-771-S04 OAK	59-771-S04 MAP	Adder Unit	51-3/16" x 35-11/16" x 28-7/16"	230	\$8,214	\$8,953		NAME OF THE OWNER OWNER OF THE OWNER OWNER OF THE OWNER OWNE
							SZZZZ	-
							ZZZZ	

59GP-771-S00 OAK	59GP-771-S00 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$8,948	\$9,753	Storage Unit
		Resin Window and	Painted Accent				
59GC-771-S00 OAK	59GC-771-S00 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$11,147	\$12,150	
		Resin Window and	Chrome Accent				
59TP-771-S00 OAK	59TP-771-S00 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$8,870	\$9,669	
		Painted Metal "T"	Accent				
59TC-771-S00 OAK	59TC-771-S00 MAP	Starter Unit with	51-3/16" x 36-7/8" x 28-7/16"	250	\$10,643	\$11,601	/
		Painted Chrome "T	" Accent				
59-771-S02 OAK	59-771-S02 MAP	Adder Unit	51-3/16" x 35-11/16" x 28-7/16"	230	\$8,324	\$9,073	
							-

# The Epoch Collection

Oak	Maple			0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE U	INIT				
59-W10-S01 OAK	59-W10-S01 MAP	10"D, Single-Faced	11	\$370	\$389
59-W12-S01 OAK	59-W12-S01 MAP	12"D, Single-Faced	14	\$391	\$410
59-W20-S01 OAK	59-W20-S01 MAP	20"D, Double-Faced	23	\$640	\$672
59-W24-S01 OAK	59-W24-S01 MAP	24"D, Double-Faced	27	\$683	\$717
To Cover TWO L	INITS				
59-W10-S02 OAK	59-W10-S02 MAP	10"D, Single-Faced	22	\$504	\$529
59-W12-S02 OAK	59-W12-S02 MAP	12"D, Single-Faced	28	\$549	\$576
59-W20-S02 OAK	59-W20-S02 MAP	20"D, Double-Faced	46	\$902	\$947
59-W24-S02 OAK	59-W24-S02 MAP	24"D, Double-Faced	54	\$1,001	\$1,051
To Cover THREE	E UNITS				
59-W10-S03 OAK	59-W10-S03 MAP	10"D, Single-Faced	33	\$629	\$660
59-W12-S03 OAK	59-W12-S03 MAP	12"D, Single-Faced	42	\$701	\$736
59-W20-S03 OAK	59-W20-S03 MAP	20"D, Double-Faced	69	\$1,220	\$1,281
59-W24-S03 OAK	59-W24-S03 MAP	24"D, Double-Faced	81	\$1,266	\$1,329
To Cover FOUR	IINITS				
59-W10-S04 OAK	59-W10-S04 MAP	10"D, Single-Faced	44	\$851	\$894
59-W12-S04 OAK	59-W12-S04 MAP	12"D, Single-Faced	56	\$938	\$985
59-W20-S04 OAK	59-W20-S04 MAP	20"D, Double-Faced	92	\$1,521	\$1,597
59-W24-S04 OAK	59-W24-S04 MAP	24"D, Double-Faced	108	\$1,714	\$1,801
To Cover FIVE U	INITS				
59-W10-S05 OAK	59-W10-S05 MAP	10"D, Single-Faced	55	\$965	\$1,014
59-W12-S05 OAK	59-W12-S05 MAP	12"D, Single-Faced	70	\$1,092	\$1,147
59-W20-S05 OAK	59-W20-S05 MAP	20"D, Double-Faced	115	\$1,839	\$1,931
59-W24-S05 OAK	59-W24-S05 MAP	24"D, Double-Faced	135	\$1,979	\$2,078
To Cover SIX UI	<u>VITS</u>				
59-W10-S06 OAK	59-W10-S06 MAP	10"D, Single-Faced	66	\$1,102	\$1,157
59-W12-S06 OAK	59-W12-S06 MAP	12"D, Single-Faced	84	\$1,245	\$1,307
59-W20-S06 OAK	59-W20-S06 MAP	20"D, Double-Faced	138	\$2,161	\$2,269
59-W24-S06 OAK	59-W24-S06 MAP	24"D, Double-Faced	162	\$2,248	\$2,360
To Cover SEVEN	<u>UNITS</u>				
59-W10-S07 OAK	59-W10-S07 MAP	10"D, Single-Faced	77	\$1,324	\$1,391
59-W12-S07 OAK	59-W12-S07 MAP	12"D, Single-Faced	98	\$1,483	\$1,557
59-W20-S07 OAK	59-W20-S07 MAP	20"D, Double-Faced	161	\$2,458	\$2,581
59-W24-S07 OAK	59-W24-S07 MAP	24"D, Double-Faced	189	\$2,696	\$2,831
To Cover EIGHT	UNITS				
59-W10-S08 OAK	59-W10-S08 MAP	10"D, Single-Faced	88	\$1,451	\$1,524
59-W12-S08 OAK	59-W12-S08 MAP	12"D, Single-Faced	112	\$1,637	\$1,719
59-W20-S08 OAK	59-W20-S08 MAP	20"D, Double-Faced	184	\$2,778	\$2,917
59-W24-S08 OAK	59-W24-S08 MAP	24"D, Double-Faced	216	\$2,949	\$3,097
To Cover NINE L	<u>UNITS</u>				
59-W10-S09 OAK	59-W10-S09 MAP	10"D, Single-Faced	99	\$1,620	\$1,701
59-W12-S09 OAK	59-W12-S09 MAP	12"D, Single-Faced	126	\$1,831	\$1,923
59-W20-S09 OAK	59-W20-S09 MAP	20"D, Double-Faced	207	\$3,139	\$3,296
59-W24-S09 OAK	59-W24-S09 MAP	24"D, Double-Faced	243	\$3,272	\$3,435

**Note:** Edge banding on the end of tops receive mitred corners. Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

0ak	Maple			Oak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE U	INIT				
59-S10-S01 OAK	59-S10-S01 MAP	10"D, Single-Faced	11	\$370	\$389
59-S12-S01 OAK	59-S12-S01 MAP	12"D, Single-Faced	14	\$391	\$410
59-S20-S01 OAK	59-S20-S01 MAP	20"D, Double-Faced	23	\$640	\$672
59-S24-S01 OAK	59-S24-S01 MAP	24"D, Double-Faced	27	\$683	\$717
To Cover TWO L	JNITS				
59-S10-S02 OAK	59-S10-S02 MAP	10"D, Single-Faced	22	\$504	\$529
59-S12-S02 OAK	59-S12-S02 MAP	12"D, Single-Faced	28	\$549	\$576
59-S20-S02 OAK	59-S20-S02 MAP	20"D, Double-Faced	46	\$902	\$947
59-S24-S02 OAK	59-S24-S02 MAP	24"D, Double-Faced	54	\$1,001	\$1,051
To Cover THREE	E UNITS				
59-S10-S03 OAK	59-S10-S03 MAP	10"D, Single-Faced	33	\$629	\$661
59-S12-S03 OAK	59-S12-S03 MAP	12"D, Single-Faced	42	\$701	\$736
59-S20-S03 OAK	59-S20-S03 MAP	20"D, Double-Faced	69	\$1,220	\$1,281
59-S24-S03 OAK	59-S24-S03 MAP	24"D, Double-Faced	81	\$1,266	\$1,329
To Cover FOUR	IINITS				
59-S10-S04 OAK	59-S10-S04 MAP	10"D, Single-Faced	44	\$851	\$894
59-S12-S04 OAK	59-S12-S04 MAP	12"D, Single-Faced	56	\$938	\$985
59-S20-S04 OAK	59-S20-S04 MAP	20"D, Double-Faced	92	\$1,521	\$1,597
59-S24-S04 OAK	59-S24-S04 MAP	24"D, Double-Faced	108	\$1,714	\$1,801
To Cover FIVE I	INITE				
<u>To Cover FIVE U</u> 59-S10-S05 OAK	59-S10-S05 MAP	10"D, Single-Faced	55	\$965	\$1,014
59-S12-S05 OAK	59-S12-S05 MAP	12"D, Single-Faced	70	\$1,092	\$1,014 \$1,147
59-S20-S05 OAK	59-S20-S05 MAP	20"D, Double-Faced	115	\$1,839	\$1,147
59-S24-S05 OAK	59-S24-S05 MAP	24"D, Double-Faced	135	\$1,839 \$1,979	\$1,731
To Cover SIV III	WITC	·			
<i>To Cover SIX UI</i> 59-S10-S06 OAK		10"D Single Faced	66	\$1,102	¢1 1E7
59-S12-S06 OAK	59-S10-S06 MAP 59-S12-S06 MAP	10"D, Single-Faced	84	•	\$1,157 \$1,207
59-S20-S06 OAK		12"D, Single-Faced 20"D, Double-Faced	138	\$1,245 \$2,141	\$1,307 \$2,269
59-S24-S06 OAK	59-S20-S06 MAP 59-S24-S06 MAP	24"D, Double-Faced	162	\$2,161 \$2,248	\$2,269 \$2,360
		21 5,50000 10000	102	Ψ <i>Σ</i> /2 10	Ψ2/000
To Cover SEVEN		40110 01 1 5 1	77	44.004	44.004
59-S10-S07 OAK	59-S10-S07 MAP	10"D, Single-Faced	77	\$1,324	\$1,391
59-S12-S07 OAK	59-S12-S07 MAP	12"D, Single-Faced	98	\$1,483	\$1,557
59-S20-S07 OAK 59-S24-S07 OAK	59-S20-S07 MAP 59-S24-S07 MAP	20"D, Double-Faced 24"D, Double-Faced	161 189	\$2,458 \$2,696	\$2,581 \$2,831
		21 5,500010 10000	107	Ψ2/070	Ψ2/001
To Cover EIGHT		10UD Charle Feed	00	<b>04.454</b>	<b>64 FO 4</b>
59-S10-S08 OAK	59-S10-S08 MAP	10"D, Single-Faced	88	\$1,451	\$1,524
59-S12-S08 OAK	59-S12-S08 MAP	12"D, Single-Faced	112	\$1,637	\$1,719
59-S20-S08 OAK	59-S20-S08 MAP	20"D, Double-Faced	184	\$2,778	\$2,917
59-S24-S08 OAK	59-S24-S08 MAP	24"D, Double-Faced	216	\$2,949	\$3,097
To Cover NINE U		10110 0: 1 5	22	*4 /55	A4 =04
59-S10-S09 OAK	59-S10-S09 MAP	10"D, Single-Faced	99	\$1,620	\$1,701
59-S12-S09 OAK	59-S12-S09 MAP	12"D, Single-Faced	126	\$1,831	\$1,923
59-S20-S09 OAK	59-S20-S09 MAP	20"D, Double-Faced	207	\$3,139	\$3,296
59-S24-S09 OAK	59-S24-S09 MAP	24"D, Double-Faced	243	\$3,272	\$3,435

**Note:** Edge Band on long side only. Tops are designed to be inset betweend end panels. If edge bands are desired on short edges, please enter the part as a modification and specify which bands to be included.

To ensure that tops for steel shelving work with each manufacturer and top method, please specify the exact width and depth of tops. Add 15% for HPL on top and bottom (Steel Shelving ONLY).

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ High-Pressure\ Laminate\ (Table\ 2).\ Details\ can\ be\ found\ on\ page\ GEN\ 4.$ 

### **END PANELS**

End panels are 1-3/16" thick, 3-ply 45# density particleboard core with select plain-sliced, slip-matched maple veneer on the inside and outside face. The vertical edges and top edge of the end panel have a 1.6mm maple external edge band. All panel edges are eased. Exact height and depth of panel must be specified when ordering. End panels are not machined for fastening. No fastening hardware is provided with end panels.

Double-face end panels have an accent window 3-3/4"H x 8-1/2"W. They have a 1/4" x 1/4" square steel rod that is embedded 3/16"D up 4" from the bottom edge and be chrome plated or powder-coated as ordered (see chrome specs). Single-face panels do not receive the accent window.

### CHROME PLATING SPECIFICATION

Where "chrome plated" is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.

### WINDOW SPECIFICATIONS

Unless otherwise specified, all resin window panels are 1/4" thick. Customers must specify the tint color they require from those offered by Brodart. The resin is held in place by 1/4" thick solid wood maple molding on both sides of the resin. The molding is sanded flush with the panel surfaces.

Note: Exact height and depth of panel must be specified when ordering. Epoch style end panels cannot be used with continuous tops that are overhung (out over the panels).

Note: Heights noted are to the bottom of the curve on the top of the panel.

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price	
Single-Faced wit	th Painted Metal Strip					Single-Faced End Panels
59P-702 MOD OAK	59P-702 MOD MAP	43-3/4" x 13-7/8"	14	\$461	\$484	
59P-703 MOD OAK	59P-703 MOD MAP	43-3/4" x 15-7/8"	16	\$488	\$512	
59P-705 MOD OAK	59P-705 MOD MAP	67-3/4" x 13-7/8"	21	\$531	\$558	
59P-706 MOD OAK	59P-706 MOD MAP	67-3/4" x 15-7/8"	26	\$557	\$585	
59P-708 MOD OAK	59P-708 MOD MAP	79-3/4" x 13-7/8"	25	\$598	\$628	
59P-709 MOD OAK	59P-709 MOD MAP	79-3/4" x 15-7/8"	30	\$625	\$656	
59P-711 MOD OAK	59P-711 MOD MAP	85-3/4" x 13-7/8"	28	\$605	\$635	
59P-712 MOD OAK	59P-712 MOD MAP	85-3/4" x 15-7/8"	33	\$629	\$661	
59P-714 MOD OAK	59P-714 MOD MAP	91-3/4" x 13-7/8"	29	\$609	\$640	
59P-715 MOD OAK	59P-715 MOD MAP	91-3/4" x 15-7/8"	35	\$635	\$667	
Single-Faced wit	th Chrome Metal Strip					
59C-702 MOD OAK	59C-702 MOD MAP	43-3/4" x 13-7/8"	14	\$531	\$558	
59C-703 MOD OAK	59C-703 MOD MAP	43-3/4" x 15-7/8"	16	\$557	\$585	
59C-705 MOD OAK	59C-705 MOD MAP	67-3/4" x 13-7/8"	21	\$602	\$632	
59C-706 MOD OAK	59C-706 MOD MAP	67-3/4" x 15-7/8"	26	\$627	\$659	
59C-708 MOD OAK	59C-708 MOD MAP	79-3/4" x 13-7/8"	25	\$669	\$702	
59C-709 MOD OAK	59C-709 MOD MAP	79-3/4" x 15-7/8"	30	\$694	\$729	
59C-711 MOD OAK	59C-711 MOD MAP	85-3/4" x 13-7/8"	28	\$675	\$708	
59C-712 MOD OAK	59C-712 MOD MAP	85-3/4" x 15-7/8"	33	\$700	\$735	
59C-714 MOD OAK	59C-714 MOD MAP	91-3/4" x 13-7/8"	29	\$680	\$714	
59C-715 MOD OAK	59C-715 MOD MAP	91-3/4" x 15-7/8"	35	\$707	\$742	
Double-Faced w	ith Painted Metal Strip					Double-Faced End Panels
59P-722 MOD OAK	59P-722 MOD MAP	43-3/4" x 24-3/8"	27	\$1,110	\$1,166	Double-1 deed End 1 driets
59P-723 MOD OAK	59P-723 MOD MAP	43-3/4" x 28-3/8"	33	\$1,128	\$1,185	
59P-725 MOD OAK	59P-725 MOD MAP	67-3/4" x 24-3/8"	43	\$1,383	\$1,452	
59P-726 MOD OAK	59P-726 MOD MAP	67-3/4" x 28-3/8"	52	\$1,401	\$1,470	
59P-728 MOD OAK	59P-728 MOD MAP	79-3/4" x 24-3/8"	51	\$1,501	\$1,576	
59P-729 MOD OAK	59P-729 MOD MAP	79-3/4" x 28-3/8"	61	\$1,517	\$1,593	
59P-731 MOD OAK	59P-731 MOD MAP	85-3/4" x 24-3/8"	55	\$1,511	\$1,586	
59P-732 MOD OAK	59P-732 MOD MAP	85-3/4" x 28-3/8"	66	\$1,527	\$1,603	
59P-734 MOD OAK	59P-734 MOD MAP	91-3/4" x 24-3/8"	59	\$1,519	\$1,595	
59P-735 MOD OAK	59P-735 MOD MAP	91-3/4" x 28-3/8"	60	\$1,536	\$1,613	
Double-Faced w	ith Chrome Metal Strip					
59C-722 MOD OAK	59C-722 MOD MAP	43-3/4" x 24-3/8"	27	\$1,179	\$1,238	
59C-723 MOD OAK	59C-723 MOD MAP	43-3/4" x 28-3/8"	33	\$1,197	\$1,257	
59C-725 MOD OAK	59C-725 MOD MAP	67-3/4" x 24-3/8"	43	\$1,454	\$1,527	
59C-726 MOD OAK	59C-726 MOD MAP	67-3/4" x 28-3/8"	52	\$1,470	\$1,544	
59C-728 MOD OAK	59C-728 MOD MAP	79-3/4" x 24-3/8"	51	\$1,571	\$1,650	
	59C-729 MOD MAP	79-3/4" x 28-3/8"	61	\$1,588	\$1,668	
59C-729 MOD OAK						
	59C-731 MOD MAP	85-3/4" x 24-3/8"	55	\$1,581	\$1.660	
59C-729 MOD OAK 59C-731 MOD OAK 59C-732 MOD OAK		85-3/4" x 24-3/8" 85-3/4" x 28-3/8"	55 66	\$1,581 \$1,597	\$1,660 \$1,677	
59C-731 MOD OAK	59C-731 MOD MAP			•	-	

Note: Epoch style end panels cannot be used with continuous tops that are overhung (out over the panels).

#### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply 45# density particleboard core or with a .050" high-pressure laminate with a .020" thick phenolic backing sheet on the underside. High-pressure laminate has a low-glare finish resistant to scratches, fading and staining in accordance with NEMA standards. Tabletops are banded on exposed edges with a 1-3/4" thick x 2" wide solid maple external chamfered edge band applied to the table core after lamination of the face plastic. The edge band is beveled down at a  $20^{\circ}$  angle with a 1/2" radius bullnose at the leading edge. Square and rectangular tabletop edge bands are mitered at all four corners and corners radiused 1/8".

### **TABLE LEG- (POWDER-COATED)**

Legs are 2-1/2" round, 16-gauge steel tubing. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Legs and plates are electrostatic powder-coat painted and have no sharp edges. The plate attaches to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The steel bracket is attached to the leg plate and leg using metal to metal fasteners. The strap may be electrostatic powder-coat painted or chrome plated. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

### **TABLE LEG-(CHROME)**

Legs are 2-1/2" round, 16-gauge steel tubing. The table is without an apron, with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Leg and plate are painted or plated to match the leg (see chrome specifications) and have no sharp edges. The plate is attached to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The bracket is attached to the leg plate and leg using metal to metal fasteners. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.

### TABLE LEG- (WOOD)


Legs are 2-1/2" round wood. The table is apronless design with legs attached to the tabletop by a 5" square x 5/16" thick steel plate. Plates are electrostatic powder coat painted and have no sharp edges. The plate attaches to the leg by a 9" x 3" x 3/8" steel angle bracket placed at a 45° angle. The steel angle bracket receives two cutout designs replicating the edge band profile. The steel bracket is attached to the leg plate and leg using metal to metal fasteners. The strap may be electrostatic powder-coat painted or chrome plated. The leg plate is attached to the tabletop by (5) 5/16" x 1" machine bolts engaging internally and externally threaded bushings embedded in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended edge band. Edge band extends 1/2" below the tabletop. Each leg has 2-1/2"D x 1"H adjustable glide mounted into a recessed threaded insert.


### CHROME PLATING SPECIFICATION


Where chrome plated is specified, Brodart uses a decorative chromium electro-plated finish that protects against tarnish and minimizes scratching. Brodart Class AA chrome plating requires a .004" to .005" thick layer of bright nickel and a layer of chromium to produce a high-quality furniture grade finish.


### **TABLETOP HEIGHT**


All tables are 16" high.











Oak Catalog No.	Maple Catalog No.	Description	H x W x D	Wt. (lbs.)	Oak Price	Maple Price	
59-610-S00 OAK	59-610-S00 MAP	Round Table with Powder-Coated	16"H x 38" Diameter	66	\$1,918	\$2,147	Round Table
59C-610-S00 OAK	59C-610-S00 MAP	Round Table with Chrome Legs	16"H x 38" Diameter	66	\$2,302	\$2,576	
59W-610-S00 OAK	59W-610-S00 MAP	Round Table with Wood Legs	16"H x 38" Diameter	66	\$1,918	\$2,147	
59-621-S00 OAK	59-621-S00 MAP	Square Table with Powder-Coated	16" x 30" x 30"	51	\$1,606	\$1,799	Square Table
59C-621-S00 OAK	59C-621-S00 MAP	Square Table with Chrome Legs	16" x 30" x 30"	51	\$1,927	\$2,158	
59W-621-S00 OAK	59W-621-S00 MAP	Square Table with Wood Legs	16" x 30" x 30"	51	\$1,606	\$1,799	
59-611-S00 OAK	59-611-S00 MAP	Rectangular Table	16" x 48" x 24"	46	\$1,499	\$1,678	Rectangular Table
59C-611-S00 OAK	59C-611-S00 MAP	with Powder-Coated Rectangular Table	d Legs 16" x 48" x 24"	46	\$1,798	\$2,013	T A T
59W-611-S00 OAK	59W-611-S00 MAP	with Chrome Legs Rectangular Table with Wood Legs	16" x 48" x 24"	46	\$1,499	\$1,678	

**-EP0 60-** F11-1-19G-EP0

# Geometrix

### CONSTRUCTION

Shelving construction is modular type, utilizing an Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB. Shelving units are designed with the starter and adder concept and measure 36" from center to center of the uprights. Oak and Maple are the standard wood species for Geometrix shelving.

### **END/FINISHING PANELS**

End panels are 1" thick, Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB. All edges are banded with matching veneer edgebanding. Edges are square, but eased. Vertical rows of holes are drilled near the front and rear of each panel for shelf adjustment on 32mm centers. Panels are drilled at front, rear, top, and bottom for embedding internal and external threaded bushings. Tops and bases are attached to end panels with 5/16" - 18 x 2" hex-head bolts and washers. Lag bolts or wood screws are not used.

### INTERMEDIATE UPRIGHT PANELS AND TRANSITIONAL PANELS

Intermediate uprights are 1" thick, Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB. All edges are banded with matching veneer edgebanding. Edges are square, but eased. Shelf pinholes are bored on both sides of the panel, but staggered so that pins can be deeply seated. Panels are drilled through at front, rear, top, and bottom for attachment of tops and bases with 5/16"-18 x 4-1/2" hex-head bolts, nuts, and washers.

### **BASE**

The base front is 3-1/4" H X 3/4" thick Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB with a 3/4" thick base shelf. A 2" x 3/4" full-length rail is tenoned to the inside of the front. Bolting cleats 1-1/4" x 1-1/4" are glued and stapled perpendicular at the ends of the rail and drilled to allow assembly bolts to pass through. A second full-length rail is glued and stapled to the rear of the bolting cleats for support and proper alignment. Bases are manufactured so the base shelf rests on the top of the base front.

### ATTACHMENT

Four bolts are used to attach each single-faced base or top. Eight bolts are used to attach each double-faced base or top, except for 23"D double-faced units, on which sixteen bolts are used. All hardware is concealed from view after assembly. Hardware kits for attaching single-faced units to the wall are available upon request and are sold separately.

### **BACKS AND PARTITIONS**

Backs and partitions are constructed of 3-ply or 5-ply furniture-grade Oak or Maple veneered plywood finished on both sides to match shelving.

Note: Backs must be ordered separately.

### STARTERS AND ADDERS

Starters and Adders include top, base, and shelves. Starters include one end panel, shelf pins and joining holes on inside only. Adders include one intermediate upright panel with shelf pins and joining holes on both sides. Finishing panels include shelf pins and joining holes on inside only.

Note: A finishing panel must be ordered separately to finish shelving.




Starter

Includes one end panel, shelf pins and joining holes on inside only. 37-3/16"W overall.



Adder

Includes one intermediate upright with shelf pins and joining holes on both sides. 36-3/16"W overall.



Wood Shelving Geometrix

### **General Specifications - Tops and Towers**

### WOOD SHELVING TOPS

Cornice tops have a 1-1/2" fascia, 3/4" thick, Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB, glued to a 3/4" thick Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB, of specified depth. On the inside surface of the top at each end, butted to the fascia, is a solid hardwood bolting cleat 1-1/4" x 1-1/4" that is both glued and stapled. For additional strength, three 1-3/4" cleats are added at the intersection of the fascia and top panel. Bolting cleats are drilled to allow assembly bolts to pass through.

Note: Tops on 72"H units are inverted.

### TRIANGLE TOWERS AND TRANSITIONAL TRIANGLE TOWERS

Triangle Towers are created using 1" thick, Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB. All edges are banded with matching veneer edgebanding. Edges are square, but eased. Vertical rows of holes are drilled near the front and rear of each panel for shelf adjustment on 32mm centers. Towers are assembled using 1-3/4" cleats attached to the inside of the tower panel. Panels are drilled at front, top, and bottom for embedding internal and external threaded bushings. Tops and bases are attached to triangle towers with 5/16" - 18 x 2" hex-head bolts and washers. Lag bolts or wood screws are not used.


# **General Specifications - Shelves & Mobile Units**

### WOOD SHELVES

Shelves are 1" thick, Industrial Grade Oriented Strand Board (OSB) as the core with two pieces of High Density Fiber (HDF) laminated to each side of the OSB. Adjustable shelves are notched 3/8" wide x 3/16" high x 3/4" long on the underside to set firmly on 1" long, 5/16" diameter threaded shelf pins, cadmium-plated. Shelf depths are nominal.

### MOBILE SHELVING UNITS

Mobile Shelving is available on 36", 42", 48", and 60-1/2" units. Shelving construction is the same as the standard shelving with the exception of the base; the base facing is 3-3/16"H. Four 2-1/2" diameter heavy-duty swivel casters attached to a 14 gauge caster bracket will be attached to the bottom of the unit with four #12 x 3/4" wood screws each. The caster assembly is hidden within the base, giving the appearance of standard unit.




**Bottom Caster View** 



Linear One Bay Mobile Unit





Arc One Bay Mobile Unit



Arc Two Bay Mobile Unit

### CONSTRUCTION

Shelving construction is modular type, utilizing thermally-fused laminate panels. Shelving units are designed with the starter and adder concept and measure 36" from center to center of the uprights. Oak, Classic Maple, Canadian Gray, Classic Black, and Bright White are the standard finishes for laminate shelving uprights, tops, and bases. Shelves are available in Orange, Red, Plum, Island Green, and Lapis Blue, in addition to the colors listed previously.

### **END/FINISHING PANELS**

End panels are 1" thick thermally-fused laminate panels. All edges are banded with matching 2MM PVC edgebanding. Edges are square, but eased. Vertical rows of holes are drilled near the front and rear of each panel for shelf adjustment on 32mm centers. Panels are drilled at front, rear, top, and bottom for embedding internal and external threaded bushings. Tops and bases are attached to end panels with 5/16" - 18 x 2" hex-head bolts and washers. Lag bolts or wood screws are not used.

### INTERMEDIATE UPRIGHT PANELS AND TRANSITIONAL PANELS

Intermediate uprights are 1" thick thermally-fused laminate panels. All edges are banded with matching 2MM PVC edgebanding. Edges are square, but eased. Shelf pinholes are bored on both sides of the panel, but staggered so that pins can be deeply seated. Panels are drilled through at front, rear, top, and bottom for attachment of tops and bases with 5/16"-18 x 4-1/2" hex-head bolts, nuts, and washers.

### **BASE**

The base front is 3-1/4"H X 3/4" thick thermally-fused laminate panel with a 3/4" thick base shelf. A full-length 2" x 3/4" rail is tenoned to the inside of the front. Bolting cleats 1-1/4" x 1-1/4" are glued and stapled perpendicular at the ends of the rail and drilled to allow assembly bolts to pass through. A second full-length rail is glued and stapled to the rear of the bolting cleats for support and proper alignment. Bases are manufactured so the base shelf rests on top of the base front.

### **ATTACHMENT**

Four bolts are used to attach each single-faced base or top. Eight bolts are used to attach each double-faced base or top, except for 23"D double-faced units, on which sixteen bolts are used. All hardware is concealed from view after assembly. Hardware kits for attaching single-faced units to the wall are available upon request and are sold separately.

### **BACKS AND PARTITIONS**

Backs and partitions are constructed with 1/4" thick thermally-fused laminate panels.

Note: Backs must be ordered separately.

### STARTERS AND ADDERS

Starters and Adders include top, base, and shelves. Starters include one end panel, shelf pins and joining holes on inside only. Adders include one intermediate upright panel with shelf pins and joining holes on both sides. Finishing panels include shelf pins and joining holes on inside only.

Note: A finishing panel must be ordered separately to finish shelving.




Includes one end panel, shelf pins and joining holes on inside only. 37-3/16"W overall.



Adder

Includes one intermediate upright with shelf pins and joining holes on both sides. 36-3/16"W overall.



Geometrix

# General Specifications - Tops and Towers

### SHELVING TOPS

Cornice tops have a 1-1/2" fascia, constructed with 3/4" thick, thermally-fused laminate panel with matching 2MM PVC edgebanding, glued to a 3/4" thick thermally-fused laminate panel of specified depth. On the inside surface of the top at each end, butted to the fascia, is a solid hardwood bolting cleat 1-1/4" x 1-1/4" that is both glued and stapled. For additional strength, three 1-3/4" cleats are added at the intersection of the fascia and top panel. Bolting cleats are drilled to allow assembly bolts to pass through.

Note: Tops on 72"H units are inverted.

### TRIANGLE TOWERS AND TRANSITIONAL TRIANGLE TOWERS

Triangle Towers are created using 1" thick, thermally-fused laminate panels. All edges are banded with matching 2mm PVC edgebanding. Edges are square, but eased. Vertical rows of holes are drilled near the front and rear of each panel for shelf adjustment on 32mm centers. Towers are assembled using 1-3/4" cleats attached to the inside of the tower panel. Panels are drilled at front, top, and bottom for embedding internal and external threaded bushings. Tops and bases are attached to triangle towers with 5/16" - 18 x 2" hex-head bolts and washers. Lag bolts or wood screws are not used.

Laminate Shelving Geometrix


## **General Specifications - Shelves & Mobile Units**

### LAMINATE SHELVES

Shelves are 3/4" thick, thermally-fused laminate, banded on front and back with matching 2MM PVC edgebanding. To ensure adequate support for heavy volumes, a 3/4" thick, 1-1/4"W support member is attached to the back edge of the bottom of each shelf. Adjustable shelves are notched 3/8"W x 3/16"H x 3/4"L on the underside to set firmly on 1" long, 5/16" diameter threaded shelf pins, cadmium-plated. Shelf depths are nominal.


### MOBILE SHELVING UNITS

Mobile Shelving is available on 36", 42", 48", and 60-1/2" units. Shelving construction is the same as the standard shelving with the exception of the base; the base facing is 3-3/16"H. Four 2-1/2" diameter heavy-duty swivel casters attached to a 14 gauge caster bracket will be attached to the bottom of the unit with four #12 x 3/4" wood screws each. The caster assembly is hidden within the base, giving the appearance of standard unit.



**Bottom Caster View** 












Arc Two Bay Mobile Unit

All Linear Single-Faced and Double-Faced, Starters and Adders. All Arc Single-Faced and Double-Faced, Starters and Adders. All Transitional Adders.

= Intermediate/Transition/
Finishing Panel
| = Back Panel Location
| = Shelving Side
| → = Open Shelving Direction

All Linear Single-Faced and Double-Faced, Tower Adders.
All Arc Single-Faced and Double-Faced, Tower Adders.
All Transitional Tower Adders.
All Three-Way Towers.



INLINE - Starter and adder back panels are on the same side of shelving units.

REVERSE - Starter and adder back panels are on the opposite side of shelving units.

TRANSITIONAL ADDERS/TOWER ADDERS - These are used when you are transitioning from a single-faced to double-faced unit, double-faced to single-faced unit, or single-faced unit to single-faced unit where the shelving units are positioned on opposite sides of the double-faced panel.

INNER SEATS - Inner seats are used on Convex Shelving.

OUTER SEATS - Outer seats are used on Concave Shelving.


SEATING - In some cases there will be two types of seating: Overlap End Panels and Inside End Panels.

**Overlap End Panels Seating** is used when you have a continuous run of seats that need to butt against each other to prevent a gap. They must overlap half of the edge of the end panel to achieve this. **Inside End Panels Seating** is used when you only need one seat or if the seat is used between two shelving units.

Note: These scenarios are labeled and depicted with images under each seating type in the seating section of the pricebook.

WHEN TO USE 37" WIDE CURVED SHELVING vs 44" WIDE CURVED SHELVING - 37" Wide Curved Shelving is used when you are transitioning from a curved Double-Faced unit to a Concave Single-Faced unit and the Single-Faced shelves are facing the inside of the curve. 44" Wide Curved Shelving is used when you are transitioning from a curved Double-Faced unit to a Single-Faced curved unit and the shelves are facing the outside of the curve.

### 37"W EXAMPLES:



Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	elves and 1 Base Si	helf						Single-Faced Starter Type 1
GEOLSS1360AKS	GEOLSS136MAPS	GEOLSS136LAMS	36" x 37-3/16" x 12"	63	\$ 670	\$ 703	\$501	
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						
GEOLSS1420AKS	GEOLSS142MAPS	GEOLSS142LAMS	42" x 37-3/16" x 12"	76	680	713	511	
GEOLSS1480AKS	GEOLSS148MAPS	GEOLSS148LAMS	48" x 37-3/16" x 12"	89	724	761	542	7
4 Adjustable She	elves and 1 Base Si	<u>helf</u>						6
GEOLSS1600AKS	GEOLSS160MAPS	GEOLSS160LAMS	60-1/2" x 37-3/16" x 12"	99	949	996	710	
GEOLSS1720AKS	GEOLSS172MAPS	GEOLSS172LAMS	72" x 37-3/16" x 12"	107	1,009	1,060	756	
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						Single-Faced Starter Type 2
GEOLSS2360AKS	GEOLSS236MAPS	GEOLSS236LAMS	36" x 37-3/16" x 12"	63	\$ 670	\$ 703	\$501	
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						
GEOLSS2420AKS	GEOLSS242MAPS	GEOLSS242LAMS	42" x 37-3/16" x 12"	76	680	713	511	
GEOLSS2480AKS	GEOLSS248MAPS	GEOLSS248LAMS	48" x 37-3/16" x 12"	89	724	761	542	
4 Adjustable She	elves and 1 Base Si	<u>helf</u>						
GEOLSS2600AKS GEOLSS2720AKS	GEOLSS260MAPS GEOLSS272MAPS	GEOLSS260LAMS GEOLSS272LAMS	60-1/2" x 37-3/16" x 12" 72" x 37-3/16" x 12"	99 107	949 1,009	996 1,060	710 756	
2 Adiostoble Che	alvas and 1 Bass C	h a l f						Single-Faced Inline Adder
•	elves and 1 Base Si		2/11-2/-2/4/11-421		A (70	d 700	<b>\$504</b>	Single-raced militie Adder
GEOLSIA360AKS	GEOLSIA36MAPS	GEOLSIA36LAMS	36" x 36-3/16" x 12"	63	\$ 670	\$ 703	\$501	
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						
GEOLSIA420AKS	GEOLSIA42MAPS	GEOLSIA42LAMS	42" x 36-3/16" x 12"	76	680	713	511	
GEOLSIA480AKS	GEOLSIA48MAPS	GEOLSIA48LAMS	48" x 36-3/16" x 12"	89	724	761	542	
4 Adjustable She	elves and 1 Base Si	<u>helf</u>						<b>1</b>
GEOLSIA600AKS	GEOLSIA60MAPS	GEOLSIA60LAMS	60-1/2" x 36-3/16" x 12"		949	996	710	
GEOLSIA72OAKS	GEOLSIA72MAPS	GEOLSIA72LAMS	72" x 36-3/16" x 12"	107	1,009	1,060	756	1/
2 Adjustable She	elves and 1 Base Si	helf						Single-Faced Reverse
GEOLSRA1360AKS	GEOLSRA136MAPS	GEOLSRA136LAMS	36" x 36-3/16" x 12"	63	\$ 670	\$ 703	\$501	Adder Type 1
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						
GEOLSRA1420AKS	GEOLSRA142MAPS	GEOLSRA142LAMS	42" x 36-3/16" x 12"	76	680	713	511	
GEOLSRA1480AKS	GEOLSRA148MAPS	GEOLSRA148LAMS	48" x 36-3/16" x 12"	89	724	761	542	
4 Adjustable She	elves and 1 Base Si	<u>helf</u>						<b>←</b>
•					0.40	007	710	1: 1: X
GEOLSRA1600AKS GEOLSRA1720AKS		GEOLSRA160LAMS GEOLSRA172LAMS	60-1/2" x 36-3/16" x 12" 72" x 36-3/16" x 12"	99 107	949 1,009	996 1,060	710 756	

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Single-Faced Reverse	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
Adder Type 2	GEOLSRA2360AKS	GEOLSRA236MAPS	GEOLSRA236LAMS	36" x 36-3/16" x 12"	63	\$ 670	\$ 703	\$501
	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOLSRA2420AKS GEOLSRA2480AKS	GEOLSRA242MAPS GEOLSRA248MAPS	GEOLSRA242LAMS GEOLSRA248LAMS	42" x 36-3/16" x 12" 48" x 36-3/16" x 12"	76 89	680 724	713 761	511 542
6				46 1 30-3/10 112	09	124	701	342
		elves and 1 Base Si						
<del>-</del>	GEOLSRA2600AKS GEOLSRA2720AKS	GEOLSRA260MAPS GEOLSRA272MAPS	GEOLSRA260LAMS GEOLSRA272LAMS	60-1/2" x 36-3/16" x 12" 72" x 36-3/16" x 12"	99 107	949 1,009	996 1,060	710 756
Single-Faced Inline Tower Adder Type 1	•	elves and 1 Base Si						
ridder Type T	GEOLSIT1360AKS	GEOLSIT136MAPS	GEOLSIT136LAMS	36" x 48-15/16" x 12"	79	\$1,082	\$1,136	\$ 810
T.	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOLSIT1420AKS GEOLSIT1480AKS	GEOLSIT142MAPS GEOLSIT148MAPS	GEOLSIT142LAMS GEOLSIT148LAMS	42" x 48-15/16" x 12" 48" x 48-15/16" x 12"	96 109	1,092 1,163	1,146 1,222	820 871
						.,	.,	<b>.</b>
	GEOLSIT1600AKS	elves and 1 Base Si GEOLSIT160MAPS	GEOLSIT160LAMS	60-1/2" x 48-15/16" x 12"	120	1,454	1,527	1,089
V."   ]	GEOLSIT1720AKS	GEOLSIT172MAPS	GEOLSIT172LAMS	72" x 48-15/16" x 12"	137	1,469	1,543	1,101
Single-Faced Inline Tower	2 Adjustable She	elves and 1 Base Si	helf					
Adder Type 2	GEOLSIT2360AKS	GEOLSIT236MAPS	GEOLSIT236LAMS	36" x 48-15/16" x 12"	79	\$1,159	\$1,218	\$ 868
1	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOLSIT2420AKS	GEOLSIT242MAPS	GEOLSIT242LAMS	42" x 48-15/16" x 12"	96	1,169	1,227	878
	GEOLSIT2480AKS	GEOLSIT248MAPS	GEOLSIT248LAMS	48" x 48-15/16" x 12"	109	1,239	1,302	928
- 7	_	elves and 1 Base Si						
	GEOLSIT2600AKS GEOLSIT2720AKS	GEOLSIT260MAPS GEOLSIT272MAPS	GEOLSIT260LAMS GEOLSIT272LAMS	60-1/2" x 48-15/16" x 12" 72" x 48-15/16" x 12"	129 137	1,537 1,546	1,614 1,623	1,151 1,159

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						Single-Faced Reverse
GEOLSRT1360AKS	GEOLSRT136MAPS	GEOLSRT136LAMS	36" x 48-15/16" x 12"	79	\$1,159	\$1,218	\$ 868	Tower Adder Type 1
2 Adjustable She	elves and 1 Base Si	<u>helf</u>						1
GEOLSRT1420AKS	GEOLSRT142MAPS	GEOLSRT142LAMS	42" x 48-15/16" x 12"	96	1,169	1,227	878	
GEOLSRT1480AKS	GEOLSRT148MAPS	GEOLSRT148LAMS	48" x 48-15/16" x 12"	109	1,239	1,302	928	
4 Adjustable She	elves and 1 Base Si	<u>helf</u>						
GEOLSRT1600AKS	GEOLSRT160MAPS	GEOLSRT160LAMS	60-1/2" x 48-15/16" x 12"	129	1,537	1,614	1,151	
GEOLSRT1720AKS	GEOLSRT172MAPS	GEOLSRT172LAMS	72" x 48-15/16" x 12"	137	1,546	1,623	1,159	

2 Adjustable She	Ives and 1 Base Si GEOLSRT236MAPS	<i>helf</i> Geolsrt236lams	36" x 48-15/16" x 12"	79	\$1,159	\$1,218	\$ 868	Single-Faced Reverse Tower Adder Type 2
					7.7.2.	7.7		
2 Adjustable She	lves and 1 Base Si	<u>helf</u>						1. 1
GEOLSRT2420AKS	GEOLSRT242MAPS	GEOLSRT242LAMS	42" x 48-15/16" x 12"	96	1,169	1,227	878	: -
GEOLSRT2480AKS	GEOLSRT248MAPS	GEOLSRT248LAMS	48" x 48-15/16" x 12"	109	1,239	1,302	928	
A Adjustable She	lves and 1 Base Si	half						<b>1</b> →
4 Aujustable Sile	ives and I base si	<u>ieii</u>						
GEOLSRT2600AKS	GEOLSRT260MAPS	GEOLSRT260LAMS	60-1/2" x 48-15/16" x 12"	129	1,537	1,614	1,151	
GEOLSRT2720AKS	GEOLSRT272MAPS	GEOLSRT272LAMS	72" x 48-15/16" x 12"	137	1,546	1,623	1,159	7 × V.
								Z .V
								N


	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Double-Faced Starter	2 Adjustable She	elves and 1 Base S	Shelf .					
	GEOLDS360AKS	GEOLDS36MAPS	GEOLDS36LAMS	36" x 37-3/16" x 23"	118	\$1,398	\$1,469	\$1,047
	2 Adjustable She	elves and 1 Base S	Shelf per Side					
6	GEOLDS420AKS GEOLDS480AKS	GEOLDS42MAPS GEOLDS48MAPS	GEOLDS42LAMS GEOLDS48LAMS	42" x 37-3/16" x 23" 48" x 37-3/16" x 23"	140 163	1,409 1,511	1,479 1,586	1,05 <i>6</i> 1,133
4	4 Adiustable Sho	elves and 1 Base S	Shelf per Side					
	GEOLDS600AKS	GEOLDS60MAPS	GEOLDS60LAMS	60-1/2" x 37-3/16" x 23"	180	2,053	2,156	1,540
/	GEOLDS720AKS	GEOLDS72MAPS	GEOLDS72LAMS	72" x 37-3/16" x 23"	194	2,369	2,488	1,77
<u>←   →</u>								
Double-Faced	2 Adjustable She	elves and 1 Base S	Shelf					
Inline Adder	GEOLDIA360AKS	GEOLDIA36MAPS	GEOLDIA36LAMS	36" x 36-3/16" x 23"	118	\$1,398	\$1,469	\$1,047
	2 Adjustable Sh	elves and 1 Base S	Shelf per Side					
	GEOLDIA420AKS GEOLDIA480AKS	GEOLDIA42MAPS GEOLDIA48MAPS	GEOLDIA42LAMS GEOLDIA48LAMS	42" x 36-3/16" x 23" 48" x 36-3/16" x 23"	140 163	1,409 1,511	1,479 1,586	1,056 1,133
	4 Adjustable She	elves and 1 Base S	Shelf per Side					
	GEOLDIA600AKS GEOLDIA720AKS	GEOLDIA60MAPS GEOLDIA72MAPS	GEOLDIA6OLAMS GEOLDIA72LAMS	60-1/2" x 36-3/16" x 23" 72" x 36-3/16" x 23"	180 194	2,053 2,369	2,156 2,488	1,540 1,777
Double-Faced Inline Tower	2 Adjustable She	elves and 1 Base S	Shelf					
Adder Type 1	GEOLDIT1360AKS	GEOLDIT136MAPS	GEOLDIT136LAMS	36" x 59-15/16" x 23"	156	\$2,158	\$2,266	\$1,617
	2 Adjustable She	elves and 1 Base S	Shelf per Side					
7	GEOLDIT1420AKS GEOLDIT1480AKS	GEOLDIT142MAPS GEOLDIT148MAPS	GEOLDIT142LAMS GEOLDIT148LAMS	42" x 59-15/16" x 23" 48" x 59-15/16" x 23"	178 209	2,169 2,271	2,277 2,384	1,626 1,703
	4 Adjustable She	elves and 1 Base S	Shelf per Side					
	GEOLDIT1600AKS GEOLDIT1720AKS	GEOLDIT160MAPS GEOLDIT172MAPS	GEOLDIT160LAMS GEOLDIT172LAMS	60-1/2" x 59-15/16" x 23' 72" x 59-15/16" x 23"	236 266	2,807 3,030	2,947 3,182	2,105 2,273
÷ 1 ?	Diago chooifuWaad Fin	nich (Tabla 1) ar l'aminata	(Table 4) Details can be	found on page GEN 4 and GEN	I E			

Note: Shelving Finishing Panels are sold separately and are located on page GEO 34.

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	elves and 1 Base S	<u>helf</u>						Double-Faced Inline Towe
GEOLDIT2360AKS	GEOLDIT236MAPS	GEOLDIT236LAMS	36" x 59-15/16" x 23"	156	\$2,158	\$2,266	\$1,617	Adder Type 2
2 Adjustable She	elves and 1 Base S	helf per Side						
GEOLDIT2420AKS	GEOLDIT242MAPS	GEOLDIT242LAMS	42" x 59-15/16" x 23"	178	2,169	2,277	1,626	7
GEOLDIT2480AKS	GEOLDIT248MAPS	GEOLDIT248LAMS	48" x 59-15/16" x 23"	209	2,271	2,384	1,703	
4 Adjustable She	elves and 1 Base S	helf per Side						1 7
GEOLDIT2600AKS	GEOLDIT260MAPS	GEOLDIT260LAMS	60-1/2" x 59-15/16" x 23"	236	2,807	2,947	2,105	
GEOLDIT2720AKS	GEOLDIT272MAPS	GEOLDIT272LAMS	72" x 59-15/16" x 23"	266	3,030	3,182	2,273	
								÷ 1 ÷
								<i>√</i> .∠
								1/

2 Adjustable She	elves and 1 Base S	<u>helf</u>						Transitional Adders, Type 1
GEOLTSS1360AKS	GEOLTSS136MAPS	GEOLTSS136LAMS	36" x 36-3/16" x 23"	71	\$747	\$784	\$559	Single- to Single-Faced
2 Adjustable She	elves and 1 Base S	<u>helf</u>						1
GEOLTSS1420AKS	GEOLTSS142MAPS	GEOLTSS142LAMS	42" x 36-3/16" x 23"	86	757	794	569	
GEOLTSS1480AKS	GEOLTSS148MAPS	GEOLTSS148LAMS	48" x 36-3/16" x 23"	99	789	830	591	
4 Adjustable She	elves and 1 Base S	<u>helf</u>						
GEOLTSS1600AKS	GEOLTSS160MAPS	GEOLTSS160LAMS	60-1/2" x 36-3/16" x 23"	114	1,092	1,147	818	
GEOLTSS1720AKS	GEOLTSS172MAPS	GEOLTSS172LAMS	72" x 36-3/16" x 23"	122	1,136	1,193	851	L]
								<u>←</u>

2 Adjustable She	elves and 1 Base Si	<u>helf</u>								
GEOLTSS2360AKS	GEOLTSS236MAPS	GEOLTSS236LAMS	36" x 36-3/16" x 23"	71	\$747	\$784	\$559			
2 Adjustable Shelves and 1 Base Shelf										
GEOLTSS2420AKS	GEOLTSS242MAPS	GEOLTSS242LAMS	42" x 36-3/16" x 23"	86	757	794	569			
GEOLTSS2480AKS	GEOLTSS248MAPS	GEOLTSS248LAMS	48" x 36-3/16" x 23"	99	789	830	591			
4 Adjustable She	elves and 1 Base Si	<u>helf</u>								
GEOLTSS2600AKS	GEOLTSS260MAPS	GEOLTSS260LAMS	60-1/2" x 36-3/16" x 23"	114	1,092	1,147	818			
GEOLTSS2720AKS	GEOLTSS272MAPS	GEOLTSS272LAMS	72" x 36-3/16" x 23"	122	1,136	1,193	851			






	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Transitional Adders, Type 1	2 Adjustable She	elves and 1 Base S	helf per Side					
Single- to Double-Faced	GEOLTSD1360AKS	GEOLTSD136MAPS	GEOLTSD136LAMS	36" x 36-3/16" x 23"	118	\$1,398	\$1,469	\$1,047
- 1	2 Adjustable She	elves and 1 Base S	helf per Side					
	GEOLTSD1420AKS	GEOLTSD142MAPS	GEOLTSD142LAMS	42" x 36-3/16" x 23"	140	1,409	1,479	1,056
	GEOLTSD1480AKS	GEOLTSD148MAPS	GEOLTSD148LAMS	48" x 36-3/16" x 23"	163	1,511	1,586	1,133
	4 Adjustable She	elves and 1 Base S	helf per Side					
	GEOLTSD1600AKS	GEOLTSD160MAPS	GEOLTSD160LAMS	60-1/2" x 36-3/16" x 23"	180	2,053	2,156	1,540
	GEOLTSD1720AKS	GEOLTSD172MAPS	GEOLTSD172LAMS	72" x 36-3/16" x 23"	194	2,369	2,488	1,777
←   →								
<u>•</u>								
Transitional Adders, Type 2	2 Adjustable She	elves and 1 Base S	helf per Side					
Single- to Double-Faced	GEOLTSD2360AKS	GEOLTSD236MAPS	-	36" x 36-3/16" x 23"	118	\$1,398	\$1,469	\$1,047
	2 Adjustable She	olyos and 1 Paso S	half par Sida					
1	-	elves and 1 Base S	-	4011 - 27 274711 - 2211	1.10	1 400	4 470	4.057
	GEOLTSD2420AKS GEOLTSD2480AKS	GEOLTSD242MAPS GEOLTSD248MAPS	GEOLTSD242LAMS GEOLTSD248LAMS	42" x 36-3/16" x 23" 48" x 36-3/16" x 23"	140 163	1,409 1,511	1,479 1,586	1,056 1,133
	4 Adjustable She	elves and 1 Base S	helf per Side					
	GEOLTSD2600AKS	GEOLTSD260MAPS	GEOLTSD260LAMS	60-1/2" x 36-3/16" x 23"	180	2,053	2,156	1,540
	GEOLTSD2720AKS	GEOLTSD272MAPS	GEOLTSD272LAMS	72" x 36-3/16" x 23"	194	2,369	2,488	1,777
Transitional Adders, Type 1	2 Adjustable She	elves and 1 Base S	helf					
Double- to Single-Faced	GEOLTDS1360AKS	GEOLTDS136MAPS	GEOLTDS136LAMS	36" x 36-3/16" x 23"	71	\$ 747	\$ 784	\$559
11: 1	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
	GEOLTDS1420AKS	GEOLTDS142MAPS	GEOLTDS142LAMS	42" x 36-3/16" x 23"	86	757	794	569
	GEOLTDS1480AKS	GEOLTDS148MAPS	GEOLTDS148LAMS	48" x 36-3/16" x 23"	99	789	830	591
	4 Adjustable She	elves and 1 Base S	helf					
	GEOLTDS1600AKS	GEOLTDS160MAPS	GEOLTDS160LAMS	60-1/2" x 36-3/16" x 23"	114	1,092	1,147	818
	GEOLTDS1720AKS	GEOLTDS172MAPS	GEOLTDS172LAMS	72" x 36-3/16" x 23"	122	1,136	1,193	851

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ or\ Laminate\ (Table\ 4).\ Details\ can\ be\ found\ on\ page\ GEN\ 4\ and\ GEN\ 5.$ 

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	elves and 1 Base S	<u>helf</u>						Transitional Adders, Type 2
GEOLTDS2360AKS	GEOLTDS236MAPS	GEOLTDS136LAMS	36" x 36-3/16" x 23"	71	\$ 747	\$ 784	\$559	Double- to Single-Faced
2 Adjustable She	elves and 1 Base S	<u>helf</u>						
GEOLTDS2420AKS	GEOLTDS242MAPS	GEOLTDS142LAMS	42" x 36-3/16" x 23"	86	757	794	569	
GEOLTDS2480AKS	GEOLTDS248MAPS	GEOLTDS148LAMS	48" x 36-3/16" x 23"	99	789	830	591	
4 Adjustable She	elves and 1 Base S	<u>helf</u>						
GEOLTDS2600AKS	GEOLTDS260MAPS	GEOLTDS160LAMS	60-1/2" x 36-3/16" x 23"	114	1,092	1,147	818	
GEOLTDS2720AKS	GEOLTDS272MAPS	GEOLTDS172LAMS	72" x 36-3/16" x 23"	122	1,136	1,193	851	//
								_   →
								<u>•</u>


2 Adjustable Shelves and 1 Base Shelf per Side										
GEOLTTSD1360AKS	GEOLTTSD136MAPS	GEOLTTSD136LAMS	36" x 59-15/16" x 23"	156	\$2,158	\$2,266	\$1,617			
2 Adjustable She	lves and 1 Base Sh	nelf per Side								
GEOLTTSD1420AKS	GEOLTTSD142MAPS	GEOLTTSD142LAMS	42" x 59-15/16" x 23"	178	2,169	2,277	1,626			
GEOLTTSD1480AKS	GEOLTTSD148MAPS	GEOLTTSD148LAMS	48" x 59-15/16" x 23"	209	2,271	2,384	1,703			
4 Adjustable She	lves and 1 Base Sh	nelf per Side								
GEOLTTSD1600AKS	GEOLTTSD160MAPS	GEOLTTSD160LAMS	60-1/2" x 59-15/16" x 23"	236	2,807	2,947	2,105			
GEOLTTSD1720AKS	GEOLTTSD172MAPS	GEOLTTSD172LAMS	72" x 59-15/16" x 23"	266	3,030	3,182	2,273			

Transitional Tower Adders, Type 1 Single- to Double-Faced



2 Adjustable She	lves and 1 Base Sh	nelf per Side					
GEOLTTSD2360AKS	GEOLTTSD236MAPS	GEOLTTSD236LAMS	36" x 59-15/16" x 23"	156	\$2,158	\$2,266	\$1,617
2 Adjustable She	lves and 1 Base Sh	nelf per Side					
GEOLTTSD2420AKS	GEOLTTSD242MAPS	GEOLTTSD242LAMS	42" x 59-15/16" x 23"	178	2,169	2,277	1,626
GEOLTTSD2480AKS	GEOLTTSD248MAPS	GEOLTTSD248LAMS	48" x 59-15/16" x 23"	209	2,271	2,384	1,703
4 Adjustable She	lves and 1 Base Sh	nelf per Side					
GEOLTTSD2600AKS	GEOLTTSD260MAPS	GEOLTTSD260LAMS	60-1/2" x 59-15/16" x 23"	236	2,807	2,947	2,105
GEOLTTSD2720AKS	GEOLTTSD272MAPS	GEOLTTSD272LAMS	72" x 59-15/16" x 23"	266	3,030	3,182	2,273


Transitional Tower Adders, Type 2 Single- to Double-Faced



 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ or\ Laminate\ (Table\ 4).\ Details\ can\ be\ found\ on\ page\ GEN\ 4\ and\ GEN\ 5.$ 

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	0ak Price	Maple Price	Laminate Price
Transitional Tower Adders,	2 Adjustable She	lves and 1 Base SI	nelf per Side					
Type 3 Single- to Double-Faced	GEOLTTSD3360AKS	GEOLTTSD336MAPS	GEOLTTSD336LAMS	36" x 59-15/16" x 23"	156	\$2,158	\$2,266	\$1,617
	2 Adjustable She	lves and 1 Base SI	nelf per Side					
		GEOLTTSD342MAPS GEOLTTSD348MAPS		42" x 59-15/16" x 23" 48" x 59-15/16" x 23"	178 209	2,169 2,271	2,277 2,384	1,626 1,703
	4 Adjustable She	lves and 1 Base SI	nelf per Side					
		GEOLTTSD360MAPS GEOLTTSD372MAPS		60-1/2" x 59-15/16" x 23' 72" x 59-15/16" x 23"	236 266	2,807 3,030	2,947 3,182	2,105 2,273
Transitional Tower Adders,	2 Adjustable She	lves and 1 Base Sl	nelf per Side					
Type 4 Single- to Double-Faced	GEOLTTSD4360AKS	GEOLTTSD436MAPS	GEOLTTSD436LAMS	36" x 59-15/16" x 23"	156	\$2,158	\$2,266	\$1,617
	2 Adjustable She	lves and 1 Base SI	nelf per Side					
		GEOLTTSD442MAPS GEOLTTSD448MAPS		42" x 59-15/16" x 23" 48" x 59-15/16" x 23"	178 209	2,169 2,271	2,277 2,384	1,626 1,703
2 1 12	4 Adjustable She	lves and 1 Base SI	helf per Side					
		GEOLTTSD460MAPS GEOLTTSD472MAPS		60-1/2" x59-15/16" x23' 72" x59-15/16" x23"	236 266	2,807 3,030	2,947 3,182	2,105 2,273
Transitional Tower Adders,	2 Adjustable She	lves and 1 Base Sl	nelf					
Type 1 Double- to Single-Faced	GEOLTTDS1360AKS	GEOLTTDS136MAPS	GEOLTTDS136LAMS	36" x 59-15/16" x 23"	101	\$1,563	\$1,641	\$1,171
	2 Adjustable She	lves and 1 Base SI	<u>nelf</u>					
		GEOLTTDS142MAPS GEOLTTDS148MAPS	GEOLTTDS142LAMS GEOLTTDS148LAMS	42" x 59-15/16" x 23" 48" x 59-15/16" x 23"	112 135	1,573 1,609	1,651 1,690	1,181 1,205
411	4 Adjustable She	lves and 1 Base Si	<u>nelf</u>					
			GEOLTTDS160LAMS GEOLTTDS172LAMS	60-1/2" x 59-15/16" x 23' 72" x 59-15/16" x 23"	155 179	1,980 2,044	2,079 2,147	1,483 1,533
* I								

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	lves and 1 Base Sh	nelf						
GEOLTTDS2360AKS	GEOLTTDS236MAPS	GEOLTTDS236LAMS	36" x 59-15/16" x 23"	101	\$1,563	\$1,641	\$1,171	
2 Adjustable She	lves and 1 Base Sh	<u>nelf</u>						
GEOLTTDS2420AKS	GEOLTTDS242MAPS	GEOLTTDS242LAMS	42" x 59-15/16" x 23"	112	1,573	1,651	1,181	
GEOLTTDS2480AKS	GEOLTTDS248MAPS	GEOLTTDS248LAMS	48" x 59-15/16" x 23"	135	1,609	1,690	1,205	
4 Adjustable She	lves and 1 Base Sh	nelf						
GEOLTTDS2600AKS	GEOLTTDS260MAPS	GEOLTTDS260LAMS	60-1/2" x 59-15/16" x 23'	155	1,980	2,079	1,483	
GEOLTTDS2720AKS	GEOLTTDS272MAPS	GEOLTTDS272LAMS	72" x 59-15/16" x 23"	179	2,044	2,147	1,533	





2 Adjustable Shelves and 1 Base Shelf GEOLTTDS336OAKS GEOLTTDS336MAPS GEOLTTDS336LAMS 36"x59-15/16"x23" \$1,171 \$1,563 \$1,641 2 Adjustable Shelves and 1 Base Shelf GEOLTTDS3420AKS GEOLTTDS342MAPS GEOLTTDS342LAMS 42" x 59-15/16" x 23" 1,573 1,651 1,181 GEOLTTDS3480AKS GEOLTTDS348MAPS GEOLTTDS348LAMS 48" x 59-15/16" x 23" 1,205 1,609 1,690 4 Adjustable Shelves and 1 Base Shelf GEOLTTDS3600AKS GEOLTTDS360MAPS GEOLTTDS360LAMS 60-1/2" x 59-15/16" x 23" 155 1,980 2,079 1,483 GEOLTTDS3720AKS GEOLTTDS372MAPS GEOLTTDS372LAMS 72" x 59-15/16" x 23" 2,044 2,147 1,533

Transitional Tower Adders, Type 3 Double- to Single-Faced



2 Adjustable Shelves and 1 Base Shelf GEOLTTDS4360AKS GEOLTTDS436MAPS GEOLTTDS436LAMS 36"x59-15/16"x23" \$1,563 \$1,641 \$1,171 2 Adjustable Shelves and 1 Base Shelf GEOLTTDS4420AKS GEOLTTDS442MAPS GEOLTTDS442LAMS 42" x 59-15/16" x 23" 1,651 1,573 1,181 **GEOLTTDS4480AKS GEOLTTDS448MAPS GEOLTTDS448LAMS** 48" x 59-15/16" x 23" 1,205 1,609 1,690 4 Adjustable Shelves and 1 Base Shelf GEOLTTDS4600AKS GEOLTTDS460MAPS GEOLTTDS460LAMS 60-1/2" x 59-15/16" x 23" 155 1,980 2,079 1,483 GEOLTTDS4720AKS GEOLTTDS472MAPS GEOLTTDS472LAMS 72" x 59-15/16" x 23" 2,044 1,533 2,147





Please specify Wood Finish (Table 1) or Laminate (Table 4). Details can be found on page GEN 4 and GEN 5.

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Convex Single-Faced	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
Starter Type 1	GEOAXSS1360AKS	GEOAXSS136MAPS	GEOAXSS136LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857
	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
	GEOAXSS1420AKS	GEOAXSS142MAPS	GEOAXSS142LAMS	42" x 44" x 12"	88	1,003	1,053	866
	GEOAXSS1480AKS	GEOAXSS148MAPS	GEOAXSS148LAMS	48" x 44" x 12"	101	1,069	1,123	923
	4 Adjustable She	elves and 1 Base S	<u>helf</u>					
1 →	GEOAXSS1600AKS	GEOAXSS160MAPS	GEOAXSS160LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218
	GEOAXSS1720AKS	GEOAXSS172MAPS	GEOAXSS172LAMS	72" x 44" x 12"	119	1,503	1,578	1,299
Convex Single-Faced Starter Type 2	-	elves and 1 Base S						
Starter Type 2	GEOAXSS2360AKS	GEOAXSS236MAPS	GEOAXSS236LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857
	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOAXSS2420AKS	GEOAXSS242MAPS	GEOAXSS242LAMS	42" x 44" x 12"	88	1,003	1,053	866
	GEOAXSS2480AKS	GEOAXSS248MAPS	GEOAXSS248LAMS	48" x 44" x 12"	101	1,069	1,123	923
	4 Adjustable She	elves and 1 Base Si	<u>helf</u>					
÷   0	GEOAXSS2600AKS	GEOAXSS260MAPS	GEOAXSS260LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218
	GEOAXSS272OAKS	GEOAXSS272MAPS	GEOAXSS272LAMS	72" x 44" x 12"	119	1,503	1,578	1,299
Convex Single-Faced	_	elves and 1 Base S						
IIIIII o Addel	GEOAXSIA360AKS	GEOAXSIA36MAPS	GEOAXSIA36LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857
	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
	GEOAXSIA420AKS	GEOAXSIA42MAPS	GEOAXSIA42LAMS	42" x 44" x 12"	88	1,003	1,053	866
	GEOAXSIA480AKS	GEOAXSIA48MAPS	GEOAXSIA48LAMS	48'' x 44'' x 12''	101	1,069	1,123	923
ı →     /	4 Adjustable She	elves and 1 Base S	<u>helf</u>					
<u>·</u>	GEOAXSIA600AKS GEOAXSIA720AKS	GEOAXSIA60MAPS GEOAXSIA72MAPS	GEOAXSIA60LAMS GEOAXSIA72LAMS	60-1/2" x 44" x 12" 72" x 44" x 12"	111 119	1,411 1,503	1,482 1,578	1,218 1,299



Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable Shel	ves and 1 Base She	<u>If</u>						Convex Single-Faced
GEOAXSRA1360AKS	GEOAXSRA136MAPS	GEOAXSRA136LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857	Reverse Adder Type 1
2 Adjustable Shel	ves and 1 Base She	<u>If</u>						1.
GEOAXSRA1420AKS	GEOAXSRA142MAPS	GEOAXSRA142LAMS	42" x 44" x 12"	88	1,003	1,053	866	: :
GEOAXSRA1480AKS	GEOAXSRA148MAPS	GEOAXSRA148LAMS	48" x 44" x 12"	101	1,069	1,123	923	
4 Adjustable Shel	ves and 1 Base She	<u>lf</u>						←
GEOAXSRA1600AKS	GEOAXSRA160MAPS	GEOAXSRA160LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218	
GEOAXSRA1720AKS	GEOAXSRA172MAPS	GEOAXSRA172LAMS	72" x 44" x 12"	119	1,503	1,578	1,299	
								-
								•

2 Adjustable Shel	ves and 1 Base She	<u>If</u>						Convex Single-Faced
GEOAXSRA2360AKS	GEOAXSRA236MAPS	GEOAXSRA236LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857	Reverse Adder Type 2
2 Adjustable Shel	ves and 1 Base She	<u>If</u>						
GEOAXSRA2420AKS	GEOAXSRA242MAPS	GEOAXSRA242LAMS	42" x 44" x 12"	88	1,003	1,053	866	
GEOAXSRA2480AKS	GEOAXSRA248MAPS	GEOAXSRA248LAMS	48" x 44" x 12"	101	1,069	1,123	923	
4 Adjustable Shel	ves and 1 Base She	<u>If</u>						<b>1</b> →
GEOAXSRA2600AKS	GEOAXSRA260MAPS	GEOAXSRA260LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218	
GEOAXSRA2720AKS	GEOAXSRA272MAPS	GEOAXSRA272LAMS	72" x 44" x 12"	119	1,503	1,578	1,299	÷ 1
								. ://



	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
oncave Single-Faced	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
4" Wide Starter Type 1	GEOAVSS1360AKS	GEOAVSS136MAPS	GEOAVSS136LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857
	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
	GEOAVSS1420AKS	GEOAVSS142MAPS	GEOAVSS142LAMS	42" x 44" x 12"	88	1,033	1,053	866
	GEOAVSS1480AKS	GEOAVSS148MAPS	GEOAVSS148LAMS	48" x 44" x 12"	101	1,069	1,123	923
6	4 Adjustable She	elves and 1 Base S	<u>helf</u>					
· /	GEOAVSS1600AKS	GEOAVSS160MAPS	GEOAVSS160LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218
<u> </u>	GEOAVSS1720AKS	GEOAVSS172MAPS	GEOAVSS172LAMS	72" x 44" x 12"	119	1,503	1,578	1,299
ncave Single-Faced	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
Wide Starter Type 2	GEOAVSS2360AKS	GEOAVSS236MAPS	GEOAVSS236LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857
//	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
	GEOAVSS2420AKS	GEOAVSS242MAPS	GEOAVSS242LAMS	42" x 44" x 12"	88	1,033	1,053	866
	GEOAVSS2480AKS	GEOAVSS248MAPS	GEOAVSS248LAMS	48" x 44" x 12"	101	1,069	1,123	923
	4 Adjustable She	elves and 1 Base S	<u>helf</u>					
/	GEOAVSS2600AKS	GEOAVSS260MAPS	GEOAVSS260LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218
/	GEOAVSS2720AKS	GEOAVSS272MAPS	GEOAVSS272LAMS	72" x 44" x 12"	119	1,503	1,578	1,299
oncave Single-Faced	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
7" Wide Starter Type 3	GEOAVSS3360AKS	GEOAVSS336MAPS	GEOAVSS336LAMS	36" x 37" x 12"	63	\$ 993	\$1,043	\$ 857
	2 Adjustable She	elves and 1 Base S	<u>helf</u>					
	GEOAVSS3420AKS	GEOAVSS342MAPS	GEOAVSS342LAMS	42" x 37" x 12"	76	1,003	1,053	866
	GEOAVSS3480AKS	GEOAVSS348MAPS	GEOAVSS348LAMS	48" x 37" x 12"	89	1,069	1,123	923
	4 Adjustable She	elves and 1 Base S	<u>helf</u>					
÷ 7	GEOAVSS3600AKS	GEOAVSS360MAPS	GEOAVSS360LAMS	60-1/2" x 37" x 12"	99	1,411	1,482	1,218
<u> </u>	GEOAVSS3720AKS	GEOAVSS372MAPS	GEOAVSS372LAMS	72" x 37" x 12"	107	1,503	1,578	1,299
ncave Single-Faced	2 Adiustable She	elves and 1 Base S	helf					
7" Wide Starter Type 4		GEOAVSS436MAPS		36" x 37" x 12"	63	\$ 993	\$1,043	\$ 857
9. 9	2 Adiustable She	elves and 1 Base S	helf					
21			GEOAVSS442LAMS	42" x 37" x 12"	76	1,003	1 052	866
	CEONVECAAOONVE	CECVICCIIIIVIVEC		42 X37 X12		-	1,053	
	GEOAVSS4420AKS GEOAVSS4480AKS	GEOAVSS442MAPS GEOAVSS448MAPS	GEOAVSS448LAMS	48" x 37" x 12"	89	1,069	1,123	923
	GEOAVSS4480AKS		GEOAVSS448LAMS	48" x 37" x 12"	89	1,069	1,123	923
	GEOAVSS4480AKS	GEOAVSS448MAPS elves and 1 Base S	GEOAVSS448LAMS	48" x 37" x 12" 60-1/2" x 37" x 12"	89 99	1,069	1,123	923 1,218

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable Shelv	es and 1 Base Sheli	f						Concave Single-Faced
GEOAVSIA1360AKS	GEOAVSIA136MAPS	GEOAVSIA136LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857	44" Wide Inline Adder Type 1
2 Adjustable Shelv	ves and 1 Base Sheli	<u>f</u>						· ·
GEOAVSIA1420AKS	GEOAVSIA142MAPS	GEOAVSIA142LAMS	42" x 44" x 12"	88	1,003	1,053	866	
GEOAVSIA1480AKS	GEOAVSIA148MAPS	GEOAVSIA148LAMS	48" x 44" x 12"	101	1,069	1,123	923	
4 Adjustable Shelt	ves and 1 Base Sheli	f						A . →
GEOAVSIA1600AKS	GEOAVSIA160MAPS	GEOAVSIA160LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218	
GEOAVSIA1720AKS	GEOAVSIA172MAPS	GEOAVSIA172LAMS	72" x 44" x 12"	119	1,503	1,578	1,299	
2 Adjustable Shelv	ves and 1 Base Sheli	<u> </u>						Concave Single-Faced
GEOAVSIA2360AKS	GEOAVSIA236MAPS	GEOAVSIA236LAMS	36" x 37" x 12"	63	\$ 993	\$1,043	\$ 857	37" Wide Inline Adder Type 2
2 Adjustable Sheli	ves and 1 Base Sheli	f						· ·
<i>E Adjustable Sheh</i> GEOAVSIA2420AKS	GEOAVSIA242MAPS	GEOAVSIA242LAMS	42" x 37" x 12"	76	1,003	1,053	866	
GEOAVSIA248OAKS	GEOAVSIA242MAPS	GEOAVSIA248LAMS	48" x 37" x 12"	89	1,069	1,123	923	
1 Adiustable Sheli	ves and 1 Base Sheli	F						7
<i>4 Aujustabie Shen</i> Geoavsia2600aks	GEOAVSIA260MAPS	GEOAVSIA260LAMS	60-1/2" x 37" x 12"	99	1,411	1,482	1,218	
GEOAVSIA2720AKS	GEOAVSIA272MAPS	GEOAVSIA270LAMS	72" x 37" x 12"	107	1,503	1,578	1,216	
2 Adjustable Shelv	ves and 1 Base Sheli	f						Concave Single-Faced
GEOAVSRA1360AKS	GEOAVSRA136MAPS	GEOAVSRA136LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857	44" Wide Reverse Adder
2 Adjustable Shelv	ves and 1 Base Sheli	<u>f</u>						Type 1
GEOAVSRA1420AKS	GEOAVSRA142MAPS	GEOAVSRA142LAMS	42" x 44" x 12"	88	1,003	1,053	866	
GEOAVSRA1480AKS	GEOAVSRA148MAPS	GEOAVSRA148LAMS	48" x 44" x 12"	101	1,069	1,123	923	
4 Adjustable Shelv	ves and 1 Base Sheli	f						←
GEOAVSRA1600AKS	GEOAVSRA160MAPS	GEOAVSRA160LAMS	60-1/2" x 44" x 12"	111	1,411	1,482	1,218	/ · · ·
GEOAVSRA1720AKS	GEOAVSRA172MAPS	GEOAVSRA172LAMS	72" x 44" x 12"	119	1,503	1,578	1,299	·   ·
								· · · · · · · · · · · · · · · · · · ·
2 Adjustable Shelt	es and 1 Base Sheli	f						Concave Single-Faced 44" Wide Reverse Adder
	GEOAVSRA236MAPS	GEOAVSRA236LAMS	36" x 44" x 12"	75	\$ 993	\$1,043	\$ 857	Type 2
GEOAVSRA2360AKS		•						
	es and 1 Base Sheli	<u>.</u>						- 401
<i>2 Adjustable Shel</i> u GEOAVSRA2420AKS	GEOAVSRA242MAPS	GEOAVSRA242LAMS	42" x 44" x 12"	88	1,003	1,053	866	
<i>2 Adjustable Shel</i> u GEOAVSRA242OAKS GEOAVSRA248OAKS	GEOAVSRA242MAPS GEOAVSRA248MAPS	GEOAVSRA242LAMS GEOAVSRA248LAMS	42" x 44" x 12" 48" x 44" x 12"	88 101	1,003 1,069	1,053 1,123	866 923	
<i>2 Adjustable Shel</i> u GEOAVSRA242OAKS GEOAVSRA248OAKS <i>4 Adjustable Shel</i> u	GEOAVSRA242MAPS GEOAVSRA248MAPS yes and 1 Base Sheli	GEOAVSRA242LAMS GEOAVSRA248LAMS	48" x 44" x 12"	101	1,069	1,123	923	Z <sub>1</sub>
<i>2 Adjustable Shel</i> u GEOAVSRA242OAKS GEOAVSRA248OAKS	GEOAVSRA242MAPS GEOAVSRA248MAPS	GEOAVSRA242LAMS GEOAVSRA248LAMS	48" x 44" x 12"		-			

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
ouble-Faced 44"Wide	2 Adjustable Sh	elves and 1 Base S	Shelf per Side					
arter	GEOADS360AKS	GEOADS36MAPS	GEOADS36LAMS	36" x 44" x 23"	142	\$1,962	\$2,061	\$1,667
	2 Adjustable Sh	elves and 1 Base S	Shelf per Side					
	GEOADS420AKS	GEOADS42MAPS	GEOADS42LAMS	42" x 44" x 23"	166	1,973	2,071	1,677
V	GEOADS480AKS	GEOADS48MAPS	GEOADS48LAMS	48" x 44" x 23"	190	2,125	2,231	1,806
1/	4 Adjustable Sh	elves and 1 Base S	Shelf per Side					
( )	GEOADS600AKS	GEOADS60MAPS	GEOADS60LAMS	60-1/2" x 44" x 23"	210	2,572	2,701	2,187
	GEOADS720AKS	GEOADS72MAPS	GEOADS72LAMS	72" x 44" x 23"	223	2,834	2,975	2,409
<u>←   →</u>								
	2 Adjustable Sh	elves and 1 Base S	Shelf per Side					
	<i>2 Adjustable Sh</i> GEOADIA360AKS	<i>elves and 1 Base S</i> GEOADIA36MAPS	Shelf per Side GEOADIA36LAMS	36" x 44" x 23"	142	\$1,962	\$2,061	\$1,667
	GEOADIA360AKS		GEOADIA36LAMS	36" x 44" x 23"	142	\$1,962	\$2,061	\$1,667
ne Adder	GEOADIA360AKS	GEOADIA36MAPS	GEOADIA36LAMS	36" x 44" x 23" 42" x 44" x 23"	142	\$1,962 1,973	\$2,061 2,071	
ine Adder	GEOADIA360AKS  2 Adjustable Sh	GEOADIA36MAPS elves and 1 Base 5	GEOADIA36LAMS			•		1,677
ine Adder	GEOADIA36OAKS  2 Adjustable Sh GEOADIA42OAKS GEOADIA48OAKS	GEOADIA36MAPS  elves and 1 Base S  GEOADIA42MAPS	GEOADIA36LAMS  Shelf per Side  GEOADIA42LAMS GEOADIA48LAMS	42" x 44" x 23"	166	1,973	2,071	1,677
ouble-Faced 44"Wide	GEOADIA36OAKS  2 Adjustable Sh GEOADIA42OAKS GEOADIA48OAKS	GEOADIA36MAPS  elves and 1 Base S  GEOADIA42MAPS GEOADIA48MAPS	GEOADIA36LAMS  Shelf per Side  GEOADIA42LAMS GEOADIA48LAMS	42" x 44" x 23"	166	1,973	2,071	\$1,667 1,677 1,806
	GEOADIA36OAKS  2 Adjustable Sh GEOADIA42OAKS GEOADIA48OAKS 4 Adjustable Sh	GEOADIA36MAPS  elves and 1 Base S  GEOADIA42MAPS GEOADIA48MAPS  elves and 1 Base S	GEOADIA36LAMS  Shelf per Side  GEOADIA42LAMS GEOADIA48LAMS  Shelf per Side	42" x 44" x 23" 48" x 44" x 23"	166 190	1,973 2,125	2,071 2,231	1,677 1,806
ine Adder	GEOADIA36OAKS  2 Adjustable Sh GEOADIA42OAKS GEOADIA48OAKS  4 Adjustable Sh GEOADIA60OAKS	GEOADIA36MAPS  elves and 1 Base S  GEOADIA42MAPS GEOADIA48MAPS  elves and 1 Base S  GEOADIA60MAPS	GEOADIA36LAMS  Shelf per Side  GEOADIA42LAMS GEOADIA48LAMS  Shelf per Side  GEOADIA60LAMS	42" x 44" x 23" 48" x 44" x 23" 60-1/2" x 44" x 23"	166 190 210	1,973 2,125 2,572	2,071 2,231 2,701	1,677 1,806 2,187

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	lves and 1 Base Si	<u>helf</u>						Transitional Adders
GEOATSS1360AKS	GEOATSS136MAPS	GEOATSS136LAMS	36" x 44" x 23"	95	\$1,108	\$1,163	\$955	44"Wide Type 1 Single- to Single-Faced
2 Adjustable She	lves and 1 Base Si	<u>helf</u>						
GEOATSS1420AKS GEOATSS1480AKS	GEOATSS142MAPS GEOATSS148MAPS	GEOATSS142LAMS GEOATSS148LAMS	42" x 44" x 23" 48" x 44" x 23"	108 121	1,118 1,216	1,173 1,277	964 1,048	
4 Adjustable She	Ives and 1 Base Si	<u>helf</u>						
GEOATSS1600AKS GEOATSS1720AKS	GEOATSS160MAPS GEOATSS172MAPS	GEOATSS160LAMS GEOATSS172LAMS	60-1/2" x 44" x 23" 72" x 44" x 23"	131 139	1,507 1,704	1,582 1,789	1,300 1,470	
								<u>←  </u>
2 Adjustable She	lves and 1 Base Si	<u>helf</u>						Transitional Adders
GEOATSS2360AKS	GEOATSS236MAPS	GEOATSS236LAMS	36" x 44" x 23"	95	\$1,108	\$1,163	\$955	44"Wide Type 2 Single- to Single-Faced
2 Adjustable She	Ives and 1 Base Si	<u>helf</u>						1 1
GEOATSS242OAKS GEOATSS248OAKS	GEOATSS242MAPS GEOATSS248MAPS	GEOATSS242LAMS GEOATSS248LAMS	42" x 44" x 23" 48" x 44" x 23"	108 121	1,118 1,216	1,173 1,277	964 1,048	5
4 Adjustable She	lves and 1 Base Si	<u>helf</u>						
GEOATSS2600AKS GEOATSS2720AKS	GEOATSS260MAPS GEOATSS272MAPS	GEOATSS260LAMS GEOATSS272LAMS	60-1/2" x 44" x 23" 72" x 44" x 23"	131 139	1,507 1,704	1,582 1,789	1,300 1,470	
								→
2 Adjustable She	lves and 1 Base Si	<u>helf</u>						Transitional Adders 44"Wide Type 3
GEOATSS3360AKS	GEOATSS336MAPS	GEOATSS336LAMS	36" x 44" x 23"	95	\$1,108	\$1,163	\$955	Single- to Single-Faced
2 Adjustable She	lves and 1 Base Si	<u>helf</u>						
GEOATSS342OAKS GEOATSS348OAKS	GEOATSS342MAPS GEOATSS348MAPS	GEOATSS342LAMS GEOATSS348LAMS	42" x 44" x 23" 48" x 44" x 23"	108 121	1,118 1,216	1,173 1,277	964 1,048	
4 Adjustable She	lves and 1 Base Si	<u>helf</u>						
GEOATSS3600AKS GEOATSS3720AKS	GEOATSS360MAPS GEOATSS372MAPS	GEOATSS360LAMS GEOATSS372LAMS	60-1/2" x 44" x 23" 72" x 44" x 23"	131 139	1,507 1,704	1,582 1,789	1,300 1,470	
								÷   !: .!
								<del></del>

ISS4360AKS IUSTABLE She ISS4420AKS IUSTABLE She ISS4600AKS ISS4720AKS IUSTABLE She ISS5360AKS IUSTABLE She ISS5360AKS IUSTABLE She ISS5420AKS ISS5420AKS	GEOATSS442MAPS GEOATSS448MAPS GEOATSS460MAPS GEOATSS460MAPS GEOATSS472MAPS	GEOATSS436LAMS  helf  GEOATSS442LAMS GEOATSS448LAMS  helf  GEOATSS460LAMS GEOATSS472LAMS	36" x 44" x 23" 42" x 44" x 23" 48" x 44" x 23" 60-1/2" x 44" x 23" 72" x 44" x 23" 36" x 37" x 23" 42" x 37" x 23" 48" x 37" x 23"	95 108 121 131 139 83	\$1,108 1,118 1,216 1,507 1,704 \$1,108	\$1,163 1,173 1,277 1,582 1,789 \$1,163	\$955 964 1,048 1,300 1,470 \$955
ISS4420AKS ISS4480AKS ISS4480AKS ISS4600AKS ISS4720AKS ISS4720AKS ISS5360AKS ISS5360AKS ISS5360AKS ISS5480AKS	GEOATSS442MAPS GEOATSS448MAPS GEOATSS448MAPS GEOATSS460MAPS GEOATSS472MAPS GEOATSS472MAPS GEOATSS536MAPS GEOATSS536MAPS GEOATSS536MAPS GEOATSS542MAPS	helf GEOATSS442LAMS GEOATSS448LAMS helf GEOATSS460LAMS GEOATSS472LAMS helf GEOATSS536LAMS helf GEOATSS542LAMS	42" x 44" x 23" 48" x 44" x 23" 60-1/2" x 44" x 23" 72" x 44" x 23" 36" x 37" x 23"	108 121 131 139 83	1,118 1,216 1,507 1,704 \$1,108	1,173 1,277 1,582 1,789 \$1,163	964 1,048 1,300 1,470 \$958
ISS4420AKS ISS4480AKS IUSTABLE She ISS4600AKS ISS4720AKS IUSTABLE She ISS5360AKS IUSTABLE She ISS5420AKS ISS5480AKS	GEOATSS442MAPS GEOATSS448MAPS elves and 1 Base S GEOATSS460MAPS GEOATSS472MAPS elves and 1 Base S GEOATSS536MAPS elves and 1 Base S GEOATSS542MAPS	GEOATSS442LAMS GEOATSS448LAMS  helf GEOATSS460LAMS GEOATSS472LAMS  helf GEOATSS536LAMS  helf GEOATSS536LAMS	48" x 44" x 23" 60-1/2" x 44" x 23" 72" x 44" x 23" 36" x 37" x 23"	121 131 139 83	1,216 1,507 1,704 \$1,108	1,277 1,582 1,789 \$1,163	1,048 1,300 1,470 \$958
ISS4480AKS IUSTABLE She ISS4600AKS ISS4720AKS ISS5360AKS IUSTABLE She ISS5420AKS ISS5480AKS	GEOATSS448MAPS  elves and 1 Base S  GEOATSS460MAPS GEOATSS472MAPS  elves and 1 Base S  GEOATSS536MAPS elves and 1 Base S  GEOATSS542MAPS	helf GEOATSS448LAMS helf GEOATSS460LAMS GEOATSS472LAMS helf GEOATSS536LAMS helf GEOATSS542LAMS	48" x 44" x 23" 60-1/2" x 44" x 23" 72" x 44" x 23" 36" x 37" x 23"	121 131 139 83	1,216 1,507 1,704 \$1,108	1,277 1,582 1,789 \$1,163	1,048 1,300 1,470 \$958
ISS4600AKS ISS4720AKS ISS4720AKS ISS5360AKS ISS5360AKS ISS5420AKS ISS5480AKS	GEOATSS5460MAPS GEOATSS472MAPS GEOATSS5472MAPS GEOATSS536MAPS GEOATSS536MAPS GEOATSS542MAPS	helf GEOATSS460LAMS GEOATSS472LAMS  helf GEOATSS536LAMS helf GEOATSS542LAMS	60-1/2" x 44" x 23" 72" x 44" x 23" 36" x 37" x 23" 42" x 37" x 23"	131 139 83	1,507 1,704 \$1,108	1,582 1,789 \$1,163	1,30 1,47 \$95
ISS4600AKS ISS4720AKS IUSTABLE She ISS5360AKS IUSTABLE She ISS5420AKS ISS5480AKS	GEOATSS460MAPS GEOATSS472MAPS  elves and 1 Base S GEOATSS536MAPS elves and 1 Base S GEOATSS542MAPS	GEOATSS460LAMS GEOATSS472LAMS  helf GEOATSS536LAMS helf GEOATSS542LAMS	72" x 44" x 23" 36" x 37" x 23" 42" x 37" x 23"	139 83	\$1,704 \$1,108	1,789 \$1,163	1,47 \$95
iustable She rss5360AKS iustable She rss5420AKS rss5480AKS	GEOATSS472MAPS  Pelves and 1 Base S GEOATSS536MAPS  Pelves and 1 Base S GEOATSS542MAPS	helf GEOATSS536LAMS helf GEOATSS542LAMS	72" x 44" x 23" 36" x 37" x 23" 42" x 37" x 23"	139 83	\$1,704 \$1,108	1,789 \$1,163	1,47/ \$95
iustable She ISS5360AKS iustable She ISS5420AKS ISS5480AKS	elves and 1 Base S GEOATSS536MAPS elves and 1 Base S GEOATSS542MAPS	<i>helf</i> GEOATSS536LAMS <i>helf</i> GEOATSS542LAMS	36" x 37" x 23" 42" x 37" x 23"	83	\$1,108 1,118	\$1,163	\$95
TSS5360AKS TSS5420AKS TSS5480AKS	GEOATSS536MAPS  elves and 1 Base S  GEOATSS542MAPS	GEOATSS536LAMS  helf  GEOATSS542LAMS	42" x 37" x 23"	96	1,118	•	
iustable She ISS5420AKS ISS5480AKS	elves and 1 Base S	<i>helf</i> GEOATSS542LAMS	42" x 37" x 23"	96	1,118	•	
TSS5420AKS TSS5480AKS	GEOATSS542MAPS	GEOATSS542LAMS				1,173	96
TSS5480AKS						1,173	96
	GEOATSS548MAPS	GEOATSS548LAMS	48" x 37" x 23"	100			, ,
iustable She				109	1,216	1,277	1,04
	elves and 1 Base S	<u>helf</u>					
TSS5600AKS TSS5720AKS	GEOATSS560MAPS GEOATSS572MAPS	GEOATSS560LAMS GEOATSS572LAMS	60-1/2" x 37" x 23" 72" x 37" x 23"	119 127	1,507 1,704	1,582 1,789	1,30 1,47
			26" v 27" v 22"	92	¢1 100	 \$1.162	\$95
133030UAK3	GEUATSSOSOIVIAPS	GEOATSSOSOLAIVIS	30 X37 X23	03	\$1,100	\$1,103	<b>\$</b> 90
iustable She	elves and 1 Base S	<u>helf</u>					
TSS6420AKS TSS6480AKS	GEOATSS642MAPS GEOATSS648MAPS	GEOATSS642LAMS GEOATSS648LAMS	42" x 37" x 23" 48" x 37" x 23"	96 109	1,118 1,216	1,173 1,277	96 1,04
iustable She	elves and 1 Base S	<u>helf</u>					
rss6600AKS	GEOATSS660MAPS	GEOATSS660LAMS	60-1/2" x 37" x 23"	119	1,507	1,582	1,30
rss6720AKS	GEOATSS672MAPS	GEOATSS672LAMS	72" x 37" x 23"	127	1,704	1,789	1,47
	SS6360AKS  SS6420AKS SS6480AKS  SS6480AKS	SS6360AKS GEOATSS636MAPS  SUSTABLE Shelves and 1 Base States SS6420AKS GEOATSS642MAPS SS6480AKS GEOATSS648MAPS SUSTABLE Shelves and 1 Base States SS6600AKS GEOATSS660MAPS	USTABLE Shelves and 1 Base Shelf  SS6420AKS GEOATSS642MAPS GEOATSS642LAMS SS6480AKS GEOATSS648MAPS GEOATSS648LAMS  SUSTABLE Shelves and 1 Base Shelf SS6600AKS GEOATSS660MAPS GEOATSS660LAMS	SS6360AKS GEOATSS636MAPS GEOATSS636LAMS 36" x 37" x 23"  SUSTABLE Shelves and 1 Base Shelf SS6420AKS GEOATSS642MAPS GEOATSS642LAMS 42" x 37" x 23" SS6480AKS GEOATSS648MAPS GEOATSS648LAMS 48" x 37" x 23"  SUSTABLE Shelves and 1 Base Shelf SS6600AKS GEOATSS660MAPS GEOATSS660LAMS 60-1/2" x 37" x 23"	### ### ### ### ### ### ### ### ### ##	### SS6360AKS GEOATSS636MAPS GEOATSS636LAMS 36" x 37" x 23" 83 \$1,108 ### SS6420AKS GEOATSS642MAPS GEOATSS642LAMS 42" x 37" x 23" 96 1,118 ### SS6480AKS GEOATSS648MAPS GEOATSS648LAMS 48" x 37" x 23" 109 1,216 ### SS6600AKS GEOATSS660MAPS GEOATSS660LAMS 60-1/2" x 37" x 23" 119 1,507	\$\text{SS6360AKS}\$ \text{ GEOATSS636MAPS}\$ \text{ GEOATSS636LAMS} \text{ 36" x 37" x 23"} \text{ 83 } \$1,108 \$1,163 \$\text{ sustable Shelves and 1 Base Shelf}\$ \$\text{SS642OAKS}\$ \text{ GEOATSS642MAPS}\$ \text{ GEOATSS642LAMS} \text{ 42" x 37" x 23"} \text{ 96 } 1,118 \$1,173 \$\text{ SS6480AKS}\$ \text{ GEOATSS648MAPS}\$ \text{ GEOATSS648LAMS} \text{ 48" x 37" x 23"} \text{ 109 } 1,216 \$1,277 \$\text{ sustable Shelves and 1 Base Shelf}\$ \$\text{ SS660OAKS}\$ \text{ GEOATSS660MAPS}\$ \text{ GEOATSS660LAMS} \text{ 60-1/2" x 37" x 23"} \text{ 119 } 1,507 \$1,582 \$\text{ 1,582}\$

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	elves and 1 Base S	helf per Side						Transitional Adders, Type 1
GEOATSD1360AKS	GEOATSD136MAPS	GEOATSD136LAMS	36" x 44" x 23"	142	\$1,962	\$2,061	\$1,667	Single- to Double-Faced
2 Adjustable She	elves and 1 Base S	helf per Side						
GEOATSD1420AKS	GEOATSD142MAPS	GEOATSD142LAMS	42" x 44" x 23"	166	1,973	2,071	1,677	
GEOATSD1480AKS	GEOATSD148MAPS	GEOATSD148LAMS	48" x 44" x 23"	190	2,125	2,231	1,806	
4 Adjustable She	elves and 1 Base S	helf per Side						
GEOATSD1600AKS	GEOATSD160MAPS	GEOATSD160LAMS	60-1/2" x 44" x 23"	210	2,572	2,701	2,187	
GEOATSD1720AKS	GEOATSD172MAPS	GEOATSD172LAMS	72" x 44" x 23"	223	2,834	2,975	2,409	
								←   →
								<b>.</b> ∣

2 Adjustable She	elves and 1 Base Si	<u>helf per Side</u>					
GEOATSD2360AKS	GEOATSD236MAPS	GEOATSD236LAMS	36" x 44" x 23"	142	\$1,962	\$2,061	\$1,667
2 Adjustable She	elves and 1 Base Si	helf per Side					
GEOATSD2420AKS	GEOATSD242MAPS	GEOATSD242LAMS	42" x 44" x 23"	166	1,973	2,071	1,677
GEOATSD2480AKS	GEOATSD248MAPS	GEOATSD248LAMS	48" x 44" x 23"	190	2,125	2,231	1,806
4 Adjustable She	elves and 1 Base Si	helf per Side					
GEOATSD2600AKS	GEOATSD260MAPS	GEOATSD260LAMS	60-1/2" x 44" x 23"	210	2,572	2,701	2,187
GEOATSD2720AKS	GEOATSD272MAPS	GEOATSD272LAMS	72" x 44" x 23"	223	2,834	2,975	2,409

Transitional Adders, Type 2

2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
GEOATDS1360AKS	GEOATDS136MAPS	GEOATDS136LAMS	36" x 37" x 23"	83	\$1,108	\$1,163	\$ 955
2 Adjustable She	elves and 1 Base Si	half					
<u>z Hujustable Slie</u>	eives and i base si	<u>ileli</u>					
GEOATDS1420AKS	GEOATDS142MAPS	GEOATDS142LAMS	42" x 37" x 23"	96	1,118	1,173	964
GEOATDS1480AKS	GEOATDS148MAPS	GEOATDS148LAMS	48" x 37" x 23"	109	1,216	1,277	1,048
1 Adjustable She	olyac and 1 Paca C	half					
4 Aujustable Sile	elves and 1 Base Si	<u>nen</u>					
GEOATDS1600AKS	GEOATDS160MAPS	GEOATDS160LAMS	60-1/2" x 37" x 23"	119	1,507	1,582	1,300
GEOATDS1720AKS	GEOATDS172MAPS	GEOATDS172LAMS	72" x 37" x 23"	127	1,704	1,789	1,470

Transitional Adders, 37"Wide Type 1 Double- to Single-Faced



 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ or\ Laminate\ (Table\ 4).\ Details\ can\ be\ found\ on\ page\ GEN\ 4\ and\ GEN\ 5.$ 

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Transitional Adders,	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
44"Wide Type 2 Double- to Single-Faced	GEOATDS2360AKS	GEOATDS236MAPS	GEOATDS236LAMS	36" x 44" x 23"	95	\$1,108	\$1,163	\$ 955
11	2 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOATDS2420AKS	GEOATDS242MAPS	GEOATDS242LAMS	42" x 44" x 23"	108	1,118	1,173	964
	GEOATDS2480AKS	GEOATDS248MAPS	GEOATDS248LAMS	48'' x 44'' x 23''	121	1,216	1,277	1,048
	4 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOATDS2600AKS GEOATDS2720AKS	GEOATDS260MAPS GEOATDS272MAPS	GEOATDS260LAMS GEOATDS272LAMS	60-1/2" x 44" x 23" 72" x 44" x 23"	131 139	1,507 1,704	1,582 1,789	1,300 1,470
ransitional Adders,	2 Adjustable She	elves and 1 Base Si	helf					
44"Wide Type 3	GEOATDS3360AKS	GEOATDS336MAPS	GEOATDS336LAMS	36" x 44" x 23"	95	\$1,108	\$1,163	\$ 955
ouble- to Single-Faced	2 Adiustable Che	oluge and 1 Dags C	half					
	GEOATDS3420AKS	elves and 1 Base Si GEOATDS342MAPS	GEOATDS342LAMS	42" x 44" x 23"	108	1,118	1,173	964
	GEOATDS3420AKS	GEOATDS342MAPS	GEOATDS342LAMS	48" x 44" x 23"	121	1,216	1,173	1,048
	4 Adjustable She	elves and 1 Base Si	helf					
	GEOATDS3600AKS GEOATDS3720AKS	GEOATDS360MAPS GEOATDS372MAPS	GEOATDS360LAMS GEOATDS372LAMS	60-1/2" x 44" x 23" 72" x 44" x 23"	131 139	1,507 1,704	1,582 1,789	1,300 1,470
ransitional Adders, 87"Wide Type 4 Double- to Single-Faced	•	elves and 1 Base Si GEOATDS436MAPS		36" x37" x23"	83	\$1,108	\$1,163	\$ 955
Double- to Single-i aceu	2 Adiustable She	elves and 1 Base Si	helf					
	GEOATDS4420AKS	GEOATDS442MAPS	GEOATDS442LAMS	42" x 37" x 23"	96	1,118	1,173	964
	GEOATDS4480AKS	GEOATDS448MAPS	GEOATDS448LAMS	48" x 37" x 23"	109	1,216	1,277	1,048
	4 Adjustable She	elves and 1 Base Si	<u>helf</u>					
	GEOATDS4600AKS GEOATDS4720AKS	GEOATDS460MAPS GEOATDS472MAPS	GEOATDS460LAMS GEOATDS472LAMS	60-1/2" x 37" x 23" 72" x 37" x 23"	119 127	1,507 1,704	1,582 1,789	1,300 1,470

3-Way Towers Geometrix


Single-Faced 3-Way Towers Only (Adders sold separately)

▼ = Tower/Transitional Tower

= Back Panel Location


• = Shelving Side

→ = Open Shelving Direction




Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	1.
Single-Faced 3-V	Vay Towers, Type 1	-						Single-Faced Type 1
GE03WST1360AKS	GE03WST136MAPS	GE03WST136LAMS	36" x 12" x 12"	29	\$604	\$635	\$451	
GE03WST1420AKS	GE03WST142MAPS	GE03WST142LAMS	42" x 12" x 12"	35	615	646	462	
GE03WST1480AKS	GE03WST148MAPS	GE03WST148LAMS	48" x 12" x 12"	41	626	657	473	<b>←</b> 1
GE03WST1600AKS	GE03WST160MAPS	GE03WST160LAMS	60-1/2" x 12" x 12"	48	648	679	495	1 1
GE03WST1720AKS	GE03WST172MAPS	GE03WST172LAMS	72" x 12" x 12"	60	670	701	517	
Single-Faced 3-V	Vav Towers Tyne 2							Single-Faced Type 2


Single-Facea 3-VI	ray rowers, rype z						
GE03WST2360AKS	GE03WST236MAPS	GE03WST236LAMS	36" x 12" x 12"	29	\$604	\$635	\$451
GE03WST2420AKS	GE03WST242MAPS	GE03WST242LAMS	42" x 12" x 12"	35	615	646	462
GE03WST2480AKS	GE03WST248MAPS	GE03WST248LAMS	48" x 12" x 12"	41	626	657	473
GE03WST2600AKS	GE03WST260MAPS	GE03WST260LAMS	60-1/2" x 12" x 12"	48	648	679	495
GE03WST2720AKS	GE03WST272MAPS	GE03WST272LAMS	72" x 12" x 12"	60	670	701	517



Single-Faced 3-W	<u>/ay Towers, Type 3</u>						
GE03WST3360AKS	GE03WST336MAPS	GE03WST336LAMS	36" x 12" x 12"	29	\$604	\$635	\$451
GE03WST3420AKS	GE03WST342MAPS	GE03WST342LAMS	42" x 12" x 12"	35	615	646	462
GE03WST3480AKS	GE03WST348MAPS	GE03WST348LAMS	48" x 12" x 12"	41	626	657	473
GE03WST3600AKS	GE03WST360MAPS	GE03WST360LAMS	60-1/2" x 12" x 12"	48	648	679	495
GE03WST3720AKS	GE03WST372MAPS	GE03WST372LAMS	72" x 12" x 12"	60	670	701	517



Single-Faced 3-W	<u>/ay Towers, Type 4</u>						
GE03WST4360AKS	GE03WST436MAPS	GE03WST436LAMS	36" x 12" x 12"	29	\$604	\$635	\$451
GE03WST4420AKS	GE03WST442MAPS	GE03WST442LAMS	42" x 12" x 12"	35	615	646	462
GE03WST4480AKS	GE03WST448MAPS	GE03WST448LAMS	48" x 12" x 12"	41	626	657	473
GE03WST4600AKS	GE03WST460MAPS	GE03WST460LAMS	60-1/2" x 12" x 12"	48	648	679	495
GE03WST4720AKS	GE03WST472MAPS	GE03WST472LAMS	72" x 12" x 12"	60	670	701	517



Geometrix



Double-Faced 3-Way Towers Only (Adders sold separately)

∇ = Tower/Transitional Tower

= Back Panel Location


• = Shelving Side

→ = Open Shelving Direction

Doub	le-Fa	ced	4	
9		11		
/		V	1.	

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Double-Faced 3-	Way Towers						
GE03WDT360AKS	GE03WDT36MAPS	GE03WDT36LAMS	36" x 23" x 23"	56	\$ 945	\$ 990	\$708
GE03WDT420AKS	GE03WDT42MAPS	GE03WDT42LAMS	42" x 23" x 23"	68	956	1,001	719
GE03WDT480AKS	GE03WDT48MAPS	GE03WDT48LAMS	48" x 23" x 23"	70	967	1,012	730
GE03WDT600AKS	GE03WDT60MAPS	GE03WDT60LAMS	60-1/2" x 23" x 23"	74	989	1,034	752
GE03WDT720AKS	GE03WDT72MAPS	GE03WDT72LAMS	72" x 23" x 23"	96	1,011	1,056	774


Double- to Single-Faced Type 1



### Double-Faced 3-Way Towers, Type 1

GE03WDT1360AKS	GE03WDT136MAPS	GE03WDT136LAMS	36" x 23" x 23"	56	\$945	\$990	\$708
GE03WDT1420AKS	GE03WDT142MAPS	GE03WDT142LAMS	42" x 23" x 23"	68	956	1,001	719
GE03WDT1480AKS	GE03WDT48MAPS	GE03WDT148LAMS	48" x 23" x 23"	70	967	1,012	730
GE03WDT1600AKS	GE03WDT160MAPS	GE03WDT160LAMS	60-1/2" x 23" x 23"	74	989	1,034	752
GF03WDT1720AKS	GF03WDT172MAPS	GF03WDT172LAMS	72" x 23" x 23"	96	1 011	1 056	774

## Double- to Single-Faced Type 2



#### Double-Faced 3-Way Towers, Type 2

	-						
GE03WDT2360AKS	GE03WDT236MAPS	GE03WDT236LAMS	36" x 23" x 23"	56	\$945	\$990	\$708
GE03WDT2420AKS	GE03WDT242MAPS	GE03WDT242LAMS	42" x 23" x 23"	68	956	1,001	719
GE03WDT2480AKS	GE03WDT248MAPS	GE03WDT248LAMS	48" x 23" x 23"	70	967	1,012	730
GE03WDT2600AKS	GE03WDT260MAPS	GE03WDT260LAMS	60-1/2" x 23" x 23"	74	989	1,034	752
GE03WDT2720AKS	GE03WDT272MAPS	GE03WDT272LAMS	72" x 23" x 23"	96	1,011	1,056	774

3-Way Towers Geometrix


Trapezoid 3-Way Towers Only (Adders sold separately)

▼ = Tower/Transitional Tower


= Back Panel Location

• = Shelving Side

→ = Open Shelving Direction



Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
3-Way Trapezoid To	owers, Type 1							Trapezoid Type 1
GE03WTT1360AKS	GE03WTT136MAPS	GE03WTT136LAMS	36" x 23" x 12"	50	\$ 911	\$ 956	\$682	F T 1
GE03WTT1420AKS	GE03WTT142MAPS	GE03WTT142LAMS	42" x 23" x 12"	51	931	976	702	
GE03WTT1480AKS	GE03WTT148MAPS	GE03WTT148LAMS	48" x 23" x 12"	60	951	996	722	4 11 4
GE03WTT1600AKS	GE03WTT160MAPS	GE03WTT160LAMS	60-1/2" x 23" x 12"	64	991	1,036	762	1
GE03WTT1720AKS	GE03WTT172MAPS	GE03WTT172LAMS	72" x 23" x 12"	86	1,031	1,076	802	
3-Way Trapezoid To	owers, Whiteboard T	ype 1						/, /
GE03WTTW1360AKS	GE03WTTW136MAPS	GE03WTTW136LAMS	36" x 23" x 12"	52	\$ 957	\$1,002	\$728	
GE03WTTW1420AKS	GE03WTTW142MAPS	GE03WTTW142LAMS	42" x 23" x 12"	53	977	1,022	748	
GE03WTTW1480AKS	GE03WTTW148MAPS	GE03WTTW148LAMS	48" x 23" x 12"	62	997	1,042	768	
GE03WTTW1600AKS	GE03WTTW160MAPS	GE03WTTW160LAMS	60-1/2" x 23" x 12"	66	1,037	1,082	808	
GE03WTTW1720AKS	GE03WTTW172MAPS	GE03WTTW172LAMS	72" x 23" x 12"	88	1,077	1,122	848	
3-Way Trapezoid To	owers, Magnetic Whi	teboard Type 1						
GE03WTTM1360AKS	GE03WTTM136MAPS	GE03WTTM136LAMS	36" x 23" x 12"	52	\$ 987	\$1,032	\$758	
GE03WTTM1420AKS	GE03WTTM142MAPS	GE03WTTM142LAMS	42" x 23" x 12"	53	1,007	1,052	778	
GE03WTTM1480AKS	GE03WTTM148MAPS	GE03WTTM148LAMS	48" x 23" x 12"	62	1,027	1,072	798	
GE03WTTM1600AKS	GE03WTTM160MAPS	GE03WTTM160LAMS	60-1/2" x 23" x 12"	66	1,067	1,112	838	
GE03WTTM1720AKS	GE03WTTM172MAPS	GE03WTTM172LAMS	72" x 23" x 12"	88	1,107	1,152	878	
3-Way Trapezoid To	owers, Tackboard Ty	pe 1						
GE03WTTT1360AKS	GE03WTTT136MAPS	GE03WTTT136LAMS	36" x 23" x 12"	54	\$ 963	\$1,008	\$734	
GE03WTTT1420AKS	GE03WTTT142MAPS	GE03WTTT142LAMS	42" x 23" x 12"	55	983	1,028	754	
GE03WTTT1480AKS	GE03WTTT148MAPS	GE03WTTT148LAMS	48" x 23" x 12"	64	1,003	1,048	774	
GE03WTTT1600AKS	GE03WTTT160MAPS	GE03WTTT160LAMS	60-1/2" x 23" x 12"	68	1,043	1,088	814	
GE03WTTT1720AKS	GE03WTTT172MAPS	GE03WTT172LAMS	72" x 23" x 12"	90	1,083	1,128	854	
3.Way Transzoid To	owers, Upholstered 1	ivne 1						
	· •							
GE03WTTU1360AKS	GE03WTTU136MAPS	GE03WTTU136LAMS	36" x 23" x 12"	56	\$1,048	\$1,093	\$819	
GE03WTTU1420AKS	GE03WTTU142MAPS	GE03WTTU142LAMS	42" x 23" x 12"	57	1,068	1,113	839	
GE03WTTU1480AKS	GE03WTTU148MAPS	GE03WTTU148LAMS	48" x 23" x 12"	66	1,088	1,133	859	
GE03WTTU1600AKS	GE03WTTU160MAPS	GE03WTTU160LAMS	60-1/2" x 23" x 12"	70	1,128	1,173	899	
GE03WTTU1720AKS	GE03WTTU172MAPS	GE03WTTU172LAMS	72" x 23" x 12"	92	1,168	1,213	939	



Trapezoid 3-Way Towers Only (Adders sold separately)


▼ = Tower/Transitional Tower

= Back Panel Location

• = Shelving Side

→ = Open Shelving Direction

Trapezoid Type 2



Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
3-Way Trapezoid To	owers, Type 2						
GE03WTT2360AKS	GE03WTT236MAPS	GE03WTT236LAMS	36" x 23" x 12"	50	\$ 911	\$ 956	\$682
GE03WTT2420AKS	GE03WTT242MAPS	GE03WTT242LAMS	42" x 23" x 12"	51	931	976	702
GE03WTT2480AKS	GE03WTT248MAPS	GE03WTT248LAMS	48" x 23" x 12"	60	951	996	722
GE03WTT2600AKS	GE03WTT260MAPS	GE03WTT260LAMS	60-1/2" x 23" x 12"	64	991	1,036	762
GE03WTT2720AKS	GE03WTT272MAPS	GE03WTT272LAMS	72" x 23" x 12"	86	1,031	1,076	802
3-Way Trapezoid To	owers, Whiteboard Ty	ype 2					
GE03WTTW2360AKS	GE03WTTW236MAPS	GE03WTTW236LAMS	36" x 23" x 12"	52	\$ 957	\$1,002	\$728
GE03WTTW2420AKS	GE03WTTW242MAPS	GE03WTTW242LAMS	42" x 23" x 12"	53	977	1,022	748
GE03WTTW2480AKS	GE03WTTW248MAPS	GE03WTTW248LAMS	48" x 23" x 12"	62	997	1,042	768
GE03WTTW2600AKS	GE03WTTW260MAPS	GE03WTTW260LAMS	60-1/2" x 23" x 12"	66	1,037	1,082	808
GE03WTTW2720AKS	GE03WTTW272MAPS	GE03WTTW272LAMS	72" x 23" x 12"	88	1,077	1,122	848
3-Way Trapezoid To	owers, Magnetic Whi	teboard Type 2					
GE03WTTM2360AKS	GE03WTTM236MAPS	GE03WTTM236LAMS	36" x 23" x 12"	52	\$ 987	\$1,032	\$758
GE03WTTM2420AKS	GE03WTTM242MAPS	GE03WTTM242LAMS	42" x 23" x 12"	53	1,007	1,052	778
GE03WTTM2480AKS	GE03WTTM248MAPS	GE03WTTM248LAMS	48" x 23" x 12"	62	1,027	1,072	798
GE03WTTM2600AKS	GE03WTTM260MAPS	GE03WTTM260LAMS	60-1/2" x 23" x 12"	66	1,067	1,112	838
GE03WTTM2720AKS	GE03WTTM272MAPS	GE03WTTM272LAMS	72" x 23" x 12"	88	1,107	1,152	878
3-Way Trapezoid To	owers, Tackboard Typ	pe 2					
GE03WTTT2360AKS	GE03WTTT236MAPS	GE03WTTT236LAMS	36" x 23" x 12"	54	\$ 963	\$1,008	\$734
GE03WTTT2420AKS	GE03WTTT242MAPS	GE03WTTT242LAMS	42" x 23" x 12"	55	983	1,028	754
GE03WTTT2480AKS	GE03WTTT248MAPS	GE03WTTT248LAMS	48" x 23" x 12"	64	1,003	1,048	774
GE03WTTT2600AKS	GE03WTTT260MAPS	GE03WTTT260LAMS	60-1/2" x 23" x 12"	68	1,043	1,088	814
GE03WTTT2720AKS	GE03WTTT272MAPS	GE03WTTT272LAMS	72" x 23" x 12"	90	1,083	1,128	854
3-Way Trapezoid To	owers, Upholstered T	ype 2					
GE03WTTU2360AKS	GE03WTTU236MAPS	GE03WTTU236LAMS	36" x 23" x 12"	56	\$1,048	\$1,093	\$819
GE03WTTU2420AKS	GE03WTTU242MAPS	GE03WTTU242LAMS	42" x 23" x 12"	57	1,068	1,113	839
GE03WTTU2480AKS	GE03WTTU248MAPS	GE03WTTU248LAMS	48" x 23" x 12"	66	1,088	1,133	859
GE03WTTU2600AKS	GE03WTTU260MAPS	GE03WTTU260LAMS	60-1/2" x 23" x 12"	70	1,128	1,173	899
GE03WTTU2720AKS	GE03WTTU272MAPS	GE03WTTU272LAMS	72" x 23" x 12"	92	1,168	1,213	939

3-Way Towers Geometrix

Trapezoid 3-Way Towers Only (Adders sold separately)

▼ = Tower/Transitional Tower

= Back Panel Location

• = Shelving Side

→ = Open Shelving Direction



Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	\.\.\.\
3-Way Trapezoid To	owers, Type 3							Trapezoid Type 3
GE03WTT3360AKS	GE03WTT336MAPS	GE03WTT336LAMS	36" x 23" x 12"	50	\$ 911	\$ 956	\$682	1 1 1
GE03WTT3420AKS	GE03WTT342MAPS	GE03WTT342LAMS	42" x 23" x 12"	51	931	976	702	
GE03WTT3480AKS	GE03WTT348MAPS	GE03WTT348LAMS	48" x 23" x 12"	60	951	996	722	e 111 -
GE03WTT3600AKS	GE03WTT360MAPS	GE03WTT360LAMS	60-1/2" x 23" x 12"	64	991	1,036	762	
GE03WTT3720AKS	GE03WTT372MAPS	GE03WTT372LAMS	72" x 23" x 12"	86	1,031	1,076	802	
3.Way Tranezoid To	owers, Whiteboard T	vne 3						
		•					4=00	
GEO3WTTW336OAKS	GEO3WTTW336MAPS	GEO3WTTW336LAMS	36" x 23" x 12"	52	\$ 957	\$1,002	\$728	
GEO3WTTW342OAKS	GEO3WTTW342MAPS	GEO3WTTW342LAMS	42" x 23" x 12"	53	977	1,022	748	
GEO3WTTW3480AKS GEO3WTTW3600AKS	GEO3WTTW348MAPS GEO3WTTW360MAPS	GEO3WTTW348LAMS GEO3WTTW360LAMS	48" x 23" x 12" 60-1/2" x 23" x 12"	62 66	997 1,037	1,042 1,082	768 808	
GEO3WTTW3600AKS	GEO3WTTW360MAPS	GEO3WTTW360LAWS	72" x 23" x 12"	88	1,037	1,122	848	
GEOSWITW372OARS	GEOSWITW3/2WAF3	GEOSVITIVS/ZLAIVIS	72 X23 X12	00	1,077	1,122	040	
3-Way Trapezoid To	owers, Magnetic Whi	teboard Type 3						
GE03WTTM3360AKS	GE03WTTM336MAPS	GE03WTTM336LAMS	36" x 23" x 12"	52	\$ 987	\$1,032	\$758	
GE03WTTM3420AKS	GE03WTTM342MAPS	GE03WTTM342LAMS	42" x 23" x 12"	53	1,007	1,052	778	
GE03WTTM3480AKS	GE03WTTM348MAPS	GE03WTTM348LAMS	48" x 23" x 12"	62	1,027	1,072	798	
GE03WTTM3600AKS	GE03WTTM360MAPS	GE03WTTM360LAMS	60-1/2" x 23" x 12"	66	1,067	1,112	838	
GE03WTTM3720AKS	GE03WTTM372MAPS	GE03WTTM372LAMS	72" x 23" x 12"	88	1,107	1,152	878	
3-Way Trapezoid To	owers, Tackboard Typ	pe 3						
GE03WTTT3360AKS	GE03WTTT336MAPS	GE03WTTT336LAMS	36" x 23" x 12"	54	\$ 963	\$1,008	\$734	
GE03WTTT3420AKS	GE03WTTT342MAPS	GE03WTTT342LAMS	42" x 23" x 12"	55	983	1,028	754	
GE03WTTT3480AKS	GE03WTTT348MAPS	GE03WTTT348LAMS	48" x 23" x 12"	64	1,003	1,048	774	
GE03WTTT3600AKS	GE03WTTT360MAPS	GE03WTTT360LAMS	60-1/2" x 23" x 12"	68	1,043	1,088	814	
GE03WTTT3720AKS	GE03WTTT372MAPS	GE03WTTT372LAMS	72" x 23" x 12"	90	1,083	1,128	854	
3-Way Trapezoid To	owers, Upholstered 1	ype 3						
GE03WTTU3360AKS	GE03WTTU336MAPS	GE03WTTU336LAMS	36" x 23" x 12"	56	\$1,048	\$1,093	\$819	
GE03WTTU3420AKS	GE03WTTU342MAPS	GE03WTTU342LAMS	42" x 23" x 12"	57	1,068	1,113	839	
GE03WTTU3480AKS	GE03WTTU348MAPS	GE03WTTU348LAMS	48" x 23" x 12"	66	1,088	1,133	859	
GE03WTTU3600AKS	GE03WTTU360MAPS	GE03WTTU360LAMS	60-1/2" x 23" x 12"	70	1,128	1,173	899	
GE03WTTU3720AKS	GE03WTTU372MAPS	GE03WTTU372LAMS	72" x 23" x 12"	92	1,168	1,213	939	




Trapezoid 3-Way Towers Only (Adders sold separately)

= Back Panel Location

• = Shelving Side

→ = Open Shelving Direction

Trapezoid Type 4



Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
3-Way Trapezoid To	owers, Type 4						
GE03WTT4360AKS	GE03WTT436MAPS	GE03WTT436LAMS	36" x 23" x 12"	50	\$ 911	\$ 956	\$682
GE03WTT4420AKS	GE03WTT442MAPS	GE03WTT442LAMS	42" x 23" x 12"	51	931	976	702
GE03WTT4480AKS	GE03WTT448MAPS	GE03WTT448LAMS	48" x 23" x 12"	60	951	996	722
GE03WTT4600AKS	GE03WTT460MAPS	GE03WTT460LAMS	60-1/2" x 23" x 12"	64	991	1,036	762
GE03WTT4720AKS	GE03WTT472MAPS	GE03WTT472LAMS	72" x 23" x 12"	86	1,031	1,076	802
3-Way Trapezoid To	owers, Whiteboard T	ype 4					
GE03WTTW4360AKS	GE03WTTW436MAPS	GE03WTTW436LAMS	36" x 23" x 12"	52	\$ 957	\$1,002	\$728
GE03WTTW4420AKS	GE03WTTW442MAPS	GE03WTTW442LAMS	42" x 23" x 12"	53	977	1,022	748
GE03WTTW4480AKS	GE03WTTW448MAPS	GE03WTTW448LAMS	48" x 23" x 12"	62	997	1,042	768
GE03WTTW4600AKS	GE03WTTW460MAPS	GE03WTTW460LAMS	60-1/2" x 23" x 12"	66	1,037	1,082	808
GE03WTTW4720AKS	GE03WTTW472MAPS	GE03WTTW472LAMS	72" x 23" x 12"	88	1,077	1,122	848
3-Way Trapezoid To	owers, Magnetic Whi	teboard Type 4					
GE03WTTM4360AKS	GE03WTTM436MAPS	GE03WTTM436LAMS	36" x 23" x 12"	52	\$ 987	\$1,032	\$758
GE03WTTM4420AKS	GE03WTTM442MAPS	GE03WTTM442LAMS	42" x 23" x 12"	53	1,007	1,052	778
GE03WTTM4480AKS	GE03WTTM448MAPS	GE03WTTM448LAMS	48" x 23" x 12"	62	1,027	1,072	798
GE03WTTM4600AKS	GE03WTTM460MAPS	GE03WTTM460LAMS	60-1/2" x 23" x 12"	66	1,067	1,112	838
GE03WTTM4720AKS	GE03WTTM472MAPS	GE03WTTM472LAMS	72" x 23" x 12"	88	1,107	1,152	878
3-Way Trapezoid To	owers, Tackboard Ty <sub>l</sub>	pe 4					
GE03WTTT4360AKS	GE03WTTT436MAPS	GE03WTTT436LAMS	36" x 23" x 12"	54	\$ 963	\$1,008	\$734
GE03WTTT4420AKS	GE03WTTT442MAPS	GE03WTTT442LAMS	42" x 23" x 12"	55	983	1,028	754
GE03WTTT4480AKS	GE03WTTT448MAPS	GE03WTTT448LAMS	48" x 23" x 12"	64	1,003	1,048	774
GE03WTTT4600AKS	GE03WTTT460MAPS	GE03WTTT460LAMS	60-1/2" x 23" x 12"	68	1,043	1,088	814
GE03WTTT4720AKS	GE03WTTT472MAPS	GE03WTTT472LAMS	72" x 23" x 12"	90	1,083	1,128	854
3-Way Trapezoid To	owers, Upholstered 1	<b>Туре 4</b>					
GE03WTTU4360AKS	GE03WTTU436MAPS	GE03WTTU436LAMS	36" x 23" x 12"	56	\$1,048	\$1,093	\$819
GE03WTTU4420AKS	GE03WTTU442MAPS	GE03WTTU442LAMS	42" x 23" x 12"	57	1,068	1,113	839
GE03WTTU4480AKS	GE03WTTU448MAPS	GE03WTTU448LAMS	48" x 23" x 12"	66	1,088	1,133	859
GE03WTTU4600AKS	GE03WTTU460MAPS	GE03WTTU460LAMS	60-1/2" x 23" x 12"	70	1,128	1,173	899
GE03WTTU4720AKS	GE03WTTU472MAPS	GE03WTTU472LAMS	72" x 23" x 12"	92	1,168	1,213	939

Price	Price	Oak Price	Wt. (lbs.)	Height	Laminate Catalog No.	Maple Catalog No.	Oak Catalog No.
						d 2 Shelves	1 Top, 1 Base, an
\$359	\$501	\$478	55	36"	GEOLSKIT36LAMS	GEOLSKIT36MAPS	GEOLSKIT360AKS
359	501	478	66	42"	GEOLSKIT42LAMS	GEOLSKIT42MAPS	GEOLSKIT420AKS
359	501	478	77	48''	GEOLSKIT48LAMS	GEOLSKIT48MAPS	GEOLSKIT480AKS
						d 4 Shelves	1 Top, 1 Base, an
504	708	675	83	60-1/2"	GEOLSKIT60LAMS	GEOLSKIT60MAPS	GEOLSKIT600AKS
504	708	675	87	72"	GEOLSKIT72LAMS	GEOLSKIT72MAPS	GEOLSKIT720AKS
					tition	Sholyos and 1 Par	1 Top. 1 Page 4.9
							• • • • • • • • • • • • • • • • • • • •
							GEOLDKIT360AKS
							GEOLDKIT420AKS
821	1,149	1,093	139	48''	GEOLDKIT48LAMS	GEOLDKIT48MAPS	GEOLDKIT480AKS
					tition	Shelves, and 1 Par	1 Top, 1 Base, 8 \$
1,193	1,670	1,590	148	60-1/2"	GEOLDKIT60LAMS	GEOLDKIT60MAPS	GEOLDKIT600AKS
1,193	1,670	1,590	154	72"	GEOLDKIT72LAMS	GEOLDKIT72MAPS	GEOLDKIT720AKS
	\$ 821 821 821 1,193	\$1,149 \$ 821 1,149 821 1,670 1,193	\$1,093 \$1,149 \$821 1,093 1,149 821 1,590 1,670 1,193	66 478 501 359 77 478 501 359 83 675 708 504 87 675 708 504 102 \$1,093 \$1,149 \$821 120 1,093 1,149 821 139 1,093 1,149 821 148 1,590 1,670 1,193	42" 66 478 501 359 48" 77 478 501 359 60-1/2" 83 675 708 504 72" 87 675 708 504 36" 102 \$1,093 \$1,149 \$821 42" 120 1,093 1,149 821 48" 139 1,093 1,149 821 60-1/2" 148 1,590 1,670 1,193	GEOLSKIT42LAMS 42" 66 478 501 359 GEOLSKIT48LAMS 48" 77 478 501 359  GEOLSKIT60LAMS 60-1/2" 83 675 708 504 GEOLSKIT72LAMS 72" 87 675 708 504  GEOLDKIT36LAMS 36" 102 \$1,093 \$1,149 \$821 GEOLDKIT42LAMS 42" 120 1,093 1,149 821 GEOLDKIT48LAMS 48" 139 1,093 1,149 821  tition  GEOLDKIT60LAMS 60-1/2" 148 1,590 1,670 1,193	GEOLSKIT42MAPS GEOLSKIT42LAMS 42" 66 478 501 359 GEOLSKIT48MAPS GEOLSKIT48LAMS 48" 77 478 501 359 dd 4 Shelves  GEOLSKIT60MAPS GEOLSKIT60LAMS 60-1/2" 83 675 708 504 GEOLSKIT72MAPS GEOLSKIT72LAMS 72" 87 675 708 504 504 675 708 675 708 504 675 708 675 708 504 675 708 675 708 675 708 504 675 708 675

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Single-Faced Left Panel	GEOFSL360AKS	GEOFSL36MAPS	GEOFSL36LAMS	36" x 1" x 12"	8	\$192	\$202	\$142
	GEOFSL420AKS	GEOFSL42MAPS	GEOFSL42LAMS	42" x 1" x 12"	10	202	212	151
	GEOFSL480AKS	GEOFSL48MAPS	GEOFSL48LAMS	48" x 1" x 12"	12	223	235	168
	GEOFSL600AKS	GEOFSL60MAPS	GEOFSL60LAMS	60-1/2" x 1" x 12"	16	274	288	206
	GEOFSL720AKS	GEOFSL72MAPS	GEOFSL72LAMS	72" x 1" x 12"	20	343	360	257
Single-Faced Right Panel	GEOFSR360AKS GEOFSR420AKS GEOFSR480AKS GEOFSR600AKS GEOFSR720AKS	GEOFSR36MAPS GEOFSR42MAPS GEOFSR48MAPS GEOFSR60MAPS GEOFSR72MAPS	GEOFSR36LAMS GEOFSR42LAMS GEOFSR48LAMS GEOFSR60LAMS GEOFSR72LAMS	36" x1" x12" 42" x1" x12" 48" x1" x12" 60-1/2" x1" x12" 72" x1" x12"	8 10 12 16 20	\$192 202 223 274 343	\$202 212 235 288 360	\$142 151 168 206 257
Double-Faced Panel	GEOFD360AKS GEOFD420AKS GEOFD480AKS GEOFD600AKS GEOFD720AKS	GEOFD36MAPS GEOFD42MAPS GEOFD48MAPS GEOFD60MAPS GEOFD72MAPS	GEOFD36LAMS GEOFD42LAMS GEOFD48LAMS GEOFD60LAMS GEOFD72LAMS	36"x1"x23" 42"x1"x23" 48"x1"x23" 60-1/2"x1"x23" 72"x1"x23"	16 20 24 32 40	\$305 315 362 463 560	\$320 331 380 486 588	\$226 236 272 347 420

Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price	
2 Adjustable She	elves and 1 Base S	helf per Side						Linear Double-Faced
GEOMLDB360AKS	GEOMLDB36MAPS	GEOMLDB36LAMS	36" x 36" x 23"	138	\$1,977	\$2,076	\$1,480	Mobile, One Bay
2 Adjustable She	elves and 1 Base S	helf per Side						
GEOMLDB420AKS	GEOMLDB42MAPS	GEOMLDB42LAMS	42" x 36" x 23"	164	1,987	2,086	1,490	I
GEOMLDB480AKS	GEOMLDB48MAPS	GEOMLDB48LAMS	48" x 36" x 23"	191	2,128	2,234	1,596	
4 Adjustable She	elves and 1 Base S	helf per Side						
GEOMLDB600AKS	GEOMLDB60MAPS	GEOMLDB60LAMS	60-1/2" x 36" x 23""	216	2,700	2,835	2,025	
2 Adjustable She	elves and 1 Base S	helf per Side						Linear Double-Faced
GEOMLDBB360AKS	GEOMLDBB36MAPS	GEOMLDBB36LAMS	36" x 72" x 23"	256	\$3,563	\$3,741	\$2,669	Mobile, Two Bay
2 Adjustable She	elves and 1 Base S	helf per Side						
GEOMLDBB420AKS	GEOMLDBB42MAPS	GEOMLDBB42LAMS	42" x 72" x 23"	304	3,573	3,752	2,680	
GEOMLDBB480AKS	GEOMLDBB48MAPS	GEOMLDBB48LAMS	48" x 72" x 23"	354	3,833	4,025	2,875	
4 Adjustable She	elves and 1 Base S	helf per Side						
GEOMLDBB600AKS	GEOMLDBB60MAPS	GEOMLDBB60LAMS	60-1/2" x 72" x 23"	396	4,860	5,103	3,645	

Note: Shelving Back Panels are sold separately on pages GEO 37-GEO 46.

	Oak Catalog No.	Maple Catalog No.	Laminate Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Laminate Price
Arc Convex Mobile	2 Adjustable She	lves and 1 Base She	e <u>lf</u>					
SingleFaced	GEOMAXS360AKS	GEOMAXS36MAPS	GEOMAXS36LAMS	36" x 44" x 18"	148	\$1,752	\$1,840	\$1,313
	2 Adjustable She	lves and 1 Base She	e <i>lf</i>					
	GEOMAXS420AKS	GEOMAXS42MAPS	GEOMAXS42LAMS	42" x 44" x 18"	176	1,762	1,850	1,322
	GEOMAXS480AKS	GEOMAXS48MAPS	GEOMAXS48LAMS	48" x 44" x 18"	206	1,860	1,954	1,394
Arc Concave Mobile	2 Adjustable She	lves and 1 Base She	<u>elf</u>					
SingleFaced	GEOMAVS360AKS	GEOMAVS36MAPS	GEOMAVS36LAMS	36" x 44" x 18"	148	\$1,752	\$1,840	\$1,313
	2 Adjustable She	lves and 1 Base She	e <b>lf</b>					
	GEOMAVS420AKS	GEOMAVS42MAPS	GEOMAVS42LAMS	42" x 44" x 18"	176	1,762	1,850	1,322
	GEOMAVS48OAKS	GEOMAVS48MAPS	GEOMAVS48LAMS	48" x 44" x 18"	206	1,860	1,954	1,394
Arc Double-Faced	2 Adjustable She	lves and 1 Base She	elf per Side					
Mobile, One Bay	GEOMAD360AKS	GEOMAD36MAPS	GEOMAD36LAMS	36" x 44" x 23"	158	\$2,434	\$2,556	\$1,823
	2 Adjustable She	lves and 1 Base She	elf per Side					
	GEOMAD420AKS	GEOMAD42MAPS	GEOMAD42LAMS	42" x 44" x 23"	186	2,444	2,566	1,833
	GEOMAD480AKS	GEOMAD48MAPS	GEOMAD48LAMS	48" x 44" x 23"	216	2,599	2,729	1,949
	4 Adjustable She	lves and 1 Base She	elf per Side					
	GEOMAD600AKS	GEOMAD60MAPS	GEOMAD60LAMS	60-1/2" x 44" x 23"	236	3,221	3,382	2,416
Arc Double-Faced	2 Adjustable She	lves and 1 Base She	elf per Side					
Mobile, Two Bay	-	GEOMADBB36MAPS	-	36" x 88" x 23"	302	\$4,868	\$5,112	\$3,646
	2 Adjustable Sho	lvas and 1 Rasa Sha	elf ner Side					
	-	Ives and 1 Base She GEOMADBB42MAPS		42" x 88" x 23"	352	4,888	5,132	2//5
		GEOMADBB48MAPS		48" x 88" x 23"	408	5,198	5,132	3,665 3,898
	4 Adjustable She	lves and 1 Base She	elf per Side					

Note: Shelving Back Panels are sold separately on pages GEO 37-GEO 46.

Linear Back Panels Geometrix

### **General Specifications**

#### OAK AND MAPLE BACKS

Backs are constructed of 3-ply or 5-ply furniture-grade Oak or Maple veneered plywood finished on both sides to match shelving.

#### LAMINATE BACKS

Backs are constructed with 1/4" thick thermally-fused laminate panels.

#### WHITEBOARD BACKS

Whiteboards will be 1/32" thick and applied to oak, maple or laminate backs using heavy-duty glue.

#### MAGNETIC WHITEBOARD BACKS

Magnetic Whiteboards will be 1/32" thick and applied to oak, maple or laminate backs using heavy-duty glue.

#### TACKBOARD BACKS

Tackboards will be 1/4" thick and applied to oak, maple or laminate backs using heavy-duty glue.

#### **UPHOLSTERED BACKS**

Upholstered appliques will be 1/2" thick and applied to oak, maple or laminate backs using velcro strips. Quantity of velcro strips will be determined by size of upholstered back. Upholstered backs will be constructed using a 3/8" thick wood panel with a 1/4" thick foam piece covered with choice of Brodart fabrics.

Catalog No.         Description         H x W x D         (lbs.)           36"H Shelving           GEOLSO36S         Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         9           GEOLSM36S         Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         9           GEOLSL36S         Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         9           GEOLSW036S         Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWM36S         Whiteboard/Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWL36S         Whiteboard/Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSM036S         Magnetic Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         13           GEOLSMM36S         Magnetic Whiteboard/Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         13	\$129 136 96 274 274 274 365 365 365 293 293	Linear Single-Faced Shelving
GEOLSM36S         Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         9           GEOLSL36S         Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         9           GEOLSW036S         Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWM36S         Whiteboard/Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWL36S         Whiteboard/Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSM036S         Magnetic Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         13	136 96 274 274 274 365 365 365 293 293	
GEOLSL36S         Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         9           GEOLSW036S         Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWM36S         Whiteboard/Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWL36S         Whiteboard/Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSM036S         Magnetic Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         13	136 96 274 274 274 365 365 365 293 293	
GEOLSW036S         Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWM36S         Whiteboard/Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWL36S         Whiteboard/Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSM036S         Magnetic Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         13	274 274 274 365 365 365 293 293	
GEOLSWM36S         Whiteboard/Maple Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSWL36S         Whiteboard/Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSMO36S         Magnetic Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         13	274 274 365 365 365 293 293	
GEOLSWL36S         Whiteboard/Laminate Back Panel         31-5/8" x 35-5/8" x 1/4"         12.5           GEOLSMO36S         Magnetic Whiteboard/Oak Back Panel         31-5/8" x 35-5/8" x 1/4"         13	274 365 365 365 293 293	
GEOLSMO36S Magnetic Whiteboard/Oak Back Panel 31-5/8" x 35-5/8" x 1/4" 13	365 365 365 293 293	
<b>y</b>	365 365 293 293	
GEOLSMM36S Magnetic Whiteboard/Maple Back Panel 31-5/8" x 35-5/8" x 1/4" 13	365 293 293	
	293 293	
GEOLSML36S Magnetic Whiteboard/Laminate Back Panel 31-5/8" x 35-5/8" x 1/4" 13	293	
<b>GEOLSTO36S</b> Tackboard/Oak Back Panel 31-5/8" x 35-5/8" x 1/2" 16		
<b>GEOLSTM36S</b> Tackboard/Maple Back Panel 31-5/8" x 35-5/8" x 1/2" 16	202	
GEOLSTL36S Tackboard/Laminate Back Panel 31-5/8" x 35-5/8" x 1/2" 16	293	
<b>GEOLSU036S</b> Upholstered/Oak Back Panel 31-5/8" x 35-5/8" x 3/4" 18	548	
GEOLSUM36S Upholstered/Maple Back Panel 31-5/8" x 35-5/8" x 3/4" 18	548	
GEOLSUL36S Upholstered/Laminate Back Panel 31-5/8" x 35-5/8" x 3/4" 18	548	
42"H Shelving		
<b>GEOLSO42S</b> Oak Back Panel 37-5/8" x 35-5/8" x 1/4" 12	\$139	
<b>GEOLSM42S</b> Maple Back Panel 37-5/8" x 35-5/8" x 1/4" 12	147	
GEOLSL42S Laminate Back Panel 37-5/8" x 35-5/8" x 1/4" 12	106	
<b>GEOLSWO42S</b> Whiteboard/Oak Back Panel 37-5/8" x 35-5/8" x 1/4" 16	326	
<b>GEOLSWM42S</b> Whiteboard/Maple Back Panel 37-5/8" x 35-5/8" x 1/4" 16	326	
GEOLSWL42S Whiteboard/Laminate Back Panel 37-5/8" x 35-5/8" x 1/4" 16	326	
<b>GEOLSMO42S</b> Magnetic Whiteboard/Oak Back Panel 37-5/8" x 35-5/8" x 1/4" 16.5	435	
GEOLSMM42S Magnetic Whiteboard/Maple Back Panel 37-5/8" x 35-5/8" x 1/4" 16.5	435	
GEOLSML42S Magnetic Whiteboard/Laminate Back Panel 37-5/8" x 35-5/8" x 1/4" 16.5	435	
<b>GEOLSTO42S</b> Tackboard/Oak Back Panel 37-5/8" x 35-5/8" x 1/2" 20	349	
<b>GEOLSTM42S</b> Tackboard/Maple Back Panel 37-5/8" x 35-5/8" x 1/2" 20	349	
GEOLSTL42S Tackboard/Laminate Back Panel 37-5/8" x 35-5/8" x 1/2" 20	349	
<b>GEOLSUO42S</b> Upholstered/Oak Back Panel 37-5/8" x 35-5/8" x 3/4" 23	652	
GEOLSUM42S Upholstered/Maple Back Panel 37-5/8" x 35-5/8" x 3/4" 23	652	
GEOLSUL42S Upholstered/Laminate Back Panel 37-5/8" x 35-5/8" x 3/4" 23	652	



	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Linear Single-Faced Shelving	48"H Shelving	•			
	GEOLSO48S	Oak Back Panel	43-5/8" x 35-5/8" x 1/4"	15	\$152
	GEOLSM48S	Maple Back Panel	43-5/8" x 35-5/8" x 1/4"	15	159
	GEOLSL48S	Laminate Back Panel	43-5/8" x 35-5/8" x 1/4"	15	115
	GEOLSW048S	Whiteboard/Oak Back Panel	43-5/8" x 35-5/8" x 1/4"	19.5	356
	GEOLSWM48S	Whiteboard/Maple Back Panel	43-5/8" x 35-5/8" x 1/4"	19.5	356
	GEOLSWL48S	Whiteboard/Laminate Back Panel	43-5/8" x 35-5/8" x 1/4"	19.5	356
	GEOLSMO48S	Magnetic Whiteboard/Oak Back Panel	43-5/8" x 35-5/8" x 1/4"	20	475
	GEOLSMM48S	Magnetic Whiteboard/Maple Back Panel	43-5/8" x 35-5/8" x 1/4"	20	475
	GEOLSML48S	Magnetic Whiteboard/Laminate Back Panel	43-5/8" x 35-5/8" x 1/4"	20	475
	GEOLSTO48S	Tackboard/Oak Back Panel	43-5/8" x 35-5/8" x 1/2"	24	381
	GEOLSTM48S	Tackboard/Maple Back Panel	43-5/8" x 35-5/8" x 1/2"	24	381
	GEOLSTL48S	Tackboard/Laminate Back Panel	43-5/8" x 35-5/8" x 1/2"	24	381
	GEOLSU048S	Upholstered/Oak Back Panel	43-5/8" x 35-5/8" x 3/4"	28	712
	GEOLSUM48S	Upholstered/Maple Back Panel	43-5/8" x 35-5/8" x 3/4"	28	712
	GEOLSUL48S	Upholstered/Laminate Back Panel	43-5/8" x 35-5/8" x 3/4"	28	712
	<u>60-1/2"H Shelvi</u>	na			
			E/ 1/011 :: 2E E/011 :: 1/411	10	¢ 207
	GEOLSO60S	Oak Back Panel	56-1/8" x 35-5/8" x 1/4"	18	\$ 206
	GEOLSM60S	Maple Back Panel	56-1/8" x 35-5/8" x 1/4"	18	216
	GEOLSL60S	Laminate Back Panel	56-1/8" x 35-5/8" x 1/4"	18	156
	GEOLSW060S	Whiteboard / Manla Back Panel	56-1/8" x 35-5/8" x 1/4"	23.5	536
	GEOLSWM60S	Whiteboard/Maple Back Panel	56-1/8" x 35-5/8" x 1/4"	23.5	536
	GEOLSWL60S	Whiteboard/Laminate Back Panel	56-1/8" x 35-5/8" x 1/4"	23.5	536
	GEOLSM060S	Magnetic Whiteboard / Mayla Back Panel	56-1/8" x 35-5/8" x 1/4"	24	714
	GEOLSMM60S	Magnetic Whiteboard/Maple Back Panel	56-1/8" x 35-5/8" x 1/4"	24	714
	GEOLSML60S	Magnetic Whiteboard/Laminate Back Panel	56-1/8" x 35-5/8" x 1/4"	24	714
	GEOLSTO60S	Tackboard / Marla Back Panel	56-1/8" x 35-5/8" x 1/2"	29	574
	GEOLSTM60S	Tackboard/Maple Back Panel	56-1/8" x 35-5/8" x 1/2"	29	574
	GEOLSTL60S	Tackboard/Laminate Back Panel	56-1/8" x 35-5/8" x 1/2"	29	574
	GEOLSUNGOS	Upholstered/Oak Back Panel	56-1/8" x 35-5/8" x 3/4"	36	1,072
	GEOLSUM60S GEOLSUL60S	Upholstered/Maple Back Panel Upholstered/Laminate Back Panel	56-1/8" x 35-5/8" x 3/4" 56-1/8" x 35-5/8" x 3/4"	36 36	1,072 1,072
	72"H Shelving				
	_	0.1.01.01	(	00	A 000
	GEOLSO72S	Oak Back Panel	66-1/8" x 35-5/8" x 1/4"	20	\$ 223
	GEOLSM72S	Maple Back Panel	66-1/8" x 35-5/8" x 1/4"	20	234
	GEOLSL72S	Laminate Back Panel	66-1/8" x 35-5/8" x 1/4"	20	168
	GEOLSW072S	Whiteboard/Oak Back Panel	66-1/8" x 35-5/8" x 1/4"	26.5	556
	GEOLSWM72S	Whiteboard/Maple Back Panel	66-1/8" x 35-5/8" x 1/4"	26.5	556
	GEOLSWL72S	Whiteboard/Laminate Back Panel	66-1/8" x 35-5/8" x 1/4"	26.5	556
	GEOLSM072S	Magnetic Whiteboard / Manla Back Panel	66-1/8" x 35-5/8" x 1/4"	27	741
	GEOLSMM72S	Magnetic Whiteboard/Maple Back Panel	66-1/8" x 35-5/8" x 1/4"	27	741
	GEOLSML72S	Magnetic Whiteboard/Laminate Back Panel	66-1/8" x 35-5/8" x 1/4"	27	741
	GEOLST072S	Tackboard/Oak Back Panel	66-1/8" x 35-5/8" x 1/2"	34	595
	GEOLSTM72S	Tackboard/Maple Back Panel	66-1/8" x 35-5/8" x 1/2"	34	595
	GEOLSTL72S	Tackboard/Laminate Back Panel	66-1/8" x 35-5/8" x 1/2"	34	595
	GEOLSU072S	Upholstered/Oak Back Panel	66-1/8" x 35-5/8" x 3/4"	42	1,112
	GEOLSUM72S	Upholstered/Maple Back Panel	66-1/8" x 35-5/8" x 3/4"	42	1,112
	GEOLSUL72S	Upholstered/Laminate Back Panel	66-1/8" x 35-5/8" x 3/4"	42	1,112

Arc Convex Single-Faced Shelving 9 \$129 9 136 9 96 12.5 274 12.5 274 16 293 16 293 16 293 18 548 18	9 9 12.5 12.5 12.5	31-5/8" x 36-15/16" x 1/4" 31-5/8" x 36-15/16" x 1/4"		
9 \$129 9 136 9 96 12.5 274 12.5 274 12.5 274 16 293 16 293 16 293 18 548 18 548 18 548 18 548 18 548 18 548 18 548 18 548 18 548 20 349 20 349 20 349 23 652 23 652	9 9 12.5 12.5 12.5			36"H Shelving
9 136 9 96 12.5 274 12.5 274 16 293 16 293 16 293 18 548 18 548 18 548 18 548 18 548 10 293 11 2 147 12 106 16 326 16 326 16 326 16 326 10 326 10 326 11 326 12 349 12 349 12 349 12 349 12 349 12 349 12 349 13 349 14 32 349 15 32 349 16 326 17 32 349 18	9 9 12.5 12.5 12.5		Oak Back Panel	GEOAXSO36S
9 96 12.5 274 12.5 274 12.5 274 16 293 16 293 16 293 18 548 18 548 18 548 18 548 18 548 18 548 18 548 18 548 106 1106 1106 1106 1106 1106 1106 1106	9 12.5 12.5 12.5		Maple Back Panel	GEOAXSM36S
12.5	12.5 12.5 12.5	31-5/8" x 36-15/16" x 1/4"	Laminate Back Panel	GEOAXSL36S
12.5	12.5 12.5	31-5/8" x 36-15/16" x 1/4"	Whiteboard/Oak Back Panel	GEOAXSW036S
12.5 274 16 293 16 293 16 293 18 548 18 548 18 548 18 548 18 548  12 \$139 12 147 12 106 16 326 16 326 16 326 20 349 20 349 20 349 20 349 23 652 23 652	12.5	31-5/8" x 36-15/16" x 1/4"	Whiteboard/Maple Back Panel	GEOAXSWM36S
16       293         16       293         18       548         18       548         18       548         12       \$139         12       147         12       106         16       326         16       326         20       349         20       349         20       349         23       652         23       652		31-5/8" x 36-15/16" x 1/4"	Whiteboard/Laminate Back Panel	GEOAXSWL36S
16       293         16       293         18       548         18       548         18       548         12       \$139         12       \$147         12       \$106         16       \$326         16       \$326         20       \$49         20       \$49         20       \$49         23       \$652         23       \$652		31-5/8" x 36-15/16" x 1/2"	Tackboard/Oak Back Panel	GEOAXSWESOS GEOAXSTO36S
16       293         18       548         18       548         18       548             12       \$139         12       147         12       106         16       326         16       326         20       349         20       349         20       349         23       652         23       652		31-5/8" x 36-15/16" x 1/2"	Tackboard/Maple Back Panel	GEOAXSTM36S
18       548         18       548         18       548             12       \$139         12       147         12       106         16       326         16       326         20       349         20       349         20       349         23       652         23       652		31-5/8" x 36-15/16" x 1/2"	Tackboard/Laminate Back Panel	GEOAXSTL36S
18 548 18 548 12 \$139 12 147 12 106 16 326 16 326 16 326 20 349 20 349 20 349 20 349 23 652 23 652		31-5/8" x 36-15/16" x 3/4"	Upholstered/Oak Back Panel	GEOAXSU036S
12 \$139 12 147 12 106 16 326 16 326 16 326 20 349 20 349 20 349 23 652 23 652		31-5/8" x 36-15/16" x 3/4"	Upholstered/Maple Back Panel	GEOAXSUM36S
12 147 12 106 16 326 16 326 16 326 20 349 20 349 20 349 23 652 23 652		31-5/8" x 36-15/16" x 3/4"	Upholstered/Laminate Back Panel	GEOAXSUL36S
12 147 12 106 16 326 16 326 16 326 20 349 20 349 20 349 23 652 23 652				42"H Shelving
12 147 12 106 16 326 16 326 16 326 20 349 20 349 20 349 23 652 23 652	12	37-5/8" x 36-15/16" x 1/4"	Oak Back Panel	GEOAXSO42S
12 106 16 326 16 326 16 326 20 349 20 349 20 349 23 652 23 652		37-5/8" x 36-15/16" x 1/4"	Maple Back Panel	GEOAXSM42S
16 326 16 326 16 326 20 349 20 349 20 349 23 652 23 652		37-5/8" x 36-15/16" x 1/4"	Laminate Back Panel	GEOAXSL42S
16 326 16 326 20 349 20 349 20 349 23 652 23 652		37-5/8" x 36-15/16" x 1/4"	Whiteboard/Oak Back Panel	GEOAXSW042S
16 326 20 349 20 349 20 349 23 652 23 652		37-5/8" x 36-15/16" x 1/4"		GEOAXSWM42S
20 349 20 349 20 349 23 652 23 652		37-5/8" x 36-15/16" x 1/4"	Whiteboard/Maple Back Panel Whiteboard/Laminate Back Panel	GEOAXSWL42S
20 349 20 349 23 652 23 652			Tackboard/Oak Back Panel	GEOAXSTO42S
20 <b>349</b> 23 <b>652</b> 23 <b>652</b>		37-5/8" x 36-15/16" x 1/2"		GEOAXSTM42S
23 <b>652</b> 23 <b>652</b>		37-5/8" x 36-15/16" x 1/2" 37-5/8" x 36-15/16" x 1/2"	Tackboard/Maple Back Panel Tackboard/Laminate Back Panel	GEOAXSTL42S
23 <b>652</b>				
		37-5/8" x 36-15/16" x 3/4"	Upholstered/Oak Back Panel	GEOAXSU042S
		37-5/8" x 36-15/16" x 3/4" 37-5/8" x 36-15/16" x 3/4"	Upholstered/Maple Back Panel Upholstered/Laminate Back Panel	GEOAXSUM42S GEOAXSUL42S
				48"H Shelving
15 <b>\$152</b>	15	43-5/8" x 36-15/16" x 1/4"	Oak Back Panel	GEOAXSO48S
15 <b>159</b>		43-5/8" x 36-15/16" x 1/4"	Maple Back Panel	GEOAXSM48S
15 <b>115</b>		43-5/8" x 36-15/16" x 1/4"	Laminate Back Panel	GEOAXSL48S
19.5 356		43-5/8" x 36-15/16" x 1/4"	Whiteboard/Oak Back Panel	GEOAXSW048S
19.5 356		43-5/8" x 36-15/16" x 1/4"	Whiteboard/Maple Back Panel	GEOAXSWM48S
19.5 <b>356</b>		43-5/8" x 36-15/16" x 1/4"	Whiteboard/Laminate Back Panel	GEOAXSWL48S
24 381		43-5/8" x 36-15/16" x 1/2"	Tackboard/Oak Back Panel	GEOAXSTO48S
24 381		43-5/8" x 36-15/16" x 1/2"	Tackboard/Maple Back Panel	GEOAXSTM48S
24 381		43-5/8" x 36-15/16" x 1/2"	Tackboard/Laminate Back Panel	GEOAXSTL48S
28 712		43-5/8" x 36-15/16" x 3/4"	Upholstered/Oak Back Panel	GEOAXSUO48S
28 712		43-5/8" x 36-15/16" x 3/4"	Upholstered/Maple Back Panel	GEOAXSUM48S
28 712	20	43-5/8" x 36-15/16" x 3/4"	Upholstered/Laminate Back Panel	GEOAXSUL48S

# Geometrix

	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Arc Convex	60-1/2"H Shelvi	ng			
Single-Faced Shelving	GEOAXSO60S	Oak Back Panel	56-1/8" x 36-15/16" x 1/4"	18	\$ 206
	GEOAXSM60S	Maple Back Panel	56-1/8" x 36-15/16" x 1/4"	18	216
	GEOAXSL60S	Laminate Back Panel	56-1/8" x 36-15/16" x 1/4"	18	156
	GEOAXSW060S	Whiteboard/Oak Back Panel	56-1/8" x 36-15/16" x 1/4"	23.5	536
	GEOAXSWM60S	Whiteboard/Maple Back Panel	56-1/8" x 36-15/16" x 1/4"	23.5	536
	GEOAXSWL60S	Whiteboard/Laminate Back Panel	56-1/8" x 36-15/16" x 1/4"	23.5	536
	GEOAXSTO60S	Tackboard/Oak Back Panel	56-1/8" x 36-15/16" x 1/2"	29	574
	GEOAXSTM60S	Tackboard/Maple Back Panel	56-1/8" x 36-15/16" x 1/2"	29	574
	GEOAXSTL60S	Tackboard/Laminate Back Panel	56-1/8" x 36-15/16" x 1/2"	29	574
	GEOAXSU060S	Upholstered/Oak Back Panel	56-1/8" x 36-15/16" x 3/4"	36	1,072
	GEOAXSUM60S	Upholstered/Maple Back Panel	56-1/8" x 36-15/16" x 3/4"	36	1,072
	GEOAXSUL60S	Upholstered/Laminate Back Panel	56-1/8" x 36-15/16" x 3/4"	36	1,072
	72"H Shelving				
	GEOAXSO72S	Oak Back Panel	66-1/8" x 36-15/16" x 1/4"	20	\$ 223
	GEOAXSM72S	Maple Back Panel	66-1/8" x 36-15/16" x 1/4"	20	234
	GEOAXSL72S	Laminate Back Panel	66-1/8" x 36-15/16" x 1/4"	20	168
	GEOAXSW072S	Whiteboard/Oak Back Panel	66-1/8" x 36-15/16" x 1/4"	26.5	556
	GEOAXSWM72S	Whiteboard/Maple Back Panel	66-1/8" x 36-15/16" x 1/4"	26.5	556
	GEOAXSWL72S	Whiteboard/Laminate Back Panel	66-1/8" x 36-15/16" x 1/4"	26.5	556
	GEOAXSTO72S	Tackboard/Oak Back Panel	66-1/8" x 36-15/16" x 1/2"	34	595
	GEOAXSTM72S	Tackboard/Maple Back Panel	66-1/8" x 36-15/16" x 1/2"	34	595
	GEOAXSTL72S	Tackboard/Laminate Back Panel	66-1/8" x 36-15/16" x 1/2"	34	595
	GEOAXSU072S	Upholstered/Oak Back Panel	66-1/8" x 36-15/16" x 3/4"	42	1,112
	GEOAXSUM72S	Upholstered/Maple Back Panel	66-1/8" x 36-15/16" x 3/4"	42	1,112
	GEOAXSUL72S	Upholstered/Laminate Back Panel	66-1/8" x 36-15/16" x 3/4"	42	1,112

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
36"H Shelving					Arc Concave Single-Faced
GEOAV1S036S	Oak Back Panel	31-5/8" x 42-5/8" x 1/4"	10.5	\$129	Shelving Type 1 (44"W)
GEOAV1SM36S	Maple Back Panel	31-5/8" x 42-5/8" x 1/4"	10.5	136	
GEOAV1SN36S	Laminate Back Panel	31-5/8" x 42-5/8" x 1/4"	10.5	96	
GEOAV1SE303 GEOAV1SW036S	Whiteboard/Oak Back Panel	31-5/8" x 42-5/8" x 1/4"	10.5	299	
GEOAV1SWM36S	Whiteboard/Maple Back Panel	31-5/8" x 42-5/8" x 1/4"	14	299	
GEOAV1SWL36S	Whiteboard/Laminate Back Panel	31-5/8" x 42-5/8" x 1/4"	14	299	
GEOAV1SW2303	Tackboard/Oak Back Panel	31-5/8" x 42-5/8" x 1/2"	19	320	
GEOAV1STM36S	Tackboard/Maple Back Panel	31-5/8" x 42-5/8" x 1/2"	19	320	
GEOAV1STL36S	Tackboard/Laminate Back Panel	31-5/8" x 42-5/8" x 1/2"	19	320	
GEOAV1S1L303 GEOAV1SU036S	Upholstered/Oak Back Panel	31-5/8" x 42-5/8" x 3/4"	20	593	
GEOAV1SUM36S	Upholstered/Maple Back Panel	31-5/8" x 42-5/8" x 3/4"	20	593	
GEOAV1SUL36S	Upholstered/Laminate Back Panel	31-5/8" x 42-5/8" x 3/4"	20	593	
GEUAV ISUL303	opnoistered/Laminate Back Paner	31-5/8 X42-5/8 X3/4	20	593	
42"H Shelving					
GEOAV1SO42S	Oak Back Panel	37-5/8" x 42-5/8" x 1/4"	13.5	\$139	
GEOAV1SM42S	Maple Back Panel	37-5/8" x 42-5/8" x 1/4"	13.5	147	
GEOAV1SL42S	Laminate Back Panel	37-5/8" x 42-5/8" x 1/4"	13.5	106	
GEOAV1SW042S	Whiteboard/Oak Back Panel	37-5/8" x 42-5/8" x 1/4"	17.5	351	
GEOAV1SWM42S	Whiteboard/Maple Back Panel	37-5/8" x 42-5/8" x 1/4"	17.5	351	
GEOAV1SWL42S	Whiteboard/Laminate Back Panel	37-5/8" x 42-5/8" x 1/4"	17.5	351	
GEOAV1STO42S	Tackboard/Oak Back Panel	37-5/8" x 42-5/8" x 1/2"	23	375	
GEOAV1STM42S	Tackboard/Maple Back Panel	37-5/8" x 42-5/8" x 1/2"	23	375	
GEOAV1STL42S	Tackboard/Laminate Back Panel	37-5/8" x 42-5/8" x 1/2"	23	375	
GEOAV1SU042S	Upholstered/Oak Back Panel	37-5/8" x 42-5/8" x 3/4"	25	697	
GEOAV1SUM42S	Upholstered/Maple Back Panel	37-5/8" x 42-5/8" x 3/4"	25	697	
GEOAV1SUL42S	Upholstered/Laminate Back Panel	37-5/8" x 42-5/8" x 3/4"	25	697	
48"H Shelving					
GEOAV1SO48S	Oak Back Panel	43-5/8" x 42-5/8" x 1/4"	16.5	\$152	
GEOAV1SM48S	Maple Back Panel	43-5/8" x 42-5/8" x 1/4"	16.5	159	
GEOAV1SL48S	Laminate Back Panel	43-5/8" x 42-5/8" x 1/4"	16.5	115	
GEOAV1SW048S	Whiteboard/Oak Back Panel	43-5/8" x 42-5/8" x 1/4"	21	381	
			21	381	
GEOAV1SWM48S GEOAV1SWL48S	Whiteboard/Maple Back Panel Whiteboard/Laminate Back Panel	43-5/8" x 42-5/8" x 1/4" 43-5/8" x 42-5/8" x 1/4"	21 21	381 381	
GEOAV1SWL48S	Tackboard/Oak Back Panel		21 27	381 407	
		43-5/8" x 42-5/8" x 1/2"			
GEOAV1STM48S	Tackboard/Maple Back Panel	43-5/8" x 42-5/8" x 1/2"	27	407	
GEOAV1STL48S	Tackboard/Laminate Back Panel	43-5/8" x 42-5/8" x 1/2"	27	407	
GEOAV1SU048S	Upholstered/Oak Back Panel	43-5/8" x 42-5/8" x 3/4"	30	757	
GEOAV1SUM48S	Upholstered/Maple Back Panel	43-5/8" x 42-5/8" x 3/4"	30	757	
GEOAV1SUL48S	Upholstered/Laminate Back Panel	43-5/8" x 42-5/8" x 3/4"	30	757	

	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Arc Concave Single-Faced	60-1/2"H Shelvin	· · · · · · · · · · · · · · · · · · ·		(iiii)	
Shelving Type 1 (44"W)	GEOAV1SO60S	Oak Back Panel	56-1/8" x 42-5/8" x 1/4"	19.5	\$ 206
	GEOAV1SM60S	Maple Back Panel	56-1/8" x 42-5/8" x 1/4"	19.5	216
	GEOAV1SL60S	Laminate Back Panel	56-1/8" x 42-5/8" x 1/4"	19.5	156
	GEOAV1SW060S	Whiteboard/Oak Back Panel	56-1/8" x 42-5/8" x 1/4"	25	561
	GEOAV1SWM60S	Whiteboard/Maple Back Panel	56-1/8" x 42-5/8" x 1/4"	25	561
	GEOAV1SWL60S	Whiteboard/Laminate Back Panel	56-1/8" x 42-5/8" x 1/4"	25	561
	GEOAV1STO60S	Tackboard/Oak Back Panel	56-1/8" x 42-5/8" x 1/2"	32	600
	GEOAV1STM60S	Tackboard/Maple Back Panel	56-1/8" x 42-5/8" x 1/2"	32	600
	GEOAV1STL60S	Tackboard/Laminate Back Panel	56-1/8" x 42-5/8" x 1/2"	32	600
	GEOAV1SU060S	Upholstered/Oak Back Panel	56-1/8" x 42-5/8" x 3/4"	38	1,117
	GEOAV1SUM60S	Upholstered/Maple Back Panel	56-1/8" x 42-5/8" x 3/4"	38	1,117
	GEOAV1SUL60S	Upholstered/Laminate Back Panel	56-1/8" x 42-5/8" x 3/4"	38	1,117
	72"H Shelving				
	GEOAV1SO72S	Oak Back Panel	66-1/8" x 42-5/8" x 1/4"	21.5	\$ 223
	GEOAV1SM72S	Maple Back Panel	66-1/8" x 42-5/8" x 1/4"	21.5	234
	GEOAV1SL72S	Laminate Back Panel	66-1/8" x 42-5/8" x 1/4"	21.5	168
	GEOAV1SW072S	Whiteboard/Oak Back Panel	66-1/8" x 42-5/8" x 1/4"	28	581
	GEOAV1SWM72S	Whiteboard/Maple Back Panel	66-1/8" x 42-5/8" x 1/4"	28	581
	GEOAV1SWL72S	Whiteboard/Laminate Back Panel	66-1/8" x 42-5/8" x 1/4"	28	581
	GEOAV1ST072S	Tackboard/Oak Back Panel	66-1/8" x 42-5/8" x 1/2"	37	621
	GEOAV1STM72S	Tackboard/Maple Back Panel	66-1/8" x 42-5/8" x 1/2"	37	621
	GEOAV1STL72S	Tackboard/Laminate Back Panel	66-1/8" x 42-5/8" x 1/2"	37	621
	GEOAV1SU072S	Upholstered/Oak Back Panel	66-1/8" x 42-5/8" x 3/4"	44	1,157
	GEOAV1SUM72S	Upholstered/Maple Back Panel	66-1/8" x 42-5/8" x 3/4"	44	1,157
	GEOAV1SUL72S	Upholstered/Laminate Back Panel	66-1/8" x 42-5/8" x 3/4"	44	1,157

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
36"H Shelving					Arc Concave Single-Faced
GEOAV2SO36S	Oak Back Panel	31-5/8" x 36-23/32" x 1/4"	9.5	\$129	Shelving Type 2 (37"W)
GEOAV2SM36S	Maple Back Panel	31-5/8" x 36-23/32" x 1/4"	9.5	136	
GEOAV2SIVISOS	Laminate Back Panel	31-5/8" x 36-23/32" x 1/4"	9.5	96	
GEOAV2SW036S	Whiteboard/Oak Back Panel	31-5/8" x 36-23/32" x 1/4"	13	294	
GEOAV2SWM36S	Whiteboard/Maple Back Panel	31-5/8" x 36-23/32" x 1/4"	13	294	
GEOAV2SWL36S	Whiteboard/Laminate Back Panel	31-5/8" x 36-23/32" x 1/4"	13	294	
GEOAV2STO36S	Tackboard/Oak Back Panel	31-5/8" x 36-23/32" x 1/4"	18	315	
GEOAV2STM36S	Tackboard/Maple Back Panel	31-5/8" x 36-23/32" x 1/2"	18	315	
GEOAV2STL36S	Tackboard/Laminate Back Panel	31-5/8" x 36-23/32" x 1/2"	18	315	
GEOAV2SILSOS GEOAV2SUO36S	Upholstered/Oak Back Panel	31-5/8" x 36-23/32" x 3/4"	19	588	
GEOAV2SUM36S	Upholstered/Maple Back Panel	31-5/8" x 36-23/32" x 3/4"	19	588	
GEOAV2SUL36S	Upholstered/Laminate Back Panel	31-5/8" x 36-23/32" x 3/4"	19	588	
42"H Shelving					
GEOAV2SO42S	Oak Back Panel	37-5/8" x 36-23/32" x 1/4"	12.5	\$139	
GEOAV2SM42S	Maple Back Panel	37-5/8" x 36-23/32" x 1/4"	12.5	147	
GEOAV2SIVI42S	Laminate Back Panel	37-5/8" x 36-23/32" x 1/4"	12.5	106	
GEOAV2SL42S	Whiteboard/Oak Back Panel	37-5/8" x 36-23/32" x 1/4"	16.5	346	
GEOAV2SWM42S	Whiteboard/Maple Back Panel	37-5/8" x 36-23/32" x 1/4"	16.5	346 346	
GEOAV2SWL42S	Whiteboard/Laminate Back Panel	37-5/8" x 36-23/32" x 1/4"	16.5	346	
GEOAV2SVL42S	Tackboard/Oak Back Panel	37-5/8" x 36-23/32" x 1/2"	22	370	
GEOAV2STM42S		37-5/8" x 36-23/32" x 1/2"	22	370 370	
GEOAV2STN42S	Tackboard/Maple Back Panel Tackboard/Laminate Back Panel	37-5/8" x 36-23/32" x 1/2"	22	370 370	
GEOAV2SU042S	Upholstered/Oak Back Panel	37-5/8" x 36-23/32" x 3/4"	24	692	
GEOAV2SUM42S GEOAV2SUL42S	Upholstered/Maple Back Panel Upholstered/Laminate Back Panel	37-5/8" x 36-23/32" x 3/4" 37-5/8" x 36-23/32" x 3/4"	24 24	692 692	
48"H Shelving					
GEOAV2SO48S	Oak Back Panel	43-5/8" x 36-23/32" x 1/4"	15.5	\$152	
GEOAV2SM48S	Maple Back Panel	43-5/8" x 36-23/32" x 1/4"	15.5	159	
GEOAV2SL48S	Laminate Back Panel	43-5/8" x 36-23/32" x 1/4"	15.5	115	
GEOAV2SW048S	Whiteboard/Oak Back Panel	43-5/8" x 36-23/32" x 1/4"	20	376	
GEOAV2SWM48S	Whiteboard/Maple Back Panel	43-5/8" x 36-23/32" x 1/4"	20	376	
GEOAV2SWL48S	Whiteboard/Laminate Back Panel	43-5/8" x 36-23/32" x 1/4"	20	376	
GEOAV2SWL48S	Tackboard/Oak Back Panel	43-5/8" x 36-23/32" x 1/2"	26	402	
GEOAV2STM48S	Tackboard/Maple Back Panel	43-5/8" x 36-23/32" x 1/2"	26	402	
GEOAV2STL48S	Tackboard/Laminate Back Panel	43-5/8" x 36-23/32" x 1/2"	26	402	
GEOAV2SU048S	Upholstered/Oak Back Panel	43-5/8" x 36-23/32" x 3/4"	29	752	
GEOAV2SUM48S	Upholstered/Maple Back Panel	43-5/8" x 36-23/32" x 3/4"	29	752 752	
GEOAV2SUL48S	Upholstered/Laminate Back Panel	43-5/8" x 36-23/32" x 3/4"	29	752 752	
GLUAVZJUL403	ophoistereu/ Laminate Dack Panel	43-3/0 830-23/32 83/4	27	132	

	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Arc Concave Single-Faced	60-1/2"H Shelvir	ng			
Shelving Type 2 (37"W)	GEOAV2SO60S	Oak Back Panel	56-5/8" x 36-23/32" x 1/4"	18.5	\$ 206
	GEOAV2SM60S	Maple Back Panel	56-5/8" x 36-23/32" x 1/4"	18.5	216
	GEOAV2SL60S	Laminate Back Panel	56-5/8" x 36-23/32" x 1/4"	18.5	156
	GEOAV2SW060S	Whiteboard/Oak Back Panel	56-5/8" x 36-23/32" x 1/4"	24	556
	GEOAV2SWM60S	Whiteboard/Maple Back Panel	56-5/8" x 36-23/32" x 1/4"	24	556
	GEOAV2SWL60S	Whiteboard/Laminate Back Panel	56-5/8" x 36-23/32" x 1/4"	24	556
	GEOAV2STO60S	Tackboard/Oak Back Panel	56-5/8" x 36-23/32" x 1/2"	31	595
	GEOAV2STM60S	Tackboard/Maple Back Panel	56-5/8" x 36-23/32" x 1/2"	31	595
	GEOAV2STL60S	Tackboard/Laminate Back Panel	56-5/8" x 36-23/32" x 1/2"	31	595
	GEOAV2SU060S	Upholstered/Oak Back Panel	56-5/8" x 36-23/32" x 3/4"	37	1,112
	GEOAV2SUM60S	Upholstered/Maple Back Panel	56-5/8" x 36-23/32" x 3/4"	37	1,112
	GEOAV2SUL60S	Upholstered/Laminate Back Panel	56-5/8" x 36-23/32" x 3/4"	37	1,112
	72"H Shelving				
	GEOAV2SO72S	Oak Back Panel	66-5/8" x 36-23/32" x 1/4"	20.5	\$ 223
	GEOAV2SM72S	Maple Back Panel	66-5/8" x 36-23/32" x 1/4"	20.5	234
	GEOAV2SL72S	Laminate Back Panel	66-5/8" x 36-23/32" x 1/4"	20.5	168
	GEOAV2SW072S	Whiteboard/Oak Back Panel	66-5/8" x 36-23/32" x 1/4"	27	576
	GEOAV2SWM72S	Whiteboard/Maple Back Panel	66-5/8" x 36-23/32" x 1/4"	27	576
	GEOAV2SWL72S	Whiteboard/Laminate Back Panel	66-5/8" x 36-23/32" x 1/4"	27	576
	GEOAV2ST072S	Tackboard/Oak Back Panel	66-5/8" x 36-23/32" x 1/2"	36	616
	GEOAV2STM72S	Tackboard/Maple Back Panel	66-5/8" x 36-23/32" x 1/2"	36	616
	GEOAV2STL72S	Tackboard/Laminate Back Panel	66-5/8" x 36-23/32" x 1/2"	36	616
	GEOAV2SU072S	Upholstered/Oak Back Panel	66-5/8" x 36-23/32" x 3/4"	43	1,152
	GEOAV2SUM72S	Upholstered/Maple Back Panel	66-5/8" x 36-23/32" x 3/4"	43	1,152
	GEOAV2SUL72S	Upholstered/Laminate Back Panel	66-5/8" x 36-23/32" x 3/4"	43	1,152

	Price	Wt. (lbs.)	HxWxD	Description	Catalog No.
Mobile Arc Conve					36"H Shelving
Single-Faced Shelvir	\$129	9	31-3/16" x 36-17/32" x 1/4"	Oak Back Panel	GEOMAXSO36S
	136	9	31-3/16 x 36-17/32 x 1/4"	Maple Back Panel	GEOMAXSM36S
	96	9	31-3/16" x 36-17/32" x 1/4"	Laminate Back Panel	GEOMAXSL36S
	274	12.5	31-3/16" x 36-17/32" x 1/4"	Whiteboard/Oak Back Panel	GEOMAXSW036S
	274	12.5	31-3/16" x 36-17/32" x 1/4"	Whiteboard/Maple Back Panel	GEOMAXSWM36S
	274	12.5	31-3/16" x 36-17/32" x 1/4"	Whiteboard/Laminate Back Panel	GEOMAXSWL36S
	293	16	31-3/16" x 36-17/32" x 1/4"	Tackboard/Oak Back Panel	GEOMAXSTO36S
	293	16	31-3/16" x 36-17/32" x 1/2"	Tackboard/Maple Back Panel	GEOMAXSTM36S
	293	16	31-3/16" x 36-17/32" x 1/2"	Tackboard/Laminate Back Panel	GEOMAXSTU36S
	548	18	31-3/16 x 36-17/32 x 1/2 31-3/16" x 36-17/32" x 3/4"	Upholstered/Oak Back Panel	GEOMAXSU036S
	548	18	31-3/16" x 36-17/32" x 3/4"	Upholstered/Maple Back Panel	GEOMAXSUM36S
	548	18	31-3/16 x 36-17/32 x 3/4"	Upholstered/Laminate Back Panel	GEOMAXSUL36S
	040	10	31 3/10 ×30 17/32 ×3/4	ophostered/ Editinate back raner	OLOWING CLOUD
					42"H Shelving
	\$139	12	37-3/16" x 36-17/32" x 1/4"	Oak Back Panel	GEOMAXSO42S
	147	12	37-3/16" x 36-17/32" x 1/4"	Maple Back Panel	GEOMAXSM42S
	106	12	37-3/16" x 36-17/32" x 1/4"	Laminate Back Panel	GEOMAXSL42S
	326	16	37-3/16" x 36-17/32" x 1/4"	Whiteboard/Oak Back Panel	GEOMAXSW042S
	326	16	37-3/16" x 36-17/32" x 1/4"	Whiteboard/Maple Back Panel	GEOMAXSWM42S
	326	16	37-3/16" x 36-17/32" x 1/4"	Whiteboard/Laminate Back Panel	GEOMAXSWL42S
	349	20	37-3/16" x 36-17/32" x 1/2"	Tackboard/Oak Back Panel	GEOMAXSTO42S
	349	20	37-3/16" x 36-17/32" x 1/2"	Tackboard/Maple Back Panel	GEOMAXSTM42S
	349	20	37-3/16" x 36-17/32" x 1/2"	Tackboard/Laminate Back Panel	GEOMAXSTL42S
	652	23	37-3/16" x 36-17/32" x 3/4"	Upholstered/Oak Back Panel	GEOMAXSU042S
	652	23	37-3/16" x 36-17/32" x 3/4"	Upholstered/Maple Back Panel	GEOMAXSUM42S
	652	23	37-3/16" x 36-17/32" x 3/4"	Upholstered/Laminate Back Panel	GEOMAXSUL42S
					48"H Shelving
	\$152	15	43-3/16" x 36-17/32" x 1/4"	Oak Back Panel	GEOMAXSO48S
	159	15	43-3/16" x 36-17/32" x 1/4"	Maple Back Panel	GEOMAXSM48S
	115	15	43-3/16" x 36-17/32" x 1/4"	Laminate Back Panel	GEOMAXSL48S
	356	19.5	43-3/16" x 36-17/32" x 1/4"	Whiteboard/Oak Back Panel	GEOMAXSW048S
	356	19.5	43-3/16" x 36-17/32" x 1/4"	Whiteboard/Maple Back Panel	GEOMAXSWM48S
	356	19.5	43-3/16" x 36-17/32" x 1/4"	Whiteboard/Laminate Back Panel	GEOMAXSWL48S
	381	24	43-3/16" x 36-17/32" x 1/2"	Tackboard/Oak Back Panel	GEOMAXSTO48S
	381	24	43-3/16" x 36-17/32" x 1/2"	Tackboard/Maple Back Panel	GEOMAXSTM48S
	381	24	43-3/16" x 36-17/32" x 1/2"	Tackboard/Laminate Back Panel	GEOMAXSTL48S
	712	28	43-3/16" x 36-17/32" x 3/4"	Upholstered/Oak Back Panel	GEOMAXSUO48S
	712	28	43-3/16" x 36-17/32" x 3/4"	Upholstered/Maple Back Panel	GEOMAXSUM48S
	712	28	43-3/16" x 36-17/32" x 3/4"	Upholstered/Laminate Back Panel	GEOMAXSUL48S

Single-Faced Shelving   GEOMAVS036S   Mileboard/Oak Back Panel   31-3/16" x45-27/32" x1/4"   10.5   Mileboard/Oak Back Panel   31-3/16" x45-27/32" x1/4"   14   Mileboard/Oak Back Panel   31-3/16" x45-27/32" x1/4"   14   Mileboard/Oak Back Panel   31-3/16" x45-27/32" x1/4"   14   Mileboard/Oak Back Panel   31-3/16" x45-27/32" x1/2"   19   GEOMAVS036S   Upholstered/Oak Back Panel   31-3/16" x45-27/32" x1/2"   19   GEOMAVS036S   GEOMAVS036S   Upholstered/Oak Back Panel   31-3/16" x45-27/32" x1/2"   20   GEOMAVS036S   GEOMAVS036S   Upholstered/Naple Back Panel   31-3/16" x45-27/32" x1/4"   20   GEOMAVS036S   GEOMAVS036S   Upholstered/Naple Back Panel   31-3/16" x45-27/32" x1/4"   20   GEOMAVS0342S   GEOMAVS0342S   GEOMAVS042S   GEOMAVS0		Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
GEOMAVSO/36S Maple Back Panel 31-3/16" x 45-27/32" x 1/4" 10.5 GEOMAVSI/36S Laminate Back Panel 31-3/16" x 45-27/32" x 1/4" 10.5 GEOMAVSW/36S Whiteboard/Oak Back Panel 31-3/16" x 45-27/32" x 1/4" 14. Whiteboard/SW/36S Whiteboard/Oak Back Panel 31-3/16" x 45-27/32" x 1/4" 14. Whiteboard/Oak Back Panel 31-3/16" x 45-27/32" x 1/4" 14. GEOMAVSW/36S GEOMAVSW/36S Iackboard/Oak Back Panel 31-3/16" x 45-27/32" x 1/4" 14. GEOMAVSTM/36S Iackboard/Oak Back Panel 31-3/16" x 45-27/32" x 1/2" 19. GEOMAVSTM/36S Tackboard/Jaminate Back Panel 31-3/16" x 45-27/32" x 1/2" 19. GEOMAVSU/36S		36"H Shelving					
GEOMAVSM36S GEOMAVSM36S GEOMAVSM36S GEOMAVSW36S GEOMAVSWM36S GEOMAVSWM36S GEOMAVSW36S GEOM	Single-Faced Shelving	•	Oak Back Panel	31-3/16" x 45-27/32" x 1/4"	10.5	\$129	
GEOMAVSUA36S GEOMAVSW036S Whiteboard/Oak Back Panel GEOMAVSW136S Whiteboard/Ample Back Panel GEOMAVSW136S Whiteboard/Ample Back Panel GEOMAVSW136S GEOMAVSW136S GEOMAVSW136S GEOMAVSW136S GEOMAVSW136S GEOMAVSW136S GEOMAVSTM36S GEOMAVSTM36S GEOMAVSTM36S GEOMAVSTM36S GEOMAVSTM36S GEOMAVSTM36S GEOMAVSW136S GEOMAVSW142S GEOMAVSW25 GEOMAVSW142S GEO						136	
GEOMAVSWM36S GEOMAVSWM36S GEOMAVSWM36S GEOMAVSWM36S GEOMAVSWM36S GEOMAVST036S GEOMAVSU36S GEOMAVSU48S GEOMAVSU48S GEOMAVSU42S GEOMAVSU42S GEOMAVSU42S GEOMAVSWM42S GEOMAVSWM48S GEOMAVSWM48S GEOMAVSWA4S Able Back Panel 43.3/16" x45.27/32" x1/4" 16.5 GEOMAVSWA4S GEOMAVSWA4S Able Back Panel 43.3/16" x45.27/32" x1/4" 16.5 GEOMAVSWA4S GEOMAVSWA4S Able Back Panel 43.3/16" x45.27/32" x1/4" 16.5 GEOMAVSWA4S GEOMAVSWA4S Able Back Panel 43.3/16" x45.27/32" x1/4" 21 GEOMAVSWA4S GEOMAVSWA4S Able Back P			•			96	
GEOMAVSWM36S GEOMAVSWL36S GEOMAVSWL36S GEOMAVSWL36S GEOMAVSTM36S GEOMAVSU36S GEOM						294	
GEOMAVSTO36S GEOMAVSTO36S GEOMAVSTO36S GEOMAVSTO36S GEOMAVSTO36S GEOMAVSTO36S GEOMAVSTO36S GEOMAVSTIM36S GEOMAVSTIM36S GEOMAVSTO36S GEOMAVSTIA36S GEOMAVSTO36S GEOMAVSTO36S GEOMAVSU036S GEOMAVSU042S GEOMAVSU036S GEOMAVSU042S GEOMAVSU036S GEOMAVSU042S GEOMAVSU036S GEOMAVSU042S GEOMAVSU036S GEOMAVSU036S GEOMAVSU042S GEOMAVSU036S GEOMAVSU042S GEOMAVSU048S GEOMAVSU048S GEOMAVSU048S GEOMAVSU048S GEOMAVSU048S GEOMAVSU048S GEOMAVSU048S GEOMAVSU048S Whiteboard/Daiple Back Panel  43-3/16" x45-27/32" x1/4" 16.5 GEOMAVSU048S GEOMAVSU048S Whiteboard/Daiple Back Panel  43-3/16" x45-27/32" x1/4" 16.5 GEOMAVSU048S GEOMAVSU048S Whiteboard/Daiple Back Panel  43-3/16" x45-27/32" x1/4" 16.5 GEOMAVSU048S GEOMAVSU048S Hiteboard/Maple Back Panel  43-3/16" x45-27/32" x1/4" 16.5 GEOMAVSU048S GEOMAVSU048S Hiteboard/Maple Back Panel  43-3/16" x45-27/32" x1/4" 16.5 GEOMAVSU048S GEOMAVSU048S Hiteboard/Maple Back Panel  43-3/16" x45-27/32" x1/4" 16.5 GEOMAVSU048S GEOMAVSU048S Hitebo						294	
GEOMAVSTU36S   Tackboard/Oak Back Panel   31-3/16" x 45-27/32" x 1/2"   19   19   19   19   19   19   19   1			•			294	
GEOMAVSTIA36S   Tackboard/Ample Back Panel   31-3/16" x 45-27/32" x 1/2"   19   GEOMAVSU036S   Tackboard/Amrinate Back Panel   31-3/16" x 45-27/32" x 1/2"   19   GEOMAVSU036S   Upholstered/Ababack Panel   31-3/16" x 45-27/32" x 3/4"   20   20   20   20   20   20   20   2						315	
GEOMAVSUJO36S Upholstered/Dak Back Panel 31-3/16" x 45-27/32" x 1/2" 20 31-3/16" x 45-27/32" x 3/4" 20 GEOMAVSUJO36S Upholstered/Dak Back Panel 31-3/16" x 45-27/32" x 3/4" 20 31-3/16" x 45-27/32" x 3/4" 31.5 31-3/16" x 4						315	
GEOMAVSUM36S Upholstered/Oak Back Panel 31-3/16" x 45-27/32" x 3/4" 20 GEOMAVSUL36S Upholstered/Maple Back Panel 31-3/16" x 45-27/32" x 3/4" 20  ### Shelving GEOMAVSUL36S Upholstered/Laminate Back Panel 31-3/16" x 45-27/32" x 3/4" 20  ###################################						315	
GEOMAVSUIA36S GEOMAVSUIA36S Upholstered/Maple Back Panel J1-3/16" x 45-27/32" x 3/4"  20  A2"H Shelving GEOMAVSU42S GEOMAVSU42S GEOMAVSM42S GEOMAVSU42S GEOMAVSW42S GEOMAVSW48S GEOMAVSW48						588	
### Shelving  GEOMAVSUL36S  Upholstered/Laminate Back Panel  ### Shelving  GEOMAVSO42S  GEOMAVSO42S  GEOMAVSUM42S  GEOMAVSUM42S  GEOMAVSUM42S  GEOMAVSUM42S  GEOMAVSUM42S  GEOMAVSUM42S  Milteboard/Oak Back Panel  GEOMAVSUM42S  GEOMAVSWUM42S  Whiteboard/Oak Back Panel  GEOMAVSWUM42S  GEOMAVSWUM42S  Whiteboard/Oak Back Panel  GEOMAVSWUM42S  GEOMAVSWUM42S  GEOMAVSUM42S  Upholstered/Oak Back Panel  ###################################			•			588	
GEOMAVSU42S Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSM42S Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSW042S Whiteboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSW042S Whiteboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSWW142S Whiteboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSW142S Whiteboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVST042S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVST142S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU4S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU48S Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU48S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTU48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTU48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21			·			588	
GEOMAVSU42S Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSM42S Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSU42S Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSW042S Whiteboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSW042S Whiteboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSWL42S Whiteboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVST042S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVST142S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU42S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUA4S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU48S Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU48S Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSU48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Laminate Back Panel 43		42"H Shelvina					
GEOMAVSM42S GEOMAVSL42S GEOMAVSU42S GEOMAVSW042S Whiteboard/Oak Back Panel         37-3/16" x 45-27/32" x 1/4"         13.5           GEOMAVSW042S GEOMAVSW042S Whiteboard/Oak Back Panel         37-3/16" x 45-27/32" x 1/4"         17.5           GEOMAVSWM42S GEOMAVSW142S GEOMAVSTW42S GEOMAVSTO42S GEOMAVSTO42S GEOMAVSTA42S GEOMAVSTM42S GEOMAVSTM42S GEOMAVSTM42S GEOMAVSTM42S GEOMAVSTM42S GEOMAVSU42S GEOMAVSU42S GEOMAVSU42S Upholstered/Oak Back Panel         37-3/16" x 45-27/32" x 1/2"         23           GEOMAVSU42S GEOMAVSU42S GEOMAVSU42S GEOMAVSU42S Upholstered/Oak Back Panel         37-3/16" x 45-27/32" x 3/4"         25           GEOMAVSU42S GEOMAVSU42S GEOMAVSU42S Upholstered/Laminate Back Panel         37-3/16" x 45-27/32" x 3/4"         25           GEOMAVSU42S GEOMAVSU42S Upholstered/Laminate Back Panel         37-3/16" x 45-27/32" x 3/4"         25           48"H Shelving GEOMAVSW48S GEOMAVSW48S Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSU48S GEOMAVSW48S Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSW48S Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSW48S Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSW48S Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSW48S Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTM48S G		_	Oak Back Panal	27-2/16" v //5-27/22" v 1///"	12.5	\$139	
GEOMAVSL42S Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 13.5 GEOMAVSW042S Whiteboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSWM42S Whiteboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSWL42S Whiteboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTM42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTL42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSUM42S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUA2S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUA4S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUA4S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUA4S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWA4S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWA4S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWA4S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWA8S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWA8S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27						147	
GEOMAVSW042S Whiteboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSW142S Whiteboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSW142S Whiteboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTIM42S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTL42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 25 GEOMAVSUA8S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUA8S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUA8S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSW048S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSW148S Whiteboard/Dak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSW148S Whiteboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSW148S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTIN48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 27 GEOMAVSTIN48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTIN48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTIN48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27			•			106	
GEOMAVSWM42S Whiteboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTM42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTI42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL4S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL4S Upholstered/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUM48S Uhiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWUA8S Whiteboard/Cambe Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWUA8S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO4S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO4S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO4S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO4S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO4S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO4S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTU48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTU48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTL48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27						346	
GEOMAVSWL42S Whiteboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/4" 17.5 GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTM42S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSUL42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSUM42S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25  GEOMAVSUL42S Upholstered/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSUL48S Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWOM48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWUA8S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWUA8S Whiteboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWOM48S Tackboard/Caminate Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTUA8S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTUA8S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTUA8S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTUA8S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27						346	
GEOMAVSTO42S Tackboard/Oak Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTM42S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTL42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSL48S Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSW048S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSW048S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWL48S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSW148S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTL48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27			·			346	
GEOMAVSTM42S Tackboard/Maple Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSTL42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSU042S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25  ### Shelving GEOMAVSU42S Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSL48S Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSW048S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWW48S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWL48S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWL48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVST048S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTL48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27						370	
GEOMAVSTL42S Tackboard/Laminate Back Panel 37-3/16" x 45-27/32" x 1/2" 23 GEOMAVSUO42S Upholstered/Oak Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUM42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25 GEOMAVSUL42S Upholstered/Laminate Back Panel 37-3/16" x 45-27/32" x 3/4" 25  ### Shelving  GEOMAVSO48S Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSM48S Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5 GEOMAVSWO48S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSWU48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTO48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21 GEOMAVSTM48S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTM48S Tackboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/2" 27 GEOMAVSTL48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27						370	
GEOMAVSU042S       Upholstered/Oak Back Panel       37-3/16" x 45-27/32" x 3/4"       25         GEOMAVSUM42S       Upholstered/Maple Back Panel       37-3/16" x 45-27/32" x 3/4"       25         GEOMAVSUL42S       Upholstered/Laminate Back Panel       37-3/16" x 45-27/32" x 3/4"       25         A8"H Shelving         GEOMAVSO48S       Oak Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSM48S       Maple Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSL48S       Laminate Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSWO48S       Whiteboard/Oak Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSWM48S       Whiteboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSWL48S       Whiteboard/Laminate Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSTO48S       Tackboard/Oak Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTM48S       Tackboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTL48S       Tackboard/Laminate Back Panel       43-3/16" x 45-27/32" x 1/2"       27			•			370	
GEOMAVSUL42S Upholstered/Maple Back Panel 37-3/16" x 45-27/32" x 3/4" 25  ### Shelving  GEOMAVSO48S Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5  GEOMAVSM48S Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5  GEOMAVSL48S Laminate Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5  GEOMAVSW048S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 16.5  GEOMAVSW048S Whiteboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21  GEOMAVSWM48S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21  GEOMAVSW148S Whiteboard/Maple Back Panel 43-3/16" x 45-27/32" x 1/4" 21  GEOMAVSW148S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/4" 21  GEOMAVST048S Tackboard/Oak Back Panel 43-3/16" x 45-27/32" x 1/2" 27  GEOMAVST148S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27  GEOMAVST148S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27						692	
GEOMAVSUL42S       Upholstered/Laminate Back Panel       37-3/16" x 45-27/32" x 3/4"       25         48"H Shelving         GEOMAVSO48S       Oak Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSM48S       Maple Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSW048S       Whiteboard/Oak Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSWM48S       Whiteboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSWL48S       Whiteboard/Laminate Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSTO48S       Tackboard/Oak Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTL48S       Tackboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTL48S       Tackboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTL48S       Tackboard/Laminate Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTL48S       Tackboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/2" <td cols<="" td=""><td></td><td></td><td>•</td><td></td><td></td><td>692</td></td>	<td></td> <td></td> <td>•</td> <td></td> <td></td> <td>692</td>			•			692
48"H Shelving         GEOMAVSO48S       Oak Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSM48S       Maple Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSL48S       Laminate Back Panel       43-3/16" x 45-27/32" x 1/4"       16.5         GEOMAVSWO48S       Whiteboard/Oak Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSWM48S       Whiteboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSWL48S       Whiteboard/Laminate Back Panel       43-3/16" x 45-27/32" x 1/4"       21         GEOMAVSTO48S       Tackboard/Oak Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTM48S       Tackboard/Maple Back Panel       43-3/16" x 45-27/32" x 1/2"       27         GEOMAVSTL48S       Tackboard/Laminate Back Panel       43-3/16" x 45-27/32" x 1/2"       27			·				
GEOMAVSO48S         Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSM48S         Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSL48S         Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSWO48S         Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWM48S         Whiteboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27		GEOIVIAVSUL42S	upnoistered/Laminate Back Panei	37-3/16 X45-21/32 X3/4	25	692	
GEOMAVSM48S         Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSL48S         Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSW048S         Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWM48S         Whiteboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27		48"H Shelving					
GEOMAVSL48S         Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSW048S         Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWM48S         Whiteboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTM48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27		GEOMAVS048S	Oak Back Panel	43-3/16" x 45-27/32" x 1/4"	16.5	\$152	
GEOMAVSL48S         Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         16.5           GEOMAVSW048S         Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWM48S         Whiteboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27		GEOMAVSM48S	Maple Back Panel			159	
GEOMAVSW048S         Whiteboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWM48S         Whiteboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTM48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27			•			115	
GEOMAVSWM48S         Whiteboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTM48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27						376	
GEOMAVSWL48S         Whiteboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/4"         21           GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTM48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27					21	376	
GEOMAVSTO48S         Tackboard/Oak Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTM48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27			•			376	
GEOMAVSTM48S         Tackboard/Maple Back Panel         43-3/16" x 45-27/32" x 1/2"         27           GEOMAVSTL48S         Tackboard/Laminate Back Panel         43-3/16" x 45-27/32" x 1/2"         27						402	
GEOMAVSTL48S Tackboard/Laminate Back Panel 43-3/16" x 45-27/32" x 1/2" 27						402	
			•			402	
GEOMAVSUO48S Upholstered/Oak Back Panel 43-3/16" x 45-27/32" x 3/4" 30		GEOMAVSU048S	Upholstered/Oak Back Panel	43-3/16" x 45-27/32" x 3/4"	30	752	
GEOMAVSUM48S Upholstered/Maple Back Panel 43-3/16" x 45-27/32" x 3/4" 30			•			752	
GEOMAVSUL48S Upholstered/Laminate Back Panel 43-3/16" x 45-27/32" x 3/4" 30			·			752	

Linear Seating Geometrix

### **General Specifications for all Seating**

#### **SEAT FRAME**

Seat frame will be 3/4" thick engineered hardwood. Frame components and corner blocks are glued and stapled. Foam for vertical surfaces will be 1/2" thick, 1.5 density, 45 CFR. Seat foam will be 2" thick, 2.5 density, #55 Ultra-cell.

#### BASE (TOE KICK)

Linear wood seating bases will be 3/4" thick hardwood. Curved seating bases will be 3/4" thick engineered plywood. Linear laminated seating bases will be 3/4" thick thermally-fused laminate panels. Curved seating bases will be 3/4" plywood laminated with high-pressure laminate.

Catalog No.	Seat HxWxD	Wt. (lbs.)	COM Price	Grade 1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Trapezoid Seat 1,	1 Unit with Oak Toe K 17" x 35-29/32" x 24"	<i>ick</i> 36		\$2,085					Linear Trapezoid 1 Unit Seating
•	1 Unit with Maple Toe			¢2.00E					
GEOLTSEAT1MAPS  Trapezoid Seat 1,	17" x 35-29/32" x 24"  1 Unit with Laminate	<sup>36</sup> <i>Toe Kic</i>		\$2,085					
GEOLTSEAT1LAMS	17" x 35-29/32" x 24"	36		\$2,034					

		<i></i> .				Linear Trapezoid
<u>Irapezoid Seat 2, 2</u>	<u> 2 Units with Oak Toe k</u>	<u>(ICK</u>				2 Unit Seating
GEOLTSEAT2OAKS	17" x 71-13/16" x 24"	60		\$2,978	 	 
Trapezoid Seat 2,	2 Units with Maple To	e Kick				
GEOLTSEAT2MAPS	17" x 71-13/16" x 24"	60		\$2,978	 	 
Trapezoid Seat 2,	2 Units with Laminate	Toe K	<u>ick</u>			
GEOLTSEAT2LAMS17"	x 71-13/16" x 24"	60		\$2,906	 	 

Please specify Wood Finish (Table 1) and Upholstery (Table 5). Details can be found on pages GEN 4 and GEN 5.

		0.1	1871	0014	0 1 4	0 1 0	0.10	0 1 4	0 15		
	Catalog No.	Seat H x W x D	Wt. (lbs.)	COM Price	Grade 1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price		
Linear Rectangle 1 Unit Seating, Type 1	Rectangle Seat 1, 1	Units with Oak Toe I	<u>Kick</u>								
(Overlap End Panels)	GEOLRSEAT10AKS	17" x 36-1/4" x 24"	32		\$1,886						
	Rectangle Seat 1, 1	Rectangle Seat 1, 1 Units with Maple Toe Kick									
	GEOLRSEAT1MAPS	17" x 36-1/4" x 24"	32		\$1,886						
	Rectangle Seat 1, 1	Units with Laminate	Toe Kick								
	GEOLRSEAT1LAMS	17" x 36-1/4" x 24"	32		\$1,840						
OVERLAP END PANEL	SEAT										
END PANEL	SHELVING UNIT										
Linear Rectangle	Rectangle Seat 2, 1	Units with Oak Toe I	Kick								
1 Unit Seating, Type 2 (Inside End Panels)	GEOLRSEAT2OAKS	17" x 35-1/4" x 24"	32		\$1,886						
	Rectangle Seat 2, 1	Units with Maple To	e Kick								
	GEOLRSEAT2MAPS	17" x 35-1/4" x 24"	32		\$1,886						
	Rectangle Seat 2, 1	Units with Laminate	Toe Kick								
	GEOLRSEAT2LAMS	17" x 35-1/4" x 24"	32		\$1,840						
INSIDE END PANEL	SEAT										
END PANEL	SHELVING UNIT										
Linear Left Angled	Left Angled Seat wi	th Oak Toe Kick									
Seating	GEOLSEATLOAKS	17" x 36-1/4" x 24"	30		\$1,985						
	Left Angled Seat wi	th Maple Toe Kick									
	GEOLSEATLMAPS	17" x 36-1/4" x 24"	30		\$1,985						
	l eft Angled Seat wi	th Laminate Toe Kicl	k								
	GEOLSEATLLAMS	17" x 36-1/4" x 24"	30		\$1,937						
Linear Right Angled	Right Angled Seat v	vith Oak Toe Kick									
Seating	GEOLSEATROAKS	17" x 36-1/4" x 24"	30		\$1,985						
	Right Angled Seat v	vith Maple Toe Kick									
	GEOLSEATRMAPS	17" x 36-1/4" x 24"	30		\$1,985						
	Right Analed Seat w	vith Laminate Toe Kie	ck								
	GEOLSEATRLAMS	17" x 36-1/4" x 24"	30		\$1,937						
		n (Table 1) and Upholstery (Ta									
	Note: Please Call your Cu	istomer service representa	auve ivi Grac	ıe∠ triougn	i Graue 5 ani	u coivi pricin	ıy.				

talog No. H		Wt. bs.)	COM Price		Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
rc Inner Seat Type 1 with Oa	ak Toe Kick								Arc Inner
		32		\$1,922					Type 1 Seating (Overlap End Panels)
rc Inner Seat Type 1 with M	aple Toe Kick								
		32		\$1,922					
rc Inner Seat Type 1 with La	aminate Toe Ki	<u>ck</u>							
COAISEAT1LAMS 17-1/4"	x 36-3/4" x 24"	32		\$1,844					
						0/	/ERLAP END PA	<b>\</b>	SEAT
									CONVEX SHELVING UNIT
rc Inner Seat Type 2 with O	ak Toe Kick								Arc Innel
OAISEAT2OAKS 17-1/4"	x 35-3/4" x 24"	32		\$1,922					Type 2 Seating (Inside End Panels)
rc Inner Seat Type 2 with M	aple Toe Kick								
OAISEAT2MAPS 17-1/4"	x 35-3/4" x 24"	32		\$1,922					
rc Inner Seat Type 2 with La	aminate Toe Ki	<u>ck</u>							
COAISEAT2LAMS 17-1/4"	x 35-3/4" x 24"	32		\$1,844					1
							INSIDE END PA	ANEL-	SEAT
							END DANI	· /	J.
							END PAN		CONVEX SHELVING UNIT
rc Outer Seat Type 1 with O	ak Too Kiek								Arc Oute
		8		\$2,361					Type 1 Seating (Overlap End Panels)
rc Outer Seat Type 1 with M	laple Toe Kick								
		8		\$2,256				-	
rc Outer Seat Type 1 with La	aminate Toe Ki	ick							
COAOSEAT1LAMS 17-1/4" x 5	5-7/16" x 24" 4	8		\$2,152				- 1	
nte: Arc Outer Type 1 Seating is us	sed with 44"W Cor	ncave	Single-Faced	I Inline Adders	s Type 1.	ov	ERLAP END PA	NEL-\	SEAT
								ANEL-	CONCAVE

	Catalog No.	Seat H x W x D	Wt. (lbs.)	COM Price	Grade 1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price		
Arc Outer	Arc Outer Seat Tvr	oe 2 with Oak Toe Kicl	k								
Type 2 Seating (Overlap End Panels)	GEOAOSEAT2OAKS	17-1/4" x 49-5/8" x 24"	45		\$2,135						
	Arc Outer Seat Type 2 with Maple Toe Kick										
	GEOAOSEAT2MAPS	17-1/4" x 49-5/8" x 24"	45		\$2,135						
	Arc Outer Seat Typ	oe 2 with Laminate To	e Kick								
	GEOAOSEAT2LAMS	17-1/4" x 49-5/8" x 24"	45		\$2,048						
OVERLAP END PANEL  END PANEL	SEAT  CONCAVE SHELVING UNIT	<b>Note</b> : Arc Outer Type 2 Se	ating is u	ised with 37	7"W Concave	Single-Face	ed Inline Ad	ders Type 2			
Arc Outer	Arc Outer Seat Tvr	oe 3 with Oak Toe Kicl	· · · · · · · · · · · · · · · · · · ·								
Type 3 Seating (Inside End Panels)	GEOAOSEAT3OAKS	17-1/4" x 48-5/8" x 24"	45		\$2,135						
	Arc Outer Seat Type 3 with Maple Toe Kick										
	GEOAOSEAT3MAPS	17-1/4" x 48-5/8" x 24"	45		\$2,135						
	Arc Outer Seat Typ GEOAOSEAT3LAMS	<i>pe 3 with Laminate To</i> 17-1/4" x 48-5/8" x 24"	<i>e Kick</i> 45		\$2,048						
INSIDE END PANEL  END PANEL	SEAT  CONCAVE SHELVING UNIT	Note: Arc Outer Type 3 Se	ating is u	ised with 37	7"W Concave	Single-Face	ed Inline Ad	ders Type 2.			
Arc Outer	Arc Outer Seat Typ	oe 4 with Oak Toe Kicl	<u>k</u>								
Type 4 Seating (Inside End Panels)	GEOAOSEAT4OAKS	17-1/4" x 54-7/16" x 24"	45		\$2,361						
	Arc Outer Seat Typ	oe 4 with Maple Toe K	ick								
	GEOAOSEAT4MAPS	17-1/4" x 54-7/16" x 24"	45		\$2,256						
	Arc Outer Seat Typ	oe 4 with Laminate To	e Kick								
	GEOAOSEAT4LAMS	17-1/4" x 54-7/16" x 24"	45		\$2,152						
INSIDE END PANEL	SEAT	Note: Arc Outer Type 4 Se	ating is u	sed with 44	1"W Concave	Single-Face	ed Inline Ad	ders Type 2.			

### **General Specifications**

#### TABLETOP FOR WOOD VENEER

Tabletop will be 1" thick veneer particleboard. Wood veneer tops receive a 1/4" thick x 1"W wood (Maple or Oak) edgeband.

#### TABLETOP FOR THERMALLY-FUSED LAMINATE (TFL)

Tabletop will be 1" thick MDF, with .050" thick thermally-fused laminate surface and .020" thick backing sheet for balanced construction. TFL tops receive a T-mold edgeband, which will be flexible polyethylene, 2mm thick x 1"W.

#### TABLETOP FOR HIGH-PRESSURE LAMINATE (HPL)

Tabletop will be 1" thick particle board, with .050" thick high-pressure laminate surface and .020" thick backing sheet for balanced construction. HPL tops receive a T-mold edgeband, which will be flexible polyethylene, 2mm thick x 1"W. Tabletops can also receive a 5/8" thick x 1-1/16"W wood (Maple or Oak) edgeband.

#### **BLADE LEGS (METAL)**


Legs will be 1" x 3" steel rectangular tubing with a wall thickness no less than 2mm. Legs are supplied with a standard glide insert. Metal legs attach to table top by means of a flange welded to the leg. Attachment flange will be 3-3/4" x 3-3/4" metal plate formed and welded on two sides to the leg. Each leg attachment flange is attached to the metal apron support frame using four #8 x 3/4" screws and then attached to the underneath of the tabletop by five #12 x 3/4" screws. Legs will be finished with electrostatic applied epoxy powder-coat paint.

#### APRON SUPPORT FRAME

A metal frame 1"W x 2"H x 2mm thick in various lengths will be attached to underside of the tabletop using #12 x 3/4" screws. Each leg attachment flange will be attached to the apron support frame using four #8 x 3/4" screws.

#### **ASSEMBLED TABLES**


Finished tables come in heights of 30"H, 36"H, and 42"H.



Catalog No.	Seat H x W x D	Wt. (lbs.)	COM Price	Grade 1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Table with Oak I	Veneer Top, Matching V	Vood Edg	eband, M	atching To	e Kick, an	d Upholst	ered Base	2	Table with
GEOTABUVO26S	26" x 26-3/16" x 31-3/4"	42		\$1,945					Upholstered Base
Table with Maple	e Veneer Top, Matching	Wood E	dgeband,	<u>Matching</u>	Toe Kick,	and Upho	Istered Ba	<u>ise</u>	
GEOTABUVM26S	26" x 26-3/16" x 31-3/4"	42		\$1,945					
Table with TFL To	op, T-Mold Edgeband, N	<u>latching</u>	Toe Kick,	and Upho	Istered Ba	<u>se</u>			
GEOTABUTT26S	26" x 26-3/16" x 31-3/4"	42		\$1,559					
Table with HPL 1	Top, Oak Edgeband, Ma	tching To	e Kick, aı	nd Upholst	ered Base	•			
GEOTABUHO26S	26" x 26-3/16" x 31-3/4"	42		\$1,842					
Table with HPL 1	op, Maple Edgeband, N	/latching	Toe Kick,	and Upho	Istered Ba	<u>ise</u>			
GEOTABUHM26S	26" x 26-3/16" x 31-3/4"	42		\$1,842					
Table with HPL 1	Top, T-Mold Edgeband, I	<i>Matching</i>	Toe Kick,	and Upho	lstered Ba	<u>ise</u>			
GEOTABUHT26S	26" x 26-3/16" x 31-3/4"	42		\$1,693					

Please specify Wood Finish (Table 1) and Upholstery (Table 5). Details can be found on pages GEN 4 and GEN 5.





Please specify Wood Finish (Table 1), Laminate Color (Tables 2 and 4), Edgeband Color (Table 4), and Metal Leg Color (Table 3).

Details can be found on page GEN 4 and GEN 5

Note: Edgeband Color does NOT have to match Laminate Color

# The Horizons Collection

### **General Specifications**

#### **DESKTOP**

Standard desktops are 1-3/16" thick, 3-ply, 45# density, particleboard core, with a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thickness for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Top receives a 5/8" thick x 1-3/16" solid maple edge band on the patron side with edges radiused to form a bullnose shape. A 1/4" thick, solid maple edge band is applied to the remaining three sides, with top and bottom edges radiused to 1/8". All edges are applied to the desktop after the top and bottom laminate sheets are applied, constituting an external edge band. Desktop is positioned over the end panels of the desk module, flush with the outside edges of the end panels.

#### **END PANEL**

Desk module end panels are 1" thick, 3-ply, 45# density particleboard core with select plain-sliced maple veneer on both sides. Exposed edges are externally banded with a maple band. The end panels and front panel are joined and secured with 3/4" x 3/4" thick solid hardwood cleats screwed to the inside surfaces of the panels. The bottom of each end panel receives two adjustable glides to allow leveling of the individual units. Each end panel receives a 3" diameter egress and grommet to provide for wire passage.

#### FRONT PANEL

The front panel is 3/4" thick, comprised of select plain-sliced face veneers maple over a 45# density particle board core. Exposed edges are externally banded with a maple band. The front incorporates a 6"H x 3/4"D recessed, ebonized, toe space at the bottom of the panel. The front panel is positioned over the end panels of the desk module, flush with the outside edges of the end panels. Double wide units have two front panels to give the appearance of two individual units. At the top of the front panel, a 6"W x 1/4" thick maple plywood accent panel is attached that runs the full width of the desk unit front. The grain direction runs horizontally. This panel has a large cutout design as selected by the customer. The inside edges of the cutout and outer edges of the accent panel are blackened to provide a finished appearance. When the cutout design is large enough, a matching cutout of colored high-pressure laminate is inlaid in the cutout. When the cutout is small (such as the sports stick figures) no high-pressure laminate is inlaid.

#### **WORK SURFACE**

Work surfaces are 1-3/16" thick, 3-ply particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thickness for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. The exposed edge receives a 1/4" thick, solid maple internal edge band in straight design. The back edge of the work surface has a black plastic band 1-1/2"W which projects above the work surface 1/4" to act as a retainer. The work surface is 24-1/2"D and is positioned 1-1/2" away from the front panel, creating a cord drop space. Adjustable work surfaces are available in single wide standing height desks. Work surfaces in standing-height desks (catalog number 77-012) may be positioned at heights of 36", 32" or 27".


**Note:** See Brodart optional electrical accessories for electrical power distribution system for desk modules.

#### **SHELVES**

Shelves are constructed of 7-ply veneer-core plywood, with plain sliced maple face veneer. Exposed edges receive a maple edge band.

#### DRAWFR

Drawers aree constructed of solid hardwood with 1/4" thick wood bottom panel. Drawers have 3-ply particleboard fronts with select maple-face veneer. Box drawers have extension slides with 100# load capacity. File drawers have full-extension slides with 100# load capacity.




Horizons Flush Edge

#### **DESK DIMENSIONS**

Standing-Height Desk, overall: 39-3/16"Hx70"Wx30"D.


Sitting-Height Desk, overall: 32-3/16"H x 70"W x 30"D.



# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
77-012-S00 OAK	77-012-S00 MAP	Standing Height Desk with Patron Service Ledge	39-3/16" x 35" x 30"	140	\$3,322	\$3,621	Single-Wide Desk with Patron Service Ledge
		Inside dimensions: 33"W x 26-3/47-7/8" patron ledge is at a height <b>Note</b> : Adjustable-height work surfat heights of 36", 32" or 27".	of 39-3/16"H.				
77-E12-S00 OAK	77-E12-S00 MAP	Sitting Height Desk with Patron Service Ledge	32-3/16" x 35" x 30"	125	\$3,184	\$3,471	
		Inside dimensions: 33"W x 26-3/47-7/8" patron ledge is at a height <b>Note:</b> Work surface is fixed at 27"	of 32-3/16"H.				
77-014-S00 OAK	77-014-S00 MAP	Standing Height Desk without Patron Service Ledge	39-3/16" x 35" x 30"	135	\$2,973	\$3,240	Single-Wide Desk without Patron Service Ledge
		Inside dimensions: 33"W x 26-3/4 work surface is at 39-3/16"H. Two grommets are located in the work s	3" diamenter				0
77-E14-S00 OAK	77-E14-S00 MAP	Sitting Height Desk without Patron Service Ledge	32-3/16" x 35" x 30"	120	\$2,727	\$2,972	
		Inside dimensions: 33"W x 26-3/4 work surface is at 32-3/16"H. Two grommets are located in the work s	3" diamenter				
77-015-S00 OAK	77-015-S00 MAP	Standing Height Book Return Unit	39-3/16" x 35" x 30"	135	\$2,900	\$3,161	Book Return Unit
		Inside dimensions: 33"W x 26-3/4 work surface is at 39-3/16"H. Unifinished opening centered in the froof books and a book chute to direct depressible book truck. (Depressib Two 3" diameter grommets are loc	t has a 5"H x 12"W ont panel for passage t the books over a mobile le book truck not included).				0
77-E15-S00 OAK	77-E15-S00 MAP	Sitting Height Book Return Unit Inside dimensions: 33"W x 26-3/4	32-3/16" x 35" x 30" 4"D. The	120	\$2,763	\$3,012	
		work surface is at 32-3/16"H. Unifinished opening centered in the froof books and a book chute to direct depressible book truck. (Depressib Two 3" diameter grommets are loc	t has a 5"H x 12"W ont panel for passage t the books over a mobile le book truck not included).				0

Standing Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Cupboard and Open Shelf	77-121-S00 OAK	77-121-S00 MAP	Standing Height Cupboard and Open Shelf	39-3/16" x 35" x 30"	175	\$5,137	\$5,519
			This unit has one fixed and two adjushelves. A hidden drawer is position the lockable storage compartment. grommets are located in the work storage.	ned above Two 3'' diameter			
	77-E21-S00 OAK	77-E21-S00 MAP	Sitting Height Cupboard	32-3/16" x 35" x 30"	160	\$4,841	\$5,276
			This unit has one fixed and one adjushelf. A hidden drawer is positioned the lockable storage compartment. grommets are located in the work s	d above Two 3'' diameter			
Full Width Drawer,	77-122-S00 OAK	77-122-S00 MAP	Standing Height Full Width Drawer, Cupboard and Drawers	39-3/16" x 35" x 30"	225	\$6,822	\$7,436
Cupboard and Drawers  Output  Output			This unit has one full-width drawer, two file drawers, and a lockable sto compartment. Two 3" diameter gro are located in the work surface.  Note: Available in 39"H only.	•			



# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
77-124-S00 OAK	77-124-S00 MAP	Standing Height Open Shelf and Drawer Unit	39-3/16" x 35" x 30"	200	\$5,684	\$6,196	Open Shelf and Drawer Unit
		This unit has one lockable box dra and two file drawers. Shelf section two adjustable shelves, and one f Two 3" diameter grommets are lo	n has ixed base shelf.				
77-E24-S00 OAK	77-E24-S00 MAP	Sitting Height Open Shelf and Drawer Unit	32-3/16" x 35" x 30"	125	\$5,262	\$5,735	
		This unit has one lockable box dra and one file drawer. Shelf section one adjustable shelf, and one fixe Two 3" diameter grommets are lo	has ad base shelf.				
77-131-S00 OAK	77-131-S00 MAP	Standing Height Cash Drawer Uni	t 39-3/16" x 35" x 30"	150	\$4,047	\$4,412	Cash Drawer Unit
		Inside dimensions: 33"W x 26-3/ The work surface is at 39-3/16"H has locking drawer with a coin and Two 3" diameter grommets are lo	I. Desk d currency tray.				
77-E31-S00 OAK	77-E31-S00 MAP	Sitting Height Cash Drawer Unit Inside dimensions: 33"W x 26-3, The work surface is at 32-3/16"H has locking drawer with a coin and Two 3" diameter grommets are lo	I. Desk d currency tray.	135	\$5,241	\$5,713	
77-E32-S00 OAK	77-E32-S00 MAP	Sitting Height ADA Station	32-3/16" x 35" x 40-1/2"	' 185	\$2,727	\$2,972	ADA Station
		The ADA transaction station is designed to provide wheelchair are on the patrons' side. The knee spon the patrons' side is 22-1/4" a staff side is 16". Two 3" diamete are located in the work surface. O egress with sleeve is located in each	ace depth and on the r grommets ne 3-1/2'' diameter	).			

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Full Width Drawer Unit		77-133-S00 OAK	77-133-S00 MAP	Standing Height Full Width Drawer Unit	39-3/16" x 35" x 30"	160	\$4,145	\$4,519
				This drawer unit has a full-width di 10"H x 33"W x 18-3/4"D. Two 3 grommets are located in the work <b>Note</b> : Available in 39-3/16"H or	3" diameter surface.			

**Full Width Drawer and Cupboard Unit** 



77-135-S00 OAK 77-135-S00 MAP

Standing Height Full Width **Drawer and Cupboard Unit**  39-3/16" x 35" x 30"

\$4,544

\$4,953

This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Hinged doors have a catch, lock and door pulls. Two 3" diameter grommets are located in the work surface.

Note: Available in 39-3/16"H only.

Discharge Unit 77-172-S00 OAK 77-172-S00 MAP Standing Height Discharge Unit 39-3/16" x 35" x 30" \$4,307 \$4,694 These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 39-3/16"H. Note: Standing-height roll unders do not work with this unit. 77-E72-S00 OAK 77-E72-S00 MAP Sitting Height Discharge Unit 32-3/16" x 35" x 30" \$4,478 These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 32-3/16"H.


Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
77-174-S00 OAK	77-174-S00 MAP	Standing Height Open Shelf Unit	39-3/16" x 35" x 30"	175	\$3,358	\$3,660	Open Shelf Unit
		This unit has a full-depth fixed base shelf and two full-depth adjustable s Two 3" diameter grommets are local the work surface.	ted in			i	
77-E74-S00 OAK	77-E74-S00 MAP	Sitting Height Open Shelf Unit This unit has a full-depth fixed base shelf and two full-depth adjustable s Two 3" diameter grommets are local the work surface.		155	\$3,058	\$3,333	
77.477.600.047	77.47/.000 MAD	Charles Height Contract Heigh	20.2 (4/    25   20	200	<b>#4.000</b>	<b>\$4.200</b>	
77-176-S00 OAK	77-176-S00 MAP	Standing Height Cupboard Unit This unit has a full-depth fixed base shelf and two full-depth adjustable s Hinged doors have a catch, lock and Two 3" diameter grommets are local work surface.	door pulls.	200	\$4,028	\$4,390	Cupboard Unit
77-E76-S00 OAK	77-E76-S00 MAP	Sitting Height Cupboard Unit This unit has a full-depth fixed base shelf and one full-depth adjustable s Hinged doors have a catch, lock and Two 3" diameter grommets are local work surface.	door pulls.	180	\$3,870	\$4,218	
77-234-S00 OAK	77-234-S00 MAP	Standing Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work su	39-3/16" x 35" x 30" rface.	180	\$3,951	\$4,307	Full Width Drawer and Open Shelves
77-E34-S00 OAK	77-E34-S00 MAP	Sitting Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work su	32-3/16" x 35" x 30" urface.	165	\$3,753	\$4,091	

225 \$5,103	25 \$5,103 \$	25 <b>\$5,103</b> \$
205 <b>\$4,738</b>	05 <b>\$4,738</b> \$	05 <b>\$4,738</b> \$

# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
77-011-S00 OAK	77-011-S00 MAP	Standing Height Double-Wide Desk with Patron Service Ledge	39-3/16" x 70" x 30"	245	\$5,126	\$5,587	Double-Wide Desk with Patron Service Ledge,
		Work Surface at 35"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a h Two 3" diameter grommets are loc Note: Standing-height roll unders	neight of 39-3/16". cated in the work surface.		0		
77-E11-S00 OAK	77-E11-S00 MAP	Sitting Height Double-Wide Desk with Patron Service Ledge Work Surface at 28"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a h Two 3" diameter grommets are loc	neight of 32-3/16".	210	\$4,902	\$5,343	
77-011-SEA OAK	77-011-SEA MAP	Standing Height Double-Wide Desk with Patron Service Ledge Work Surface at 28"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a 1 Two 3" diameter grommets are loo <b>Note</b> : Standing-height roll unders	neight of 39-3/16". cated in the work surface.	245	\$5,139	\$5,601	
77-013-S00 OAK	77-013-S00 MAP	Standing Height Double-Wide	39-3/16" x 70" x 30"	230	\$4,684	\$5,106	Double-Wide Desk
		Desk without Patron Service Ledge Inside dimensions are 68"W x 26- The work surface is at 39-3/16" H diameter grommets are located in	3/4"D. . Two 3"		0		without Patron Service Ledge
77-E13-S00 OAK	77-E13-S00 MAP	Sitting Height Double-Wide Desk without Patron Service Ledge Inside dimensions are 68"W x 26- The work surface is at 32-3/16" H diameter grommets are located in	3/4"D. . Two 3"	195	\$4,509	\$4,915	

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Do Work Desk	ouble Pedestal	77-E37-S00 OAK	77-E37-S00 MAP	Sitting Height Double-Wide Double Pedestal Work Desk	32-3/16" x 70" x 30"	260	\$9,284	\$10,120
		1 1 1		Inside dimensions are 68"W x 26- This unit has two drawer pedestals on each side consisting of one lock one file drawer with hanging file ra Two center drawers are mounted b Two 3" diameter grommets are loc Note: Available in 32-3/16" H or	, one mounted king drawer at top; ck at bottom. etween the two pedestals. cated in the work surface.			



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
77-010-S00 OAK	77-010-S00 MAP	Standing Height 90 Degree Multi-Purpose Corner	39-3/16" x 71-3/4" x	30" 250	\$8,050	\$8,775	90 Degree Multi-Purpose Corner
		Unit has 29-5/16"W port area angled areas to the left and righ grommet is located in the work- with sleeve is located in each er	nt of the desk module. One 3 surface top. One 3-1/2" di	" diameter	SS	0	
77-E10-S00 OAK	77-E10-S00 MAP	Sitting Height 90 Degree Multi-Purpose Corner	32-3/16" x 71-3/4" x	30" 215	\$7,706	\$8,401	
		Unit has 29-5/16"W port area angled areas to the left and righ grommet is located in the work- with sleeve is located in each er	nt of the desk module. One 3 surface top. One 3-1/2" di	" diameter	SS		
77-017-S00 OAK	77-017-S00 MAP	Standing Height 90 Degree Multi-Purpose with Patron Servi	39-3/16" x 71-3/4" x ice Ledge	30" 245	\$10,364	\$11,296	90 Degree Multi-Purpose Corner with Patron Service Ledge
		Unit has 29-5/16"W port area 39-3/16". Work surface is at 3 areas to the left and right of the work surface top. One 3-1/2"d panel for wire passage.	35"H. Storage shelves are lo module. One 3" diameter g	cated in the rommet is l	e two angled ocated in th		0
77-E17-S00 OAK	77-E17-S00 MAP	Sitting Height 90 Degree Multi-Purpose with Patron Servi	32-3/16" x 71-3/4" x ice Ledge	30" 210	\$9,905	\$10,797	
		Unit has 29-5/16"W port area Work surface is at 28"H. Stora and right of the module. One 3 3-1/2" diameter egress with sl	ge shelves are located in the '' diameter grommet is locat	two angled ed in the wo	areas to the rk surface to	eleft	
77-016-S00 OAK	77-016-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"H	140	\$3,787	\$4,128	90 Degree Closed Corner Unit
		This 90 degree unit is used to fo This is not available with patron in each end panel for wire passa	ledge. One 3-1/2" diamete	er egress is l		0	
77-E16-S00 OAK	77-E16-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"H	120	\$3,627	\$3,953	0 0
		This 90 degree unit is used to fo This is not available with patron in each end panel for wire pass	ledge. One 3-1/2" diamete	er egress is l			

		0ak	Maple			Wt.	Oak	Manla
Standing	Sitting	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Oak Price	Maple Price
45 Degree Curved Closed Corner Uni		77-018-S00 OAK	77-018-S00 MAP	Standing Height 45 Degree Curved Closed Corner Unit	39-3/16" x 22-3/8" x 30'	' 130	\$3,787	\$4,128
		,		This unit is used to create a 45 de It is not available with patron ledg		esk.		
		77-E18-S00 OAK	77-E18-S00 MAP	Sitting Height 45 Degree Curved Closed Corner Unit	32-3/16" x 22-3/8" x 30'	' 110	\$3,627	\$3,953
				This unit is used to create a 45 de It is not available with patron ledg		lesk.		
90 Degree Open C	Corner Shelf	77-143-S00 OAK	77-143-S00 MAP	Standing Height 90 Degree Open Corner Shelf	39-3/16"H x 30"D	140	\$3,495	\$3,810
	ŽTI.			This 90 degree unit is used to form Has one fixed base shelf and two: <b>Note:</b> Units must be modified on on open corner units.	adjustable shelves.	-		gh
		77-E43-S00 OAK	77-E43-S00 MAP	Sitting Height 90 Degree Open Corner Shelf	32-3/16"H x 30"D	120	\$3,345	\$3,647
le le				This 90 degree unit is used to form Has one fixed base shelf and two: <b>Note</b> : Units must be modified on on open corner units.	adjustable shelves.	-		gh
90 Degree Square	e Corner Unit	77-150-S00 OAK	77-150-S00 MAP	Standing Height 90 Degree Square Corner Unit	39-3/16" x 30" x 30"	160	\$4,157	\$4,531
				This square corner unit is used to One 3" diameter egress is located a continuous ABS tube.				
		77-E50-S00 OAK	77-E50-S00 MAP	Sitting Height 90 Degree Square Corner Unit	32-3/16" x 30" x 30"	140	\$3,813	\$4,157
0				This square corner unit is used to One 3" diameter egress is located a continuous ABS tube.		-		

# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
77-178-S00 OAK	77-178-S00 MAP	Detachable End Panels (Pair)	37-1/2" x 1" x 26-3/4"	52	\$2,226	\$2,426	Detachable End Panels (Pair)
		End panels are 1" thick, 3-ply, 45 particleboard core with plain-slice veneers. Exposed edges are extern with 1.6mm thick, solid Northern-	ed oak or maple nally banded	nd.			
77-E78-S00 OAK	77-E78-S00 MAP	Detachable End Panels (Pair)	30-1/2" x 1" x 26-3/4"	42	\$2,178	\$2,374	
		End panels are 1" thick, 3-ply, 45 particleboard core with plain-slice veneers. Exposed edges are extern with 1.6mm thick, solid Northern-	ed oak or maple nally banded	nd.			

77-196-S00 OAK	77-196-S00 MAP	Single-Wide Add On 7"H Patron Ledge	7" x 35" x 7-7/8"	10	\$526	\$574	Single-Wide Add On 7"H Patron Ledge
			tron Ledge Assembly will attach x 2-1/2" screws inserted through	n			

77-197-S00 OAK	77-197-S00 MAP	Double-Wide Add On 7''H Patron Ledge	7" x70" x 7-7/8"	20	\$665	\$725	Double-Wide Add On 7"H Patron Ledge
		Unit is designed to be added or without a patron ledge. The Pat to the desktop by means of #8 the work surface into the ledge	ron Ledge Assembly will attach x 2-1/2" screws inserted througl	h			

#### **TABLETOPS**

Standard tabletops are 1-3/16" thick, 9-ply plywood core, or a 1-3/16" thick particleboard core, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thickness for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are solid maple. Drop edge band is 5/8" thick x 1-5/8" externally banded to form a bullnose.


#### **TABLE LEGS**

Legs are solid maple wood, 2-1/2" diameter. Each leg has a 3-1/2" diameter x 2-5/8"H glued-up maple bun-foot. Each bun-foot has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the bun-foot by means of a counter-sunk boring which accepts the upper two-thirds of the glide.


Legs attach to tabletops by means of a 5" square x 5/16" thick steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind, and be hidden by, the extended table edge band.

#### TABLETOP SUPPORT


For maximum rigidity, rectangular tables, 60" or more wide, receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60" W, receive two steel keels parallel to the length of the table. Tables 90" or wider receive two extra matching legs located under the center of the table to provide added support.



Horizons Drop Edge



Horizons Wood Leg



Horizons External Edge Band

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Round Oak Tabi	<u>le</u>						Round Table
77-109-S00 OAK	77-109-S02 OAK	Adult Table	29"H x 36" Diameter	100	\$2,051	\$1,966	
77-Y09-S00 OAK	77-Y09-S02 OAK	Youth Table	27-1/2"H x 36" Diameter	100	\$2,051	\$1,966	
77-J09-S00 OAK	77-J09-S02 OAK	Juvenile Table	25"H x 36" Diameter	100	\$2,051	\$1,966	
77-129-S00 OAK	77-129-S02 OAK	Adult Table	29"H x 42" Diameter	110	\$2,173	\$2,087	
77-Y29-S00 OAK	77-Y29-S02 OAK	Youth Table	27-1/2"H x 42" Diameter	110	\$2,173	\$2,087	
77-J29-S00 OAK	77-J29-S02 OAK	Juvenile Table	25"H x 42" Diameter	110	\$2,173	\$2,087	
77-141-S00 OAK	77-141-S02 OAK	Adult Table	29"H x 48" Diameter	120	\$2,173	\$2,087	o A a A
77-Y41-S00 OAK	77-Y41-S02 OAK	Youth Table	27-1/2"H x 48" Diameter	120	\$2,173	\$2,087	
77-J41-S00 OAK	77-J41-S02 OAK	Juvenile Table	25"H x 48" Diameter	120	\$2,173	\$2,087	
N/A	77-130-S02 OAK	Adult Table	29"H x 60" Diameter	140	N/A	\$2,548	
N/A	77-Y30-S02 OAK	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$2,548	
N/A	77-J30-S02 OAK	Juvenile Table	25"H x 60" Diameter	140	N/A	\$2,548	
Round Maple Ta	able						
77-109-S00 MAP	77-109-S02 MAP	Adult Table	29"H x 36" Diameter	100	\$2,236	\$2,143	
77-Y09-S00 MAP	77-Y09-S02 MAP	Youth Table	27-1/2"H x 36" Diameter	100	\$2,236	\$2,143	
77-J09-S00 MAP	77-J09-S02 MAP	Juvenile Table	25"H x 36" Diameter	100	\$2,236	\$2,143	
77-129-S00 MAP	77-129-S02 MAP	Adult Table	29"H x 42" Diameter	110	\$2,368	\$2,274	
77-Y29-S00 MAP	77-Y29-S02 MAP	Youth Table	27-1/2"H x 42" Diameter	110	\$2,368	\$2,274	
77-J29-S00 MAP	77-J29-S02 MAP	Juvenile Table	25"H x 42" Diameter	110	\$2,368	\$2,274	
77-141-S00 MAP	77-141-S02 MAP	Adult Table	29"H x 48" Diameter	120	\$2,368	\$2,274	
77-Y41-S00 MAP	77-Y41-S02 MAP	Youth Table	27-1/2"H x 48" Diameter	120	\$2,368	\$2,274	
77-J41-S00 MAP	77-J41-S02 MAP	Juvenile Table	25"H x 48" Diameter	120	\$2,368	\$2,274	
N/A	77-130-S02 MAP	Adult Table	29"H x 60" Diameter	140	N/A	\$2,777	
N/A	77-Y30-S02 MAP	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$2,777	
N/A	77-J30-S02 MAP	Juvenile Table	25"H x 60" Diameter	140	N/A	\$2,777	
Square Oak Tab	nla						
77-191-S00 OAK	77-191-S02 OAK	Adult Table	29" x 30" x 30"	110	\$1,617	\$1,470	Square Table
77-Y91-S00 OAK	77-Y91-S02 OAK	Youth Table	27-1/2" x 30" x 30"	110	\$1,617	\$1,470	
77-J91-S00 OAK	77-J91-S02 OAK	Juvenile Table	25" x 30" x 30"	110	\$1,617	\$1,470	
77-137-S00 OAK	77-137-S02 OAK	Adult Table	29" x 42" x 42"	110	\$1,738	\$1,590	
77-Y37-S00 OAK	77-Y37-S02 OAK	Youth Table	27-1/2" x 42" x 42"	110	\$1,738	\$1,590	
77-J37-S00 OAK	77-J37-S02 OAK	Juvenile Table	25" x 42" x 42"	110	\$1,738	\$1,590	
77-154-S00 OAK	77-154-S02 OAK	Adult Table	29" x 48" x 48"	110	\$1,872	\$1,725	
77-Y54-S00 OAK	77-Y54-S02 OAK	Youth Table	27-1/2" x 48" x 48"	110	\$1,872	\$1,725	
77-J54-S00 OAK	77-J54-S02 OAK	Juvenile Table	25" x 48" x 48"	110	\$1,872	\$1,725	
Square Maple T	able						
77-191-S00 MAP	77-191-S02 MAP	Adult Table	29" x 30" x 30"	110	\$1,762	\$1,601	
77-Y91-S00 MAP	77-Y91-S02 MAP	Youth Table	27-1/2" x 30" x 30"	110	\$1,762	\$1,601	
77-J91-S00 MAP	77-J91-S02 MAP	Juvenile Table	25" x 30" x 30"	110	\$1,762	\$1,601	
77-137-S00 MAP	77-137-S02 MAP	Adult Table	29" x 42" x 42"	110	\$1,894	\$1,733	
77-Y37-S00 MAP	77-Y37-S02 MAP	Youth Table	27-1/2" x 42" x 42"	110	\$1,894	\$1,733	
77-J37-S00 MAP	77-J37-S02 MAP	Juvenile Table	25" x 42" x 42"	110	\$1,894	\$1,733	
77-154-S00 MAP	77-154-S02 MAP	Adult Table	29" x 48" x 48"	110	\$2,041	\$1,880	
77-Y54-S00 MAP	77-Y54-S02 MAP	Youth Table	27-1/2" x 48" x 48"	110	\$2,041	\$1,880	
77-J54-S00 MAP	77-J54-S02 MAP	Juvenile Table	25" x 48" x 48"	110	\$2,041	\$1,880	

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Re	ctangular Oak Tal	ole				
Rectrangular Table	77-194-S00 OAK	77-194-S02 OAK	Adult Table	29" x 30" x 60"	120	\$1,911	\$1,728
	77-Y94-S00 OAK	77-Y94-S02 OAK	Youth Table	27-1/2" x 30" x 60"	120	\$1,911	\$1,728
	77-J94-S00 OAK	77-J94-S02 OAK	Juvenile Table	25" x 30" x 60"	120	\$1,911	\$1,728
	77-195-S00 OAK	77-195-S02 OAK	Adult Table	29" x 30" x 72"	140	\$2,051	\$1,869
	77-Y95-S00 OAK	77-Y95-S02 OAK	Youth Table	27-1/2" x 30" x 72"	140	\$2,051	\$1,869
	77-J95-S00 OAK	77-J95-S02 OAK	Juvenile Table	25" x 30" x 72"	140	\$2,051	\$1,869
	Four-Reader Re	ctangular Maple 1	able				
	77-194-S00 MAP	77-194-S02 MAP	Adult Table	29" x 30" x 60"	120	\$2,084	\$1,884
	77-Y94-S00 MAP	77-Y94-S02 MAP	Youth Table	27-1/2" x 30" x 60"	120	\$2,084	\$1,884
	77-J94-S00 MAP	77-J94-S02 MAP	Juvenile Table	25" x 30" x 60"	120	\$2,084	\$1,884
	77-195-S00 MAP	77-195-S02 MAP	Adult Table	29" x 30" x 72"	140	\$2,236	\$2,036
	77-Y95-S00 MAP	77-Y95-S02 MAP	Youth Table	27-1/2" x 30" x 72"	140	\$2,236	\$2,036
	77-J95-S00 MAP	77-J95-S02 MAP	Juvenile Table	25" x 30" x 72"	140	\$2,236	\$2,036

Six-Reader	Six-Reader Rec	tangular Oak Tabl	<u>le</u>				
Rectrangular Table	77-144-S00 OAK	77-144-S02 OAK	Adult Table	29" x 36" x 60"	120	\$1,992	\$1,808
· ·	77-Y44-S00 OAK	77-Y44-S02 OAK	Youth Table	27-1/2" x 36" x 60"	120	\$1,992	\$1,808
	77-J44-S00 OAK	77-J44-S02 OAK	Juvenile Table	25" x 36" x 60"	120	\$1,992	\$1,808
	77-138-S00 OAK	77-138-S02 OAK	Adult Table	29" x 36" x 72"	140	\$2,132	\$1,948
1 4 1	77-Y38-S00 OAK	77-Y38-S02 OAK	Youth Table	27-1/2" x 36" x 72"	140	\$2,132	\$1,948
J	77-J38-S00 OAK	77-J38-S02 OAK	Juvenile Table	25" x 36" x 72"	140	\$2,132	\$1,948
	77-145-S00 OAK	77-145-S02 OAK	Adult Table	29" x 48" x 72"	170	\$2,753	\$2,291
	77-Y45-S00 OAK	77-Y45-S02 OAK	Youth Table	27-1/2" x 48" x 72"	170	\$2,753	\$2,291
	77-J45-S00 OAK	77-J45-S02 OAK	Juvenile Table	25" x 48" x 72"	170	\$2,753	\$2,291
	Six-Reader Rec	tangular Maple Ta	able				
	77-144-S00 MAP	77-144-S02 MAP	Adult Table	29" x 36" x 60"	120	\$2,172	\$1,971
	77-Y44-S00 MAP	77-Y44-S02 MAP	Youth Table	27-1/2" x 36" x 60"	120	\$2,172	\$1,971
	77-J44-S00 MAP	77-J44-S02 MAP	Juvenile Table	25" x 36" x 60"	120	\$2,172	\$1,971
	77-138-S00 MAP	77-138-S02 MAP	Adult Table	29" x 36" x 72"	140	\$2,324	\$2,124
	77-Y38-S00 MAP	77-Y38-S02 MAP	Youth Table	27-1/2" x 36" x 72"	140	\$2,324	\$2,124
	77-J38-S00 MAP	77-J38-S02 MAP	Juvenile Table	25" x 36" x 72"	140	\$2,324	\$2,124
	77-145-S00 MAP	77-145-S02 MAP	Adult Table	29" x 48" x 72"	170	\$3,001	\$2,496
	77-Y45-S00 MAP	77-Y45-S02 MAP	Youth Table	27-1/2" x 48" x 72"	170	\$3,001	\$2,496
	77-J45-S00 MAP	77-J45-S02 MAP	Juvenile Table	25" x 48" x 72"	170	\$3,001	\$2,496

	Particleboard Core Price	Plywood Core Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Rectangular Table wit				egs	er Support Le	k Table with Cente	Rectangular Oa
Center Support Leç	\$2,561	\$2,732	165	29" x 30" x 90"	Adult Table	77-198-S02 OAK	77-198-S00 OAK
	\$2,561	\$2,732	165	27-1/2" x 30" x 90"	Youth Table	77-Y98-S02 OAK	77-Y98-S00 OAK
	\$2,561	\$2,732	165	25" x 30" x 90"	Juvenile Table	77-J98-S02 OAK	77-J98-S00 OAK
	\$2,641	\$2,813	165	29" x 36" x 90"	Adult Table	77-146-S02 OAK	77-146-S00 OAK
	\$2,641	\$2,813	165	27-1/2" x 36" x 90"	Youth Table	77-Y46-S02 OAK	77-Y46-S00 OAK
	\$2,641	\$2,813	165	25" x 36" x 90"	Juvenile Table	77-J46-S02 OAK	77-J46-S00 OAK
A	\$2,879	\$3,079	185	29" x 48" x 90"	Adult Table	77-134-S02 OAK	77-134-S00 OAK
	\$2,879	\$3,079	185	27-1/2" x 48" x 90"	Youth Table	77-Y34-S02 OAK	77-Y34S00 OAK
	\$2,879	\$3,079	185	25" x 48" x 90"	Juvenile Table	77-J34-S02 OAK	77-J34-S00 OAK
				<u>Legs</u>	nter Support	ple Table with Cel	Rectangular Ma
	\$2,791	\$2,979	165	29" x 30" x 90"	Adult Table	77-198-S02 MAP	77-198-S00 MAP
	\$2,791	\$2,979	165	27-1/2" x 30" x 90"	Youth Table	77-Y98-S02 MAP	77-Y98-S00 MAP
	\$2,791	\$2,979	165	25" x 30" x 90"	Juvenile Table	77-J98-S02 MAP	77-J98-S00 MAP
	\$2,879	\$3,067	165	29" x 36" x 90"	Adult Table	77-146-S02 MAP	77-146-S00 MAP
	\$2,879	\$3,067	165	27-1/2" x 36" x 90"	Youth Table	77-Y46-S02 MAP	77-Y46-S00 MAP
	\$2,879	\$3,067	165	25" x 36" x 90"	Juvenile Table	77-J46-S02 MAP	77-J46-S00 MAP
	\$3,138	\$3,357	185	29" x 48" x 90"	Adult Table	77-134-S02 MAP	77-134-S00 MAP
	\$3,138	\$3,357	185	27-1/2" x 48" x 90"	Youth Table	77-Y34-S02 MAP	77-Y34-S00 MAP
	\$3,138	\$3,357	185	25" x 48" x 90"	Juvenile Table	77-J34-S02 MAP	77-J34-S00 MAP

#### **TABLETOPS**


Standard tabletops are 1-3/16" thick, 5-ply solid-lumber core, except 90"W tables which have a 1-3/16" thick particleboard core, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thickness for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are solid maple. Drop edge band is 5/8" thick x 1-5/8" externally banded to form a bullnose.

#### **TABLE LEGS**


Each leg is 2-1/2" diameter, 16-gauge steel tubing and has a 3-1/2" diameter x 2-5/8"H glued-up maple bun-foot as a design feature. Each bun-foot has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the bun-foot by means of a counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is fillet-welded to the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind, and be hidden by, the extended table edge band.

#### **TABLETOP SUPPORT**


For maximum rigidity, rectangular tables, 60" or more wide, receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 90" or wider receive two extra matching legs located under the center of the table to provide added support.



Horizons Drop Edge



Horizons Metal Leg



Horizons External Edge Band

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Round Oak Table	<u>e</u>						Round Table
77M-Y09-S00 OAK	77M-109-S02 OAK 77M-Y09-S02 OAK 77M-J09-S02 OAK	Adult Table Youth Table Juvenile Table	29"H x 36" Diameter 27-1/2"H x 36" Diameter 25"H x 36" Diameter	100 100 100	\$2,159 \$2,159 \$2,159	\$2,025 \$2,025 \$2,025	
77M-Y29-S00 OAK	77M-129-S02 OAK 77M-Y29-S02 OAK 77M-J29-S02 OAK	Adult Table Youth Table Juvenile Table	29"H x 42" Diameter 27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110 110	\$2,280 \$2,280 \$2,280	\$2,145 \$2,145 \$2,145	
77M-Y41-S00 OAK	77M-141-S02 OAK 77M-Y41-S02 OAK 77M-J41-S02 OAK	Adult Table Youth Table Juvenile Table	29"H x 48" Diameter 27-1/2"H x 48" Diameter 25"H x 48" Diameter	120 120 120	\$2,280 \$2,280 \$2,280	\$2,145 \$2,145 \$2,145	
N/A N/A N/A	77M-130-S02 OAK 77M-Y30-S02 OAK 77M-J30-S02 OAK		29"H x 60" Diameter 27-1/2"H x 60" Diameter 25"H x 60" Diameter	140 140 140	N/A N/A N/A	\$2,575 \$2,575 \$2,575	
Round Maple Ta	ble						
77M-109-S00 MAP 77M-Y09-S00 MAP	77M-109-S02 MAP 77M-Y09-S02 MAP 77M-J09-S02 MAP	Adult Table Youth Table Juvenile Table	29"H x 36" Diameter 27-1/2"H x 36" Diameter 25"H x 36" Diameter	100 100 100	\$2,353 \$2,353 \$2,353	\$2,207 \$2,207 \$2,207	
77M-Y29-S00 MAP	77M-129-S02 MAP 77M-Y29-S02 MAP 77M-J29-S02 MAP	Adult Table Youth Table Juvenile Table	29"H x 42" Diameter 27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110 110	\$2,485 \$2,485 \$2,485	\$2,338 \$2,338 \$2,338	
77M-Y41-S00 MAP	77M-141-S02 MAP 77M-Y41-S02 MAP 77M-J41-S02 MAP		29"H x 48" Diameter 27-1/2"H x 48" Diameter 25"H x 48" Diameter	120 120 120	\$2,485 \$2,485 \$2,485	\$2,338 \$2,338 \$2,338	
N/A N/A N/A	77M-130-S02 MAP 77M-Y30-S02 MAP 77M-J30-S02 MAP		29"H x 60" Diameter 27-1/2"H x 60" Diameter 25"H x 60" Diameter	140 140 140	N/A N/A N/A	\$2,806 \$2,806 \$2,806	
Square Oak Tab	le.						Square Table
77M-191-S00 OAK 77M-Y91-S00 OAK	77M-191-S02 OAK 77M-Y91-S02 OAK 77M-J91-S02 OAK	Adult Table Youth Table Juvenile Table	29" x 30" x 30" 27-1/2" x 30" x 30" 25" x 30" x 30"	110 110 110	\$1,744 \$1,744 \$1,744	\$1,571 \$1,571 \$1,571	Square Table
77M-Y37-S00 OAK	77M-137-S02 OAK 77M-Y37-S02 OAK 77M-J37-S02 OAK	Youth Table	29" x 42" x 42" 27-1/2" x 42" x 42" 25" x 42" x 42"	110 110 110	\$1,865 \$1,865 \$1,865	\$1,692 \$1,692 \$1,692	
77M-Y54-S00 OAK	77M-154-S02 OAK 77M-Y54-S02 OAK 77M-J54-S02 OAK		29" x 48" x 48" 27-1/2" x 48" x 48" 25" x 48" x 48"	110 110 110	\$1,999 \$1,999 \$1,999	\$1,827 \$1,827 \$1,827	
Square Maple Ta	able						
77M-191-S00 MAP 77M-Y91-S00 MAP	77M-191-S02 MAP 77M-Y91-S02 MAP 77M-J91-S02 MAP		29" x 30" x 30" 27-1/2" x 30" x 30" 25" x 30" x 30"	110 110 110	\$1,901 \$1,901 \$1,901	\$1,712 \$1,712 \$1,712	
77M-Y37-S00 MAP	77M-137-S02 MAP 77M-Y37-S02 MAP 77M-J37-S02 MAP		29" x 42" x 42" 27-1/2" x 42" x 42" 25" x 42" x 42"	110 110 110	\$2,033 \$2,033 \$2,033	\$1,844 \$1,844 \$1,844	
77M-Y54-S00 MAP	77M-154-S02 MAP 77M-Y54-S02 MAP 77M-J54-S02 MAP	Adult Table	29" x 48" x 48" 27-1/2" x 48" x 48" 25" x 48" x 48"	110 110 110	\$2,180 \$2,180 \$2,180	\$1,991 \$1,991 \$1,991	

Please specify Wood Finish (Table 1) High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Red	tangular Oak Tabl	<u>e</u>				
Rectrangular Table	77M-194-S00 OAK	77M-194-S02 OAK	Adult Table	29" x 30" x 60"	120	\$2,045	\$1,832
	77M-Y94-S00 OAK	77M-Y94-S02 OAK	Youth Table	27-1/2" x 30" x 60"	120	\$2,045	\$1,832
	77M-J94-S00 OAK	77M-J94-S02 OAK	Juvenile Table	25" x 30" x 60"	120	\$2,045	\$1,832
	77M-195-S00 OAK	77M-195-S02 OAK	Adult Table	29" x 30" x 72"	140	\$2,154	\$1,973
	77M-Y95-S00 OAK	77M-Y95-S02 OAK	Youth Table	27-1/2" x 30" x 72"	140	\$2,154	\$1,973
	77M-J95-S00 OAK	77M-J95-S02 OAK	Juvenile Table	25" x 30" x 72"	140	\$2,154	\$1,973
	Four-Reader Red	tangular Maple Ta	<u>ble</u>				
	77M-194-S00 MAP	77M-194-S02 MAP	Adult Table	29" x 30" x 60"	120	\$2,229	\$1,997
	77M-Y94-S00 MAP	77M-Y94-S02 MAP	Youth Table	27-1/2" x 30" x 60"	120	\$2,229	\$1,997
	77M-J94-S00 MAP	77M-J94-S02 MAP	Juvenile Table	25" x 30" x 60"	120	\$2,229	\$1,997
	77M-195-S00 MAP	77M-195-S02 MAP	Adult Table	29" x 30" x 72"	140	\$2,348	\$2,150
	77M-Y95-S00 MAP	77M-Y95-S02 MAP	Youth Table	27-1/2" x 30" x 72"	140	\$2,348	\$2,150
	77M-J95-S00 MAP	77M-J95-S02 MAP	Juvenile Table	25" x 30" x 72"	140	\$2,348	\$2,150

Six-Reader	Six-Reader Recta	<u>angular Oak Table</u>					
Rectrangular Table	77M-144-S00 OAK	77M-144-S02 OAK	Adult Table	29" x 36" x 60"	120	\$2,099	\$1,911
•	77M-Y44-S00 OAK	77M-Y44-S02 OAK	Youth Table	27-1/2" x 36" x 60"	120	\$2,099	\$1,911
	77M-J44-S00 OAK	77M-J44-S02 OAK	Juvenile Table	25" x 36" x 60"	120	\$2,099	\$1,911
	77M-138-S00 OAK	77M-138-S02 OAK	Adult Table	29" x 36" x 72"	140	\$2,235	\$2,052
	77M-Y38-S00 OAK	77M-Y38-S02 OAK	Youth Table	27-1/2" x 36" x 72"	140	\$2,235	\$2,052
3	77M-J38-S00 OAK	77M-J38-S02 OAK	Juvenile Table	25" x 36" x 72"	140	\$2,235	\$2,052
O.	77M-145-S00 OAK	77M-145-S02 OAK	Adult Table	29" x 48" x 72"	170	\$2,856	\$2,394
	77M-Y45-S00 OAK	77M-Y45-S02 OAK	Youth Table	27-1/2" x 48" x 72"	170	\$2,856	\$2,394
	77M-J45-S00 OAK	77M-J45-S02 OAK	Juvenile Table	25" x 48" x 72"	170	\$2,856	\$2,394
	Six-Reader Recta	angular Maple Tab	o <u>le</u>				
	77M-144-S00 MAP	77M-144-S02 MAP	Adult Table	29" x 36" x 60"	120	\$2,287	\$2,084
	77M-Y44-S00 MAP	77M-Y44-S02 MAP	Youth Table	27-1/2" x 36" x 60"	120	\$2,287	\$2,084
	77M-J44-S00 MAP	77M-J44-S02 MAP	Juvenile Table	25" x 36" x 60"	120	\$2,287	\$2,084
	77M-138-S00 MAP	77M-138-S02 MAP	Adult Table	29" x 36" x 72"	140	\$2,436	\$2,237
	77M-Y38-S00 MAP	77M-Y38-S02 MAP	Youth Table	27-1/2" x 36" x 72"	140	\$2,436	\$2,237
	77M-J38-S00 MAP	77M-J38-S02 MAP	Juvenile Table	25" x 36" x 72"	140	\$2,436	\$2,237
	77M-145-S00 MAP	77M-145-S02 MAP	Adult Table	29" x 48" x 72"	170	\$3,113	\$2,609
	77M-Y45-S00 MAP	77M-Y45-S02 MAP	Youth Table	27-1/2" x 48" x 72"	170	\$3,113	\$2,609
	77M-J45-S00 MAP	77M-J45-S02 MAP	Juvenile Table	25" x 48" x 72"	170	\$3,113	\$2,609

Please specify Wood Finish (Table 1) High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

	Particleboard Core Price	Plywood Core Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Rectangular Table wi				<u>gs</u>	Support Le	Table with Center	Rectangular Oak
Center Support Le	\$2,710	\$2,732	165	29" x 30" x 90"	Adult Table	77M-198-S02 OAK	77M-198-S00 OAK
	\$2,710	\$2,732	165	27-1/2" x 30" x 90"	Youth Table	77M-Y98-S02 OAK	77M-Y98-S00 OAK
	\$2,710	\$2,732	165	25" x 30" x 90"	Juvenile Table	77M-J98-S02 OAK	77M-J98-S00 OAK
	\$2,790	\$3,006	165	29" x 36" x 90"	Adult Table	77M-146-S02 OAK	77M-146-S00 OAK
	\$2,790	\$3,006	165	27-1/2" x 36" x 90"	Youth Table	77M-Y46-S02 OAK	77M-Y46-S00 OAK
	\$2,790	\$3,006	165	25" x 36" x 90"	Juvenile Table	77M-J46-S02 OAK	77M-J46-S00 OAK
8	\$3,072	\$3,272	185	29" x 48" x 90"	Adult Table	77M-134-S02 OAK	77M-134-S00 OAK
	\$3,072	\$3,272	185	27-1/2" x 48" x 90"	Youth Table	77M-Y34-S02 OAK	77M-Y34S00 OAK
	\$3,072	\$3,272	185	25" x 48" x 90"	Juvenile Table	77M-J34-S02 OAK	77M-J34-S00 OAK
				<u>Legs</u>	ter Support l	ole Table with Cent	Rectangular Map
	\$2,954	\$2,979	165	29" x 30" x 90"	Adult Table	77M-198-S02 MAP	77M-198-S00 MAP
	\$2,954	\$2,979	165	27-1/2" x 30" x 90"	Youth Table	77M-Y98-S02 MAP	77M-Y98-S00 MAP
	\$2,954	\$2,979	165	25" x 30" x 90"	Juvenile Table	77M-J98-S02 MAP	77M-J98-S00 MAP
	\$3,041	\$3,277	165	29" x 36" x 90"	Adult Table	77M-146-S02 MAP	77M-146-S00 MAP
	\$3,041	\$3,277	165	27-1/2" x 36" x 90"	Youth Table	77M-Y46-S02 MAP	77M-Y46-S00 MAP
	\$3,041	\$3,277	165	25" x 36" x 90"	Juvenile Table	77M-J46-S02 MAP	77M-J46-S00 MAP
	\$3,349	\$3,567	185	29" x 48" x 90"	Adult Table	77M-134-S02 MAP	77M-134-S00 MAP
	\$3,349	\$3,567	185	27-1/2" x 48" x 90"	Youth Table	77M-Y34-S02 MAP	77M-Y34-S00 MAP
	\$3,349	\$3,567	185	25" x 48" x 90"	Juvenile Table	77M-J34-S02 MAP	77M-J34-S00 MAP

Please specify Wood Finish (Table 1) High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

#### WORKSTATIONS

Workstations are of modular starter and adder design, with overall height 33". Workstations are available in 36", 48", 72", 96" and 108" widths. A knee-space panel located below the work surface supports all work surfaces greater than 48"W. Work surface height is 27-1/2". Work surface depth is 27-1/2" with an additional 1-1/2"W cord drop between the work surface and back panel to allow passage of electrical cords. Work surface is attached to end and intermediate panels by means of two metal 22-1/2" long "Z" brackets with 5/16" – 18 hex-head bolts engaging internally and externally threaded bushings embedded into panels. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end and intermediate panels and back panels with 3/4" x 3/4" steel, black painted angle brackets and black #8 screws.

#### **WORK SURFACE**

Standard work surface is 1-3/16" thick, 3-ply, 45# density particleboard, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thickness for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Front edge of work surface has a 5/8" x 1-5/8" solid maple edge band in a half-round bullnose shape. The back edge of the top has a black plastic band 1-1/2"W which projects above the work surface 1/4" to act as a retainer.

#### **END AND INTERMEDIATE PANELS**

End panels are 1" thick and intermediate panels are 1-3/16" thick particleboard with select face veneers of maple wood. All edges are banded with a 5/8" maple wood edge band. Intermediate panels receive a 3" diameter grommet below the work surface to allow passage of electrical and data wires. Each panel receives two 1-1/4" adjustable glides.

#### **BACK PANEL**

Back panel is 3/4" thick, 45# density particleboard core with face veneers of select maple wood. The top and bottom edges of the back panel receive 1.6mm thick maple wood edge bands. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The back panel on double-faced units receives a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### **DESIGN CUTOUTS**

The wooden 1" thick end panels have a laser cut out design as selected by the customer. The inside edges of the cutout are blackened to provide a finished appearance. Cutouts are available on starter units only (end panels).

#### **SHELF**


Shelf is 3/4" thick x 8"D 45# density particleboard core with face veneers of select maple wood. Shelf is banded on the front edge with a 1.6mm maple wood band. Shelf attachs to end and intermediate panels by means of a pair of metal "L" brackets. Back corners of shelf have a 3" x 3" cutout to allow for the passage of electrical cords. The shelf is positioned 10" below the bottom of the work surface.

#### WIRE MANAGEMENT DOOR

The wire management door is positioned between the bottom of the work surface and the shelf and is designed to form a concealed wire management channel 8-1/2"H x 9-1/2"D. The door is 1/4" thick with select maple wood face veneers. The door slides in two aluminum tracks, one that is attached to the bottom of the work surface while the other is attached to the top of the shelf.

#### **KNEE-SPACE PANEL**

All 72" and 96"W workstations, as well as functional corner units, have a knee-space panel positioned under the work surface for additional work surface support. Units 108"W have two knee-space panels. The knee-space panel is 1-1/8" thick, 45# density particleboard core with select face veneers of maple wood. The panel is banded on exposed edges with a 1.6mm maple wood band. The knee-space panel is attached to the back panel using a 1-3/4" square post, grooved to receive the knee space panel and back panels. Panels attach to the post using recessed metal fasteners and shoulder screws. The knee-space panel is angled in the back to create a space to allow passage of electrical and data cords. The knee-space panel receives two 1-1/4" diameter black adjustable glides.



\_HOR 22 \_

# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Workii	ng Space						Single-Faced One-Position
77-S31-SS0 OAK	77-S31-SS0 MAP	One-Position S/F Starter	33-1/2" x 37-1/2" x 31"	130	\$2,348	\$2,560	Starter
77-S31-SA0 OAK	77-S31-SA0 MAP	One-Position S/F Adder	33-1/2" x 36-1/2" x 31"	100	\$1,751	\$1,909	a Da
48" Wide Workii	ng Space						
77-S41-SS0 OAK	77-S41-SS0 MAP	One-Position S/F Starter	33-1/2" x 49-1/4" x 31"	155	\$2,496	\$2,721	Adder
77-S41-SA0 OAK	77-S41-SA0 MAP	One-Position S/F Adder	33-1/2" x 48" x 31"	125	\$1,860	\$2,028	

36" Wide Workin	ng Space						Double-Faced One-Position
77-D31-SS0 OAK	77-D31-SS0 MAP	One-Position	33-1/2" x 37-1/2" x 59-1/2"	215	\$4,282	\$4,668	Starter
77-D31-SA0 OAK	77-D31-SA0 MAP	D/F Starter One-Position D/F Adder	33-1/2" x 36-1/2" x 59-1/2"	155	\$3,120	\$3,401	A A A A
48" Wide Workin	g Space						
77-D41-SS0 OAK	77-D41-SS0 MAP	One-Position D/F Starter	33-1/2" x 49-1/4" x 59-1/2"	255	\$4,539	\$4,947	
77-D41-SA0 OAK	77-D41-SA0 MAP	One-Position D/F Adder	33-1/2" x 48" x 59-1/2"	195	\$3,356	\$3,658	Adder

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
36" Wide Worki	ing Space					
77-S32-SS0 OAK	77-S32-SS0 MAP	Two-Position S/F Starter	33-1/2" x 74" x 31"	195	\$3,160	\$3,444
77-S32-SAO OAK	77-S32-SA0 MAP	Two-Position S/F Adder	33-1/2" x 73" x 31"	165	\$2,525	\$2,752
48" Wide Worki	ing Space					
77-S42-SS0 OAK	77-S42-SS0 MAP	Two-Position S/F Starter	33-1/2" x 97-1/4" x 31"	235	\$3,401	\$3,707
77-S42-SA0 OAK	77-S42-SA0 MAP	Two-Position S/F Adder	33-1/2" x 96" x 31"	205	\$2,752	\$3,001
	Catalog No.  36" Wide Worki 77-S32-SS0 OAK 77-S32-SA0 OAK  48" Wide Worki 77-S42-SS0 OAK	Catalog No.         Catalog No.           36" Wide Working Space           77-S32-SS0 OAK         77-S32-SS0 MAP           77-S32-SA0 OAK         77-S32-SA0 MAP           48" Wide Working Space         77-S42-SS0 OAK           77-S42-SS0 OAK         77-S42-SS0 MAP	Catalog No.         Catalog No.         Description           36" Wide Working Space         77-S32-SS0 MAP         Two-Position S/F Starter           77-S32-SA0 OAK         77-S32-SA0 MAP         Two-Position S/F Adder           48" Wide Working Space         77-S42-SS0 OAK         Tvo-Position S/F Starter           77-S42-SA0 OAK         77-S42-SA0 MAP         Two-Position S/F Starter           77-S42-SA0 OAK         77-S42-SA0 MAP         Two-Position	Catalog No.         Description         H x W x D           36" Wide Working Space           77-S32-SS0 OAK         77-S32-SS0 MAP         Two-Position S/F Starter           77-S32-SA0 OAK         77-S32-SA0 MAP         Two-Position 33-1/2" x 73" x 31" S/F Adder           48" Wide Working Space           77-S42-SS0 OAK         77-S42-SS0 MAP         Two-Position 33-1/2" x 97-1/4" x 31" S/F Starter           77-S42-SA0 OAK         77-S42-SA0 MAP         Two-Position 33-1/2" x 96" x 31"	Catalog No.         Catalog No.         Description         H x W x D         (lbs.)           36" Wide Working Space         77-S32-SS0 MAP         Two-Position S/F Starter         33-1/2" x 74" x 31"         195           77-S32-SA0 OAK         77-S32-SA0 MAP         Two-Position S/F Adder         33-1/2" x 73" x 31"         165           48" Wide Working Space         77-S42-SS0 OAK         77-S42-SS0 MAP         Two-Position S/F Starter         33-1/2" x 97-1/4" x 31"         235           77-S42-SA0 OAK         77-S42-SA0 MAP         Two-Position S/F Starter         33-1/2" x 96" x 31"         205	Catalog No.         Description         H x W x D         (lbs.)         Price           36" Wide Working Space         77-S32-SS0 OAK         77-S32-SS0 MAP         Two-Position S/F Starter         33-1/2" x 74" x 31"         195         \$3,160           77-S32-SA0 OAK         77-S32-SA0 MAP         Two-Position S/F Adder         33-1/2" x 73" x 31"         165         \$2,525           48" Wide Working Space         77-S42-SS0 OAK         77-S42-SS0 MAP         Two-Position S/F Starter         33-1/2" x 97-1/4" x 31"         235         \$3,401           77-S42-SA0 OAK         77-S42-SA0 MAP         Two-Position 33-1/2" x 96" x 31"         205         \$2,752

Double-Faced Two-Position	36" Wide Worki	ing Space					
Starter	77-D32-SS0 OAK	77-D32-SS0 MAP	Two-Position D/F Starter	33-1/2" x 74" x 59-1/2"	330	\$5,702	\$6,215
0 1 1 0 0	77-D32-SAO OAK	77-D32-SA0 MAP	Two-Position D/F Adder	33-1/2" x 73" x 59-1/2"	270	\$4,567	\$4,978
	48" Wide Worki	ing Space					
	77-D42-SS0 OAK	77-D42-SS0 MAP	Two-Position D/F Starter	33-1/2" x 97-1/4" x 59-1/2"	410	\$6,117	\$6,668
Adder	77-D42-SAO OAK	77-D42-SA0 MAP	Two-Position D/F Adder	33-1/2" x 96" x 59-1/2"	155	\$4,977	\$5,425

# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Workii	ng Space						Single-Faced Three-Position
77-S33-SS0 OAK	77-S33-SS0 MAP	Three-Position S/F Starter	33-1/2" x 110-1/2" x 31"	260	\$4,125	\$4,496	Starter
						7	O HOLD
							Adder
77-S33-SAO OAK	77-S33-SA0 MAP	Three-Position S/F Adder	33-1/2" x 109-1/4" x 31"	230	\$3,322	\$3,621	

36" Wide Working	<u>Space</u>					Double-Faced Three-Position
77-D33-SS0 OAK	77-D33-SS0 MAP	Three-Position	33-1/2" x 110-1/2" x 59-1/2"	445	\$7,456	\$8,127 Starter
		D/F Starter				4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4
						Adder
77-D33-SA0 OAK	77-D33-SA0 MAP	Three Position D/F Adder	33-1/2" x 109-1/4" x 59-1/2"	385	\$6,263	\$6,826

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
90° Functional Corner Unit	36" Wide Worki	ng Space					
Starter	77-SCR-SSO OAK	77-SCR-SSO MAP	90-Degree Functional Corner Starter	33-1/2" x 62" x 31"	225	\$4,937	\$5,381
Adder	77-SCR-SAO OAK	77-SCR-SAO MAP	90-Degree Functional Corner Adder	33-1/2" x 62" x 31"	195	\$4,432	\$4,831

# The Horizons Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
77-112-S00 OAK	77-112-S00 MAP	D/F Book Browser 3 with 2 Cutouts per pane	33-3/4" x 57-3/4" x 35-3/4" !	300	\$6,509	\$7,095	Double-Faced Mobile Book Browser
		The bottom portion has	ction. The top portion has (8) 13 (8) 16-1/2"H x 13"W x 17"D s casters (which are supplied). Ea	storage compar	tments. The ur	nit is	with 2 Cutouts per Panel
		_	wooden 1" thick end panels ha e customer. The inside edges of			-	e w
77-262-S00 OAK	77-262-S00 MAP	D/F Book Mobile Brows with 3 Cutouts per pane		200	\$2,704	\$2,947	Double-Faced Book Browser with 3 Cutouts per Panel
			ction. The top portion has (4) 10 ad panel receives two floor leveli		3/16''D displa	ny	3
			wooden 1" thick end panels ha osen by the customer. The inside pearance.				
77-263-S00 OAK	77-263-S00 MAP	with 2 Cutouts per pane Maple plywood constru	ser24-3/4" x 25" x 23*3/4" el ction. The top portion has (2) 10 is (1) bench seat. Each end pane		-	-	Single-Faced Mobile Book Browser with Seat and 2 Cutouts per Panel
		_	wooden 1" thick end panels ha osen by the customer. The inside pearance.		-	-	Z'nne
77-264-S00 OAK	77-264-S00 MAP	D/F Book Mobile Brows with 4 Cutouts per pane	ser 24-5/8" x 25" x 45"	190	\$3,792	\$4,133	Double-Faced Mobile Book Browser with Seat
			ction. The top portion has (4) 10 is (2) bench seats, 23" W x 10"			-	and 4 Cutouts per Panel
		_	wooden 1" thick end panels ha osen by the customer. The inside pearance.				The state of the s

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Picture Book Displayer with Cutout	77-140-S00 OAK	77-140-S00 MAP	Picture Book Table with 3 Cutouts per panel	31-1/2" x 48-1/2" x 34-1/2"	100	\$3,506	\$3,822
	77-142-S00 OAK	77-142-S00 MAP	Picture Book Table with 3 Cutouts per panel	31-1/2" x 78-1/2" x 34-1/2"	190	\$3,896	\$4,247
			high-pressure laminate, wi construction. High-pressur staining that meets or exce thick, externally banded to tops, is a display book bin <b>Design cutouts:</b> The wo and have a laser cut chose to provide a finished appear	nick, particleboard core, including a ith a backing sheet not less than .02 re laminate has a lo-glare finish resiseeds NEMA standards. Edges are so of form a bullnose. Loaded in the cen 3-3/4"W running the full length of noden 1" thick end panels have a 24 on by the customer. The inside edges arance.  Book Tables are located in the Dis	20" thickn stant to so lid maple. ter of the t the table. " radius o s of the cut	ess for balar ratches, fadi The edge ba able, betwee on the top ed out are black	nced ing, and and is 5/8" en the two ige

#### END PANELS

77L-723-MOD OAK

77L-725-MOD OAK

77L-726-MOD OAK

77L-728-MOD OAK

77L-729-MOD OAK

77L-731-MOD OAK

77L-732-MOD OAK

77L-734-MOD OAK

77L-735-MOD OAK

77L-723-MOD MAP

77L-725-MOD MAP

77L-726-MOD MAP

77L-728-MOD MAP

77L-729-MOD MAP

77L731-MOD MAP

77L-732-MOD MAP

77L-734-MOD MAP

77L-735-MOD MAP

43-3/4" x 28-3/8"

67-3/4" x 24-3/8"

67-3/4" x 28-3/8"

79-3/4" x 24-3/8"

79-3/4" x 28-3/8"

85-3/4" x 24-3/8"

85-3/4" x 28-3/8"

91-3/4" x 24-3/8"

91-3/4" x 28-3/8"

The end panel is of maple plywood construction 1-14" thick with 1.6mm banded edges. The end panel has a large cutout design as selected by the customer. The inside edges of the cutouts are blackened to provide a finished appearance. When the cutout design is large enough, a matching cutout of colored high-pressure laminate is inlaid in the cutout of the panel. When the cutout is small (such as the sports stick figures) no high-pressure laminate is inlaid but the panel is 1" thick maple plywood construction and the cutout goes completely through the panel. End panels are not machined. No fastening hardware is provided with end panels.

End panels for steel shelving with continuous tops or canopy top inset are designed to have the canopy top "inset" between the end panels.

Note: Exact height and depth of panel must be specified when ordering.

Oak Catalog No.	Maple Catalog No.	Description	# of Cutouts per Panel	Wt. (lbs.)	Oak Price	Maple Price	
77L-702-MOD OAK	77L-702-MOD MAP	43-3/4" x 13-7/8"	3	14	\$1,025	\$1,076	Single-Faced w/Laser Cutouts
77L-703-MOD OAK	77L-703-MOD MAP	43-3/4" x 15-7/8"	3	16	\$1,032	\$1,083	& Laminate Inlays End Panels
77L-705-MOD OAK 77L-706-MOD OAK	77L-705-MOD MAP 77L-706-MOD MAP	67-3/4" x 13-7/8" 67-3/4" x 15-7/8"	4 4	21 26	\$1,290 \$1,301	\$1,354 \$1,366	<b>6</b> °:
77L-708-MOD OAK	77L-708-MOD MAP	79-3/4" x 13-7/8"	4	25	\$1,375	\$1,443	
77L-709-MOD OAK	77L-709-MOD MAP	79-3/4" x 15-7/8"	4	30	\$1,390	\$1,459	7"
77L-711-MOD OAK	77L-711-MOD MAP	85-3/4" x 13-7/8"	4	28	\$1,415	\$1,486	
77L-712-MOD OAK	77L-712-MOD MAP	85-3/4" x 15-7/8"	4	33	\$1,432	\$1,504	
77L-714-MOD OAK	77L-714-MOD MAP	91-3/4" x 13-7/8"	5	29	\$1,552	\$1,630	
77L-715-MOD OAK	77L-715-MOD MAP	91-3/4" x 15-7/8"	5	35	\$1,568	\$1,647	
							豪
77L-722-MOD OAK	77L-722-MOD MAP	43-3/4" x 24-3/8"	3	27	\$1,110	\$1,166	Double-Faced w/Laser Cutouts

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

Note: Specify Cutout Design. Details can be found on page HOR 32.

3

4

4

4

4

4

5

5

33

43

52

51

61

55

66

59

60

\$1,127

\$1,447

\$1,467

\$1,540

\$1,563

\$1,586

\$1,612

\$1,728

\$1,753

\$1,184

\$1,519

\$1,541

\$1,617

\$1,641

\$1,665

\$1,692

\$1,814

\$1,840

& Laminate Inlays End Panels

#### **CHAIR FRAME**

Each frame member is constructed from 1-1/4" hardwoods. All frame joints are mortised, tenoned and glued. All frames have a 3/4" solid hardwood support brace in each corner to give the chair added strength. All seats are fastened with six "Z" brackets routed into the frame and screwed into the bottom of the seat.

#### **CHAIR SEAT**

Chair seats are 1/2" thick bent multi-ply faced with select hardwood veneers.

#### **UPHOLSTERED SEAT**

Upholstered seats receive 1-1/2" thick HR-55, 2.8 density 55 ILD foam prior to being covered by a selected upholstery material that is wrapped around and stapled to the underside of the seat panel.

#### WOOD CHAIR BACKS

Chair backs are 5/8" thick bent multi-ply faced with select hardwood veneers. Adult backs: 6-1/2"H x 20-1/4"W. Youth backs: 5-7/8"H x 17-3/8"W.

#### **DESIGN CUTOUTS**

The wood chair backs only have a laser cutout design as selected by the customer. The inside edges of the cutout are blackened to provide a finished appearance.


#### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire-rated.


Fabrics that meet Calif. Technical Bulletin #133 are available.

#### **GLIDES**

Each chair leg is equipped with a 7/8" diameter rubber-cushioned glide.



# Upholstered Seat Chair with Cutouts



## Wood Frame Chair with Upholstered Seat

77-572-S00	31-1/4"H Adult	18" x 20" x 19-5/8"	23	\$655	\$648	\$734	\$760	\$946	\$1,001
77-562-S00	28-1/4"H Youth	16" x 16" x 17-1/4"	22	\$655	\$648	\$734	\$760	\$946	\$1,001

Fabric Requirements: 3/4 yard per chair, Non-directional, 54" wide.

Please specify Wood Finish (Table 1) and Upholstery (Table 5). Details can be found on pages GEN 4 and GEN 5.

Note: Specify Cutout Design. Details can be found on page HOR 32.

#### **CHAIR FRAME**

The chair frame is constructed of 16-gauge steel tubing. All joints are mig-welded. The front and back legs are 1-34" diameter and the side and front stretchers are 1-1/2" x 3/4" rectangular tubing. The framing includes four metal brackets attaching the seat.

#### **CHAIR SEAT**

Chair seats are 5/8" thick bent multi-ply faced with maple.

#### **UPHOLSTERED SEAT**

Upholstered seats receive 1-1/2" thick HR-55, 2.8 density 55 ILD foam prior to being covered by a selected upholstery material that is wrapped around and stapled to the underside of the seat panel.

#### WOOD CHAIR BACKS

Chair backs are 5/8" thick bent multi-ply faced with maple. Adult backs: 10"H x 19-1/2"W. Youth backs: 8"H x 15-7/8"W.

#### **DESIGN CUTOUTS**

The wood chair backs only have a laser cutout design as selected by the customer. The inside edges of the cutout are blackened to provide a finished appearance.

#### **UPHOLSTERY MATERIALS AND FABRICS**


Brodart fabric selections and polyurethane foam are fire-rated. Fabrics that meet Calif. Technical Bulletin #133 are available.


#### **BALL GLIDES**

Each chair leg ends with a 2" diameter solid maple ball glide. The bottom of the ball glide has a surface of high-density polyethylene to protect the glide and floor.

Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Wood Seat an	d Back with Cu	ıtouts and Metal I	rame C	hair, Oal	k Wood					Wood Seat/Back Chair w/Cutouts
77A-571-S00 OAK	32-1/2"H Adult	18" x 20-1/4" x 17-1/	2" 25		\$846					W/ Outouts
77A-561-S00 OAK	28"H Youth	16" x 17-1/8" x 15'	25		\$846					D . V
Wood Seat an	d Back with Cu	utouts and Metal I	rame C	hair, Ma	ple Wood					
77A-571-S00 MAP	32-1/2"H Adult	18" x 20-1/4" x 17-1/	2" 25		\$872					
77A-561-S00 MAP	28"H Youth	16" x 17-1/8" x 15'	25		\$872					

Upholstered a	nd Wood Back	with Cutouts and M	etal Fi	ame Chair	r, Oak Wo	ood			
77A-572-S00 OAK 77A-562-S00 OAK	32-1/2"H Adult 28"H Youth	18" x 20-1/4" x 17-1/2" 16" x 17-1/8" x 15"	25 25	\$954 \$902	\$947 \$897	\$1,079 \$1,010	\$1,108 \$1,045	\$1,383 \$1,309	\$1,463 \$1,384
<u>Upholstered a</u>	nd Wood Back	with Cutouts and M	etal Fi	rame Chair	<i>r, Maple</i> I	<i>Nood</i>			






Please specify Wood Finish (Table 1), Metal Color (Table 3) and Upholstery (Table 5). Details can be found on pages GEN 4 and GEN 5.

Note: Specify Cutout Design. Details can be found on page HOR 32.

#### **CUTOUTS**

The following standard cutouts are available at no charge. Cutouts must be specified for each product and each location on the furniture item. All cutouts are available in most positions on the furniture. Please contact Brodart for a cutout location page for each specific product you have interest in. Custom designs are available on a quote-per-design basis.

Note: The cutout size varies depending on location.



**-HOR 32 –** F11-1-19G-HOR

# The Matrix Collection

#### DESKTOP

Standard desktops are 1-3/16" thick, 45# density particleboard core, with a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Top receives a 5/8" thick, solid northern-grown white maple edge band on the patron side, and it is of a straight design with a 1/4" radius on the top and bottom edges. The remaining three edges receive a 1/4" solid white maple band with 1/8 radius. All four edges are externally banded being applied after the laminate and backing. The top sits flush with the unit's ends and back side and overhangs 2-1/2" at the front side. (See band variation on adjustable or set in work surfaces.)

#### **END PANELS**

Desk module end panels are 1" thick, 45# density particleboard core with grade A-A plain-sliced northern grown white maple veneers, slip-matched on both faces. The four edges are banded with matching maple wood banding. The end panels and front panel are joined together with 3/4" x 3/4" cleats and screws. The bottom of each end receives two adjustable leveling glides. Each end also has a 3" diameter grommet hole for power and data cord passage.

#### **DETACHABLE END PANELS**

Detachable end panels are 1" thick, 45# density particleboard core with grade A-A plain-sliced northern grown white maple veneers, slip-matched on both faces. The four edges are banded with matching maple wood banding. The decorative end panel has four bolting holes to attach at the end of a range of desk units. These detachable end panels are offered as a pair. The outside face on the panels receive a series of black 1/2" design squares, two rows of ten squares and one row of nine squares. The design pattern of squares is centered left to right and begins 3-3/4" down from the top edge of the panel.

#### FRONT PANELS

The front panel is 3/4" thick, 45# density particleboard core with Grade A-A plain-sliced, northern-grown white maple veneers, slip-matched on both faces. The edges are banded with matching white maple wood. Connected to the bottom area of the front is a 6"H x 3/4"D recessed, ebonized kick plate. The front panel is positioned over the front edges of the end panels of the desk module, flush with the outside edges of the desk unit. Double-wide units have two front panels to maintain the uniform look of 35"W units for aesthetic purposes. The front panels of all units receive a series of black 1/2" design squares to form a design pattern. Single-wide units receive two rows of 14 squares and one row of 13 squares. Double-wide units receive twice as many squares. The design pattern of squares is centered left to right and begins 3-3/4" down from the top edge of each front. All corner units receive a matching design pattern of 1/2" black squares.

#### ADJUSTABLE WORK SURFACE (Available on limited units)

Work surfaces are 1-3/16" thick, 45# density particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. Plastic laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. The exposed edge at the rear of the desk receives a 1/4" thick, maple internal edge band in straight design with a 1/4" radius on the top and bottom edges. Available in standing height unit only and adjustable to 36", 32" and 27"H.

#### **SHELVES**

Shelves are constructed of plywood with matching wood veneers, the front edge receive a matching maple wood band.

#### **DRAWERS**

Drawers are constructed of solid hardwood with 1/4" thick plywood bottom panel. Fronts are 3/4" thick with matching maple veneer faces and banded edges. Box drawers have 3/4" full extension metal slides, and file drawers have full extension metal slides; each are 100 lb. load capacity.

#### **ELECTRICAL**


See Brodart optional electrical accessories for electrical power distribution and wire management components.

#### **DESK DIMENSIONS**

Standing-Height Desk, Overall: Single Units: 39-3/16"H x 35"W x 30"D Double Units: 39-3/16"H x 70"W x 30"D

Sitting-Height Desk, Overall:


Single Units: 32-3/16"H x 35"W x 30"D Double Units: 32-3/16"H x 70"W x 30"D



Matrix Series Flush Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
93-012-S00 OAK	93-012-S00 MAP	Standing Height Desk with Patron Service Ledge	39-3/16" x 35" x 30"	140	\$2,868	\$3,126	Single-Wide Desk with Patron Service Ledge
		Inside dimensions: 33"W x 26-3/47-7/8" patron ledge is at a height of Note: Adjustable-height work surfat heights of 36", 32" or 27".	of 39-3/16"H.				0
93-E12-S00 OAK	93-E12-S00 MAP	Sitting Height Desk with Patron Service Ledge	32-3/16" x 35" x 30"	125	\$2,730	\$2,976	
		Inside dimensions: 33"W x 26-3/4 7-7/8" patron ledge is at a height o <b>Note</b> : Work surface is fixed at 27"	of 32-3/16"H.				
93-014-S00 OAK	93-014-S00 MAP	Standing Height Desk without Patron Service Ledge	39-3/16" x 35" x 30"	135	\$2,518	\$2,745	Single-Wide Desk without Patron Service Ledge
		Inside dimensions: 33"W x 26-3/4 work surface is at 39-3/16"H. Two grommets are located in the work su	3" diamenter				0
93-E14-S00 OAK	93-E14-S00 MAP	Sitting Height Desk without Patron Service Ledge	32-3/16" x 35" x 30"	120	\$2,273	\$2,477	
		Inside dimensions: 33"W x 26-3/4 work surface is at 32-3/16"H. Two grommets are located in the work su	3" diamenter				0
93-015-S00 OAK	93-015-S00 MAP	Standing Height Book Return Unit	39-3/16" x 35" x 30"	135	\$2,446	\$2,665	Book Return Unit
		Inside dimensions: 33"W x 26-3/4 work surface is at 39-3/16"H. Unit finished opening centered in the fro of books and a book chute to direct depressible book truck. (Depressibl Two 3" diameter grommets are local	has a 5"H x 12"W int panel for passage the books over a mobile be book truck not included).				0
93-E15-S00 OAK	93-E15-S00 MAP	Sitting Height Book Return Unit	32-3/16" x 35" x 30"	120	\$2,309	\$2,516	
		Inside dimensions: 33"W x 26-3/4 work surface is at 32-3/16"H. Unit finished opening centered in the fro of books and a book chute to direct depressible book truck. (Depressibl Two 3" diameter grommets are local	has a 5"H x 12"W int panel for passage the books over a mobile e book truck not included).				0

Standing Sitting Cupboard and Open Shelf	Oak Catalog No. 93-121-S00 OAK	Maple Catalog No. 93-121-S00 MAP	Description Standing Height Cupboard and Open Shelf	HxWxD 39-3/16" x35" x30"	Wt. (lbs.)	Oak Price \$4,684	Maple Price \$5,106
0 0			This unit has one fixed and two adjushelves. A hidden drawer is position the lockable storage compartment. grommets are located in the work storage.	ned above Two 3" diameter urface.			
	93-E21-S00 OAK	93-E21-S00 MAP	Sitting Height Cupboard	32-3/16" x 35" x 30"	160	\$4,389	\$4,784
			This unit has one fixed and one adjushelf. A hidden drawer is positioned the lockable storage compartment. grommets are located in the work support the control of the cont	l above Two 3'' diameter			
Full Width Drawer, Cupboard and Drawers	93-122-S00 OAK	93-122-S00 MAP	Standing Height Full Width Drawer, Cupboard and Drawers	39-3/16" x 35" x 30"	225	\$6,371	\$6,944
			This unit has one full-width drawer, two file drawers, and a lockable sto compartment. Two 3" diameter gro are located in the work surface.  Note: Available in 39"H only.	-			



# The Matrix Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
93-124-S00 OAK	93-124-S00 MAP	Standing Height Open Shelf and Drawer Unit	39-3/16" x 35" x 30"	200	\$5,231	\$5,702	Open Shelf and Drawer Unit
		This unit has one lockable box drav and two file drawers. Shelf section two adjustable shelves, and one fix Two 3" diameter grommets are loc	has red base shelf.				0
93-E24-S00 OAK	93-E24-S00 MAP	Sitting Height Open Shelf and Drawer Unit	32-3/16" x 35" x 30"	125	\$4,809	\$5,242	
		This unit has one lockable box drav and one file drawer. Shelf section h one adjustable shelf, and one fixed Two 3" diameter grommets are loc	nas I base shelf.				
93-131-S00 OAK	93-131-S00 MAP	Standing Height Cash Drawer Unit	39-3/16" x 35" x 30"	150	\$3,596	\$3,920	Cash Drawer Unit
		Inside dimensions: 33"W x 26-3/4 The work surface is at 39-3/16"H. has locking drawer with a coin and Two 3" diameter grommets are loc	Desk currency tray.				
93-E31-S00 OAK	93-E31-S00 MAP	Sitting Height Cash Drawer Unit	32-3/16" x 35" x 30"	135	\$3,447	\$3,758	
		Inside dimensions: 33"W x 26-3/4 The work surface is at 32-3/16"H. has locking drawer with a coin and Two 3" diameter grommets are loc	Desk currency tray.				
93-E32-S00 OAK	93-E32-S00 MAP	Sitting Height ADA Station	32-3/16" x 35" x 40-1/2	" 185	\$2,730	\$2,976	ADA Station
		The ADA transaction station is designed to provide wheelchair acc on the patrons' side. The knee spa on the patrons' side is 22-1/4" ar staff side is 16". Two 3" diameter are located in the work surface. On egress with sleeve is located in each	ce depth nd on the grommets e 3-1/2" diameter	e.			

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Full Width Draw	er Unit	93-133-S00 OAK	93-133-S00 MAP	Standing Height Full Width Drawer Unit	39-3/16" x 35" x 30"	160	\$3,693	\$4,025
0				This drawer unit has a full-width of 10"H x 33"W x 18-3/4"D. Two grommets are located in the work Note: Available in 39" H only.	3" diameter			

**Full Width Drawer and Cupboard Unit** 



93-135-S00 OAK 93-135-S00 MAP Standing Height Full Width Drawer and Cupboard Unit 39-3/16" x 35" x 30"

\$4,092

\$4,460

This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth

shelf. Hinged doors have a catch, lock and door pulls. Two 3" diameter grommets are located in the work surface.


Discharge Unit 93-172-S00 MAP 93-172-S00 OAK Standing Height Discharge Unit 39-3/16" x 35" x 30" 165 \$3,854 \$4,201 These units have a full-width well with seven removable wood trays for 5"Hx3"W cards. The 7-7/8"patron ledge is at a height of 39-3/16"H. Note: Standing-height roll unders do not work with this unit. 93-E72-S00 OAK 93-E72-S00 MAP Sitting Height Discharge Unit 32-3/16" x 35" x 30" \$3,655 \$3,984 145 These units have a full-width well with seven removable wood trays for 5 "H x 3 "W cards. The 7-7/8" patron ledge is at a height of 32-3/16"H.

Oak	Maple			Wt.	0ak	Maple	0. 1. 0
Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price	Standing Sitting
93-174-S00 OAK	93-174-S00 MAP	Standing Height Open Shelf Unit This unit has a full-depth fixed base shelf and two full-depth adjustable: Two 3" diameter grommets are loca the work surface.		175	\$2,904	\$3,165	Open Shelf Unit
93-E74-S00 OAK	93-E74-S00 MAP	Sitting Height Open Shelf Unit This unit has a full-depth fixed base shelf and two full-depth adjustable s Two 3" diameter grommets are loca the work surface.		155	\$2,605	\$2,839	
93-176-S00 OAK	93-176-S00 MAP	Standing Height Cupboard Unit	39-3/16" x 35" x 30"	200	\$3,575	\$3,896	Cupboard Unit
93-E76-S00 OAK	93-E76-S00 MAP	This unit has a full-depth fixed base shelf and two full-depth adjustables. Hinged doors have a catch, lock and Two 3" diameter grommets are local work surface.  Sitting Height Cupboard Unit This unit has a full-depth fixed base shelf and one full-depth adjustables. Hinged doors have a catch, lock and Two 3" diameter grommets are local work surface.	I door pulls. Ited in the  32-3/16" x 35" x 30" Shelf. I door pulls.	180	\$3,418	\$3,726	
93-234-S00 OAK	93-234-S00 MAP	Standing Height Full Width Drawer and Open Shelves	39-3/16" x 35" x 30"	180	\$3,498	\$3,813	Full Width Drawer and Open Shelves
		This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work su	ırface.				
93-E34-S00 OAK	93-E34-S00 MAP	Sitting Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work su	32-3/16" x 35" x 30" urface.	165	\$3,300	\$3,597	

	Catalog No.	Description	HxWxD	(lbs.)	Price	Maple Price
93-236-S00 0 <i>i</i>	AK 93-236-S00 MAP	Standing Height Media Storage Unit	39-3/16" x 35" x 30"	225	\$4,984	\$5,433
		This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me	edia storage.			
93-E36-S00 0/	AK 93-E36-S00 MAP	Sitting Height Media Storage Unit	32-3/16" x 35" x 30"	205	\$4,620	\$5,036
		8-1/2"H x 33"W x 24"D with each				
	93-E36-S00 0A	93-E36-S00 OAK 93-E36-S00 MAP	This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me storage Unit  This unit has three full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me	This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for media storage.  93-E36-S00 OAK 93-E36-S00 MAP Sitting Height Media 32-3/16" x 35" x 30" Storage Unit This unit has three full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for media storage.	This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for media storage.  93-E36-S00 OAK 93-E36-S00 MAP Sitting Height Media 32-3/16" x 35" x 30" 205 Storage Unit This unit has three full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for media storage.	This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for media storage.  93-E36-S00 OAK 93-E36-S00 MAP Sitting Height Media 32-3/16" x 35" x 30" 205 \$4,620 Storage Unit This unit has three full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for media storage.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sit	ting
93-011-S00 OAK	93-011-S00 MAP	Standing Height Double-Wide 39-3/16" x 70" x 30 Desk with Patron Service Ledge		245	\$4,218	\$4,598	Double-Wide Double	
		Work Surface at 35"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a h Two 3" diameter grommets are loc Note: Standing-height roll unders	eight of 39-3/16". ated in the work surface.		0			
93-E11-S00 OAK	93-E11-S00 MAP	Sitting Height Double-Wide Desk with Patron Service Ledge	32-3/16" x 70" x 30"	210	\$3,992	\$4,351		
		Work Surface at 28"H Inside dimensions are 68"W x 26-3/4"D. The 7-7/8"D patron ledge is at a height of 32-3/16". Two 3" diameter grommets are located in the work surface.						
93-011-SEA OAK	93-011-SEA MAP	Standing Height Double-Wide 39-3/16" x 70" x 30" Desk with Patron Service Ledge		245	\$4,229	\$4,610		
		Work Surface at 28"H Inside dimensions are 68"W x 26-3/4"D. The 7-7/8"D patron ledge is at a height of 39-3/16". Two 3" diameter grommets are located in the work surface. Note: Standing-height roll unders do not work with this unit.			0			
			22.2.(411		40.777		Double-Wide Do	
93-013-S00 OAK	93-013-S00 MAP	Standing Height Double-Wide Desk without Patron Service Ledge		230	\$3,777	\$4,116	without Patron Service Lec	
		Inside dimensions are 68"W x 26-3/4"D. The work surface is at 39-3/16" H. Two 3" diameter grommets are located in the work surface.			0		0	
93-E13-S00 OAK	93-E13-S00 MAP	Sitting Height Double-Wide	32-3/16" x 70" x 30"	30" 195	\$3,601	\$3,925		
		Desk without Patron Service Ledge Inside dimensions are 68"W x 26-3/4"D. The work surface is at 32-3/16" H. Two 3" diameter grommets are located in the work surface.						

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Double Pedestal Work Desk		93-E37-S00 OAK	93-E37-S00 MAP	Sitting Height Double-Wide Double Pedestal Work Desk	32-3/16" x 70" x 30"	260	\$8,380	\$9,134
				Inside dimensions are 68"W x 26-3/4"D. This unit has two drawer pedestals, one mounted on each side consisting of one locking drawer at top; one file drawer with hanging file rack at bottom. Two center drawers are mounted between the two pedestals. Two 3" diameter grommets are located in the work surface. Note: Available in 32-3/16" H only.				



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
93-010-S00 OAK	93-010-S00 MAP	Standing Height 90 Degree Multi-Purpose Corner	39-3/16" x 71-3/4" x 30	)" 250	\$7,143	\$7,786	Multi-Purp	90 Degree ose Corner
		Unit has 29-5/16"W port area angled areas to the left and righ grommet is located in the workwith sleeve is located in each er	nt of the desk module. One 3" of surface top. One 3-1/2" dian	diameter	SS	0		0
93-E10-S00 OAK	93-E10-S00 MAP	Sitting Height 90 Degree Multi-Purpose Corner	32-3/16" x 71-3/4" x 30	)" 215	\$6,801	\$7,413	•	•
		Unit has 29-5/16"W port area angled areas to the left and righ grommet is located in the workwith sleeve is located in each er	nt of the desk module. One 3" of surface top. One 3-1/2" diam	diameter	ss		0	0
93-017-S00 OAK	93-017-S00 MAP	Standing Height 90 Degree Multi-Purpose with Patron Serv	39-3/16" x 71-3/4" x 30	)" 245	\$9,461	\$10,312	90 Degree Multi-Purp with Patron Ser	
		Unit has 29-5/16"W port area Work surface is at 35"H. Stora and right of the module. One 3' One 3-1/2"diameter egress w	ge shelves are located in the tv ' diameter grommet is located	vo angled in the wor	areas to the k surface to	e left op.		
93-E17-S00 OAK	93-E17-S00 MAP	Sitting Height 90 Degree Multi-Purpose with Patron Servi	32-3/16" x 71-3/4" x 30	)" 210	\$9,001	\$9,811	•	
		Unit has 29-5/16"W port area Work surface is at 28"H. Stora and right of the module. One 3 3-1/2" diameter egress with sl	ge shelves are located in the to " diameter grommet is located	vo angled I in the wo	areas to the rk surface t	e left	0	0
93-016-S00 OAK	93-016-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"H	140	\$3,333	\$3,633		90 Degree Corner Unit
		This 90 degree unit is used to for This is not available with patron in each end panel for wire passa	ledge. One 3-1/2" diameter	egress is lo		0	0	
93-E16-S00 OAK	93-E16-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"H	120	\$3,172	\$3,457		
		This 90 degree unit is used to for This is not available with patron in each end panel for wire passa	ledge. One 3-1/2" diameter	egress is lo				

		Oak	Maple			Wt.	0ak	Maple
Standing	Sitting	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
45 Degree Clo	sed Corner Unit	93-018-S00 OAK	93-018-S00 MAP	Standing Height 45 Degree Closed Corner Unit	39-3/16" x 22-7/8" x 30	' 130	\$3,333	\$3,633
0				This corner unit is used to create a This unit is not available with a pa		ation de	sk.	
		93-E18-S00 OAK	93-E18-S00 MAP	Sitting Height 45 Degree Closed Corner Unit	32-3/16" x 22-7/8" x 30	' 110	\$3,172	\$3,457
				This corner unit is used to create a This unit is not available with a pa		ation de	sk.	
90 Degree Ope	en Curved Corner ervice Ledge	93-040-S00 OAK	93-040-S00 MAP	Standing Height 90 Degree Open Curved Corner with Patron S	39-3/16" x 70-1/8" x 30' Service Ledge	' 245	\$10,560	\$11,510
0	0			The 7-7/8"D patron ledge is at a Unit has 26-5/8"W port area. St and right of the desk module. One 3-12" diameter egress with	orage shelves are located in t e 3" diameter grommet is loca	ne two a nted in th	ngled areas ne work surf	to the left ace top.
		93-E40-S00 OAK	93-E40-S00 MAP	Sitting Height 90 Degree Open Curved Corner with Patron S	32-3/16'' x 70-1/8'' x 30' Service Ledge	' 210	\$10,045	\$10,949
0		0		The 7-7/8"D patron ledge is at a Unit has 26-5/8"W port area. St and right of the desk module. One 0ne 3-12" diameter egress with	orage shelves are located in t e 3" diameter grommet is loca	ne two a nted in th	ngled areas ie work surf	to the left ace top.
90 Degree Ope	en Curved Corner	93-041-S00 OAK	93-041-S00 MAP	Standing Height 90 Degree Open Curved Corner	39-3/16" x 70-1/8" x 30	' 245	\$9,160	\$9,984
				Work surface is at 39-3/16"H. U	nit has 26.5/8''W nort area	Storage	chaluac ara	located
0	0			in the two angled areas to the left is located in the work-surface top in each end panel for wire passag	and right of the desk module.  One 3-1/2" diameter egres	One 3''	diameter g	rommet
	•	93-E41-S00 OAK	93-E41-S00 MAP	Sitting Height 90 Degree Open Curved Corner	32-3/16" x 70-1/8" x 30	' 210	\$8,720	\$9,505
0		0		Work surface is at 32-3/16"H. U in the two angled areas to the left is located in the work-surface top in each end panel for wire passage	and right of the desk module.  One 3-1/2" diameter egres	One 3''	diameter g	rommet

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Si
93-047-S00 OAK	93-047-S00 MAP	Standing Height 60 Degree Curved Corner with Patron Servio	39-3/16" x 80-3/4" x 30" ce Ledge	245	\$12,787	\$13,938	60 Degree Curved Co with Patron Service Le
		The 7-7/8"D patron ledge is at Unit has 49-1/16" W port area. the left and right of the desk mor surface top. One 3-1/2" diame wire passage.	Storage shelves are located in dule. One 3" diameter gromme	the two a	angled area	s to ork	
93-E47-S00 OAK	93-E47-S00 MAP	Sitting Height 60 Degree Curved Corner with Patron Servio	32-3/16" x 80-3/4" x 30" ce Ledge	210	\$12,161	\$13,255	
		The 7-7/8"D patron ledge is at Unit has 49-1/16" W port area. left and right of the desk module top. One 3-1/2" diameter egre	Storage shelves are located in a. One 3" diameter grommet is l	the two a ocated i	angled area	s to the surface	
93-048-S00 OAK	93-048-S00 MAP	Standing Height 60 Degree Curved Corner	39-3/16" x 80-3/4" x 30"	245	\$11,391	\$12,416	60 Degree Curved Co
		Work surface is at 39-3/16"H. located in the two angled areas grommet is located in the work s located in each end panel for will	to the left and right of the desk r surface top. One 3-1/2" diame	nodule. (	One 3" dia	meter 📉	
93-E48-S00 OAK	93-E48-S00 MAP	Sitting Height 60 Degree Curved Corner	32-3/16" x 80-3/4" x 30"	210	\$10,853	\$11,830	
		Work surface is at 32-3/16"H. located in the two angled areas grommet is located in the works located in each end panel for will	to the left and right of the desk r surface top. One 3-1/2" diame	nodule. (	One 3'' dia	meter	
93-055-S00 OAK	93-055-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"Hx30"D	140	\$3,985	\$4,344	90 Degree Cu Closed Corner
		This 90 degree unit is used to for This unit is provided with a curve		rrangem	ent.		
93-E55-S00 OAK	93-E55-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"Hx30"D	120	\$3,614	\$3,940	
		This 90 degree unit is used to for This unit is provided with a curve		rrangem	ent.		

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
45 Degree Curve Closed Corner Un		93-058-S00 OAK	93-058-S00 MAP	Standing Height 45 Degree Curved Closed Corner Unit	39-3/16" x 22-3/8" x 30	130	\$3,985	\$4,344
0				This unit is used to create a 45 de It is not available with patron ledg		lesk.		
	· · · · · · · · · · · · · · · · · · ·	93-E58-S00 OAK	93-E58-S00 MAP	Sitting Height 45 Degree Curved Closed Corner Unit	32-3/16" x 22-3/8" x 30	" 110	\$3,614	\$3,940
				This unit is used to create a 45 de It is not available with patron ledo		lesk.		
90 Degree Open	Corner Shelf	93-143-S00 OAK	93-143-S00 MAP	Standing Height 90 Degree Open Corner Shelf	39-3/16"H x 30"D	140	\$3,498	\$3,813
				This 90 degree unit is used to for Has one fixed base shelf and two <b>Note</b> : Units must be modified or on open corner units.	adjustable shelves.	_		ıgh
7		93-E43-S00 OAK	93-E43-S00 MAP	Sitting Height 90 Degree Open Corner Shelf	32-3/16"H x 30"D	120	\$3,348	\$3,650
				This 90 degree unit is used to for Has one fixed base shelf and two <b>Note</b> : Units must be modified or on open corner units.	adjustable shelves.	_		ıgh
90 Degree Squar	re Corner Unit	93-150-S00 OAK	93-150-S00 MAP	Standing Height 90 Degree Square Corner Unit	39-3/16" x 30" x 30"	160	\$3,820	\$4,164
0	0			This square corner unit is used to One 3" diameter egress is locate a continuous ABS tube.				
		93-E50-S00 OAK	93-E50-S00 MAP	Sitting Height 90 Degree Square Corner Unit	32-3/16" x 30" x 30"	140	\$3,477	\$3,789
	0 0			This square corner unit is used to One 3" diameter egress is locate a continuous ABS tube.				

## The Matrix Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
93-178-S00 OAK	93-178-S00 MAP	Detachable End Panels (Pair) End panels are 1" thick, 3-ply, 45 particleboard core with plain-slice veneers. Exposed edges are exterr with 1.6mm thick, solid Northern-	ed oak or maple nally banded	52 nd.	\$1,315 t	\$1,433	Detachable End Panels (Pair)
93-E78-S00 OAK	93-E78-S00 MAP	Detachable End Panels (Pair) End panels are 1" thick, 3-ply, 45 particleboard core with plain-slice veneers. Exposed edges are exterr with 1.6mm thick, solid Northern-	ed oak or maple nally banded	42 nd.	\$1,267	\$1,381	
93-196-S00 OAK	93-196-S00 MAP	Single-Wide Add On 7"H Patron Ledge Unit is designed to be added onto without a patron ledge. The Patror to the desktop by means of #8 x 2 the work surface into the ledge as:	n Ledge Assembly will attach -1/2" screws inserted throug	10 gh	\$526	\$574	Single-Wide Add On 7"H Patron Ledge
93-197-S00 OAK	93-197-S00 MAP	Double-Wide Add On 7"H Patron Ledge Unit is designed to be added onto without a patron ledge. The Patror to the desktop by means of #8 x 2 the work surface into the ledge as:	n Ledge Assembly will attach -1/2" screws inserted throug	20	\$665	\$725	Double-Wide Add On 7"H Patron Ledge

### **TABLETOP**


Standard tabletops are 1-3/16" thick, a plywood core or 3-ply particleboard core, as specified, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction, unless the top is over 72" long in which case it is .050" thick to prevent warping. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are white hardrock maple. This edge band is 5/8" thick x 1-5/8"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. The four tabletop corners are eased.

### **LEGS**


Legs are round with compound tapers. The leg is 3-1/2" diameter at the top and 2-1/2" diameter 8" down from the top. At the bottom of the leg the diameter is 1-7/8". 8" down from the top of the leg is a vein-line 1/8"D x 1/8"W. The leg is one piece solid maple. The bottom of the leg has an 1/8" chamfer and an adjustable, leveling floor glide. The legs attach to the underside of the tabletop by means of a 5" square x 5/16" thick steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" long machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The steel plate is attached to the tabletop by five 5/16"-18 x 1" long machine screws engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind, and hidden by, the extended table edge band.

### **TABLETOP SUPPORT**

For maximum rigidity, rectangular tables, 60" or more wide, receive a hat-shaped, 1-7/16"H x 1-1/2"W, steel keel securely fastened to the underside of the center of the tabletop. Tables 48"D receive two steel keels. Tables 90" or wider also receive two extra legs located under the center of the table to provide added support. The additional legs are 2-1/4" square solid Maple with a 1/2" radius on vertical edges. Added legs are stained black.



Matrix Series Wood Leg



Matrix Series Drop Edge

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Round Oak Tabl	<u>'e</u>						Round Table
93-109-S00 OAK	93-109-S02 OAK	Adult Table	29"H x 36" Diameter	100	\$1,959	\$1,900	
93-Y09-S00 OAK	93-Y09-S02 OAK	Youth Table	27-1/2"H x 36" Diameter	100	\$1,959	\$1,900	
93-J09-S00 OAK	93-J09-S02 OAK	Juvenile Table	25"H x 36" Diameter	100	\$1,959	\$1,900	HIT
93-129-S00 OAK	93-129-S02 OAK	Adult Table	29"H x 42" Diameter	110	\$2,080	\$1,913	
93-Y29-S00 OAK 93-J29-S00 OAK	93-Y29-S02 OAK 93-J29-S02 OAK	Youth Table Juvenile Table	27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110	\$2,080 \$2,080	\$1,913 \$1,913	
93-141-S00 OAK 93-Y41-S00 OAK	93-141-S02 OAK 93-Y41-S02 OAK	Adult Table Youth Table	29"H x 48" Diameter 27-1/2"H x 48" Diameter	120 120	\$2,080 \$2,080	\$1,913 \$1,913	
93-J41-S00 OAK	93-J41-S02 OAK	Juvenile Table	25"H x 48" Diameter	120	\$2,080	\$1,913	U
N/A	93-130-S02 OAK	Adult Table	29"H x 60" Diameter	140	N/A	\$2,698	
N/A	93-Y30-S02 OAK	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$2,698	
N/A	93-J30-S02 OAK	Juvenile Table	25"H x 60" Diameter	140	N/A	\$2,698	
Round Maple Ta	nhla						
<i>Round Maple Ta</i> 93-109-S00 MAP	93-109-S02 MAP	Adult Table	29"H x 36" Diameter	100	\$2,136	\$2,071	
93-Y09-S00 MAP	93-Y09-S02 MAP	Youth Table	27-1/2"H x 36" Diameter	100	\$2,136	\$2,071	
93-J09-S00 MAP	93-J09-S02 MAP	Juvenile Table	25"H x 36" Diameter	100	\$2,136	\$2,071	
93-129-S00 MAP	93-129-S02 MAP	Adult Table	29"H x 42" Diameter	110	\$2,268	\$2,085	
93-Y29-S00 MAP	93-Y29-S02 MAP	Youth Table	27-1/2"H x 42" Diameter	110	\$2,268	\$2,085	
93-J29-S00 MAP	93-J29-S02 MAP	Juvenile Table	25"H x 42" Diameter	110	\$2,268	\$2,085	
93-141-S00 MAP	93-141-S02 MAP	Adult Table	29"H x 48" Diameter	120	\$2,268	\$2,085	
93-Y41-S00 MAP	93-Y41-S02 MAP	Youth Table	27-1/2"H x 48" Diameter	120	\$2,268	\$2,085	
93-J41-S00 MAP	93-J41-S02 MAP	Juvenile Table	25"H x 48" Diameter	120	\$2,268	\$2,085	
N/A	93-130-S02 MAP	Adult Table	29"H x 60" Diameter	140	N/A	\$2,940	
N/A N/A	93-Y30-S02 MAP 93-J30-S02 MAP	Youth Table Juvenile Table	27-1/2"H x 60" Diameter 25"H x 60" Diameter	140 140	N/A N/A	\$2,940 \$2,940	
	70000 002	347011110 144510	20 mmoto			4=// 10	
	<u>le</u>						Square Table
93-191-S00 OAK	93-191-S02 OAK	Adult Table	29" x 30" x 30"	110	\$1,717	\$1,605	
93-Y91-S00 OAK	93-Y91-S02 OAK	Youth Table	27-1/2" x 30" x 30"	110	\$1,717	\$1,605	
93-J91-S00 OAK	93-J91-S02 OAK	Juvenile Table	25" x 30" x 30"	110	\$1,717	\$1,605	
93-137-S00 OAK	93-137-S02 OAK	Adult Table	29" x 42" x 42"	110	\$1,839	\$1,726	
93-Y37-S00 OAK	93-Y37-S02 OAK	Youth Table	27-1/2" x 42" x 42"	110	\$1,839	\$1,726	
93-J37-S00 OAK	93-J37-S02 OAK	Juvenile Table	25" x 42" x 42"	110	\$1,839	\$1,726	
93-154-S00 OAK	93-154-S02 OAK	Adult Table	29" x 48" x 48"	110	\$1,973	\$1,859	U
93-Y54-S00 OAK 93-J54-S00 OAK	93-Y54-S02 OAK 93-J54-S02 OAK	Youth Table Juvenile Table	27-1/2" x 48" x 48" 25" x 48" x 48"	110 110	\$1,973 \$1,973	\$1,859 \$1,859	
73-334-300 OAK	73-334-302 OAK	Juvernie rabie	23 140 140	110	Ψ1,773	Ψ1,037	
Square Maple Ta	able						
93-191-S00 MAP	93-191-S02 MAP	Adult Table	29" x 30" x 30"	110	\$1,872	\$1,749	
93-Y91-S00 MAP	93-Y91-S02 MAP	Youth Table	27-1/2" x 30" x 30"	110	\$1,872	\$1,749	
93-J91-S00 MAP	93-J91-S02 MAP	Juvenile Table	25" x 30" x 30"	110	\$1,872	\$1,749	
93-137-S00 MAP	93-137-S02 MAP	Adult Table	29" x 42" x 42"	110	\$2,004	\$1,881	
93-Y37-S00 MAP	93-Y37-S02 MAP	Youth Table	27-1/2" x 42" x 42"	110	\$2,004	\$1,881	
93-J37-S00 MAP	93-J37-S02 MAP	Juvenile Table	25" x 42" x 42"	110	\$2,004	\$1,881	
93-154-S00 MAP	93-154-S02 MAP	Adult Table	29" x 48" x 48"	110	\$2,151	\$2,027	
	02 VE 4 CO2 MAD	Varida Talala	27 1 /2" v 40" v 40"	110	¢2 1E1	\$2,027	
93-Y54-S00 MAP 93-J54-S00 MAP	93-Y54-S02 MAP	Youth Table	27-1/2" x 48" x 48" 25" x 48" x 48"	110	\$2,151 \$2,151	\$2,027 \$2,027	

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Re	ctangular Oak Tab	ole				
Rectrangular Table	93-194-S00 OAK	93-194-S02 OAK	Adult Table	29" x 30" x 60"	120	\$1,872	\$1,695
	93-Y94-S00 OAK	93-Y94-S02 OAK	Youth Table	27-1/2" x 30" x 60"	120	\$1,872	\$1,695
	93-J94-S00 OAK	93-J94-S02 OAK	Juvenile Table	25" x 30" x 60"	120	\$1,872	\$1,695
II U H II	93-195-S00 OAK	93-195-S02 OAK	Adult Table	29" x 30" x 72"	140	\$2,133	\$1,906
U    U	93-Y95-S00 OAK	93-Y95-S02 OAK	Youth Table	27-1/2" x 30" x 72"	140	\$2,133	\$1,906
	93-J95-S00 OAK	93-J95-S02 OAK	Juvenile Table	25" x 30" x 72"	140	\$2,133	\$1,906
	Four-Reader Re	ctangular Maple T	able				
	93-194-S00 MAP	93-194-S02 MAP	Adult Table	29" x 30" x 60"	120	\$2,041	\$1,848
	93-Y94-S00 MAP	93-Y94-S02 MAP	Youth Table	27-1/2" x 30" x 60"	120	\$2,041	\$1,848
	93-J94-S00 MAP	93-J94-S02 MAP	Juvenile Table	25" x 30" x 60"	120	\$2,041	\$1,848
	93-195-S00 MAP	93-195-S02 MAP	Adult Table	29" x 30" x 72"	140	\$2,325	\$2,077
	93-Y95-S00 MAP	93-Y95-S02 MAP	Youth Table	27-1/2" x 30" x 72"	140	\$2,325	\$2,077
	93-J95-S00 MAP	93-J95-S02 MAP	Juvenile Table	25" x 30" x 72"	140	\$2,325	\$2,077

Six-Reader	Six-Reader Rec	tangular Oak Tabl	<u>'e</u>				
Rectrangular Table	93-144-S00 OAK	93-144-S02 OAK	Adult Table	29" x 36" x 60"	120	\$1,953	\$1,776
•	93-Y44-S00 OAK	93-Y44-S02 OAK	Youth Table	27-1/2" x 36" x 60"	120	\$1,953	\$1,776
	93-J44-S00 OAK	93-J44-S02 OAK	Juvenile Table	25" x 36" x 60"	120	\$1,953	\$1,776
	93-138-S00 OAK	93-138-S02 OAK	Adult Table	29" x 36" x 72"	140	\$2,214	\$1,985
H = H = H = H = H = H = H = H = H = H =	93-Y38-S00 OAK	93-Y38-S02 OAK	Youth Table	27-1/2" x 36" x 72"	140	\$2,214	\$1,985
	93-J38-S00 OAK	93-J38-S02 OAK	Juvenile Table	25" x 36" x 72"	140	\$2,214	\$1,985
U	93-145-S00 OAK	93-145-S02 OAK	Adult Table	29" x 48" x 72"	170	\$2,348	\$2,161
	93-Y45-S00 OAK	93-Y45-S02 OAK	Youth Table	27-1/2" x 48" x 72"	170	\$2,348	\$2,161
	93-J45-S00 OAK	93-J45-S02 OAK	Juvenile Table	25" x 48" x 72"	170	\$2,348	\$2,161
	Six-Reader Rec	tangular Maple Ta	<u>ıble</u>				
	93-144-S00 MAP	93-144-S02 MAP	Adult Table	29" x 36" x 60"	120	\$2,129	\$1,936
	93-Y44-S00 MAP	93-Y44-S02 MAP	Youth Table	27-1/2" x 36" x 60"	120	\$2,129	\$1,936
	93-J44-S00 MAP	93-J44-S02 MAP	Juvenile Table	25" x 36" x 60"	120	\$2,129	\$1,936
	93-138-S00 MAP	93-138-S02 MAP	Adult Table	29" x 36" x 72"	140	\$2,413	\$2,165
	93-Y38-S00 MAP	93-Y38-S02 MAP	Youth Table	27-1/2" x 36" x 72"	140	\$2,413	\$2,165
	93-J38-S00 MAP	93-J38-S02 MAP	Juvenile Table	25" x 36" x 72"	140	\$2,413	\$2,165
	93-145-S00 MAP	93-145-S02 MAP	Adult Table	29" x 48" x 72"	170	\$2,560	\$2,355
	93-Y45-S00 MAP	93-Y45-S02 MAP	Youth Table	27-1/2" x 48" x 72"	170	\$2,560	\$2,355
	93-J45-S00 MAP	93-J45-S02 MAP	Juvenile Table	25" x 48" x 72"	170	\$2,560	\$2,355

## The Matrix Collection

## Reading Tables with Wood Legs

	Particleboard Core Price	Plywood Core Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Rectangular Table wit				<u>egs</u>	ter Support Le	k Table with Cent	Rectangular Oa
Center Support Leg	\$2,369	\$2,730	165	29" x 30" x 90"	Adult Table	93-198-S02 OAK	93-198-S00 OAK
	\$2,369	\$2,730	165	27-1/2" x 30" x 90"	Youth Table	93-Y98-S02 OAK	93-Y98-S00 OAK
	\$2,369	\$2,730	165	25" x 30" x 90"	Juvenile Table	93-J98-S02 OAK	93-J98-S00 OAK
U H	\$2,449	\$2,811	165	29" x 36" x 90"	Adult Table	93-146-S02 OAK	93-146-S00 OAK
	\$2,449	\$2,811	165	27-1/2" x 36" x 90"	Youth Table	93-Y46-S02 OAK	93-Y46-S00 OAK
U	\$2,449	\$2,811	165	25" x 36" x 90"	Juvenile Table	93-J46-S02 OAK	93-J46-S00 OAK
	\$2,617	\$3,019	185	29" x 48" x 90"	Adult Table	93-134-S02 OAK	93-134-S00 OAK
	\$2,617	\$3,019	185	27-1/2" x 48" x 90"	Youth Table	93-Y34-S02 OAK	93-Y34S00 OAK
	\$2,617	\$3,019	185	25" x 48" x 90"	Juvenile Table	93-J34-S02 OAK	93-J34-S00 OAK
				Legs	enter Support	aple Table with Ce	Rectangular Ma
	\$2,582	\$2,976	165	29" x 30" x 60"	Adult Table	93-198-S02 MAP	93-198-S00 MAP
	\$2,582	\$2,976	165	27-1/2" x 30" x 60"	Youth Table	93-Y98-S02 MAP	93-Y98-S00 MAP
	\$2,582	\$2,976	165	25" x 30" x 60"	Juvenile Table	93-J98-S02 MAP	93-J98-S00 MAP
	\$2,670	\$3,064	165	29" x 36" x 90"	Adult Table	93-146-S02 MAP	93-146-S00 MAP
	\$2,670	\$3,064	165	27-1/2" x 36" x 90"	Youth Table	93-Y46-S02 MAP	93-Y46-S00 MAP
	\$2,670	\$3,064	165	25" x 36" x 90"	Juvenile Table	93-J46-S02 MAP	93-J46-S00 MAP
	\$2,853	\$3,291	185	29" x 48" x 90"	Adult Table	93-134-S02 MAP	93-134-S00 MAP
	\$2,853	\$3,291	185	27-1/2" x 48" x 90"	Youth Table	93-Y34-S02 MAP	93-Y34-S00 MAP
	\$2,853	\$3,291	185	25" x 48" x 90"	Juvenile Table	93-J34-S02 MAP	93-J34-S00 MAP

### **TABLETOP**


Standard tabletops are 1-3/16" thick, a plywood core or 3-ply particleboard core, as specified, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction, unless the top is over 72" long in which case it is .050" thick to prevent warping. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are white hardrock maple. This edge band is 5/8" thick x 1-5/8"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. The four tabletop corners are eased.

### **LEGS**


Legs are 11-gauge steel angle measuring 4" x 4" at the top of the leg and 1-5/8" x 1-5/8" at the bottom of the leg. The leg has two compound tapers, one goes from the inside corners down 8" at a 12° angle. One goes from the outside corner down 8" at a 12° angle, the other one picks up there and continues down to the bottom of the leg at a 2° angle. The leg attaches to the underside of the tabletop using a 5" square x 5/16" thick steel plate. The plate is fillet welded to the inside top of the leg on two edges. The steel plate is attached to the underside of the tabletop with five 5/16"-18 x 1" long machine screws engaging internally and externally threaded metal bushings embedded into the underside of the tabletop. The leg plates are positioned behind, and hidden by, the extended table edge band. Each leg has an adjustable leveling floor glide. The metal legs are finished with an electrostatically applied epoxy-powder paint.

### TABLETOP SUPPORT

For maximum rigidity, rectangular tables 60" or more long receive a 1-7/16"H x 1-1/2"W hat-shaped steel keel securely fastened to the underside of the center of the tabletop. Tables 48"D receive two steel keels. Tables 90" and longer also receive two extra legs located down the center of the table to provide added support. The additional legs are 2-1/4" square solid Maple with a 1/2" radius on vertical edges. Added legs are stained black.



Matrix Series Metal Leg




Matrix Series Drop Edge

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Round Oak Table							Round Table
93M-109-S00 OAK	93M-109-S02 OAK	Adult Table	29"H x 36" Diameter	100	\$2,061	\$1,858	
93M-Y09-S00 OAK	93M-Y09-S02 OAK	Youth Table	27-1/2"H x 36" Diameter	100	\$2,061	\$1,858	
93M-J09-S00 OAK	93M-J09-S02 OAK	Juvenile Table	25"H x 36" Diameter	100	\$2,061	\$1,858	
93M-129-S00 OAK	93M-129-S02 OAK	Adult Table	29"H x 42" Diameter	110	\$2,181	\$1,980	
93M-Y29-S00 OAK	93M-Y29-S02 OAK	Youth Table	27-1/2"H x 42" Diameter	110	\$2,181	\$1,980	
93M-J29-S00 OAK	93M-J29-S02 OAK	Juvenile Table	25"H x 42" Diameter	110	\$2,181	\$1,980	
93M-141-S00 OAK	93M-141-S02 OAK	Adult Table	29"H x 48" Diameter	120	\$2,181	\$1,980	
93M-Y41-S00 OAK	93M-Y41-S02 OAK	Youth Table	27-1/2"H x 48" Diameter	120	\$2,181	\$1,980	
93M-J41-S00 OAK	93M-J41-S02 OAK	Juvenile Table	25"H x 48" Diameter	120	\$2,181	\$1,980	
N/A	93M-130-S02 OAK	Adult Table	29"H x 60" Diameter	140	N/A	\$2,758	
N/A	93M-Y30-S02 OAK	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$2,758	
N/A	93M-J30-S02 OAK	Juvenile Table	25"H x 60" Diameter	140	N/A	\$2,758	
Round Maple Tab	le.						
93M-109-S00 MAP	93M-109-S02 MAP	Adult Table	29"H x 36" Diameter	100	\$2,246	\$2,026	
93M-Y09-S00 MAP	93M-Y09-S02 MAP	Youth Table	27-1/2"H x 36" Diameter	100	\$2,246	\$2,026	
93M-J09-S00 MAP	93M-J09-S02 MAP	Juvenile Table	25"H x 36" Diameter	100	\$2,246	\$2,026	
93M-129-S00 MAP	93M-129-S02 MAP	Adult Table	29"H x 42" Diameter	110	\$2,377	\$2,158	
93M-Y29-S00 MAP	93M-Y29-S02 MAP	Youth Table	27-1/2"H x 42" Diameter	110	\$2,377	\$2,158	
93M-J29-S00 MAP	93M-J29-S02 MAP	Juvenile Table	25"H x 42" Diameter	110	\$2,377	\$2,158	
93M-141-S00 MAP	93M-141-S02 MAP	Adult Table	29"H x 48" Diameter	120	\$2,377	\$2,158	
93M-Y41-S00 MAP	93M-Y41-S02 MAP	Youth Table	27-1/2"H x 48" Diameter	120	\$2,377	\$2,158	
93M-J41-S00 MAP	93M-J41-S02 MAP	Juvenile Table	25"H x 48" Diameter	120	\$2,377	\$2,158	
N/A	93M-130-S02 MAP	Adult Table	29"H x 60" Diameter	140	N/A	\$3,006	
N/A	93M-Y30-S02 MAP	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$3,006	
N/A	93M-J30-S02 MAP	Juvenile Table	25"H x 60" Diameter	140	N/A	\$3,006	
Square Oak Table	<u> </u>						Square Table
93M-191-S00 OAK	93M-191-S02 OAK	Adult Table	29" x 30" x 30"	110	\$1,789	\$1,657	
93M-Y91-S00 OAK	93M-Y91-S02 OAK	Youth Table	27-1/2" x 30" x 30"	110	\$1,789	\$1,657	
93M-J91-S00 OAK	93M-J91-S02 OAK	Juvenile Table	25" x 30" x 30"	110	\$1,789	\$1,657	
93M-137-S00 OAK	93M-137-S02 OAK	Adult Table	29" x 42" x 42"	110	\$1,909	\$1,778	
93M-Y37-S00 OAK	93M-Y37-S02 OAK	Youth Table	27-1/2" x 42" x 42"	110	\$1,909	\$1,778	
93M-J37-S00 OAK	93M-J37-S02 OAK	Juvenile Table	25" x 42" x 42"	110	\$1,909	\$1,778	
93M-154-S00 OAK	93M-154-S02 OAK	Adult Table	29" x 48" x 48"	110	\$2,044	\$1,913	u
93M-Y54-S00 OAK	93M-Y54-S02 OAK	Youth Table	27-1/2" x 48" x 48"	110	\$2,044	\$1,913	
93M-J54-S00 OAK	93M-J54-S02 OAK	Juvenile Table	25" x 48" x 48"	110	\$2,044	\$1,913	
Square Maple Tal	b <u>le</u>						
93M-191-S00 MAP	93M-191-S02 MAP	Adult Table	29" x 30" x 30"	110	\$1,950	\$1,806	
93M-Y91-S00 MAP	93M-Y91-S02 MAP	Youth Table	27-1/2" x 30" x 30"	110	\$1,950	\$1,806	
93M-J91-S00 MAP	93M-J91-S02 MAP	Juvenile Table	25" x 30" x 30"	110	\$1,950	\$1,806	
93M-137-S00 MAP	93M-137-S02 MAP	Adult Table	29" x 42" x 42"	110	\$2,081	\$1,938	
93M-Y37-S00 MAP	93M-Y37-S02 MAP	Youth Table	27-1/2" x 42" x 42"	110	\$2,081	\$1,938	
93M-J37-S00 MAP	93M-J37-S02 MAP	Juvenile Table	25" x 42" x 42"	110	\$2,081	\$1,938	
93M-154-S00 MAP	93M-154-S02 MAP	Adult Table	29" x 48" x 48"	110	\$2,228	\$2,085	
93M-Y54-S00 MAP	93M-Y54-S02 MAP	Youth Table	27-1/2" x 48" x 48"	110	\$2,228	\$2,085	
93M-J54-S00 MAP	93M-J54-S02 MAP	Juvenile Table	25" x 48" x 48"	110	\$2,228	\$2,085	

 $Please\ specify\ Wood\ Finish\ (Table\ 1),\ High-Pressure\ Laminate\ (Table\ 2)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ page\ GEN\ 4\ and\ GEN\ 5.$ 

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Red	ctangular Oak Tab	<u>le</u>				
Rectrangular Table	93M-194-S00 OAK	93M-194-S02 OAK	Adult Table	29" x 30" x 60"	120	\$1,920	\$1,754
	93M-Y94-S00 OAK	93M-Y94-S02 OAK	Youth Table	27-1/2" x 30" x 60"	120	\$1,920	\$1,754
	93M-J94-S00 OAK	93M-J94-S02 OAK	Juvenile Table	25" x 30" x 60"	120	\$1,920	\$1,754
	93M-195-S00 OAK	93M-195-S02 OAK	Adult Table	29" x 30" x 72"	140	\$2,262	\$1,906
	93M-Y95-S00 OAK	93M-Y95-S02 OAK	Youth Table	27-1/2" x 30" x 72"	140	\$2,262	\$1,906
J .	93M-J95-S00 OAK	93M-J95-S02 OAK	Juvenile Table	25" x 30" x 72"	140	\$2,262	\$1,906
	Four-Reader Red	ctangular Maple Ta	able				
	93M-194-S00 MAP	93M-194-S02 MAP	Adult Table	29" x 30" x 60"	120	\$2,092	\$1,911
	93M-Y94-S00 MAP	93M-Y94-S02 MAP	Youth Table	27-1/2" x 30" x 60"	120	\$2,092	\$1,911
	93M-J94-S00 MAP	93M-J94-S02 MAP	Juvenile Table	25" x 30" x 60"	120	\$2,092	\$1,911
	93M-195-S00 MAP	93M-195-S02 MAP	Adult Table	29" x 30" x 72"	140	\$2,465	\$2,077
	93M-Y95-S00 MAP	93M-Y95-S02 MAP	Youth Table	27-1/2" x 30" x 72"	140	\$2,465	\$2,077
	93M-J95-S00 MAP	93M-J95-S02 MAP	Juvenile Table	25" x 30" x 72"	140	\$2,465	\$2,077



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on page GEN 4 and GEN 5.

	Particleboard Core Price	Plywood Core Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Rectangular Table wit					upport Legs	Table with Center S	Rectangular Oak
Center Support Leg	\$2,369	\$2,730	165	29" x 30" x 90"	Adult Table	93M-198-S02 OAK	93M-198-S00 OAK
	\$2,369	\$2,730	165	27-1/2" x 30" x 90"	Youth Table	93M-Y98-S02 OAK	93M-Y98-S00 OAK
	\$2,369	\$2,730	165	25" x 30" x 90"	Juvenile Table	93M-J98-S02 OAK	93M-J98-S00 OAK
	\$2,583	\$2,885	165	29" x 36" x 90"	Adult Table	93M-146-S02 OAK	93M-146-S00 OAK
	\$2,583	\$2,885	165	27-1/2" x 36" x 90"	Youth Table	93M-Y46-S02 OAK	93M-Y46-S00 OAK
J	\$2,583	\$2,885	165	25" x 36" x 90"	Juvenile Table	93M-J46-S02 OAK	93M-J46-S00 OAK
	\$2,865	\$3,215	185	29" x 48" x 90"	Adult Table	93M-134-S02 OAK	93M-134-S00 OAK
	\$2,865	\$3,215	185	27-1/2" x 48" x 90"	Youth Table	93M-Y34-S02 OAK	93M-Y34S00 OAK
	\$2,865	\$3,215	185	25" x 48" x 90"	Juvenile Table	93M-J34-S02 OAK	93M-J34-S00 OAK
				<u>:</u>	Support Legs	le Table with Center	Rectangular Map
	\$2,582	\$2,976	165	29" x 30" x 60"	Adult Table	93M-198-S02 MAP	93M-198-S00 MAP
	\$2,582	\$2,976	165	27-1/2" x 30" x 60"	Youth Table	93M-Y98-S02 MAP	93M-Y98-S00 MAP
	\$2,582	\$2,976	165	25" x 30" x 60"	Juvenile Table	93M-J98-S02 MAP	93M-J98-S00 MAP
	\$2,816	\$3,145	165	29" x 36" x 90"	Adult Table	93M-146-S02 MAP	93M-146-S00 MAP
	\$2,816	\$3,145	165	27-1/2" x 36" x 90"	Youth Table	93M-Y46-S02 MAP	93M-Y46-S00 MAP
	\$2,816	\$3,145	165	25" x 36" x 90"	Juvenile Table	93M-J46-S02 MAP	93M-J46-S00 MAP
	\$3,123	\$3,504	185	29" x 48" x 90"	Adult Table	93M-134-S02 MAP	93M-134-S00 MAP
	\$3,123	\$3,504	185	27-1/2" x 48" x 90"	Youth Table	93M-Y34-S02 MAP	93M-Y34-S00 MAP
	\$3,123	\$3,504	185	25" x 48" x 90"	Juvenile Table	93M-J34-S02 MAP	93M-J34-S00 MAP

### **TABLETOP**


Standard tabletops are 1-3/16" thick, a plywood core or 3-ply particleboard core, as specified, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction, unless the top is over 72" long in which case it is .050" thick to prevent warping. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are white hardrock maple. This edge band is 5/8" thick x 1-5/8"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. The four tabletop corners are eased.

### **LEGS**


Each leg is 2-1/2" diameter, 16-gauge steel tubing. Each leg has a 2-1/2" diameter x 1"H adjustable glide mounted into a recessed treaded insert. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is fillet-welded to the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind, and be hidden by, the extended table edge band.

### **TABLETOP SUPPORT**

For maximum rigidity, rectangular tables, 60" or more wide, receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 90" or wider receive two extra matching legs located under the center of the table to provide added support.



Matrix Series Round Metal Leg



Matrix Series Drop Edge

	Particleboard Core Price	Plywood Core Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Round Table							Round Oak Table
	\$1,647	\$1,847	100	29"H x 36" Diameter	Adult Table	930-T-36RD-29A-RDM-S	930-T-36RD-29B-RDM-S
	\$1,647	\$1,847	100	27-1/2"H x 36" Diameter	Youth Table	930-T-36RD-27A-RDM-S	930-T-36RD-27B-RDM-S
	\$1,647	\$1,847	100	25"H x 36" Diameter	Juvenile Table	930-T-36RD-25A-RDM-S	930-T-36RD-25B-RDM-S
	\$1,767	\$1,969	110	29"Hx42" Diameter	Adult Table	930-T-42RD-29A-RDM-S	930-T-42RD-29B-RDM-S
	\$1,767	\$1,969	110	27-1/2"Hx42" Diameter	Youth Table	930-T-42RD-27A-RDM-S	930-T-42RD-27B-RDM-S
	\$1,767	\$1,969	110	25"Hx42" Diameter	Juvenile Table	930-T-42RD-25A-RDM-S	930-T-42RD-25B-RDM-S
1	\$1,767	\$1,969	120	29"Hx 48" Diameter	Adult Table	930-T-48RD-29A-RDM-S	930-T-48RD-29B-RDM-S
	\$1,767	\$1,969	120	27-1/2"Hx 48" Diameter	Youth Table	930-T-48RD-27A-RDM-S	930-T-48RD-27B-RDM-S
	\$1,767	\$1,969	120	25"Hx 48" Diameter	Juvenile Table	930-T-48RD-25A-RDM-S	930-T-48RD-25B-RDM-S
,	\$2,546	N/A	140	29"Hx60" Diameter	Adult Table	930-T-60RD-29A-RDM-S	N/A
	\$2,546	N/A	140	27-1/2"Hx60" Diameter	Youth Table	930-T-60RD-27A-RDM-S	N/A
	\$2,546	N/A	140	25"Hx60" Diameter	Juvenile Table	930-T-60RD-25A-RDM-S	N/A
							Round Maple Table
j	\$1,795	\$2,014	100	29"Hx36" Diameter	Adult Table	93M-T-36RD-29A-RDM-S	93M-T-36RD-29B-RDM-S
	\$1,795	\$2,014	100	27-1/2"Hx36" Diameter	Youth Table	93M-T-36RD-27A-RDM-S	93M-T-36RD-27B-RDM-S
	\$1,795	\$2,014	100	25"Hx36" Diameter	Juvenile Table	93M-T-36RD-25A-RDM-S	93M-T-36RD-25B-RDM-S
	\$1,926	\$2,146	110	29"H x 42" Diameter	Adult Table	93M-T-42RD-29A-RDM-S	93M-T-42RD-29B-RDM-S
	\$1,926	\$2,146	110	27-1/2"H x 42" Diameter	Youth Table	93M-T-42RD-27A-RDM-S	93M-T-42RD-27B-RDM-S
	\$1,926	\$2,146	110	25"H x 42" Diameter	Juvenile Table	93M-T-42RD-25A-RDM-S	93M-T-42RD-25B-RDM-S
	\$1,926	\$2,146	120	29"Hx 48" Diameter	Adult Table	93M-T-48RD-29A-RDM-S	93M-T-48RD-29B-RDM-S
	\$1,926	\$2,146	120	27-1/2"Hx 48" Diameter	Youth Table	93M-T-48RD-27A-RDM-S	93M-T-48RD-27B-RDM-S
	\$1,926	\$2,146	120	25"Hx 48" Diameter	Juvenile Table	93M-T-48RD-25A-RDM-S	93M-T-48RD-25B-RDM-S
5	\$2,775	N/A	140	29"Hx60" Diameter	Adult Table	93M-T-60RD-29A-RDM-S	N/A
	\$2,775	N/A	140	27-1/2"Hx60" Diameter	Youth Table	93M-T-60RD-27A-RDM-S	N/A
1	\$2,775	N/A	140	25"H x 60" Diameter	Juvenile Table	93M-T-60RD-25A-RDM-S	N/A
Square Table							Square Oak Table
	\$1,445	\$1,577	110	29" x 30" x 30"	Adult Table	930-T-3030-29A-RDM-S	930-T-3030-29B-RDM-S
	\$1,445	\$1,577	110	27-1/2" x 30" x 30"	Youth Table	930-T-3030-27A-RDM-S	930-T-3030-27B-RDM-S
	\$1,445	\$1,577	110	25" x 30" x 30"	Juvenile Table	930-T-3030-25A-RDM-S	930-T-3030-25B-RDM-S
	\$1,504	\$1,640	110	29"x36"x36"	Adult Table	930-T-3636-29A-RDM-S	930-T-3636-29B-RDM-S
	\$1,504	\$1,640	110	27-1/2"x36"x36"	Youth Table	930-T-3636-27A-RDM-S	930-T-3636-27B-RDM-S
	\$1,504	\$1,640	110	25"x36"x36"	Juvenile Table	930-T-3636-25A-RDM-S	930-T-3636-25B-RDM-S
	\$1,566 \$1,566 \$1,566	\$1,697 \$1,697 \$1,697	110 110 110	29" x 42" x 42" 27-1/2" x 42" x 42" 25" x 42" x 42"	Adult Table Youth Table Juvenile Table	930-T-4242-29A-RDM-S 930-T-4242-27A-RDM-S 930-T-4242-25A-RDM-S	930-T-4242-29B-RDM-S 930-T-4242-27B-RDM-S 930-T-4242-25B-RDM-S
	\$1,701 \$1,701 \$1,701	\$1,832 \$1,832 \$1,832	110 110 110	29" x 48" x 48" 27-1/2" x 48" x 48" 25" x 48" x 48"	Adult Table Youth Table Juvenile Table	930-T-4848-29A-RDM-S 930-T-4848-27A-RDM-S 930-T-4848-25A-RDM-S	930-T-4848-29B-RDM-S 930-T-4848-27B-RDM-S 930-T-4848-25B-RDM-S
							Square Maple Table
j	\$1,575	\$1,719	110	29" x 30" x 30"	Adult Table	93M-T-3030-29A-RDM-S	93M-T-3030-29B-RDM-S
	\$1,575	\$1,719	110	27-1/2" x 30" x 30"	Youth Table	93M-T-3030-27A-RDM-S	93M-T-3030-27B-RDM-S
	\$1,575	\$1,719	110	25" x 30" x 30"	Juvenile Table	93M-T-3030-25A-RDM-S	93M-T-3030-25B-RDM-S
)	\$1,639	\$1,787	110	29" x 36" x 36"	Adult Table	93M-T-3636-29A-RDM-S	93M-T-3636-29B-RDM-S
	\$1,639	\$1,787	110	27-1/2" x 36" x 36"	Youth Table	93M-T-3636-27A-RDM-S	93M-T-3636-27B-RDM-S
	\$1,639	\$1,787	110	25" x 36" x 36"	Juvenile Table	93M-T-3636-25A-RDM-S	93M-T-3636-25B-RDM-S
1	\$1,707	\$1,850	110	29" x 42" x 42"	Adult Table	93M-T-4242-29A-RDM-S	93M-T-4242-29B-RDM-S
	\$1,707	\$1,850	110	27-1/2" x 42" x 42"	Youth Table	93M-T-4242-27A-RDM-S	93M-T-4242-27B-RDM-S
	\$1,707	\$1,850	110	25" x 42" x 42"	Juvenile Table	93M-T-4242-25A-RDM-S	93M-T-4242-25B-RDM-S
ı	\$1,854	\$1,997	110	29" x 48" x 48"	Adult Table	93M-T-4848-29A-RDM-S	93M-T-4848-29B-RDM-S
	\$1,854	\$1,997	110	27-1/2" x 48" x 48"	Youth Table	93M-T-4848-27A-RDM-S	93M-T-4848-27B-RDM-S

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on page GEN 4 and GEN 5.

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Rectang	ular Oak Table					
Rectrangular Table	930-T-3060-29B-RDM-S	930-T-3060-29A-RDM-S	Adult Table	29" x 30" x 60"	120	\$1,707	\$1,542
	930-T-3060-27B-RDM-S	930-T-3060-27A-RDM-S	Youth Table	27-1/2" x 30" x 60"	120	\$1,707	\$1,542
	930-T-3060-25B-RDM-S	930-T-3060-25A-RDM-S	Juvenile Table	25" x 30" x 60"	120	\$1,707	\$1,542
	930-T-3072-29B-RDM-S	930-T-3072-29A-RDM-S	Adult Table	29" x 30" x 72"	140	\$2,050	\$1,693
	930-T-3072-27B-RDM-S	930-T-3072-27A-RDM-S	Youth Table	27-1/2" x 30" x 72"	140	\$2,050	\$1,693
	930-T-3072-25B-RDM-S	930-T-3072-25A-RDM-S	Juvenile Table	25" x 30" x 72"	140	\$2,050	\$1,693
	Four-Reader Rectang	ular Maple Table					
	93M-T-3060-29B-RDM-S	93M-T-3060-29A-RDM-S	Adult Table	29" x 30" x 60"	120	\$1,860	\$1,680
	93M-T-3060-27B-RDM-S	93M-T-3060-27A-RDM-S	Youth Table	27-1/2" x 30" x 60"	120	\$1,860	\$1,680
	93M-T-3060-25B-RDM-S	93M-T-3060-25A-RDM-S	Juvenile Table	25" x 30" x 60"	120	\$1,860	\$1,680
	93M-T-3072-29B-RDM-S	93M-T-3072-29A-RDM-S	Adult Table	29" x 30" x 72"	140	\$2,235	\$1,846
	93M-T-3072-27B-RDM-S	93M-T-3072-27A-RDM-S	Youth Table	27-1/2" x 30" x 72"	140	\$2,235	\$1,846
	93M-T-3072-25B-RDM-S	93M-T-3072-25A-RDM-S	Juvenile Table	25" x 30" x 72"	140	\$2,235	\$1,846

Six-Reader	Six-Reader Rectangu	<u>lar Oak Table</u>					
Rectrangular Table	930-T-3660-29B-RDM-S	930-T-3660-29A-RDM-S	Adult Table	29" x 36" x 60"	120	\$1,788	\$1,622
	930-T-3660-27B-RDM-S	930-T-3660-27A-RDM-S	Youth Table	27-1/2" x 36" x 60"	120	\$1,788	\$1,622
	930-T-3660-25B-RDM-S	930-T-3660-25A-RDM-S	Juvenile Table	25" x 36" x 60"	120	\$1,788	\$1,622
	930-T-3672-29B-RDM-S	930-T-3672-29A-RDM-S	Adult Table	29" x 36" x 72"	140	\$2,129	\$1,901
	930-T-3672-27B-RDM-S	930-T-3672-27A-RDM-S	Youth Table	27-1/2" x 36" x 72"	140	\$2,129	\$1,901
	930-T-3672-25B-RDM-S	930-T-3672-25A-RDM-S	Juvenile Table	25" x 36" x 72"	140	\$2,129	\$1,901
U	930-T-4872-29B-RDM-S	930-T-4872-29A-RDM-S	Adult Table	29" x 48" x 72"	170	\$2,417	\$2,062
	930-T-4872-27B-RDM-S	930-T-4872-27A-RDM-S	Youth Table	27-1/2" x 48" x 72"	170	\$2,417	\$2,062
	930-T-4872-25B-RDM-S	930-T-4872-25A-RDM-S	Juvenile Table	25" x 48" x 72"	170	\$2,417	\$2,062
	Six-Reader Rectangu	lar Maple Table					
	93M-T-3660-29B-RDM-S	93M-T-3660-29A-RDM-S	Adult Table	29" x 36" x 60"	120	\$1,949	\$1,768
	93M-T-3660-27B-RDM-S	93M-T-3660-27A-RDM-S	Youth Table	27-1/2" x 36" x 60"	120	\$1,949	\$1,768
	93M-T-3660-25B-RDM-S	93M-T-3660-25A-RDM-S	Juvenile Table	25" x 36" x 60"	120	\$1,949	\$1,768
	93M-T-3672-29B-RDM-S	93M-T-3672-29A-RDM-S	Adult Table	29" x 36" x 72"	140	\$2,321	\$2,072
	93M-T-3672-27B-RDM-S	93M-T-3672-27A-RDM-S	Youth Table	27-1/2" x 36" x 72"	140	\$2,321	\$2,072
	93M-T-3672-25B-RDM-S	93M-T-3672-25A-RDM-S	Juvenile Table	25" x 36" x 72"	140	\$2,321	\$2,072
	93M-T-4872-29B-RDM-S	93M-T-4872-29A-RDM-S	Adult Table	29" x 48" x 72"	170	\$2,635	\$2,248
	93M-T-4872-27B-RDM-S	93M-T-4872-27A-RDM-S	Youth Table	27-1/2" x 48" x 72"	170	\$2,635	\$2,248
	93M-T-4872-25B-RDM-S	93M-T-4872-25A-RDM-S	Juvenile Table	25" x 48" x 72"	170	\$2,635	\$2,248

 $Please\ specify\ Wood\ Finish\ (Table\ 1),\ High-Pressure\ Laminate\ (Table\ 2)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ page\ GEN\ 4\ and\ GEN\ 5.$ 

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Rectangular Oak Tab	le with Center Support	<u>Legs</u>					Rectangular Table with
930-T-3090-29B-RDM-S	930-T-3090-29A-RDM-S	Adult Table	29" x 30" x 90"	165	\$2,518	\$2,157	Center Support Legs
930-T-3090-27B-RDM-S	930-T-3090-27A-RDM-S	Youth Table	27-1/2" x 30" x 90"	165	\$2,518	\$2,157	
930-T-3090-25B-RDM-S	930-T-3090-25A-RDM-S	Juvenile Table	25" x 30" x 90"	165	\$2,518	\$2,157	
930-T-3690-29B-RDM-S	930-T-3690-29A-RDM-S	Adult Table	29" x 36" x 90"	165	\$2,674	\$2,371	
930-T-3690-27B-RDM-S	930-T-3690-27A-RDM-S	Youth Table	27-1/2"x36"x90"	165	\$2,674	\$2,371	
930-T-3690-25B-RDM-S	930-T-3690-25A-RDM-S	Juvenile Table	25" x 36" x 90"	165	\$2,674	\$2,371	
000 T 4000 00D DDM C	000 T 4000 004 DDM4 C	A .lla T . l. l .	2011 4011 0011	105	<b>#2.000</b>	<b>#0.450</b>	
930-T-4890-29B-RDM-S	930-T-4890-29A-RDM-S	Adult Table	29" x 48" x 90"	185	\$3,002	\$2,653	
930-T-4890-27B-RDM-S	930-T-4890-27A-RDM-S	Youth Table	27-1/2" x 48" x 90"	185	\$3,002	\$2,653	
930-T-4890-25B-RDM-S	930-T-4890-25A-RDM-S	Juvenile Table	25" x 48" x 90"	185	\$3,002	\$2,653	
Rectangular Maple Ta	able with Center Suppo	ort Legs					
93M-T-3090-29B-RDM-S	93M-T-3090-29A-RDM-S	Adult Table	29" x 30" x 90"	165	\$2,745	\$2,351	
93M-T-3090-27B-RDM-S	93M-T-3090-27A-RDM-S	Youth Table	27-1/2" x 30" x 90"	165	\$2,745	\$2,351	
93M-T-3090-25B-RDM-S	93M-T-3090-25A-RDM-S	Juvenile Table	25" x 30" x 90"	165	\$2,745	\$2,351	
93M-T-3690-29B-RDM-S	93M-T-3690-29A-RDM-S	Adult Table	29" x 36" x 90"	165	\$2,914	\$2,584	
93M-T-3690-27B-RDM-S	93M-T-3690-27A-RDM-S	Youth Table	27-1/2" x 36" x 90"	165	\$2,914	\$2,584	
93M-T-3690-25B-RDM-S	93M-T-3690-25A-RDM-S	Juvenile Table	25" x 36" x 90"	165	\$2,914	\$2,584	
93M-T-4890-29B-RDM-S	93M-T-4890-29A-RDM-S	Adult Table	29" x 48" x 90"	185	\$2,272	\$2,892	
93M-T-4890-27B-RDM-S	93M-T-4890-27A-RDM-S	Youth Table	27-1/2" x 48" x 90"	185	\$2,272	\$2,892	
93M-T-4890-25B-RDM-S	93M-T-4890-25A-RDM-S	Juvenile Table	25" x 48" x 90"	185	\$2,272	\$2,892	
Trapezoid Oak Table							Trapezoid Table
•	020 T 40TD 204 DD# C	Adult Tabla	20" v 40" v 20"	120	¢1.0/0	¢1 770	Trapezoiu Table
930-T-60TR-29B-RDM-S 930-T-60TR-27B-RDM-S	930-T-60TR-29A-RDM-S 930-T-60TR-27A-RDM-S	Adult Table Youth Table	29"x60"x30"	120	\$1,969 \$1,060	\$1,778 \$1,778	
930-T-60TR-27B-RDIVI-S	930-T-60TR-27A-RDIVI-S	Juvenile Table	27-1/2"x60"x30" 25"x60"x30"	120 120	\$1,969 \$1,969	\$1,778 \$1,778	
		Juverille l'able	25 860 850	120	\$1,709	\$1,776	
Trapezoid Maple Tabl					44	***	C C
93M-T-60TR-29B-RDM-S	93M-T-60TR-29A-RDM-S	Adult Table	29"x60"x30"	120	\$2,146	\$1,938	
93M-T-60TR-27B-RDM-S	93M-T-60TR-27A-RDM-S	Youth Table	27-1/2"x60"x30"	120	\$2,146	\$1,938	
93M-T-60TR-25B-RDM-S	93M-T-60TR-25A-RDM-S	Juvenile Table	25"x60"x30"	120	\$2,146	\$1,938	

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on page GEN 4 and GEN 5.

### **TABLETOP**

Standard tabletops are 1-3/16" thick 3-ply particleboard core, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction, unless the top is over 72" long in which case it is .050" thick to prevent warping. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are white hardrock maple. This edge band is 5/8" thick x 1-5/8"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. The four tabletop corners are eased.

**Note:** All standing height tables are apron leg type tables and all sitting height tables are apronless leg type tables.

### LEGS (Wood without Apron)

Legs are round with compound tapers. The leg is 3-1/2" diameter at the top and 2-1/2" diameter 8" down from the top. At the bottom of the leg the diameter is 1-7/8". 8" down from the top of the leg is a vein-line 1/8"D x 1/8"W. The leg is one piece solid maple. The bottom of the leg has an 1/8" chamfer and an adjustable, leveling floor glide. The legs attach to the underside of the tabletop by means of a 5" square x 5/16" thick steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" long machine bolt engaging a 5/8" diameter barrel nut inserted horizontally into the leg. The steel plate is attached to the underside of the tabletop by five 5/16"- $18 \times 1$ " long machine screws engaging internally and externally threaded metal bushings embedded into the underside of the tabletop. Leg plates are positioned behind, and hidden by, the extended table edge band. A 2-1/4" x 2-1/4" center leg, painted black, is used to help support the weight of computer equipment used on these types of tables.

### LEGS (Wood with Apron on 39"H Tables)

Legs are round with compound tapers. The leg is 3-1/2" diameter at the top and 2-1/2" diameter 8" down from the top. At the bottom of the leg the diameter is 1-7/8". 8" down from the top of the leg is a vein-line 1/8" D x 1/8" W. The leg is one piece solid maple. The bottom of the leg has an 1/8" chamfer and an adjustable, leveling floor glide. The legs are secured by means of a 3-1/2"W x 1" thick apron that is secured to the tabletop by attaching hardwood cleats to the inside of the apron and screwing through the cleats into the underside of the top. The bottom front edge of the apron is radiused 1/4". The legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16"-18 hex head bolts that pass through the bracket and engage threaded metal bushings embedded into the leg.

### LEGS (Metal)

Legs are 11-gauge steel angle measuring 4" x 4" at the top of the leg and 1-5/8" x 1-5/8" at the bottom of the leg. The leg has two compound tapers, one goes from the inside corners down 8" at a  $12^{\circ}$  angle. One goes from the outside corner down 8" at a  $12^{\circ}$  angle, the other one picks up there and continues down to the bottom of the leg at a  $2^{\circ}$  angle. The leg attaches to the underside of the tabletop using a 5" square x 5/16" thick steel plate. The plate is fillet welded to the inside

top of the leg on two edges. The steel plate is attached to the underside of the tabletop with five 5/16"-18 x 1" long machine screws engaging internally and externally threaded metal bushings embedded into the underside of the tabletop. The leg plates are positioned behind, and hidden by, the extended table edge band. Each leg has an adjustable leveling floor glide. The metal legs are finished with an electrostatically applied epoxy-powder paint.

### LEGS (ROUND METAL)

Each leg is 2-1/2" diameter, 16-gauge steel tubing and has a 3-1/2" diameter x 2-5/8"H glued-up maple bun-foot as a design feature. Each bun-foot has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the bun-foot by means of a counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is fillet-welded to the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind, and be hidden by, the extended table edge band.

### LEGS (Center)


Additional legs added to the center of the table for extra support are 2-1/4" square, solid maple with a 1/2" radius on vertical edges. Added legs are stained black.

### **PRIVACY PANEL**

Privacy panels are 10"H x 10-3/8"D x 1" thick, these panels and the back panel are white maple plain-sliced, slip-matched tight side out A-A veneer plywood. Exposed edges are banded with 1.6mm matching maple wood. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the bottom edges of the privacy panel. The privacy panel is assembled with metal keyways and shoulder screws. The end panels receive a series of black 1/2" design squares, two rows of four squares, and one row of three squares on the outside face. The squares are centered left to right and begin 1-1/2" down from the top edge of the panel.

### **ELECTRICAL WIRE MANAGEMENT**

Each position receives a 3" diameter grommeted hole for power and data passage. J-channel wire managers are mounted under tabletop to hold these cords. The grommets are ABS black plastic and the J-channel is 18-gauge black powder-coated steel.



Matrix Series Drop Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing with Apron	Sitting without Apron
93-645-S00 OAK	93-645-S00 MAP	Sitting Height	27-1/2" x 30" x 24"	80	\$1,681	\$1,833	One Positi	on Computer Tables
93-665-S00 OAK	93-665-S00 MAP	Sitting Height  Note: Available in 2	27-1/2" x 30" x 30" 27-1/2"H Sitting Height On	80 ly.	\$1,762	\$1,921		
93-649-S00 OAK 93-669-S00 OAK	93-649-S00 MAP 93-669-S00 MAP	Sitting Height Sitting Height	27-1/2" x 60" x 24" 27-1/2" x 60" x 30"	110 110	\$2,244 \$2,379	\$2,446 \$2,593	Two Positi	on Computer Tables
		Note: Available in 2	27-1/2"H Sitting Height On	ly.				
93-643-S00 OAK 93-663-S00 OAK	93-643-S00 MAP 93-663-S00 MAP	Sitting Height Sitting Height	27-1/2" x 36" x 24" 27-1/2" x 36" x 36"	70 80	\$2,004 \$2,137	\$2,184 \$2,329		tion Computer Table 1 10"H Privacy Panel
93-663-S05 OAK	93-663-S05 MAP	Standing Height	39" x 36" x 36"	85	\$2,137	\$2,327	VIII	i To TTT Tivacy i anei
93-642-S00 OAK	93-642-S00 MAP	Sitting Height	27-1/2" x 72" x 24"	150	\$2,582	\$2,815		tion Computer Table
93-662-S00 OAK 93-662-S05 OAK	93-662-S00 MAP 93-662-S05 MAP	Sitting Height Standing Height	27-1/2" x 72" x 36" 39" x 72" x 36"	150 150	\$2,718 \$2,785	\$2,963 \$3,036	with	10"H Privacy Panel
93-644-S00 OAK 93-664-S00 OAK	93-644-S00 MAP 93-664-S00 MAP	Sitting Height Sitting Height	27-1/2" x 90" x 24" 27-1/2" x 90" x 36"	180 170	\$3,364 \$3,499	\$3,667 \$3,814		tion Computer Table 1 10"H Privacy Panel
93-664-S05 OAK	93-664-S05 MAP	Standing Height	39" x 90" x 36"	180	\$3,566	\$3,887	VIII.	

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
One Position Computer Tables	93M-645-S00 OAK	93M-645-S00 MAP	Sitting Height	27-1/2" x 30" x 24"	80	\$1,745	\$1,902
	93M-665-S00 OAK	93M-665-S00 MAP	Sitting Height	27-1/2" x 30" x 30"	80	\$1,825	\$1,989
Two Position Computer Tables	93M-649-S00 OAK	93M-649-S00 MAP	Sitting Height	27-1/2" x 60" x 24"	110	\$2,308	\$2,515
	93M-669-S00 OAK	93M-669-S00 MAP	Sitting Height	27-1/2" x 60" x 30"	110	\$2,442	\$2,661
One Position Computer Table with 10"H Privacy Panel	93M-643-S00 OAK	93M-643-S00 MAP	Sitting Height	27-1/2" x 36" x 24"	70	\$2,066	\$2,252
	93M-663-S00 OAK	93M-663-S00 MAP	Sitting Height	27-1/2" x 36" x 36"	80	\$2,201	\$2,399
Two Position Computer Table with 10"H Privacy Panel	93M-642-S00 OAK	93M-642-S00 MAP	Sitting Height	27-1/2" x 72" x 24"	150	\$2,646	\$2,885
	93M-662-S00 OAK	93M-662-S00 MAP	Sitting Height	27-1/2" x 72" x 36"	150	\$2,780	\$3,031
Three Position Computer Table with 10"H Privacy Panel	93M-644-S00 OAK	93M-644-S00 MAP	Sitting Height	27-1/2" x 90" x 24"	180	\$3,428	\$3,737
	93M-664-S00 OAK	93M-664-S00 MAP	Sitting Height	27-1/2" x 90" x 36"	170	\$3,562	\$3,883



Note: Computer Tables with Metal Legs are available in 27-1/2"H Sitting Height Only.

 $Please \ specify \ Wood \ Finish \ (Table \ 1), \ High-Pressure \ Laminate \ (Table \ 2) \ and \ Metal \ Color \ (Table \ 3). \ Details \ can be found on page \ GEN \ 4 \ and \ GEN \ 5.$ 

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
930-ITGO-243027-RDM-S	93M-ITGO-243027-RDM-S	Sitting Height	27-1/2" x 30" x 24"	80	\$1,533	\$1,671	One Position Computer Tables
930-ITGO-303027-RDM-S	93M-ITGO-303027-RDM-S	Sitting Height	27-1/2" x 30" x 30"	80	\$1,613	\$1,758	
930-ITGO-246027-RDM-S 930-ITGO-306027-RDM-S	93M-ITGO-246027-RDM-S 93M-ITGO-306027-RDM-S		27-1/2" x 60" x 24" 27-1/2" x 60" x 30"	110 110	\$2,096 \$2,230	\$2,285 \$2,431	Two Position Computer Tables
930-ITGS-243627-RDM-S	93M-ITGS-243627-RDM-S	Sitting Height	27-1/2" x 36" x 24"	70	\$1,854	\$2,021	One Position Computer Table with 10"H Privacy Panel
930-ITGS-363627-RDM-S	93M-ITGS-363627-RDM-S	Sitting Height	27-1/2" x 36" x 36"	80	\$1,989	\$2,168	
930-ITGS-247227-RDM-S	93M-ITGS-247227-RDM-S	Sitting Height	27-1/2" x 72" x 24"	150	\$2,435	\$2,654	Two Position Computer Table with 10"H Privacy Panel
930-ITGS-367227-RDM-S	93M-ITGS-367227-RDM-S	Sitting Height	27-1/2" x 72" x 36"	150	\$2,569	\$2,800	
930-ITGS-249027-RDM-S 930-ITGS-369027-RDM-S Note: Com	93M-ITGS-249027-RDM-S 93M-ITGS-369027-RDM-S puter Tables with Metal Legs an	Sitting Height		180 170	\$3,215 \$3,350	\$3,505 \$3,652	Three Position Computer Table with 10"H Privacy Panel

 $Please\ specify\ Wood\ Finish\ (Table\ 1),\ High-Pressure\ Laminate\ (Table\ 2)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ page\ GEN\ 4\ and\ GEN\ 5.$ 

### CARRELS AND ACCESS STATIONS

Carrels and access stations are of a modular starter and adder concept, an overall height of 48" and a work surface width of 36" for the carrel and 36" or 48" for the access station. The work surface depth is 27-1/2" with an additional 1-1/2"W space between the work surface and the back panel to allow passage of electrical and data cords. The work surface is attached to the end and intermediate panels by means of 22-1/2" long steel Z-brackets and 5/16"-18 hex head bolts. Intermediates and ends have 5/16"-18 internally and externally threaded bushings to accept the bolts.

### **WORK SURFACE**

Standard work surfaces are 1-3/16" thick, 3-ply 45# density particleboard, including a top surface of .050" thick, high-pressure laminate, with a backing sheet no less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Front edge is white hardrock maple, this edge band is 5/8" thick x 1-5/8"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. The back edge of the work surface has a black plastic strip 1-1/2"W which projects above the work surface 1/4" to act as a paper and pencil retainer.

### **END AND INTERMEDIATE PANELS**

Panels are 1-3/16" thick comprised of white northern grade A-A maple veneers, slip-matched tight side out over a particleboard core. The panels are externally banded on all four edges with 1.6mm matching wood. The bottom of each panel receives two flush mounted tee-nuts and two 2-5/16"L x 3/4"W x 1/8" T steel straps and two 1-1/4" diameter adjustable chrome floor glides. The end panels on starter units receive a series of black 1/2" design squares, two rows of 12 squares and one row of 11 squares, on the outside face. The squares are centered left to right and begin 3-3/4" down from the top edge of the panel.

### **BACK PANELS**


Back panels are 3/4" thick comprised of white northern grade A-A maple veneers, slip-matched tight side out over a 45# density particleboard core. The panel is externally banded on the top and bottom with 1.6mm matching wood band.

### **SHELF**

The shelf is 3/4" thick x 10"D white northern grade A-A maple veneers, slip-matched tight side out over a 45# density particleboard core. The front edge of the shelf has a 1-3/4"H x 5/8" thick solid white hardrock maple drop edge with a 1/4" radius on the top and bottom edges. The shelf attaches to the ends and intermediates by means of a pair of metal angle brackets. The back corners of the shelf on the access stations have a cutout in them to allow passage of power and data cords. The shelf is located above the work surface on carrels and below the work surface on access stations.

### **WORKING SPACE HEIGHTS**

Working space height is adjustable. The carrel work surface may be set at 29"H or 32"H. The information access stations work surface may be set at 27"H, 32"H or 39"H.



Matrix Series Flush Edge

## The Matrix Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Worl	king Space						Single-Faced Information
93-673-S00 OAK	93-673-S00 MAP	S/F Starter	48-1/4" x 38-3/8" x 30-11/16"	170	\$2,579	\$2,811	Access Workstations/Carrels
93-672-S00 OAK	93-672-S00 MAP	S/F Adder	48-1/4" x 37-3/16" x 30-11/16"	120	\$2,130	\$2,322	
48" Wide Worl	king Space						
93-460-S00 OAK	93-460-S00 MAP	S/F Starter	48-1/4" x 50" x 30-11/16"	200	\$2,765	\$3,014	
93-459-S00 OAK	93-459-S00 MAP	S/F Adder	48-1/4" x 48-13/16" x 30-11/16"	150	\$2,290	\$2,496	
							Starter
							Adder

36" Wide Work	ring Space					
93-674-S00 OAK	93-674-S00 MAP	D/F Starter	48-1/4" x 38-3/8" x 59-5/8"	320	\$4,658	\$5,077
93-675-S00 OAK	93-675-S00 MAP	D/F Adder	48-1/4" x 37-3/16" x 59-5/8"	220	\$3,812	\$4,156
48" Wide Work	ring Snace					
		D /F Chamban	40.1/4" " FO!" " FO F /0"	200	<b>¢</b> E 0E0	фГ <b>Г</b> 12
93-461-S00 OAK	93-461-S00 MAP	D/F Starter	48-1/4" x 50" x 59-5/8"	380	\$5,058	\$5,513
93-462-S00 OAK	93-462-S00 MAP	D/F Adder	48-1/4" x 48-13/16" x 59-5/8"	280	\$4,132	\$4,504

Access Workstations/Carrels

Starter

Adder

**Double-Faced Information** 

### WORKSTATIONS

Workstations are of modular starter and adder design, with an overall height of 34". Workstations are available in 36", 48", 72", 96", and 108" widths. A knee-space panel located below the work surface supports all work surfaces greater than 48"W. Work surface height is at 27-1/2". Work surface depth is 27-1/2" with an additional 1-1/2"W cord drop between the work surface and back panel to allow passage of electrical cords. Work surface is attached to end and intermediate panels by means of two metal 22-1/2" long "Z" brackets with 5/16"–18 hex-head bolts engaging internally and externally threaded bushings embedded into panels. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end and intermediate panels and back panels with 3/4" x 3/4" steel black painted angle brackets and black #8 screws.

### **WORK SURFACE**

Standard work surface is 1-3/16" thick, 3-ply, 45# density particleboard, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Front edge is white hardrock maple. This edge band is 5/8" x 1-3/16"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. The back edge of the work surface has a black metal strip 1-1/2"W which projects above the work surface a 1/4" to act as a paper and pencil retainer.

### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-3/16" thick comprised of white northern-grown grade A-A plain-sliced maple veneers, slip-matched on both faces. The four edges are banded with matching maple wood banding. The core is 45# density particleboard. Each panel has two adjustable leveling floor glides. Intermediate panels have a 3" diameter grommet below the work surface to allow passage of power and data cords. The outside faces of the end panels receive a series of black 1/2" design squares, two rows of 12 squares and one row of 11 squares. The squares are centered left and right and begin 3-3/4" down from the top edge.

### **BACK PANEL**


Back panel is 3/4" thick with the same veneer spec as the end panels. Back panels on double-faced units have a 3" diameter grommet below the work surface.

### SHELF/WIRE MANAGEMENT COMPARTMENT

Shelf is maple, 3/4" thick and attaches to the uprights by means of a pair of metal angle brackets. The shelf is positioned 10" below the bottom of the work surface. The compartment has sliding front doors to access the electrical items behind the doors. The doors slide in aluminum tracks at the top and bottom of the doors.

### WORKING SPACE HEIGHT

The working space is fixed at 27"H.



Matrix Series Flush Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Work	ing Space						Single-Faced One-Position
93-S31-SS0 OAK	93-S31-SS0 MAP	One-Position S/F Starter	33-1/2" x 37-1/2" x 31"	130	\$2,151	\$2,345	Starter
93-S41-SS0 OAK	93-S41-SS0 MAP	One-Position S/F Starter	33-1/2" x 49-1/4" x 31"	155	\$2,296	\$2,503	
48" Wide Work	ing Space						
93-S31-SA0 OAK	93-S31-SA0 MAP	One-Position S/F Adder	33-1/2" x 36-1/2" x 31"	100	\$1,752	\$1,910	Adder
93-S41-SA0 OAK	93-S41-SA0 MAP	One-Position S/F Adder	33-1/2" x 48" x 31"	125	\$1,862	\$2,030	Auto

36" Wide Work	ing Space						Double-Faced One-Position
93-D31-SS0 OAK	93-D31-SS0 MAP	One-Position D/F Starter	33-1/2" x 37-1/2" x 59-1/2"	215	\$3,884	\$4,234	Starter
93-D41-SS0 OAK  48" Wide Work	93-D41-SSO MAP ing Space	One-Position D/F Starter	33-1/2" x 49-1/4" x 59-1/2"	255	\$4,141	\$4,513	
93-D31-SA0 OAK	93-D31-SA0 MAP	One-Position D/F Adder	33-1/2" x 36-1/2" x 59-1/2"	155	\$3,123	\$3,404	
93-D41-SA0 OAK	93-D41-SA0 MAP	One-Position D/F Adder	33-1/2" x 48" x 59-1/2"	195	\$3,358	\$3,660	Adder



	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced Two-Position	36" Wide Work	king Space					
Starter	93-S32-SS0 OAK	93-S32-SS0 MAP	Two-Position S/F Starter	33-1/2" x 74" x 31"	195	\$2,962	\$3,229
	93-S42-SS0 OAK	93-S42-SS0 MAP	Two-Position S/F Starter	33-1/2" x 97-1/4" x 31"	235	\$3,202	\$3,490
	48" Wide Work	king Space					
	Catalog No. Catalog Wo-Position  36" Wide Working Space 93-S32-SS0 OAK 93-S32- 93-S42-SS0 OAK 93-S42- 48" Wide Working Space 93-S32-SA0 OAK 93-S32-	93-S32-SA0 MAP	Two-Position S/F Adder	33-1/2" x 73" x 31"	165	\$2,527	\$2,755
Adder	93-S42-SAO OAK	93-S42-SAO MAP	Two-Position S/F Adder	33-1/2" x 96" x 31"	205	\$2,754	\$3,002

Double-Faced Two-Position	36" Wide Worl	king Space					
Starter	93-D32-SS0 OAK	93-D32-SS0 MAP	Two-Position D/F Starter	33-1/2" x 74" x 59-1/2"	330	\$5,303	\$5,780
	93-D42-SS0 OAK	93-D42-SSO MAP	Two-Position D/F Starter	33-1/2" x 97-1/4" x 59-1/2"	410	\$5,720	\$6,235
	48" Wide Worl	king Space					
	93-D32-SA0 OAK	93-D32-SA0 MAP	Two-Position D/F Adder	33-1/2" x 73" x 59-1/2"	270	\$4,571	\$4,982
Adder	93-D42-SAO OAK	93-D42-SA0 MAP	Two-Position D/F Adder	33-1/2" x 96" x 59-1/2"	155	\$4,981	\$5,430

## The Matrix Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Work	king Space						Single-Faced Three-Position
93-S33-SS0 OAK	93-S33-SS0 MAP	Three-Position S/F Starter	33-1/2" x 110-1/2" x 31"	260	\$3,926	\$4,279	Starter
93-S33-SA0 OAK	93-S33-SA0 MAP	Three-Position	33-1/2" x 109-1/4" x 31"	230	\$3,324	\$3,623	Adder
		S/F Adder					

36" Wide Work	ing Space				Double-Faced	Three-Position
93-D33-SSO OAK	93-D33-SS0 MAP	Three-Position D/F Starter	33-1/2" x 110-1/2" x 59-1/2" 445	\$7,060	\$7,695	Starter
93-D33-SA0 OAK	93-D33-SA0 MAP	Three Position D/F Adder	33-1/2" x 109-1/4" x 59-1/2" 385	\$6,269	\$6,833	Adder

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
90° Functional Corner Unit Starter	93-SCR-SSO OAK	93-SCR-SSO MAP	90-Degree Functional 3 Corner Starter	3-1/2" x 62" x 31"	225	\$4,739	\$5,165
Adder	93-SCR-SAO OAK	93-SCR-SAO MAP	90-Degree Functional 3 Corner Adder	3-1/2" x 62" x 31"	195	\$4,435	\$4,834

### WORK SURFACE

Work surface is 1-3/16" thick, 3-ply 45# density particleboard, including a top surface of .050" thick, high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. The front edges are white hardrock maple. This edge band is 5/8" thick x 1-5/8"W and is applied to the core after the top and bottom laminate sheets are applied making it an external edge. This wood edge band is rectangular in design with a 1/4" radius on the top and bottom front edges. There is a 1-1/2" space between the back of the work surface and the back panel to allow passage of power and data cords. The back edge of the work surface has a black plastic strip 1-1/2"W which projects above the work surface 1/4" to act as a paper and pencil retainer. The work surface is attached to the end and intermediate panels by means of 22-1/2" long steel "Z"-brackets and 5/16"-18 hex head bolts. Intermediates and ends have 5/16"-18 internally and externally threaded bushings embedded in them to accept the bolts.

### **END AND INTERMEDIATE PANELS**

Manla

Oak

Panels are 1-3/16" thick comprised of white northern grade A-A maple veneers, slip-matched tight side out over a particleboard core. The panels are externally banded on all four edges with 1.6mm matching wood. The bottom of each panel receive two flush mounted tee-nuts and two 2-5/16"L x 3/4"W x 1/8" T steel straps and two 1-1/4" diameter adjustable chrome floor glides. The end and intermediate panels receive a series of 1/2" design squares, two rows of two squares and one row of one square, on each face. The squares begin 1-1/2" down from the top edge of each panel and 1-1/2" in from the front edge of each panel.

### **BACK PANELS**

Back panels are 3/4" thick, comprised of white northern grade A-A maple veneers, slip-matched tight side out over a 45# density particleboard core. The panel is externally banded on the top and bottom with 1.6mm matching wood band. The back panels attach to the ends and/or intermediates by means of triangular maple wood posts and hidden keyways and shoulder screws. One of the back panels have an electrical access door, all of the back panels have a 3" diameter grommet hole for power and data cord passage.

### **SHELF**


The shelf is 3/4" thick x 10"D, with matching maple veneers over a 45# density particleboard core. The front edge of the shelf has matching wood edge. The shelf attaches to the ends and intermediates by means of a pair of metal angle brackets.

### **WORKING SPACE HEIGHTS**

Working space is adjustable to: Standing Height: 39" ADA Height: 32"

Sitting Height: 27


۱Λ/+



Matrix Series Flush Edge


Manla

Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price	
93-682-S00 OAK	93-682-S00 MAP	Six position with	42-1/4" x 99-1/4" x 99-1/4"	629	\$13,910	\$15,162	Six Position PAC Station
		angular tops.					



93-685-S00 OAK 93-685-S00 MAP Three position with 42-1/4" x 99-1/2" x 47-1/2" 401 \$7,319 \$7,978 Three Position PAC Station

angular tops. Composed of one starter unit and two adder units.



	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Dictionary Stand	93-869-S00 OAK	93-869-S00 MAP	Adult Height	45" x 25-7/8" x 15-3/4"	80	\$2,234	\$2,435
	93-469-S00 OAK	93-469-S00 MAP	Children's Height	38" x 26-3/8" x 15-3/4"	67	\$2,234	\$2,435



The top of the dictionary stand slopes down toward the front of the unit at a  $10^\circ$  angle. The top is 1-3/16" thick, consisting of a 45# density particleboard core, a top surface of .050" thick high-pressure laminate, with a backing sheet not less than .020" thick. A 5/8" x 5/8" book retainer at the front of the top keeps books from sliding off. The top edges receive maple bands. The unit has a full back panel which matches the end panels. The end panels are 1-3/16" thick with A-A plain-sliced white maple veneer, slip-matched, edges receive matching wood edge bands. The bottom edge of each end receives two adjustable floor glides. There is one adjustable shelf and one bottom fixed maple shelf. The end panels receive a series of black 1/2" design squares, two rows of six squares and one row of five squares, on the outside face. The squares are centered left to right and begin 1-12" down from the top front edge of the panel.

Atlas Stand	93-871-S00 OAK	93-871-S00 MAP	Adult Height	45" x 30" x 28-1/4"	200	\$4,019	\$4,381
	02 471 500 047	02 471 500 MAD	Children's Height	20" v 20" v 20 1 /4"	100	¢4.010	¢ // 201



The top of the atlas stand slopes down toward the front of the unit at a  $10^\circ$  angle. The top is 1-3/16" thick, consisting of a 45% density particleboard core, a top surface of .050" thick high-pressure laminate, with a backing sheet not less than .020" thick. A 5/8" x 5/8" book retainer at the front of the top keeps books from sliding off. The top edges receive maple bands. The unit has a full back panel which matches the end panels. The end panels are 1-3/16" thick with A-A plain-sliced white maple veneer, slip-matched edges receive matching wood edge bands. The bottom edge of each end receives two adjustable floor glides. There are five pull-out maple shelves on metal slides with a positive stop to prevent accidental removal. The shelves are 25-7/8"W x 23-7/8"D, with 3-1/2" space between them. The children's height atlas stand has four pull-out shelves, with 3-1/2" usable space between the shelves. The end panels receive a series of black 1/2" design squares, two rows of ten squares and one row of nine squares, on the outside face. The squares are centered left to right and begin 1-1/2" down from the top front edge of the panel.

OPAC Station	93-039-S00 OAK	93-039-S00 MAP	End-of-Range Computer Station	38-3/16" x 24-1/8" x 20"	110	\$1,889	\$2,059



Designed to fit at end of doublefaced shelving range. Standard tabletop is 1-3/16" thick with high-pressure laminate on the top surface, with one 3" diameter grommet, and with 5/8" thick external solid wood edge bands. End panels are 1-3/16" thick wood veneered and edge banded. Unit has two full-depth fixed shelves with 3" diameter grommets and one pullout shelf for the keyboard. Space above the fixed shelves is 11". Adjustable glides are provided for leveling the unit.

0ak	Maple			0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE II	NIIT				
To Cover ONE U. 93-W10-S01 OAK	93-W10-S01 MAP	10"D Single Faced	11	\$287	\$301
93-W12-S01 OAK	93-W12-S01 MAP	10"D, Single-Faced 12"D, Single-Faced	14	\$287 \$289	\$301
93-W20-S01 OAK	93-W20-S01 MAP	20"D, Double-Faced	23	\$406	\$303 \$426
93-W24-S01 OAK	93-W24-S01 MAP	24"D, Double-Faced	23 27	\$400 \$452	\$420 \$475
73-W24-30 I OAK	73-W24-30 I WAF	24 D, Double-I aceu	21	\$4JZ	\$475
To Cover TWO U	<u>INITS</u>				
93-W10-S02 OAK	93-W10-S02 MAP	10"D, Single-Faced	22	\$379	\$398
93-W12-S02 OAK	93-W12-S02 MAP	12"D, Single-Faced	28	\$402	\$422
93-W20-S02 OAK	93-W20-S02 MAP	20"D, Double-Faced	46	\$569	\$598
93-W24-S02 OAK	93-W24-S02 MAP	24"D, Double-Faced	54	\$714	\$750
To Cover THREE	LINUTO				
		10"D Cinals Food	22	¢40E	¢E20
93-W10-S03 OAK	93-W10-S03 MAP	10"D, Single-Faced	33	\$495	\$520
93-W12-S03 OAK	93-W12-S03 MAP	12"D, Single-Faced 20"D, Double-Faced	42 69	\$525	\$551
93-W20-S03 OAK	93-W20-S03 MAP 93-W24-S03 MAP	•	69 81	\$718 \$757	\$754
93-W24-S03 OAK	93-W24-3U3 IVIAP	24"D, Double-Faced	٥ı	\$757	\$795
To Cover FOUR	<u>UNITS</u>				
93-W10-S04 OAK	93-W10-S04 MAP	10"D, Single-Faced	44	\$755	\$793
93-W12-S04 OAK	93-W12-S04 MAP	12"D, Single-Faced	56	\$801	\$840
93-W20-S04 OAK	93-W20-S04 MAP	20"D, Double-Faced	92	\$1,124	\$1,180
93-W24-S04 OAK	93-W24-S04 MAP	24"D, Double-Faced	108	\$1,211	\$1,272
T 0 FU/F !!	AUTO				
To Cover FIVE U		10UD Cinale Food	FF	¢070	¢01/
93-W10-S05 OAK	93-W10-S05 MAP	10"D, Single-Faced	55	\$872	\$916
93-W12-S05 OAK	93-W12-S05 MAP	12"D, Single-Faced	70	\$928	\$974
93-W20-S05 OAK	93-W20-S05 MAP	20"D, Double-Faced	115	\$1,289	\$1,353 \$1,547
93-W24-S05 OAK	93-W24-S05 MAP	24"D, Double-Faced	135	\$1,473	\$1,547
To Cover SIX UN	<u>IITS</u>				
93-W10-S06 OAK	93-W10-S06 MAP	10"D, Single-Faced	66	\$986	\$1,035
93-W12-S06 OAK	93-W12-S06 MAP	12"D, Single-Faced	84	\$1,056	\$1,108
93-W20-S06 OAK	93-W20-S06 MAP	20"D, Double-Faced	138	\$1,435	\$1,506
93-W24-S06 OAK	93-W24-S06 MAP	24"D, Double-Faced	162	\$1,513	\$1,589
T 0 051/51					
To Cover SEVEN		10115 01 1 5 1		***	****
93-W10-S07 OAK	93-W10-S07 MAP	10"D, Single-Faced	77	\$1,271	\$1,334
93-W12-S07 OAK	93-W12-S07 MAP	12"D, Single-Faced	98	\$1,347	\$1,415
93-W20-S07 OAK	93-W20-S07 MAP	20"D, Double-Faced	161	\$1,838	\$1,930
93-W24-S07 OAK	93-W24-S07 MAP	24"D, Double-Faced	189	\$1,965	\$2,064
To Cover EIGHT	UNITS				
93-W10-S08 OAK	93-W10-S08 MAP	10"D, Single-Faced	88	\$1,363	\$1,431
93-W12-S08 OAK	93-W12-S08 MAP	12"D, Single-Faced	112	\$1,454	\$1,527
93-W20-S08 OAK	93-W20-S08 MAP	20"D, Double-Faced	184	\$2,005	\$2,105
93-W24-S08 OAK	93-W24-S08 MAP	24"D, Double-Faced	216	\$2,228	\$2,340
				-	•
To Cover NINE U		40110 01 1 5 1	0.5	Ac	A
93-W10-S09 OAK	93-W10-S09 MAP	10"D, Single-Faced	99	\$1,479	\$1,553
93-W12-S09 OAK	93-W12-S09 MAP	12"D, Single-Faced	126	\$1,580	\$1,659
93-W20-S09 OAK	93-W20-S09 MAP	20"D, Double-Faced	207	\$2,155	\$2,263
93-W24-S09 OAK	93-W24-S09 MAP	24"D, Double-Faced	243	\$2,268	\$2,381

**Note:** Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

0ak	Maple			0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE U	N/T				
93-S10-S01 OAK	93-S10-S01 MAP	10"D, Single-Faced	11	\$312	\$327
93-S12-S01 OAK	93-S12-S01 MAP	12"D, Single-Faced	14	\$313	\$329
93-S20-S01 OAK	93-S20-S01 MAP	20"D, Double-Faced	23	\$438	\$459
93-S24-S01 OAK	93-S24-S01 MAP	24"D, Double-Faced	27	\$495	\$520
To Cover TWO U	NITS				
93-S10-S02 OAK	93-S10-S02 MAP	10"D, Single-Faced	22	\$409	\$429
93-S12-S02 OAK	93-S12-S02 MAP	12"D, Single-Faced	28	\$435	\$456
93-S20-S02 OAK	93-S20-S02 MAP	20"D, Double-Faced	46	\$619	\$650
93-S24-S02 OAK	93-S24-S02 MAP	24"D, Double-Faced	54	\$776	\$815
To Cover THREE	IINITS				
93-S10-S03 OAK	93-S10-S03 MAP	10"D, Single-Faced	33	\$535	\$561
93-S12-S03 OAK	93-S12-S03 MAP	12"D, Single-Faced	42	\$535 \$571	\$601
93-S20-S03 OAK	93-S20-S03 MAP	20"D, Double-Faced	69	\$771 \$780	\$819
93-S24-S03 OAK	93-S24-S03 MAP	24"D, Double-Faced	81	\$780 \$818	\$859
		21 By Bodbie 1 dood	01	40.0	4007
To Cover FOUR ( 93-S10-S04 OAK	93-S10-S04 MAP	10"D Single Feed	44	\$822	\$864
93-S12-S04 OAK	93-S12-S04 MAP	10"D, Single-Faced 12"D, Single-Faced	56	\$872	\$916
93-S20-S04 OAK	93-S20-S04 MAP	20"D, Double-Faced	92	\$1,164	\$1,222
93-S24-S04 OAK	93-S24-S04 MAP	24"D, Double-Faced	108	\$1,104 \$1,314	\$1,222 \$1,380
		24 D, Double-I aceu	100	\$1,314	\$1,30U
To Cover FIVE U		10115 01 1 5 1		4	****
93-S10-S05 OAK	93-S10-S05 MAP	10"D, Single-Faced	55	\$942	\$890
93-S12-S05 OAK	93-S12-S05 MAP	12"D, Single-Faced	70	\$1,008	\$1,058
93-S20-S05 OAK	93-S20-S05 MAP	20"D, Double-Faced	115	\$1,398	\$1,468
93-S24-S05 OAK	93-S24-S05 MAP	24"D, Double-Faced	135	\$1,601	\$1,680
To Cover SIX UN	<u>IITS</u>				
93-S10-S06 OAK	93-S10-S06 MAP	10"D, Single-Faced	66	\$1,066	\$1,120
93-S12-S06 OAK	93-S12-S06 MAP	12"D, Single-Faced	84	\$1,149	\$1,206
93-S20-S06 OAK	93-S20-S06 MAP	20"D, Double-Faced	138	\$1,558	\$1,635
93-S24-S06 OAK	93-S24-S06 MAP	24"D, Double-Faced	162	\$1,642	\$1,724
To Cover SEVEN	UNITS				
93-S10-S07 OAK	93-S10-S07 MAP	10"D, Single-Faced	77	\$1,355	\$1,423
93-S12-S07 OAK	93-S12-S07 MAP	12"D, Single-Faced	98	\$1,445	\$1,518
93-S20-S07 OAK	93-S20-S07 MAP	20"D, Double-Faced	161	\$2,014	\$2,115
93-S24-S07 OAK	93-S24-S07 MAP	24"D, Double-Faced	189	\$2,137	\$2,244
To Cover EIGHT	UNITS				
93-S10-S08 OAK	93-S10-S08 MAP	10"D, Single-Faced	88	\$1,479	\$1,553
93-S12-S08 OAK	93-S12-S08 MAP	12"D, Single-Faced	112	\$1,580	\$1,659
93-S20-S08 OAK	93-S20-S08 MAP	20"D, Double-Faced	184	\$2,177	\$2,285
93-S24-S08 OAK	93-S24-S08 MAP	24"D, Double-Faced	216	\$2,419	\$2,540
To Cover NINE U	INITS				
93-S10-S09 OAK	93-S10-S09 MAP	10"D, Single-Faced	99	\$1,604	\$1,684
93-S12-S09 OAK	93-S12-S09 MAP	12"D, Single-Faced	126	\$1,722	\$1,808
		-			
93-S20-S09 OAK	93-S20-S09 MAP	20"D, Double-Faced	207	\$2,338	\$2,455

**Note**: Edge Band on long side only. Tops are designed to be inset betweend end panels. If edge bands are desired on short edges, please enter the part as a modification and specify which bands to be included.

To ensure that tops for steel shelving work with each manufacturer and top method, please specify the exact width and depth of tops. Add 15% for HPL on top and bottom (Steel Shelving ONLY).

### **END PANELS: STEEL SHELVING**

The end panels are 1-3/16" thick. The core is 45# density particleboard with grade A-A plain-sliced white maple veneer on both faces. The type matching of the veneers is slip-matched, tight side out. All four edges are externally banded with 1.6mm white maple. The end panels are supplied without machining or hardware for attachment. The outside face of the end panels receives three rows of black 1/2" design squares.

The number of design squares in each row are determined by the depth

of the panel. The squares are centered left to right and begin 3-3/4" down from the top edge of the panel.

End panels for steel shelving with continuous tops or canopy top inset are designed to have the canopy top "inset" between the end panels.

**Note:** Exact height and depth of panel must be specified when ordering.

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price	
93-702-MOD OAK	93-702-MOD MAP	43-3/4" x 13-7/8"	10	\$454	\$477	Single-Faced End Panels
93-703-MOD OAK	93-703-MOD MAP	43-3/4" x 15-7/8"	12	\$470	\$493	
93-705-MOD OAK	93-705-MOD MAP	67-3/4" x 13-7/8"	16	\$553	\$580	
93-706-MOD OAK	93-706-MOD MAP	67-3/4" x 15-7/8"	19	\$560	\$588	
93-708-MOD OAK	93-708-MOD MAP	79-3/4" x 13-7/8"	15	\$575	\$604	
93-709-MOD OAK	93-709-MOD MAP	79-3/4" x 15-7/8"	24	\$582	\$611	
93-711-MOD OAK	93-711-MOD MAP	85-3/4" x 13-7/8"	18	\$582	\$611	
93-712-MOD OAK	93-712-MOD MAP	85-3/4" x 15-7/8"	27	\$592	\$622	
93-714-MOD OAK	93-714-MOD MAP	91-3/4" x 13-7/8"	20	\$592	\$622	
93-715-MOD OAK	93-715-MOD MAP	91-3/4" x 15-7/8"	29	\$599	\$629	
93-722-MOD OAK	93-722-MOD MAP	43-3/4" x 24-3/8"	20	\$565	\$593	Double-Faced End Panels
93-723-MOD OAK	93-723-MOD MAP	43-3/4" x 28-3/8"	24	\$574	\$602	
93-725-MOD OAK	93-725-MOD MAP	67-3/4" x 24-3/8"	32	\$709	\$744	
93-726-MOD OAK	93-726-MOD MAP	67-3/4" x 28-3/8"	38	\$724	\$760	
93-728-MOD OAK	93-728-MOD MAP	79-3/4" x 24-3/8"	30	\$731	\$768	
93-729-MOD OAK	93-729-MOD MAP	79-3/4" x 28-3/8"	48	\$792	\$831	
93-731-MOD OAK	93-731-MOD MAP	85-3/4" x 24-3/8"	36	\$736	\$773	
93-732-MOD OAK	93-732-MOD MAP	85-3/4" x 28-3/8"	54	\$750	\$788	
93-734-MOD OAK	93-734-MOD MAP	91-3/4" x 24-3/8"	40	\$750	\$788	
93-735-MOD OAK	93-735-MOD MAP	91-3/4" x 28-3/8"	58	\$761	\$799	

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

- MAT 44 - F11-1-19G-MAT

# The Maxim Collection

### **DESKTOP**

Standard desktop is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The desk top receives a solid Northern-grown Red Oak or maple flush edge band 5/8" x 1-3/16" thick, radiused 7/8" to form a bullnose shape on the patron side. A 1/4", solid Northern-grown Red Oak or maple edge band is applied to the remaining three sides of the desk top, with top and bottom edges have a 1/8" radius. All edges are applied to the desktop after the laminate and backer sheets are applied, constituting an external edge band. Desktop is positioned over the end panels of the desk module, flush with the outside edges of the end panels.

### **END PANELS**

Desk module end panel is 1" thick, 3-ply, 45# density particleboard core with select plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges are externally banded with a 1" x 1.6mm thick solid, Northern-grown Red Oak or maple veneer edge band. The end panel and front panel are joined with 3/4" x 3/4" thick solid hardwood cleats screwed to the inside surface of the panel. Each end panel receives a 3" diameter egress grommet to provide for wire passage and two adjustable glides to allow leveling of the individual units.

### FRONT PANEL

The front panel is 3/4" thick, 45# density particleboard core comprised of select rift cut Northern-grown Red Oak veneers or maple plain sliced slip matched veneers. Exposed edges are externally banded with a solid 3/4" x 1.6mm thick, veneer edge band. A 6"H x 3/4"D recessed, ebonized toe space is incorporated at the bottom of the panel. The front panel is positioned over the end panels of the desk module, flush with the outside edges of the end panels. Double wide units have two front panels to give the appearance of two individual units.

### **WORK SURFACE**

Work surface is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The exposed edge receives a 1/4" thick, Northern-grown Red Oak or maple solid internal edge band in straight design. The back edge of the work surface has a plastic black strip, 1-1/2"W, which projects above the work surface 1/4" to act as a retainer. The work surface is 24-1/2"D and is positioned 1-1/2" away from the front panel, creating a cord drop space. Adjustable work surfaces positioned at heights of 36", 32" or 27" are available in single wide standing height desks.


**Note:** See Brodart optional electrical accessories for electrical power-distribution system for desk modules.

### **SHELVES**

Shelves are constructed of 7-ply, furniture-grade veneer-core hardwood plywood, with Northern-grown Red Oak plain sliced face veneer or maple plain sliced face veneer. Exposed edges receive a 1.6mm thick, solid-oak or maple edge band.

### **DRAWERS**

Drawers are constructed of solid Northern-grown Red Oak or maple with 1/4" thick wood bottom panel. Drawer has 3-ply particleboard fronts with select oak-face veneer or maple veneer. Box drawer has extension slides with 100# load capacity. File drawer has full-extension slides with 100# load capacity.




Maxim Series Flush Edge Band

### **DESK DIMENSIONS**


Standing-Height Desk, overall: 39-3/16"H x 70"W x 30"D.

Sitting-Height Desk, overall: 32-3/16"H x 70"W x 30"D or 32-3/16"H x 70"W x 30"D.



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
73-012-S00 OAK	73-012-S00 MAP	Standing Height Desk with Patron Service Ledge	39-3/16" x 35" x 30"	140	\$2,654	\$2,893	Single-Wide Desk with Patron Service Ledge
		Inside dimensions: 33"W x 26-3/47-7/8" patron ledge is at a height Note: Adjustable-height work surf at heights of 36", 32" or 27".	of 39-3/16"H.				0
73-E12-S00 OAK	73-E12-S00 MAP	Sitting Height Desk with Patron Service Ledge	32-3/16" x 35" x 30"	125	\$2,522	\$2,748	
		Inside dimensions: 33"W x 26-3/47-7/8" patron ledge is at a height Note: Work surface is fixed at 27"	of 32-3/16"H.				
73-014-S00 OAK	73-014-S00 MAP	Standing Height Desk without Patron Service Ledge	39-3/16" x 35" x 30"	135	\$2,317	\$2,525	Single-Wide Desk without Patron Service Ledge
		Inside dimensions: 33"W x 26-3/4 work surface is at 39-3/16"H. Two grommets are located in the work s	3" diamenter				0
73-E14-S00 OAK	73-E14-S00 MAP	Sitting Height Desk without Patron Service Ledge	32-3/16" x 35" x 30"	120	\$2,122	\$2,313	
		Inside dimensions: 33"W x 26-3/4 work surface is at 32-3/16"H. Two grommets are located in the work s	3" diamenter				
73-015-S00 OAK	73-015-S00 MAP	Standing Height Book Return Unit	39-3/16" x 35" x 30"	135	\$2,246	\$2,448	Book Return Unit
		Inside dimensions: 33"W x 26-3/4 work surface is at 39-3/16"H. Unif finished opening centered in the froof books and a book chute to direct depressible book truck. (Depressib Two 3" diameter grommets are located to the surface of t	t has a 5"H x 12"W ont panel for passage t the books over a mobile le book truck not included).				
73-E15-S00 OAK	73-E15-S00 MAP	Sitting Height Book Return Unit	32-3/16" x 35" x 30"	120	\$2,114	\$2,305	
		Inside dimensions: 33"W x 26-3/4 work surface is at 32-3/16"H. Unit finished opening centered in the fro of books and a book chute to direct depressible book truck. (Depressib Two 3" diameter grommets are loc	t has a 5"H x 12"W ont panel for passage t the books over a mobile le book truck not included).				0

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Cupboard and Oper	Shelf	73-121-S00 OAK	73-121-S00 MAP	Standing Height Cupboard and Open Shelf	39-3/16" x 35" x 30"	175	\$4,415	\$4,813
0 0				This unit has one fixed and two adjushelves. A hidden drawer is position the lockable storage compartment grommets are located in the work s	ned above Two 3'' diameter			
		73-E21-S00 OAK	73-E21-S00 MAP	Sitting Height Cupboard	32-3/16" x 35" x 30"	160	\$4,127	\$4,498
0				This unit has one fixed and one adjushelf. A hidden drawer is positioned the lockable storage compartment grommets are located in the work s	l above Two 3'' diameter			
Full Width Drawer, Cupboard and Draw	<i>l</i> ers	73-122-S00 OAK	73-122-S00 MAP	Standing Height Full Width Drawer, Cupboard and Drawers	39-3/16" x 35" x 30"	225	\$6,048	\$6,593
0				This unit has one full-width drawer, two file drawers, and a lockable sto compartment. Two 3" diameter groare located in the work surface.  Note: Available in 39"H only.	=			
Cupboard and Draw	ver Unit	73-123-S00 OAK	73-123-S00 MAP	Standing Height Cupboard and Drawer Unit	39-3/16" x 35" x 30"	225	\$5,355	\$5,837



## The Maxim Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
73-124-S00 OAK	73-124-S00 MAP	Standing Height Open Shelf and Drawer Unit	39-3/16" x 35" x 30"	200	\$4,942	\$5,387	Open Shelf and Drawer Unit
		This unit has one lockable box draw and two file drawers. Shelf section two adjustable shelves, and one fit Two 3" diameter grommets are loc	has red base shelf.				
73-E24-S00 OAK	73-E24-S00 MAP	Sitting Height Open Shelf and Drawer Unit	32-3/16" x 35" x 30"	125	\$4,510	\$4,916	
		This unit has one lockable box drain and one file drawer. Shelf section I one adjustable shelf, and one fixed Two 3" diameter grommets are loc	has d base shelf.				
73-131-S00 OAK	73-131-S00 MAP	Standing Height Cash Drawer Unit	39-3/16" x 35" x 30"	150	\$3,359	\$3,662	Cash Drawer Unit
		Inside dimensions: 33"W x 26-3/ The work surface is at 39-3/16"H has locking drawer with a coin and Two 3" diameter grommets are loc	. Desk currency tray.				0 0
73-E31-S00 OAK	73-E31-S00 MAP	Sitting Height Cash Drawer Unit	32-3/16" x 35" x 30"	135	\$3,216	\$3,505	
		Inside dimensions: 33"W x 26-3/ The work surface is at 32-3/16"H has locking drawer with a coin and Two 3" diameter grommets are loc	. Desk currency tray.				
73-E32-S00 OAK	73-E32-S00 MAP	Sitting Height ADA Station	32-3/16" x 35" x 40-1/2"	185	\$2,522	\$2,748	ADA Station
		The ADA transaction station is designed to provide wheelchair ac on the patrons' side. The knee spa on the patrons' side is 22-1/4" at staff side is 16". Two 3" diameter are located in the work surface. Or egress with sleeve is located in each	ce depth nd on the grommets e 3-1/2" diameter	ł.			

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Full Width Drawer Un	it	73-133-S00 OAK	73-133-S00 MAP	Standing Height Full Width Drawer Unit	39-3/16" x 35" x 30"	160	\$3,455	\$3,765
				This drawer unit has a full-width draw 10"H x 33"W x 18-3/4"D. Two 3" grommets are located in the work su Note: Available in 39" H only.	diameter			
Full Width Drawer and Open Shelves	d	73-134-S00 OAK	73-134-S00 MAP	Standing Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D.	39-3/16" x 35" x 30"	180	\$3,264	\$3,558
				Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work su				
0		73-E34-S00 OAK	73-E34-S00 MAP	Sitting Height Full Width Drawer and Open Shelves This unit has a full-width drawer 10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-depth shelf. Two 3" diameter grommets are located in the work su	32-3/16" x 35" x 30"  face.	165	\$3,072	\$3,349
Full Width Drawer and Cupboard Unit	d ®	73-135-S00 OAK	73-135-S00 MAP	Standing Height Full Width Drawer and Cupboard Unit This unit has a full-width drawer	39-3/16" x 35" x 30"	220	\$3,841	\$4,187
				10"H x 33"W x 18-3/4"D. Also, one fixed and one adjustable, full-de shelf. Hinged doors have a catch, loc door pulls. Two 3" diameter gromme located in the work surface.	k and			

## The Maxim Collection


Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
73-172-S00 OAK	73-172-S00 MAP	Standing Height Discharge Unit	39-3/16" x 35" x 30"	165	\$3,612	\$3,937	Discharge Unit
		These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 39-3, Note: Standing-height roll unders					
73-E72-S00 OAK	73-E72-S00 MAP	Sitting Height Discharge Unit These units have a full-width well with seven removable wood trays for 5"H x 3"W cards. The 7-7/8" patron ledge is at a height of 32-3,	32-3/16" x 35" x 30" /16"H.	145	\$3,418	\$3,725	
73-174-S00 OAK	73-174-S00 MAP	Standing Height Open Shelf Unit	39-3/16" x 35" x 30"	175	\$2,689	\$2,931	Open Shelf Unit
		This unit has a full-depth fixed base shelf and two full-depth adjustable Two 3" diameter grommets are loc the work surface.	shelves.				
73-E74-S00 OAK	73-E74-S00 MAP	Sitting Height Open Shelf Unit	32-3/16" x 35" x 30"	155	\$2,401	\$2,616	
		This unit has a full-depth fixed base shelf and two full-depth adjustable Two 3" diameter grommets are loc the work surface.	shelves.				
73-176-S00 OAK	73-176-S00 MAP	Standing Height Cupboard Unit	39-3/16" x 35" x 30"	200	\$3,340	\$3,640	Cupboard Unit
		This unit has a full-depth fixed base shelf and two full-depth adjustable Hinged doors have a catch, lock and Two 3" diameter grommets are loca work surface.	shelves. d door pulls.				
73-E76-S00 OAK	73-E76-S00 MAP	Sitting Height Cupboard Unit	32-3/16" x 35" x 30"	180	\$3,187	\$3,474	
		This unit has a full-depth fixed base shelf and one full-depth adjustable Hinged doors have a catch, lock and Two 3" diameter grommets are loca work surface.	shelf. d door pulls.				

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Media Storage Unit	≫	73-236-S00 OAK	73-236-S00 MAP	Standing Height Media Storage Unit	39-3/16" x 35" x 30"	225	\$4,613	\$5,028
				This unit has four full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me	dia storage.			
	$\downarrow$	73-E36-S00 OAK	73-E36-S00 MAP	Sitting Height Media Storage Unit	32-3/16" x 35" x 30"	205	\$4,240	\$4,621
0				This unit has three full-width drawers 8-1/2"H x 33"W x 24"D with each containing five compartments for me				

## The Maxim Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
73-011-S00 OAK	73-011-S00 MAP	Standing Height Double-Wide Desk with Patron Service Ledge	39-3/16" x 70" x 30"	245	\$3,839	\$4,185	Double-Wide Desk with Patron Service Ledge,
		Work Surface at 35"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a I Two 3" diameter grommets are loo Note: Standing-height roll unders	neight of 39-3/16". cated in the work surface.		0		
73-E11-S00 OAK	73-E11-S00 MAP	Sitting Height Double-Wide Desk with Patron Service Ledge	32-3/16" x 70" x 30"	210	\$3,621	\$3,947	
		Work Surface at 28"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a h Two 3" diameter grommets are loc	neight of 32-3/16".				
73-011-SEA OAK	73-011-SEA MAP	Standing Height Double-Wide Desk with Patron Service Ledge	39-3/16" x 70" x 30"	245	\$3,742	\$4,079	
		Work Surface at 28"H Inside dimensions are 68"W x 26- The 7-7/8"D patron ledge is at a h Two 3" diameter grommets are loo Note: Standing-height roll unders	neight of 39-3/16". cated in the work surface.		0		
73-013-S00 OAK	73-013-S00 MAP	Standing Height Double-Wide	39-3/16" x 70" x 30"	230	\$3,411	\$3,717	Double-Wide Desk
		Desk without Patron Service Ledge Inside dimensions are 68"W x 26-	•				without Patron Service Ledge
		The work surface is at 39-3/16" H diameter grommets are located in	l. Two 3''		0		
73-E13-S00 OAK	73-E13-S00 MAP	Sitting Height Double-Wide Desk without Patron Service Ledge	32-3/16" x 70" x 30"	195	\$3,240	\$3,532	0 0
		Inside dimensions are 68"W x 26- The work surface is at 32-3/16" H diameter grommets are located in	l. Two 3"				

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Double-Wide Doubl Work Desk	e Pedestal	73-E37-S00 OAK	73-E37-S00 MAP	Sitting Height Double-Wide Double Pedestal Work Desk	32-3/16" x 70" x 30"	260	\$7,872	\$8,580
0				Inside dimensions are 68"W x 26- This unit has two drawer pedestals on each side consisting of one lock one file drawer with hanging file ra Two center drawers are mounted b Two 3" diameter grommets are loo Note: Available in 32-3/16" Hor	, one mounted king drawer at top; ck at bottom. etween the two pedestals. cated in the work surface.			



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing	Sitting
73-010-S00 OAK	73-010-S00 MAP	Standing Height 90 Degree Multi-Purpose Corner	39-3/16" x 71-3/4" x 3	30" 250	\$5,013	\$5,464	Multi-Pı	90 Degree urpose Corner
		Unit has 29-5/16"W port area. Sangled areas to the left and right of grommet is located in the work-su with sleeve is located in each end	of the desk module. One 3" di urface top. One 3-1/2" diame	ameter		0		
73-E10-S00 OAK	73-E10-S00 MAP	Sitting Height 90 Degree Multi-Purpose Corner Unit has 29-5/16"W port area. S	32-3/16" x 71-3/4" x 3		\$4,797	\$5,228	0	0
		angled areas to the left and right of grommet is located in the work-su with sleeve is located in each end	of the desk module. One 3" di urface top. One 3-1/2" diame	ameter				
73-017-S00 OAK	73-017-S00 MAP	Standing Height 90 Degree Multi-Purpose with Patron Service	39-3/16" x 71-3/4" x 3	30" 245	\$6,513	\$7,099	90 Degree Multi-Pu with Patron S	ırpose Corner Service Ledge
		Unit has 29-5/16"W port area. Ti Work surface is at 35"H. Storage and right of the module. One 3"d One 3-1/2"diameter egress with	he 7-7/8"D patron ledge is at shelves are located in the two liameter grommet is located ir	angled are the work si	as to the let urface top.	ft		
73-E17-S00 OAK	73-E17-S00 MAP	Sitting Height 90 Degree Multi-Purpose with Patron Service	32-3/16" x 71-3/4" x 3 e Ledge	30" 210	\$6,239	\$6,801		
		Unit has 29-5/16"W port area. T Work surface is at 28"H. Storage and right of the module. One 3" of 3-1/2" diameter egress with slee	shelves are located in the two diameter grommet is located in	angled are n the work s	as to the let urface top.	ft	0	0
73-016-S00 OAK	73-016-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"H	140	\$2,680	\$2,921	Close	90 Degree ed Corner Unit
		This 90 degree unit is used to form This is not available with patron le in each end panel for wire passag	edge. One 3-1/2" diameter eg	ress is loca		0	0	
73-E16-S00 OAK	73-E16-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"H	120	\$2,550	\$2,779	0	0
		This 90 degree unit is used to form This is not available with patron le in each end panel for wire passag	edge. One 3-1/2" diameter eg	ress is loca				

Standing	Sitting	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
45 Degree Closed	Corner Unit	73-018-S00 OAK	73-018-S00 MAP	Standing Height 45 Degree Closed Corner Unit This corner unit is used to create a This unit is not available with a pa			<b>\$2,490</b> sk.	\$2,715
	0	73-E18-S00 OAK	73-E18-S00 MAP	Sitting Height 45 Degree Closed Corner Unit This corner unit is used to create a This unit is not available with a pa			<b>\$2,358</b> sk.	\$2,570
90 Degree Open C		73-040-S00 OAK	73-040-S00 MAP	Standing Height 90 Degree Open Curved Corner with Patron 9	39-3/16'' x 70-1/8'' x 30 Service Ledge	" 245	\$8,125	\$8,856
0	0			The 7-7/8"D patron ledge is at a Unit has 26-5/8"W port area. Si and right of the desk module. On One 3-12" diameter egress with	orage shelves are located in t e 3" diameter grommet is loc	the two a ated in th	ngled areas ie work surfa	to the left ace top.
0		73-E40-S00 OAK	73-E40-S00 MAP	Sitting Height 90 Degree Open Curved Corner with Patron S The 7-7/8"D patron ledge is at a Unit has 26-5/8"W port area. St and right of the desk module. One One 3-12" diameter egress with	height of 32-3/16". The wor corage shelves are located in t e 3" diameter grommet is loc	k surface he two a ated in th	ngled areas ie work surfa	to the left ace top.
90 Degree Open C	Curved Corner	73-041-S00 OAK	73-041-S00 MAP	Standing Height 90 Degree Open Curved Corner	39-3/16" x 70-1/8" x 30	" 245	\$7,165	\$7,809
0	0			Work surface is at 39-3/16"H. U in the two angled areas to the left is located in the work-surface top in each end panel for wire passage	and right of the desk module . One 3-1/2" diameter egree	. One 3''	diameter gr	rommet
0		73-E41-S00 OAK	73-E41-S00 MAP	Sitting Height 90 Degree Open Curved Corner Work surface is at 32-3/16"H. Ui in the two angled areas to the left is located in the work-surface top in each end panel for wire passag	and right of the desk module One 3-1/2" diameter egres	Storage s	diameter gr	rommet

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Standing Sitting
73-047-S00 OAK	73-047-S00 MAP	Standing Height 60 Degree Curved Corner with Patron Ser	39-3/16" x 80-3/4" x 30"	245		\$10,665	60 Degree Curved Corner with Patron Service Ledge
		Unit has 49-1/16" W port are left and right of the desk modu	at a height of 39-3/16". The work s a. Storage shelves are located in the ale. One 3" diameter grommet is lo ress with sleeve is located in each of	ne two ang cated in th	led areas to ne work surf	the ace	
73-E47-S00 OAK	73-E47-S00 MAP	Sitting Height 60 Degree Curved Corner with Patron Ser	32-3/16" x 80-3/4" x 30" vice Ledge	210	\$9,434	\$10,283	
		Unit has 49-1/16" W port are left and right of the desk modu	at a height of 32-3/16". The work s a. Storage shelves are located in the ale. One 3" diameter grommet is lo ress with sleeve is located in each of	ne two ang cated in th	led areas to ne work surf	ace	
73-048-S00 OAK	73-048-S00 MAP	Standing Height 60 Degree Curved Corner	39-3/16" x 80-3/4" x 30"	245	\$8,843	\$9,638	60 Degree Curved Corner
		located in the two angled area	I. Unit has 49-1/16"W port area. S s to the left and right of the desk m c surface top. One 3-1/2" diamete vire passage.	odule. On	e 3" diame		
73-E48-S00 OAK	73-E48-S00 MAP	Sitting Height 60 Degree Curved Corner	32-3/16" x 80-3/4" x 30"	210	\$8,533	\$9,301	
		located in the two angled area	I. Unit has 49-1/16"W port area. S s to the left and right of the desk m c surface top. One 3-1/2" diamete wire passage.	odule. On	e 3" diame		
73-055-S00 OAK	73-055-S00 MAP	Standing Height 90 Degree Closed Corner Unit	39-3/16"Hx30"D	140	\$3,464	\$3,776	90 Degree Curved Closed Corner Unit
		This 90 degree unit is used to this unit is provided with a cur	form a right-angle turn in a desk arr ved front panel.	rangemen	t.		
73-E55-S00 OAK	73-E55-S00 MAP	Sitting Height 90 Degree Closed Corner Unit	32-3/16"Hx30"D	120	\$3,236	\$3,527	
			form a right-angle turn in a desk arr ved front panel.	angemen	t.		

Chanding	Cittie	Oak	Maple			Wt.	0ak	Maple
Standing	Sitting	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
45 Degree Curved Closed Corner Unit		73-058-S00 OAK	73-058-S00 MAP	Standing Height 45 Degree Curved Closed Corner Unit	39-3/16" x 22-3/8" x 30	' 130	\$3,167	\$3,452
				This unit is used to create a 45 de It is not available with patron ledg		lesk.		
		73-E58-S00 OAK	73-E58-S00 MAP	Sitting Height 45 Degree Curved Closed Corner Unit	32-3/16" x 22-3/8" x 30	' 110	\$2,938	\$3,203
				This unit is used to create a 45 de It is not available with patron ledg		lesk.		
90 Degree Open Cor	ner Shelf	73-143-S00 OAK	73-143-S00 MAP	Standing Height 90 Degree Open Corner Shelf	39-3/16"H x 30"D	140	\$2,464	\$2,686
				This 90 degree unit is used to form Has one fixed base shelf and two <b>Note</b> : Units must be modified on on open corner units.	adjustable shelves.	ŭ		gh
		73-E43-S00 OAK	73-E43-S00 MAP	Sitting Height 90 Degree Open Corner Shelf	32-3/16"H x 30"D	120	\$2,281	\$2,486
				This 90 degree unit is used to form Has one fixed base shelf and two: <b>Note:</b> Units must be modified on on open corner units.	adjustable shelves.	_		gh
90 Degree Square C	orner Unit	73-150-S00 OAK	73-150-S00 MAP	Standing Height 90 Degree Square Corner Unit	39-3/16" x 30" x 30"	160	\$2,667	\$2,906
0 0				This square corner unit is used to One 3" diameter egress is located a continuous ABS tube.				
		73-E50-S00 OAK	73-E50-S00 MAP	Sitting Height 90 Degree Square Corner Unit	32-3/16" x 30" x 30"	140	\$2,514	\$2,740
0	0			This square corner unit is used to One 3" diameter egress is located a continuous ABS tube.		-		

### The Maxim Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
73-178-S00 OAK	73-178-S00 MAP	Detachable End Panels (Pair) End panels are 1" thick, 3-ply, 45 particleboard core with plain-slicu veneers. Exposed edges are exter with 1.6mm thick, solid Northern-	ed oak or maple nally banded	52 nd.	\$1,027	\$1,119	Detachable End Panels (Pair)
73-E78-S00 OAK	73-E78-S00 MAP	Detachable End Panels (Pair) End panels are 1" thick, 3-ply, 45 particleboard core with plain-slic veneers. Exposed edges are exter with 1.6mm thick, solid Northern-	ed oak or maple nally banded		\$980	\$1,068	

73-196-S00 OAK 73-196-S00 MAP Single-Wide Add On 7" x 35" x 7-7/8" 10 \$509 \$556 Single-Wide Add On 7"H Patron Ledge

Unit is designed to be added onto a single wide desk without a patron ledge. The Patron Ledge Assembly will attach to the desktop by means of #8 x 2-1/2" screws inserted through the work surface into the ledge assembly.

73-197-S00 OAK
73-197-S00 MAP
Double-Wide Add On
7"H Patron Ledge
Unit is designed to be added onto a double wide desk
without a patron ledge. The Patron Ledge Assembly will attach
to the desktop by means of #8 x 2-1/2" screws inserted through
the work surface into the ledge assembly.



# The Quorum 94T Collection

#### TABLETOP - 94T Series

Standard tabletops are 1-3/16" thick, 5-ply solid plywood or 1-3/16" thick particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are solid Northern-grown red oak. Drop edge band is 5/8" thick x 1-5/8", externally banded to form a bullnose with a 1/4" radius at corners.

#### APRON (OPTIONAL)

A 1-3/4"W x 25/32" Northern-grown red oak apron is fitted between the legs and behind the extended tabletop edge band. A 1/4" styling line, routed into the apron, highlights the tabletop and legs. The bottom edge and both ends of each apron receive a 1/2" radius.

Aprons on round tables are fitted between the legs and follow the curvature of the edge band. (Aprons are an optional feature on 94T Series tables).


#### **LEGS**


Legs are glued up, 2-1/4" square solid Northern-grown red oak. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are radiused 1/8". Each leg has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two-thirds of the glide.

Legs attach to tabletops by means of a 5" square x 5/16" thick steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind, and be hidden by, the extended table edge band.

#### TABLETOP SUPPORT

For maximum rigidity, rectangular tables 60" or more wide receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 90" or wider receive two extra legs located under the center of the table to provide added support.





94T Series Drop Edge

94T Series
External Edge Band

## Quorum 94T Collection

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
Round Oak Tabl	'e						Round Table
94T-109-S00 OAK 94T-Y09-S00 OAK	94T-109-S02 OAK 94T-Y09-S02 OAK	Adult Table Youth Table	29"H x 36" Diameter 27-1/2"H x 36" Diameter	100 100	\$1,563 \$1,563	\$1,372 \$1,372	
94T-J09-S00 OAK	94T-J09-S02 OAK	Juvenile Table	25"H x 36" Diameter	100	\$1,563	\$1,372	
94T-129-S00 OAK	94T-129-S02 OAK	Adult Table	29"H x 42" Diameter	110	\$1,696	\$1,504	
94T-Y29-S00 OAK 94T-J29-S00 OAK	94T-Y29-S02 OAK 94T-J29-S02 OAK	Youth Table Juvenile Table	27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110	\$1,696 \$1,696	\$1,504 \$1,504	
94T-141-S00 OAK	94T-141-S02 OAK	Adult Table	29"H x 48" Diameter	120	\$1,696	\$1,504	
94T-Y41-S00 OAK	94T-Y41-S02 OAK	Youth Table	27-1/2"H x 48" Diameter	120	\$1,696	\$1,504	
94T-J41-S00 OAK	94T-J41-S02 OAK	Juvenile Table	25"H x 48" Diameter	120	\$1,696	\$1,504	
N/A	94T-130-S02 OAK	Adult Table	29"H x 60" Diameter	140	N/A	\$2,003	
N/A	94T-Y30-S02 OAK	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$2,003	
N/A	94T-J30-S02 OAK	Juvenile Table	25"H x 60" Diameter	140	N/A	\$2,003	
<u>Round Maple Ta</u>	<u>ıble</u>						
94T-109-S00 MAP	94T-109-S02 MAP	Adult Table	29"H x 36" Diameter	100	\$1,703	\$1,494	
94T-Y09-S00 MAP	94T-Y09-S02 MAP	Youth Table	27-1/2"H x 36" Diameter	100	\$1,703 \$1,703	\$1,494	
94T-J09-S00 MAP	94T-J09-S02 MAP	Juvenile Table	25"H x 36" Diameter	100	\$1,703	\$1,494	
94T-129-S00 MAP	94T-129-S02 MAP	Adult Table	29"H x 42" Diameter	110	\$1,848	\$1,639	
94T-Y29-S00 MAP 94T-J29-S00 MAP	94T-Y29-S02 MAP 94T-J29-S02 MAP	Youth Table Juvenile Table	27-1/2"H x 42" Diameter 25"H x 42" Diameter	110 110	\$1,848 \$1,848	\$1,639 \$1,639	
		Adult Table	29"H x 48" Diameter	120	•	-	
94T-141-S00 MAP 94T-Y41-S00 MAP	94T-141-S02 MAP 94T-Y41-S02 MAP	Youth Table	27-1/2"H x 48" Diameter	120	\$1,848 \$1,848	\$1,639 \$1,639	
94T-J41-S00 MAP	94T-J41-S02 MAP	Juvenile Table	25"H x 48" Diameter	120	\$1,848	\$1,639	
N/A	94T-130-S02 MAP	Adult Table	29"H x 60" Diameter	140	N/A	\$2,184	
N/A	94T-Y30-S02 MAP	Youth Table	27-1/2"H x 60" Diameter	140	N/A	\$2,184	
N/A	94T-J30-S02 MAP	Juvenile Table	25"H x 60" Diameter	140	N/A	\$2,184	
Square Oak Tab	<u>le</u>						Square Tab
94T-191-S00 OAK	94T-191-S02 OAK	Adult Table	29" x 30" x 30"	110	\$1,377	\$1,216	
94T-Y91-S00 OAK	94T-Y91-S02 OAK	Youth Table	27-1/2" x 30" x 30"	110	\$1,377	\$1,216	
94T-J91-S00 OAK	94T-J91-S02 OAK	Juvenile Table	25" x 30" x 30"	110	\$1,377	\$1,216	
94T-137-S00 OAK	94T-137-S02 OAK	Adult Table	29" x 42" x 42"	110	\$1,510	\$1,307	
94T-Y37-S00 OAK 94T-J37-S00 OAK	94T-Y37-S02 OAK 94T-J37-S02 OAK	Youth Table Juvenile Table	27-1/2" x 42" x 42" 25" x 42" x 42"	110 110	\$1,510 \$1,510	\$1,307 \$1,307	
					•	•	
94T-154-S00 OAK 94T-Y54-S00 OAK	94T-154-S02 OAK 94T-Y54-S02 OAK	Adult Table Youth Table	29" x 48" x 48" 27-1/2" x 48" x 48"	110 110	\$1,647 \$1,647	\$1,460 \$1,460	
94T-J54-S00 OAK	94T-J54-S02 OAK	Juvenile Table	25" x 48" x 48"	110	\$1,647	\$1,460	•
Sauara Manta T	abla						
<i>Square Maple Ta</i> 94T-191-S00 MAP		Adult Table	29" x 30" x 30"	110	¢1 E01	¢1 224	
94T-Y91-S00 MAP	94T-191-S02 MAP 94T-Y91-S02 MAP	Youth Table	27-1/2" x 30" x 30"	110 110	\$1,501 \$1,501	\$1,326 \$1,326	
94T-J91-S00 MAP	94T-J91-S02 MAP	Juvenile Table	25" x 30" x 30"	110	\$1,501	\$1,326	
94T-137-S00 MAP	94T-137-S02 MAP	Adult Table	29" x 42" x 42"	110	\$1,646	\$1,425	
94T-Y37-S00 MAP	94T-Y37-S02 MAP	Youth Table	27-1/2" x 42" x 42"	110	\$1,646	\$1,425	
94T-J37-S00 MAP	94T-J37-S02 MAP	Juvenile Table	25" x 42" x 42"	110	\$1,646	\$1,425	
94T-154-S00 MAP	94T-154-S02 MAP	Adult Table	29" x 48" x 48"	110	\$1,795	\$1,591	
94T-Y54-S00 MAP	94T-Y54-S02 MAP	Youth Table	27-1/2" x 48" x 48"	110	\$1,795	\$1,591	
94T-J54-S00 MAP	94T-J54-S02 MAP	Juvenile Table	25" x 48" x 48"	110	\$1,795	\$1,591	
Catalog No.	Descrip	tion				Price	
						\$84	<u></u> Caster
LG-CST-S00	Wood Leg						

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ High-Pressure\ Laminate\ (Table\ 2).\ Details\ can\ be\ found\ on\ page\ GEN\ 4.$ 

Note: Optional Wood Aprons for Tables are located on page QUO 7.

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Re	ctangular Oak Tab	ole				
Rectrangular Table	94T-194-S00 OAK	94T-194-S02 OAK	Adult Table	29" x 30" x 60"	120	\$1,409	\$1,205
	94T-Y94-S00 OAK	94T-Y94-S02 OAK	Youth Table	27-1/2" x 30" x 60"	120	\$1,409	\$1,205
	94T-J94-S00 OAK	94T-J94-S02 OAK	Juvenile Table	25" x 30" x 60"	120	\$1,409	\$1,205
	94T-195-S00 OAK	94T-195-S02 OAK	Adult Table	29" x 30" x 72"	140	\$1,565	\$1,342
	94T-Y95-S00 OAK	94T-Y95-S02 OAK	Youth Table	27-1/2" x 30" x 72"	140	\$1,565	\$1,342
· ·	94T-J95-S00 OAK	94T-J95-S02 OAK	Juvenile Table	25" x 30" x 72"	140	\$1,565	\$1,342
	Four-Reader Re	ctangular Maple 1	able				
Ψ	94T-194-S00 MAP	94T-194-S02 MAP	Adult Table	29" x 30" x 60"	120	\$1,537	\$1,313
	94T-Y94-S00 MAP	94T-Y94-S02 MAP	Youth Table	27-1/2" x 30" x 60"	120	\$1,537 \$1,537	\$1,313
	94T-J94-S00 MAP	94T-J94-S02 MAP	Juvenile Table	25" x 30" x 60"	120	\$1,537	\$1,313
	94T-195-S00 MAP	94T-195-S02 MAP	Adult Table	29" x 30" x 72"	140	\$1,706	\$1,463
	94T-Y95-S00 MAP	94T-Y95-S02 MAP	Youth Table	27-1/2" x 30" x 72"	140	\$1,706	\$1,463
	94T-J95-S00 MAP	94T-J95-S02 MAP	Juvenile Table	25" x 30" x 72"	140	\$1,706	\$1,463
Six-Reader	Six-Reader Rect	tangular Oak Tabl	<u>e</u>				
Rectrangular Table	94T-144-S00 OAK	94T-144-S02 OAK	Adult Table	29" x 36" x 60"	120	\$1,489	\$1,299
	94T-Y44-S00 OAK	94T-Y44-S02 OAK	Youth Table	27-1/2" x 36" x 60"	120	\$1,489	\$1,299
	94T-J44-S00 OAK	94T-J44-S02 OAK	Juvenile Table	25" x 36" x 60"	120	\$1,489	\$1,299
	94T-138-S00 OAK	94T-138-S02 OAK	Adult Table	29" x 36" x 72"	140	\$1,633	\$1,435
	94T-Y38-S00 OAK	94T-Y38-S02 OAK	Youth Table	27-1/2" x 36" x 72"	140	\$1,633	\$1,435
	94T-J38-S00 OAK	94T-J38-S02 OAK	Juvenile Table	25" x 36" x 72"	140	\$1,633	\$1,435
	94T-145-S00 OAK	94T-145-S02 OAK	Adult Table	29" x 48" x 72"	170	\$1,792	\$1,595
$\bigvee$	94T-Y45-S00 OAK	94T-Y45-S02 OAK	Youth Table	27-1/2" x 48" x 72"	170	\$1,792	\$1,595
	94T-J45-S00 OAK	94T-J45-S02 OAK	Juvenile Table	25" x 48" x 72"	170	\$1,792	\$1,595
	Six-Reader Reci	tangular Maple Ta	ble				
		94T-144-S02 MAP	Adult Table	29" x 36" x 60"	120	\$1,623	\$1,417
	94T-Y44-S00 MAP	94T-Y44-S02 MAP	Youth Table	27-1/2" x 36" x 60"	120	\$1,623	\$1,417
	94T-J44-S00 MAP	94T-J44-S02 MAP	Juvenile Table	25" x 36" x 60"	120	\$1,623	\$1,417
	94T-138-S00 MAP	94T-138-S02 MAP	Adult Table	29" x 36" x 72"	140	\$1,780	\$1,564
	94T-Y38-S00 MAP	94T-Y38-S02 MAP	Youth Table	27-1/2" x 36" x 72"	140	\$1,780	\$1,564
	94T-J38-S00 MAP	94T-J38-S02 MAP	Juvenile Table	25" x 36" x 72"	140	\$1,780	\$1,564
	94T-145-S00 MAP	94T-145-S02 MAP	Adult Table	29" x 48" x 72"	170	\$1,953	\$1,738
	94T-Y45-S00 MAP	94T-Y45-S02 MAP	Youth Table	27-1/2" x 48" x 72"	170	\$1,953	\$1,738
	94T-J45-S00 MAP	94T-J45-S02 MAP	Juvenile Table	25" x 48" x 72"	170	\$1,953	\$1,738
	Catalog No.		Description			Price	
Casters	LG-CST-S00		Wood Leg Caste	er hooded, twin-wheel caster	with a brake	\$84	ortable leg (sold each)

Please specify Wood Finish (Table 1) and High-Pressure Laminate (Table 2). Details can be found on page GEN 4.

Note: Optional Wood Aprons for Tables are located on page QUO 7.

## Quorum 94T Collection

	Particleboard Core Price	Plywood Core Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Rectangular Table wit				e <i>gs</i>	er Support Le	k Table with Cente	Rectangular Oal
Center Support Leg	\$1,870	\$2,136	165	29" x 30" x 90"	Adult Table	94T-198-S02 OAK	94T-198-S00 OAK
	\$1,870	\$2,136	165	27-1/2" x 30" x 90"	Youth Table	94T-Y98-S02 OAK	94T-Y98-S00 OAK
	\$1,870	\$2,136	165	25" x 30" x 90"	Juvenile Table	94T-J98-S02 OAK	94T-J98-S00 OAK
	\$1,928 <b>U</b>	\$2,217	165	29" x 36" x 90"	Adult Table	94T-146-S02 OAK	94T-146-S00 OAK
	\$1,928	\$2,217	165	27-1/2" x 36" x 90"	Youth Table	94T-Y46-S02 OAK	94T-Y46-S00 OAK
	\$1,928	\$2,217	165	25" x 36" x 90"	Juvenile Table	94T-J46-S02 OAK	94T-J46-S00 OAK
	\$2,058	\$2,365	185	29" x 48" x 90"	Adult Table	94T-134-S02 OAK	94T-134-S00 OAK
$\bigvee$	\$2,058	\$2,365	185	27-1/2" x 48" x 90"	Youth Table	94T-Y34-S02 OAK	94T-Y34-S00 OAK
	\$2,058	\$2,365	185	25" x 48" x 90"	Juvenile Table	94T-J34-S02 OAK	94T-J34-S00 OAK
				<u>Legs</u>	nter Support	ple Table with Ce	Rectangular Ma
	\$2,038	\$2,329	165	29" x 30" x 90"	Adult Table	94T-198-S02 MAP	94T-198-S00 MAP
	\$2,038	\$2,329	165	27-1/2" x 30" x 90"	Youth Table	94T-Y98-S02 MAP	94T-Y98-S00 MAP
	\$2,038	\$2,329	165	25" x 30" x 90"	Juvenile Table	94T-J98-S02 MAP	94T-J98-S00 MAP
	\$2,101	\$2,416	165	29" x 36" x 90"	Adult Table	94T-146-S02 MAP	94T-146-S00 MAP
	\$2,101	\$2,416	165	27-1/2" x 36" x 90"	Youth Table	94T-Y46-S02 MAP	94T-Y46-S00 MAP
	\$2,101	\$2,416	165	25" x 36" x 90"	Juvenile Table	94T-J46-S02 MAP	94T-J46-S00 MAP
	\$2,243	\$2,579	185	29" x 48" x 90"	Adult Table	94T-134-S02 MAP	94T-134-S00 MAP
	\$2,243	\$2,579	185	27-1/2" x 48" x 90"	Youth Table	94T-Y34-S02 MAP	94T-Y34-S00 MAP
	\$2,243	\$2,579	185	25" x 48" x 90"	Juvenile Table	94T-J34-S02 MAP	94T-J34-S00 MAP

 Catalog No.
 Description
 Price

 LG-CST-S00
 Wood Leg Caster
 \$84

3" black nylon, hooded, twin-wheel caster with a brake. Add one caster per table leg (sold each).



	Plywood Core Catalog No.	Particleboard Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Price
Four-Reader with Panel Base	Four-Reader w	ith Panel Base Oa	ak Table				
	94T-P44-S00 OAK	94T-P44-S02 OAK	Four Reader Table	29" x 60" x 36"	145	\$2,040	\$1,808
	94T-P38-S00 OAK	94T-P38-S02 OAK	Four Reader Table	29" x 72" x 36"	158	\$2,114	\$1,857
	94T-P45-S00 OAK	94T-P45-S02 OAK	Four Reader Table	29" x 72" x 48"	206	\$2,561	\$2,290
	Four-Reader w	ith Panel Base Ma	aple Table				
$\searrow$	94T-P44-S00 MAP	94T-P44-S02 MAP	Four Reader Table	29" x 60" x 36"	145	\$2,224	\$1,971
	94T-P38-S00 MAP	94T-P38-S02 MAP	Four Reader Table	29" x 72" x 36"	158	\$2,304	\$2,024
	94T-P45-S00 MAP	94T-P45-S02 MAP	Four Reader Table	29" x 72" x 48"	206	\$2,791	\$2,496
Six-Reader with Panel Base	Six-Reader with	h Panel Base Oak	«Table				
Six Reader Will Fuller Base	94T-P46-S00 OAK	94T-P46-S02 OAK	Six Reader Table	29" x 90" x 36"	178	\$2,492	\$2,226
	94T-P34-S00 OAK	94T-P34-S02 OAK	Six Reader Table	29" x 90" x 48"	233	\$2,566	\$2,285
	Six-Reader with	h Panel Base Ma <sub>l</sub>	ole Table				
	94T-P46-S00 MAP	94T-P46-S02 MAP	Six Reader Table	29" x 90" x 36"	178	\$2,716	\$2,426
	94T-P34-S00 MAP	94T-P34-S02 MAP	Six Reader Table	29" x 90" x 48"	233	\$2,797	\$2,491

#### **Optional Wood Aprons for Tables**

An Apron is a 1-3/4"W x 25/32" Northern-grown red oak apron is fitted between the legs and behind the extended tabletop edge band. A 1/4" styling line, routed into the apron, highlights the tabletop and legs. The bottom edge and both ends of each apron receive a 1/2" radius.

0ak	Maple		Wt.	Oak	Maple
Catalog No.	Catalog No.	Description	(lbs.)	Price	Price
109-AK-S00 OAK	109-AK-S00 MAP	For 36" Diameter Table	5	\$209	\$228
129-AK-S00 OAK	129-AK-S00 MAP	For 42" Diameter Table	5	\$209	\$228
141-AK-S00 OAK	141-AK-S00 MAP	For 48" Diameter Table	5	\$214	\$234
130-AK-S00 OAK	130-AK-S00 MAP	For 60" Diameter Table	5	\$227	\$247
191-AK-S00 OAK	191-AK-S00 MAP	For 30" Square Table	5	\$145	\$158
137-AK-S00 OAK	137-AK-S00 MAP	For 42" Square Table	5	\$154	\$168
154-AK-S00 OAK	154-AK-S00 MAP	For 48" Square Table	5	\$170	\$186
194-AK-S00 OAK	194-AK-S00 MAP	For 30" x 60" Table	5	\$174	\$190
195-AK-S00 OAK	195-AK-S00 MAP	For 30" x 72" Table	5	\$190	\$207
198-AK-S00 OAK	198-AK-S00 MAP	For 30" x 90" Table	5	\$193	\$210
144-AK-S00 OAK	144-AK-S00 MAP	For 36" x 60" Table	8	\$180	\$197
138-AK-S00 OAK	138-AK-S00 MAP	For 36" x 72" Table	8	\$198	\$215
146-AK-S00 OAK	146-AK-S00 MAP	For 36" x 90" Table	10	\$198	\$215
145-AK-S00 OAK	145-AK-S00 MAP	For 48" x 72" Table	10	\$209	\$228
134-AK-S00 OAK	134-AK-S00 MAP	For 48" x 90" Table	12	\$214	\$234

#### TABLETOP - 94T Series

Standard tabletops are 1-3/16" thick, 5-ply solid plywood or 1-3/16" thick particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are solid Northern-grown red oak. Drop edge band is 5/8" thick x 1-5/8", externally banded to form a bullnose with a 1/4" radius at corners.

#### CHROME PEDESTAL BASE


Pedestal base consists of a 3" diameter column that is assembled to a 22-3/8" diameter floor base using a M16 x 55mm hex head bolt. The floor base comes equipped with five nylon glides. The floor base and column are attached to the 11-13/16" square table support using an M16 x 55mm hex head bolt. This base assembly is attached to the bottom of the tabletop by eight #12 x 1" phillips pan head screws.

#### BLACK POWDERED-COAT PEDESTAL BASE


Pedestal base consists of a 3" diameter column that is assembled to an "x" shaped 33" base diameter. Each leg is fitted with nylon base glides. The floor base and column are attached to the 11-13/16" square table support using an M16 x 55mm hex head bolt. This base assembly is attached to the bottom of the tabletop by eight #12 x 1" phillips pan head screws.

#### WOOD PEDESTAL BASE

Pedestal base will be solid Northern-grown Red Oak or maple. The base consists of four assembled leg components comprised of 6/4 solid material assembled using mortise and tenon construction. The upper horizontal part of the each base leg will receive borings for attaching the assembly to the tabletop. The lower horizontal piece will receive a 1-1/2" diameter, adjustable glide mounted in a recessed tee-nut which is further recessed into the leg by means of a counter-sink boring which accepts the upper two-thirds of the glide. All pedestal base edges will receive a 1/4" radius. The four assembled base components will connect to a 2-1/4" x 2-1/4" solid Northern-grown red oak or maple post using metal to metal hardware fasteners forming a one piece pedestal. Table tops are attached to base by bolting through the upper horizontal members of base into internal and external threaded bushings embedded in the under side of the table top.



94T Series Drop Edge



94T Series External Edge Band

Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
94T4230RCS00	94T4230RCS02	Round Table	42" x 30" Diameter	75	\$2,563	\$2,307	Tables with Chrome
94T4236RCS00	94T4236RCS02	Round Table	42" x 36" Diameter	95	\$2,609	\$2,450	Pedestal Base
94T4230SCS00 94T4236SCS00	94T4230SCS02 94T4236SCS02	Square Table Square Table	42" x 30" x 30" 42" x 36" x 36"	78 98	\$2,204 \$2,209	\$1,948 \$2,050	
94T4230RBS00	94T4230RBS02	Round Table	42" x 30" Diameter	70	\$1,717 \$1,712	\$1,461	Tables with Black
94T4236RBS00	94T4236RBS02	Round Table	42" x 36" Diameter	92	\$1,763	\$1,604	Powder-Coat Pedestal Base
94T4230SBS00	94T4230SBS02	Square Table	42" x 30" x 30"	75	\$1,358	\$1,102	
94T4236SBS00	94T4236SBS02	Square Table	42" x 36" x 36"	100	\$1,363	\$1,205	
94T3936RWS00	94T3936RWS02	Round Table	39" x 36" Diameter	100	\$2,471	\$2,307	Tables with Oak Wood
94T3942RWS00	94T3942RWS02	Round Table	39" x 42" Diameter	110	\$2,563	\$2,409	Pedestal Base
94T3936SWS00	94T3936SWS02	Square Table	39" x 36" x 36"	115	\$1,994	\$1,835	
94T3942SWS00	94T3942SWS02	Square Table	39" x 42" x 42"	120	\$2,076	\$1,902	
94T3936RWS00 MAP	94T3936RWS02 MAP	Round Table	39" x 36" Diameter	100	\$2,693	\$2,514	Tables with Maple Wood
94T3942RWS00 MAP	94T3942RWS02 MAP	Round Table	39" x 42" Diameter	110	\$2,793	\$2,626	Pedestal Base
94T3936SWS00 MAP	94T3936SWS02 MAP	Square Table	39" x 36" x 36"	115	\$2,173	\$2,001	
94T3942SWS00 MAP	94T3942SWS02 MAP	Square Table	39" x 42" x 42"	120	\$2,263	\$2,073	

#### TABLETOPS - QUORUM 94T Series

Standard tabletop is 1-3/16" thick 3-ply particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Edges are solid Northern-grown red oak applied to the core after the top and bottom laminate sheets are applied. (External Edge Band). Drop edge band is 1-5/8"W and 5/8" thick and extends 3/8" below the core. Note: Standing Height Tables are "Apron" construction.

#### LEGS WITHOUT APRON

Legs are glued up, 2-1/4" square Northern-grown red oak. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are radiused 1/8". Each leg has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick cold-rolled steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop. Leg plates are positioned behind and hidden by the extended table edge band.

#### LEGS WITH APRON

Legs are glued up, 2-1/4" Northern-grown red oak. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are raduised 1/8". Each leg has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16" -18 hex-head bolts per leg.

#### LEG (CENTER)

Additional leg(s) added to the center of the table for extra support are 2-1/4" square with a 1/2" radius on vertical edges.

#### APRON

A 3-1/2" W x 1" thick solid Northern-grown red oak apron is fitted between the legs and behind the extended tabletop edge band. A 1/4" styling line, routed into the apron, highlights the tabletop and legs. Bottom edge and both ends of each apron receive a 1/2" radius. Aprons are secured to the tabletop by attaching hardwood cleats to the inside surface of aprons and screwing through the cleats into the underside of the tabletop.

#### PRIVACY PANEL

Privacy panels are 10"H, constructed of 1" thick veneered particleboard. Exposed panel edges are banded with 1.6mm solid oak. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the privacy panels and is finished to match the table. Privacy panel is designed to obscure wires exiting computer equipment and to eliminate incidental tampering.

#### COMPUTER SHELF


Shelf is manufactured from steel. The shelf is 8-3/4" below the work surface and is 23"W x 17"D and is mounted under tabletop.

#### ELECTRICA


Tables receive 3" grommets in tabletop for wire passage, and J-channel wire managers mounted under tabletop to hold exces wires. Grommets are ABS, black plastic, with notched removable cap. J-channel is 18-gauge steel with electrostatically applied black powder paint.

#### TABLETOP HEIGHT

Standing Height: 39" (with Apron) Sitting Height: 27-1/2" (without Apron)



94T Series Drop Edge



## Quorum 94T Collection


645-S00 MAP 665-S00 MAP 665-S05 MAP 649-S00 MAP 669-S00 MAP 669-S05 MAP	Sitting Height Sitting Height Standing Height Sitting Height Sitting Height Sitting Height Standing Height	27-1/2" x 30" x 24" 27-1/2" x 30" x 30" 39" x 30" x 30" 27-1/2" x 60" x 24" 27-1/2" x 60" x 30" 39" x 60" x 30"	80 80 85 110 110 115	\$1,204 \$1,283 \$1,283 \$1,729 \$1,729 \$1,863 \$1,863	\$1,312 \$1,399 \$1,399 \$1,885 \$2,030 \$2,030	One Position Computer Tables  Two Position Computer Tables
665-S05 MAP 649-S00 MAP 669-S00 MAP	Standing Height  Sitting Height Sitting Height	39" x 30" x 30" 27-1/2" x 60" x 24" 27-1/2" x 60" x 30"	110 110	\$1,729 \$1,863	\$1,399 \$1,885 \$2,030	Two Position Computer Tables
649-S00 MAP 669-S00 MAP	Sitting Height Sitting Height	27-1/2" x 60" x 24" 27-1/2" x 60" x 30"	110 110	\$1,729 \$1,863	\$1,885 \$2,030	Two Position Computer Tables
669-S00 MAP	Sitting Height	27-1/2" x 60" x 30"	110	\$1,863	\$2,030	Two Position Computer Tables
	Sitting Height				\$2,030	
669-S05 MAP	Standing Height	39" x 60" x 30"	115	\$1,863	\$2,030	
643-S00 MAP 663-S00 MAP	Sitting Height Sitting Height	27-1/2" x 36" x 24" 27-1/2" x 36" x 36"	70 80	\$1,487 \$1,621	\$1,621 \$1,767	One Position Computer Table with 10"H Privacy Panel
663-S05 MAP	Standing Height	39" x 36" x 36"	85	\$1,621	\$1,767	will to tri thus, runei
	3 3					
642-S00 MAP	Sittina Heiaht	27-1/2" x 72" x 24"	150	\$2.029	\$2,211	Two Position Computer Table
662-S00 MAP	Sitting Height	27-1/2" x 72" x 36"	150	\$2,162	\$2,357	with 10"H Privacy Panel
662-S05 MAP	Standing Height	39" x 72" x 36"	150	\$2,162	\$2,357	
644-S00 MAP	Sitting Height Sitting Height	27-1/2" x 90" x 24" 27-1/2" x 90" x 36"	180 170	\$2,764 \$2,898	\$3,012 \$3,159	Three Position Computer Table with 10"H Privacy Panel
666	62-S00 MAP 62-S05 MAP	62-S00 MAP Sitting Height 62-S05 MAP Standing Height 44-S00 MAP Sitting Height 64-S00 MAP Sitting Height	62-S00 MAP Sitting Height 27-1/2" x 72" x 36"  62-S05 MAP Standing Height 39" x 72" x 36"  44-S00 MAP Sitting Height 27-1/2" x 90" x 24"  64-S00 MAP Sitting Height 27-1/2" x 90" x 36"	62-S00 MAP Sitting Height 27-1/2" x 72" x 36" 150 62-S05 MAP Standing Height 39" x 72" x 36" 150  44-S00 MAP Sitting Height 27-1/2" x 90" x 24" 180 64-S00 MAP Sitting Height 27-1/2" x 90" x 36" 170	62-S00 MAP Sitting Height 27-1/2" x 72" x 36" 150 \$2,162 62-S05 MAP Standing Height 39" x 72" x 36" 150 \$2,162  44-S00 MAP Sitting Height 27-1/2" x 90" x 24" 180 \$2,764 64-S00 MAP Sitting Height 27-1/2" x 90" x 36" 170 \$2,898	62-S00 MAP Sitting Height 27-1/2" x 72" x 36" 150 \$2,162 \$2,357 62-S05 MAP Standing Height 39" x 72" x 36" 150 \$2,162 \$2,357    44-S00 MAP Sitting Height 27-1/2" x 90" x 24" 180 \$2,764 \$3,012 64-S00 MAP Sitting Height 27-1/2" x 90" x 36" 170 \$2,898 \$3,159

Standing with Apron	Sitting without Apron	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
One Position Comp		94T-663-S02 OAK	94T-663-S02 MAP	Sitting Height	27-1/2" x 36" x 36"	90	\$1,802	\$1,964
with 10"H Privacy F		94T-663-S06 OAK	94T-663-S06 MAP	Standing Height	39" x 36" x 36"	95	\$1,802	\$1,964
Two Position Comp		94T-662-S02 OAK	94T-662-S02 MAP	Sitting Height	27-1/2" x 72" x 36"	160	\$2,444	\$2,664
with 10"H Privacy I		94T-662-S06 OAK	94T-662-S06 MAP	Standing Height	39" x 72" x 36"	160	\$2,444	\$2,664

Three Position Computer Table with 10"H Privacy Panel and Shelf

 94T-664-S02 OAK
 94T-664-S02 MAP
 Sitting Height
 27-1/2" x 90" x 36"
 190
 \$3,305
 \$3,602

 94T-664-S06 OAK
 94T-664-S06 MAP
 Standing Height
 39" x 90" x 36"
 200
 \$3,305
 \$3,602



#### **WORK SURFACE**

Work surfaces are 27-1/2"D, available in two widths: 48" and 36", and adjustable in heights to 27", 32" and 39".

Work surfaces are 1-3/16" thick, 3-ply particleboard core, including a top surface of .050" thick, high-pressure laminate with a backing sheet no less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Front edges of work surfaces have 1-5/8" x 5/8" solid-oak drop edge band which extendss 3/8" below the work surface. The back edge of the top has a black plastic band 1-1/2"W which projects above the work surface 1/4" to act as a retainer. A 1-1/2"W cord drop is located at the back of the work surface.

#### **PANELS**

End and intermediate panels are 3/4" thick x 32-1/2"H x 30"W, comprised of select face veneers of Northern-grown red oak over a 45# particleboard core. Panels are banded on the top and bottom with 1.6mm thick solid oak. Panels are mechanically fastened to the back panel. Back panels are 32-1/2"H. Back panel construction is the same as end and intermediate panels.

#### **POSTS**

Posts are 1-3/4" square, with 1/8" grooved to receive panels in one-, two-, three- and four-way configurations. Each post has a 1-1/4" diameter, adjustable glide.

#### **SHELF**


A 12"D storage shelf, located under the work surface and extends the full width of the station.

#### ELECTRICAL


To hide excess wires, a 1-1/2" separation between the work surface and back panel is provided.

#### WORK SURFACE HEIGHTS


Adjustable at 27", 32" and 39".







94T Series External Edge Band



94T Series Panel & Post

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Single-Faced Information Access	36" Wide Workii	ng Space					
Workstations/Carrels	94T-673-S00 OAK	94T-673-S00 MAP	S/F Starter	47-3/4" x 38-1/8" x 33-1/2"	90	\$2,039	\$2,223
	94T-672-S00 OAK	94T-672-S00 MAP	S/F Adder	47-3/4" x 37" x 33-1/2"	80	\$1,755	\$1,913
	48" Wide Workii	ng Space					
	94T-460-S00 OAK	94T-460-S00 MAP	S/F Starter	47-3/4" x 50" x 33-1/2"	90	\$2,191	\$2,388
	94T-459-S00 OAK	94T-459-S00 MAP	S/F Adder	47-3/4" x 48-1/2" x 33-1/2"	80	\$1,891	\$2,062

<b>Double-Faced Information Access</b>	36" Wide Workin	ng Space					
Workstations/Carrels	94T-674-S00 OAK	94T-674-S00 MAP	D/F Starter	47-3/4" x 38-1/8" x 65-1/4"	140	\$3,758	\$4,096
	94T-675-S00 OAK	94T-675-S00 MAP	D/F Adder	47-3/4" x 37" x 65-1/4"	126	\$3,124	\$3,405
	48" Wide Workir	ng Space					
	94T-461-S00 OAK	94T-461-S00 MAP	D/F Starter	47-3/4" x 50" x 65-1/4"	150	\$4,086	\$4,454
	94T-462-S00 OAK	94T-462-S00 MAP	D/F Adder	47-3/4" x 48-1/2" x 65-1/4"	136	\$3,388	\$3,693
Starter Add	er						



#### WORKSTATIONS

Workstations are of modular starter and adder design, with an overall height 33". Workstations are available in 36", 48", 72", 96", and 108" widths. A knee-space panel located below the work surface supports all work surfaces greater than 48" W. Work surface height is at 27-1/2". Work surface depth is 27-1/2" with an additional 1-1/2"W cord drop between the work surface and back panel to allow passage of electrical cords. Work surface is attached to end and intermediate panels by means of two metal 22-1/2" long "Z" brackets with 5/16" – 18 hex-head bolts engaging internally and externally threaded bushings embedded into panels. The back panel is attached to end and intermediate panels using hidden metal keyways and shoulder screws. The shelf is attached to end and intermediate panels and back panels with 3/4" x 3/4" steel, black painted angle brackets and black #8 screws.

#### **WORK SURFACE**

Standard work surface is 1-3/16" thick, 3-ply, 45# density particleboard including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Front edges of work surfaces have a 5/8" x 1-3/16" solid oak edge band in a half-round bullnose shape. The back edge of the top has a black plastic band 1-1/2"W which projects above the work surface 1/4" to act as a retainer.

#### **END AND INTERMEDIATE PANELS**

End and intermediate panels are 1-1/8" thick, 45# density particleboard core with select face veneers of Northern-grown red oak. All edges are banded with a 5/8" bullnosed solid-oak edge band. Intermediate panels receive a 3" diameter grommet below the work surface to allow passage of electrical and data wires. Each panel receives two 1-1/4" adjustable glides.

#### **BACK PANEL**

Back panel is 3/4" thick, 45# density particleboard core with face veneers of select Northern-grown red oak. The top and bottom edges of the back panel receives 5/8" bullnosed solid oak edge bands. Back panels attach to end and intermediate panels by means of recessed metal fasteners and shoulder screws. The back panel on double-faced units receive a 3" diameter grommet located below the work surface to allow passage of electrical and data wires.

#### **SHELF**


Shelf is 3/4" thick x 8"D 45# density particleboard core with face veneers of select Northern-grown red oak. Shelf is banded on the front edge with a 1.6mm solid oak band. Shelf attaches to end and intermediate panels by means of a pair of metal "L" brackets. Back corners of shelf have a 3" x 3" cutout to allow for the passage of electrical cords. The shelf is positioned 10" below the bottom of the work surface.

#### WIRE MANAGEMENT DOOR

The wire management door is positioned between the bottom of the work surface and the shelf and is designed to form a concealed wire management channel 8-1/2"H x 9-1/2"D. The door is 1/4" thick with select oak face veneers. The door slides in two aluminum tracks, one that is attached to the bottom of the work surface while the other is attached to the top of the shelf.

#### **KNEE-SPACE PANEL**

All 72" and 96"W workstations, as well as functional corner units, have a knee-space panel positioned under the work surface for additional work-surface support. Units 108" W have two knee-space panels. The knee-space panel is 1-1/8" thick, 45# density particleboard core with select face veneers of Northern-grown red oak. The panel is banded on exposed edges with a 1.6mm solid oak band. The knee-space panel is attached to the back panel using a 1-3/4" square, solid-oak post, grooved to receive the knee space panel and back panels. Panels attach to the post using recessed metal fasteners and shoulder screws. The knee-space panel is angled in the back to create a space to allow passage of electrical and data cords. The knee-space panel receives two 1-1/4" diameter black adjustable glides.



94T Series Drop Edge

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
36" Wide Worki	ing Space					
94T-S31-SS0 OAK	94T-S31-SS0 MAP	One-Position S/F Starter	33-1/2" x 37-1/2" x 31"	130	\$1,663	\$1,812
94T-S31-SA0 OAK	94T-S31-SA0 MAP	One-Position S/F Adder	33-1/2" x 36-1/2" x 31"	100	\$1,424	\$1,552
48" Wide Worki	ng Space					
94T-S41-SS0 OAK	94T-S41-SS0 MAP	One-Position S/F Starter	33-1/2" x 49-1/4" x 31"	155	\$1,795	\$1,957
94T-S41-SA0 OAK	94T-S41-SA0 MAP	One-Position S/F Adder	33-1/2" x 48" x 31"	125	\$1,521	\$1,658
	Catalog No.  36" Wide Worki 94T-S31-SS0 OAK  94T-S31-SA0 OAK  48" Wide Worki 94T-S41-SS0 OAK	Catalog No.         Catalog No.           36" Wide Working Space           94T-S31-SS0 OAK         94T-S31-SS0 MAP           94T-S31-SA0 OAK         94T-S31-SA0 MAP             48" Wide Working Space           94T-S41-SS0 OAK         94T-S41-SS0 MAP	Catalog No.         Catalog No.         Description           36" Wide Working Space           94T-S31-SS0 OAK         94T-S31-SS0 MAP         One-Position S/F Starter           94T-S31-SA0 OAK         94T-S31-SA0 MAP         One-Position S/F Adder           48" Wide Working Space           94T-S41-SS0 OAK         94T-S41-SS0 MAP         One-Position S/F Starter           94T-S41-SA0 OAK         94T-S41-SA0 MAP         One-Position One-Position	Catalog No.         Catalog No.         Description         H x W x D           36" Wide Working Space         94T-S31-SS0 OAK         94T-S31-SS0 MAP         One-Position S/F Starter           94T-S31-SA0 OAK         94T-S31-SA0 MAP         One-Position S/F Adder         33-1/2" x 36-1/2" x 31"           48" Wide Working Space         94T-S41-SS0 OAK         94T-S41-SS0 MAP         One-Position S/F Starter         33-1/2" x 49-1/4" x 31"           94T-S41-SA0 OAK         94T-S41-SA0 MAP         One-Position One-Position S/F Starter         33-1/2" x 48" x 31"	Catalog No.         Catalog No.         Description         H x W x D         (lbs.)           36" Wide Working Space         94T-S31-SS0 OAK         94T-S31-SS0 MAP         One-Position S/F Starter         33-1/2" x 37-1/2" x 31"         130           94T-S31-SA0 OAK         94T-S31-SA0 MAP         One-Position S/F Adder         33-1/2" x 36-1/2" x 31"         100           48" Wide Working Space         94T-S41-SS0 OAK         94T-S41-SS0 MAP         One-Position One-Position S/F Starter         33-1/2" x 49-1/4" x 31"         155           94T-S41-SA0 OAK         94T-S41-SA0 MAP         One-Position One-Positio	Catalog No.         Catalog No.         Description         H x W x D         (lbs.)         Price           36" Wide Working Space         94T-S31-SS0 OAK         94T-S31-SS0 MAP         One-Position S/F Starter         33-1/2" x 37-1/2" x 31"         130         \$1,663           94T-S31-SA0 OAK         94T-S31-SA0 MAP         One-Position S/F Adder         33-1/2" x 36-1/2" x 31"         100         \$1,424           48" Wide Working Space         94T-S41-SS0 OAK         94T-S41-SS0 MAP         One-Position One-Position S/F Starter         33-1/2" x 49-1/4" x 31"         155         \$1,795           94T-S41-SA0 OAK         94T-S41-SA0 MAP         One-Position One-Pos


Double-Faced One-Position	36" Wide Working Space									
Starter	94T-D31-SS0 OAK	94T-D31-SS0 MAP	One-Position D/F Starter	33-1/2" x 37-1/2" x 59-1/2"	215	\$2,985	\$3,254			
	94T-D31-SA0 OAK	94T-D31-SA0 MAP	One-Position D/F Adder	33-1/2" x 36-1/2" x 59-1/2"	155	\$2,531	\$2,759			
•	48" Wide Workin	g Space								
Adder	94T-D41-SS0 OAK	94T-D41-SS0 MAP	One-Position D/F Starter	33-1/2" x 49-1/4" x 59-1/2"	255	\$3,212	\$3,501			
	94T-D41-SA0 OAK	94T-D41-SA0 MAP	One-Position D/F Adder	33-1/2" x 48" x 59-1/2"	195	\$2,734	\$2,980			

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
36" Wide Work	ing Space						Single-Faced Two-Position
94T-S32-SS0 OAK	94T-S32-SS0 MAP	Two-Position S/F Starter	33-1/2" x 74" x 31"	195	\$2,377	\$2,591	Starter
94T-S32-SA0 OAK	94T-S32-SA0 MAP	Two-Position S/F Adder	33-1/2" x 73" x 31"	165	\$2,107	\$2,296	
48" Wide Work	ing Space						
94T-S42-SS0 OAK	94T-S42-SS0 MAP	Two-Position S/F Starter	33-1/2" x 97-1/4" x 31"	235	\$2,626	\$2,863	Adder
94T-S42-SA0 OAK	94T-S42-SA0 MAP	Two-Position S/F Adder	33-1/2" x 96" x 31"	205	\$2,305	\$2,512	

36" Wide Work	ing Space						Double-Faced Two-Position
94T-D32-SS0 OAK	94T-D32-SS0 MAP	Two-Position D/F Starter	33-1/2" x 74" x 59-1/2"	330	\$4,231	\$4,611	Starter
94T-D32-SA0 OAK	94T-D32-SA0 MAP	Two-Position D/F Adder	33-1/2" x 73" x 59-1/2"	270	\$3,802	\$4,144	
48" Wide Work	ing Space						
94T-D42-SS0 OAK	94T-D42-SS0 MAP	Two-Position D/F Starter	33-1/2" x 97-1/4" x 59-1/2"	410	\$4,598	\$5,012	Adder
94T-D42-SAO OAK	94T-D42-SAO MAP	Two-Position D/F Adder	33-1/2" x 96" x 59-1/2"	155	\$4,160	\$4,534	

Single-Faced Three-Position	Oak Catalog No. <i>36" Wide Workin</i> g	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Starter	94T-S33-SS0 OAK	94T-S33-SS0 MAP	Three-Position S/F Starter	33-1/2" x 110-1/2" x 31"	260	\$3,223	\$3,513
Adder	94T-S33-SAO OAK	94T-S33-SA0 MAP	Three-Position S/F Adder	33-1/2" x 109-1/4" x 31"	230	\$2,804	\$3,056

Double-Faced Three-Position	36" Wide Worki	ng Space					
Starter	94T-D33-SS0 OAK	94T-D33-SS0 MAP	Three-Position D/F Starter	33-1/2" x 110-1/2" x 59-1/2"	445	\$5,773	\$6,292
Adder	94T-D33-SA0 OAK	94T-D33-SA0 MAP	Three Position D/F Adder	33-1/2" x 109-1/4" x 59-1/2"	385	\$5,292	\$5,768



94T-SCR-SAO MAP

94T-SCR-SAO OAK

## Quorum 94T Collection

	Maple Price	Oak Price	Wt. (lbs.)	HxWxD	Description	Maple Catalog No.	Oak Catalog No.
90° Functional Corner Unit Starte	\$4,291	\$3,937	225	33-1/2" x 62" x 31"	90-Degree Functional Corner Starter	94T-SCR-SS0 MAP	94T-SCR-SSO OAK
Adde							

33-1/2" x 62" x 31"


195

\$3,781

\$4,121

90-Degree Functional

Corner Adder



#### TOP

Top is 1-3/16" thick, 3-ply particleboard core including a top surface of .050" thick, high-pressure laminate with a backing sheet not less than .020" thick for balanced construction. The high-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining in accordance with NEMA standards. Front edges of work surfaces have a 5/8" thick solid-oak flush edge band.

#### **VERTICAL PANELS**

Full panels are 1-3/16" thick and comprised of select face veneers of Northern-grown red oak over a particleboard core. Panels are externally banded on all four sides with a 5/8" thick solid-oak edge band in straight design. Panels receive 1/2" radius on all corners. The bottom of each panel has two flush-mounted tee-nuts to receive a 1-1/4" diameter, rubber-cushioned chrome glide. Panels are equipped with grommets to allow wire passage from station to station.

#### **BACK PANELS**

Back panels are 1-3/16" thick and comprised of select face veneers of Northern-grown red oak over particleboard core. The panel is externally banded on the top and bottom edge with a 1.6mm band. The panel attaches to the corner posts by means of mechanical fasteners.

#### **ELECTRICAL ACCESS DOOR**

(One for each 3- or 6- station unit) Access door is 3/4" thick and comprised of select face veneers of Northern-grown red oak over a particleboard core. Panel is externally banded on all four sides with a 1.6mm solid-oak edge band. Access door has a full length hinge and lock and can be located in any one of the back panels on the station. CENTER CAP

Cap is constructed of 3/4" plastic and backer. Available in full-hexagon or half-hexagon configuration, the cap closes the center opening by mounting at the top rear edge of end panels on systems arranged in full- or half-hexagon configuration.


#### **AVAILABLE WORKING SPACE**

Depth of monitor and keyboard combined cannot exceed 29".


#### **WORKING SPACE HEIGHTS**

Working space is adjustable to: Standing Height: 39" ADA Height: 32" Sitting Height: 27"

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Six Position PAC Station	94T-682-S00 OAK	94T-682-S00 MAP	Six position with angular tops.	42-1/4" x 99-1/4" x 99-1/4"	629	\$11,196	\$12,204
Four Position PAC Station	94T-688-S00 OAK	94T-688-S00 MAP	Four position with angular tops.	42-1/4" x 75-1/2" x 75-1/2"	510	\$8,598	\$9,372



Three Position PAC Station 94T-685-S00 OAK 94T-685-S00 MAP Three position with 42-1/4" x 99-1/2" x 47-1/2" 401 \$6,015 \$6,557



angular tops. Composed of one starter unit and two adder units.

#### **DESKTOPS**

Standard desktop is 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading and staining that meets or exceeds NEMA standards. The desk top receives a solid Northern-grown Red Oak or maple edge band 5/8" thick x 1-3/16" formed in a bullnose shape. All edges are applied to the desktop after the laminate and backer sheets are applied, constituting an external edge band.

#### **END PANEL**

End panels are 1-3/16" thick, 3-ply, 45# density particleboard core with select plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed vertical edges are externally banded with a 5/8" thick x 1-3/16" solid, Northern-grown Red Oak or maple edge band formed in a bullnose shape. Top and bottom of the end panels are banded with a 1/8" x 1-3/16" edge band with the edges eased.

#### FRONT PANEL


The front panels are 1-3/16" thick, 3-ply, 45# density particleboard core with select plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed vertical edges are externally banded with a 5/8" thick x 1-3/16" solid, Northern-grown Red Oak or maple edge band formed in a bullnose shape. Top and bottom of the end panels are banded with a 1/8" x 1-3/16" edge band with the edges eased.

#### **SHELVES**

Shelves are constructed of 7-ply, furniture-grade veneer-core hardwood plywood, with Northern-grown Red Oak plain sliced face veneer or maple plain sliced face veneer. Exposed edges receive a 1.6mm thick, solid-oak or maple edge band.

#### **DRAWER**

Drawer is constructed of solid Northern-grown Red Oak or maple with 1/4" thick wood bottom panel. Drawer has 3-ply particleboard fronts with select oak-face veneer or maple veneer. Box drawer has extension slides with 100# load capacity. File drawer is letter size and has full-extension slides with 100# load capacity. File drawers also have hangers to conveniently support hanging files.



94T Series Drop Edge

Bow Front Double Pedestal Desk	Oak Catalog No. 94T-501-S00 OAK	Maple Catalog No. 94T-501-S00 MAP	Description  Bow Front Double Pedestal Desk  Desk has a curved front work The left pedestal has a storag and a file drawer with lock. TI pedestal has three storage dr	e drawer ne right	Wt. (lbs.)	Oak Price \$5,954	Maple Price \$6,490
Straight Front Double Pedestal Desk	94T-502-S00 OAK	94T-502-S00 MAP	Straight Front Double Pedestal Desk Desk has a straight front work The left pedestal has a storag and a file drawer with lock. Th has three storage drawers.	e drawer	252	\$5,777	\$6,296
Straight Front Single Pedestal Desk	94T-503-S00 OAK	94T-503-S00 MAP	Straight Front Single Pedestal Desk Desk has a straight front work One pedestal with a storage of a file drawer with lock.		210	\$4,339	\$4,730
L-Shaped Left Return Desk	94T-504-S00 OAK	94T-504-S00 MAP	L-Shaped Left Return L-Shaped Left Desk  Desk has a straight front work  Desk pedestal has a storage a file drawer with lock. The ref  storage drawers.	drawer and	390	\$6,714	\$7,317

## Quorum 94T Collection

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
94T-505-S00 OAK	94T-505-S00 MAP	L-Shaped Right Return L-Shaped Right Desk	29" x 47" x 25-3/4" 29" x 72" x 30"	390	\$6,714	\$7,317	L-Shaped Right Return Desk
		Desk has a straight front wo Desk pedestal has a storag a file drawer with lock. The storage drawers.	e drawer and		Ç	9 - 9	
94T-506-S00 OAK	94T-506-S00 MAP		e storage drawer and		\$6,522	\$7,109	Storage Credenza
94T-507-S00 OAK	94T-507-S00 MAP	Kneespace Credenza The credenza contains a tw on each end. Each pedesta drawer and one letter-size f has a lock. The middle area for have knee space while v	Il contains one storage file drawer. The left pedestal of the credenza is open	245	\$5,627	\$6,133	Kneespace Credenza

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Dictionary Stand	94T-869-S00 OAK	94T-869-S00 MAP	Adult Height	45-1/2" x 25-7/8" x 16-1/2"	80	\$1,716	\$1,871
,	94T-469-S00 OAK	94T-469-S00 MAP	Children's Height	38-1/2" x 25-7/8" x 16-1/2"	67	\$1,716	\$1,871



Sloped top is 1-3/16" thick, 3-ply particleboard including a top surface of .050" thick high-pressure laminate with a backing sheet not less than .020" thick. Edge band of sloped top is 1-3/16" x 5/8" solid oak, applied to all exposed edges forming a half-round bullnose shape. Edge band is applied after the top and bottom laminate sheets are applied (External Edge Band). A 5/8" x 5/8" book retainer is positioned along the bottom edge of sloped top. The full height 1/2" plywood back is recessed into the end panels. Inside faces of end panels allow for shelf adjustment on 1/2" center. Bottom shelf is stationary. End panels are 1-3/16", 7-ply veneer-core plywood construction with select oak-veneer facings. Vertical edges receive 1/2" solid oak banding, radiused 1/4".



94T-871-S00 OAK 94T-871-S00 MAP 94T-471-S00 OAK 94T-471-S00 MAP

 Adult Height
 45-9/16" x 29-7/8" x 29"
 200
 \$3,275
 \$3,571

 Children's Height
 38-9/16" x 29-7/8" x 29"
 180
 \$3,275
 \$3,571

Sloped top is 1-3/16" thick, 3-ply particleboard including top surface of .050" thick high-pressure laminate with a backing sheet not less than .020" thick. Edge band of sloped top is 1-3/16" x5/8" solid oak, applied to all exposed edges forming a half-round bullnose shape. Edge band is applied after the top and bottom laminate sheets are applied (External Edge Band). A 5/8" x 5/8" book retainer is positioned along the bottom edge of sloped top. End panels and back panel are 1-3/16", 7-ply veneer-core plywood construction, with select oak-veneer facings. Vertical edges receive 1/2" solid-oak banding, radiused on 1/4". Sides and back are tenoned together. Each unit has five pullout shelves on nylon rollers. Stops on shelves prevent accidental removal. Shelves are 25-3/4"W x 23-7/8"D, with 3" between shelves. Children's height unit contains four pullout shelves with 2-1/2" between shelves.

	Maple Price	Oak Price	Wt. (lbs.)	HxWxD	Description	Maple Catalog No.	Oak Catalog No.
Horizontal Newspaper Rack	\$1,904	\$1,747	55	31" x 37-1/4" x 24-5/8" ceive newspapers. The rack has holder has ten U-shaped grooves	Horizontal Newspaper Rack This rack has a top frame, open to re two holders, one on each side. Each 1-1/4"W with a radius at the botton which are included.	94T-179-S00 MAP	94T-179-S00 OAK
End-of-Range	\$1,805	\$1,656	55	39-1/4" x 24-1/8" x 20"	End-of-Range Computer Station	94T-039-S00 MAP	94T-039-S00 OAK


Designed to fit at end of double-faced shelving range. Standard tabletop is 1-3/16" thick with high-pressure laminate on the top surface, with one 3" diameter grommet, and with 5/8 thick external solid wood edge bands with the 94T-series shape. End panels are 1-3/16" thick wood veneered and edge banded. Unit has two full-depth fixed shelves with 3" diameter grommets and one pullout shelf for the keyboard. Space above the fixed shelves is 11". Adjustable glides are provided for leveling the unit.



**Computer Station** 

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Picture Book Table	94T-142-S00 OAK	94T-142-S00 MAP	Picture Book Table	33-1/2" x 78" x 32"	190	\$3,509	\$3,825
			thick tops mounted on a are 26-1/2" from the fl screwed onto each top i allowed between the top Table base construction support and tabletop ed	o 78"W x 15-1/2" D x 1-3/16 a 27° angle. The lower edge of a coor. A 5/8" square retaining state are the lower edge. A space of cost o serve as a full-width book at including legs, accent strip, to add the same as the adding table specifications for s	the tops trip is 3" is well. abletop ne series		

Bench 94T-147-S00 OAK 94T-147-S00 MAP Bench 15-3/4" x 69" x 11" 50 \$1,195 \$1,303



The seat is 3/4" thick edge-banded plywood supported by a 3-1/2" x 3/4" apron on all four sides. Legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16"-18 hex-head bolts per leg.

## **General Specifications**

#### TOPS - WOOD AND STEEL SHELVING

Tops are 1-3/16" thick, 3-ply, 45# density particleboard core, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. The continuous top receives a solid Northern-grown Red Oak or Maple flush edge band, 5/8" x 1-3/16" thick, radius 1/2" to form a bullnosed shape. The maximum width of any shelving top segment is 108". This covers a range of three standard shelving sections. Tops wider than 108" are built in multiple sections by the factory, based on the total number of shelving units in the shelving range. Joints are set so they coincide with the joint in the shelving sections. Tops are splined at the joints so they can be leveled. Tight Joint fastener routes and hardware are provided. Brodart shelving tops overhang approximately 5/8". Single-faced tops are not banded on the back edge.


#### WOOD SHELVING TOPS


Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

#### STEEL SHELVING TOPS

Single-Faced Tops are banded on the front edge only. Back edge and sides are not banded. Double-Faced Tops are banded on the front and back edges only.

Exact width and depth of steel shelving tops must be specified when ordering.





94T Series External Edge Band

## Quorum 94T Collection

0ak	Maple			0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE II	N/IT				
To Cover ONE U. 94T-W10-S01 OAK	94T-W10-S01 MAP	10"D, Single-Faced	11	\$277	<b>\$29</b> 1
94T-W12-S01 OAK		12"D, Single-Faced	14	\$277 \$281	\$29 \$29!
94T-W20-S01 OAK	94T-W12-S01 MAP	20"D, Double-Faced	23	\$393	\$293 \$413
94T-W24-S01 OAK	94T-W20-S01 MAP 94T-W24-S01 MAP	24"D, Double-Faced	23 27	\$393 \$438	\$413 \$459
		21 D, Double 1 docu		<b>\$100</b>	Ψ10.
To Cover TWO U					
94T-W10-S02 OAK	94T-W10-S02 MAP	10"D, Single-Faced	22	\$366	\$38
94T-W12-S02 OAK	94T-W12-S02 MAP	12"D, Single-Faced	28	\$389	\$408
94T-W20-S02 OAK	94T-W20-S02 MAP	20"D, Double-Faced	46	\$551	\$578
94T-W24-S02 OAK	94T-W24-S02 MAP	24"D, Double-Faced	54	\$692	\$72
To Cover THREE	UNITS				
94T-W10-S03 OAK	94T-W10-S03 MAP	10"D, Single-Faced	33	\$478	\$502
94T-W12-S03 OAK	94T-W12-S03 MAP	12"D, Single-Faced	42	\$510	\$53!
94T-W20-S03 OAK	94T-W20-S03 MAP	20"D, Double-Faced	69	\$694	\$729
94T-W24-S03 OAK	94T-W24-S03 MAP	24"D, Double-Faced	81	\$733	\$770
T 0 50115					
To Cover FOUR (	94T-W10-S04 MAP	10"D Single Faced	44	\$730	\$767
		10"D, Single-Faced			
94T-W12-S04 OAK	94T-W12-S04 MAP	12"D, Single-Faced	56	\$775	\$814
94T-W20-S04 OAK	94T-W20-S04 MAP	20"D, Double-Faced	92	\$1,087	\$1,142
94T-W24-S04 OAK	94T-W24-S04 MAP	24"D, Double-Faced	108	\$1,170	\$1,228
To Cover FIVE U	<u>NITS</u>				
94T-W10-S05 OAK	94T-W10-S05 MAP	10"D, Single-Faced	55	\$843	\$88
94T-W12-S05 OAK	94T-W12-S05 MAP	12"D, Single-Faced	70	\$849	\$944
94T-W20-S05 OAK	94T-W20-S05 MAP	20"D, Double-Faced	115	\$1,245	\$1,30
94T-W24-S05 OAK	94T-W24-S05 MAP	24"D, Double-Faced	135	\$1,426	\$1,497
To Cover SIX UN	IITS				
94T-W10-S06 OAK	94T-W10-S06 MAP	10"D, Single-Faced	66	\$953	\$1,00
94T-W12-S06 OAK	94T-W12-S06 MAP	12"D, Single-Faced	84	\$1,020	\$1,00° \$1,07°
94T-W20-S06 OAK	94T-W20-S06 MAP	20"D, Double-Faced	138	\$1,389	\$1,458
94T-W24-S06 OAK	94T-W24-S06 MAP	24"D, Double-Faced	162	\$1,464	\$1,538
		2. 5,5000.0.000	.02	4.7.0	Ţ./00C
To Cover SEVEN					
94T-W10-S07 OAK	94T-W10-S07 MAP	10"D, Single-Faced	77	\$1,229	\$1,29
94T-W12-S07 OAK	94T-W12-S07 MAP	12"D, Single-Faced	98	\$1,303	\$1,368
94T-W20-S07 OAK	94T-W20-S07 MAP	20"D, Double-Faced	161	\$1,780	\$1,869
94T-W24-S07 OAK	94T-W24-S07 MAP	24"D, Double-Faced	189	\$1,902	\$1,997
To Cover EIGHT	<u>UNITS</u>				
94T-W10-S08 OAK	94T-W10-S08 MAP	10"D, Single-Faced	88	\$1,318	\$1,384
94T-W12-S08 OAK	94T-W12-S08 MAP	12"D, Single-Faced	112	\$1,409	\$1,479
94T-W20-S08 OAK	94T-W20-S08 MAP	20"D, Double-Faced	184	\$1,940	\$2,038
94T-W24-S08 OAK	94T-W24-S08 MAP	24"D, Double-Faced	216	\$2,156	\$2,26
To Cover NIME	INITC				
To Cover NINE U	94T-W10-S09 MAP	10"D, Single-Faced	99	\$1,432	\$1,50
94T-W12-S09 OAK	94T-W12-S09 MAP	12"D, Single-Faced	126	\$1,432 \$1,530	\$1,50. \$1,60
94T-W20-S09 OAK	941-W12-309 MAP	20"D, Double-Faced	207	\$1,530 \$2,084	\$2,189
94T-W24-S09 OAK	941-W20-S09 MAP	24"D, Double-Faced	243		\$2,10
741-WZ4-3U7 UAN	741-11/24-3U7 IVIAP	24 D, DUUDIE-FACEU	243	\$2,195	\$Z,3U3

**Note:** Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

Ook	Manla			Oak	Monlo
Oak	Maple	Description	M4. /II \	0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
To Cover ONE U	NIT				
94T-S10-S01 OAK	94T-S10-S01 MAP	10"D, Single-Faced	11	\$302	\$317
94T-S12-S01 OAK	94T-S12-S01 MAP	12"D, Single-Faced	14	\$304	\$319
94T-S20-S01 OAK	94T-S20-S01 MAP	20"D, Double-Faced	23	\$425	\$446
94T-S24-S01 OAK	94T-S24-S01 MAP	24"D, Double-Faced	27	\$478	\$502
To Cover TWO U	INITS				
94T-S10-S02 OAK	94T-S10-S02 MAP	10"D, Single-Faced	22	\$396	\$416
94T-S12-S02 OAK	94T-S12-S02 MAP	12"D, Single-Faced	28	\$421	\$442
94T-S20-S02 OAK	94T-S20-S02 MAP	20"D, Double-Faced	46	\$599	\$629
94T-S24-S02 OAK	94T-S24-S02 MAP	24"D, Double-Faced	54	\$750	\$788
To Cover THREE	UNITS				
94T-S10-S03 OAK	94T-S10-S03 MAP	10"D, Single-Faced	33	\$517	\$543
94T-S12-S03 OAK	94T-S12-S03 MAP	12"D, Single-Faced	42	\$554	\$581
94T-S20-S03 OAK	94T-S20-S03 MAP	20"D, Double-Faced	69	\$755	\$793
94T-S24-S03 OAK	94T-S24-S03 MAP	24"D, Double-Faced	81	\$793	\$832
To Cover FOUR	IINIITS				
94T-S10-S04 OAK	94T-S10-S04 MAP	10"D, Single-Faced	44	\$796	\$835
94T-S12-S04 OAK	94T-S12-S04 MAP	12"D, Single-Faced	56	\$843	\$885
94T-S20-S04 OAK	94T-S20-S04 MAP	20"D, Double-Faced	92	\$1,125	\$1,181
94T-S24-S04 OAK	94T-S24-S04 MAP	24"D, Double-Faced	108	\$1,123 \$1,271	\$1,101
		24 D, Double Faceu	100	Ψ1,271	Ψ1,004
<u>To Cover FIVE U</u>	<u>NITS</u>				
94T-S10-S05 OAK	94T-S10-S05 MAP	10"D, Single-Faced	55	\$911	\$956
94T-S12-S05 OAK	94T-S12-S05 MAP	12"D, Single-Faced	70	\$977	\$1,026
94T-S20-S05 OAK	94T-S20-S05 MAP	20"D, Double-Faced	115	\$1,353	\$1,421
94T-S24-S05 OAK	94T-S24-S05 MAP	24"D, Double-Faced	135	\$1,548	\$1,625
To Cover SIX UN	<u>IITS</u>				
94T-S10-S06 OAK	94T-S10-S06 MAP	10"D, Single-Faced	66	\$1,033	\$1,084
94T-S12-S06 OAK	94T-S12-S06 MAP	12"D, Single-Faced	84	\$1,112	\$1,168
94T-S20-S06 OAK	94T-S20-S06 MAP	20"D, Double-Faced	138	\$1,509	\$1,584
94T-S24-S06 OAK	94T-S24-S06 MAP	24"D, Double-Faced	162	\$1,589	\$1,669
To Cover SEVEN	I UNITS				
94T-S10-S07 OAK	94T-S10-S07 MAP	10"D, Single-Faced	77	\$1,311	\$1,376
94T-S12-S07 OAK	94T-S12-S07 MAP	12"D, Single-Faced	98	\$1,394	\$1,470
94T-S20-S07 OAK	94T-S20-S07 MAP	20"D, Double-Faced	161	\$1,948	\$2,046
94T-S24-S07 OAK	94T-S24-S07 MAP	24"D, Double-Faced	189	\$2,067	\$2,171
To Cover EIGHT	UNITS				
94T-S10-S08 OAK	94T-S10-S08 MAP	10"D, Single-Faced	88	\$1,432	\$1,503
94T-S12-S08 OAK	94T-S12-S08 MAP	12"D, Single-Faced	112	\$1,530	\$1,606
94T-S20-S08 OAK	94T-S20-S08 MAP	20"D, Double-Faced	184	\$2,107	\$2,213
94T-S24-S08 OAK	94T-S24-S08 MAP	24"D, Double-Faced	216	\$2,342	\$2,459
To Cover NINE U	INITS				
94T-S10-S09 OAK	94T-S10-S09 MAP	10"D, Single-Faced	99	\$1,553	\$1,630
94T-S12-S09 OAK	94T-S12-S09 MAP	12"D, Single-Faced	126	\$1,665	\$1,749
94T-S20-S09 OAK	94T-S20-S09 MAP	20"D, Double-Faced	207	\$2,264	\$2,377
94T-S24-S09 OAK	94T-S24-S09 MAP	24"D, Double-Faced	243	\$2,385	\$2,504
	, J 00 / Hild	5,55551014004	2.5	+=/000	+ <b>=</b> 100 i

**Note:** Edge Band on long side only. Tops are designed to be inset between end panels. If edge bands are desired on short edges, please enter the part as a modification and specify which bands to be included.

To ensure that tops for steel shelving work with each manufacturer and top method, please specify the exact width and depth of tops. Add 15% for HPL on top and bottom (Steel Shelving ONLY).

## **General Specifications**

#### **END PANELS**

End panels are 1-3/16" thick, 3-ply particleboard with select oak-veneer faces. All edges are externally banded with 5/8" solid red-oak bullnose edge bands. All edges are eased. End panels are not machined. No fastening hardware is provided with end panels.

End panels for steel shelving with continuous tops or canopy top inset are designed to have the canopy top "inset" between the end panels.

**Note:** Exact height and depth of panel must be specified when ordering.

	0ak	Maple			0ak	Maple
	Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
Single-Faced End Panels	94T-702-MOD OAK	94T-702-MOD MAP	43-3/4" x 13-7/8"	14	\$284	\$298
	94T-703-MOD OAK	94T-703-MOD MAP	43-3/4" x 15-7/8"	16	\$297	\$311
	94T-705-MOD OAK	94T-705-MOD MAP	67-3/4" x 13-7/8"	21	\$364	\$382
	94T-706-MOD OAK	94T-706-MOD MAP	67-3/4" x 15-7/8"	26	\$370	\$389
	94T-708-MOD OAK	94T-708-MOD MAP	79-3/4" x 13-7/8"	25	\$384	\$403
	94T-709-MOD OAK	94T-709-MOD MAP	79-3/4" x 15-7/8"	30	\$390	\$409
	94T-711-MOD OAK	94T-711-MOD MAP	85-3/4" x 13-7/8"	28	\$390	\$409
	94T-712-MOD OAK	94T-712-MOD MAP	85-3/4" x 15-7/8"	33	\$399	\$419
	94T-714-MOD OAK	94T-714-MOD MAP	91-3/4" x 13-7/8"	29	\$399	\$419
	94T-715-MOD OAK	94T-715-MOD MAP	91-3/4" x 15-7/8"	35	\$403	\$423
	94T-722-MOD OAK	94T-722-MOD MAP	43-3/4" x 24-3/8"	27	\$364	\$382
Double-Faceu End Faneis	94T-723-MOD OAK	94T-723-MOD MAP	43-3/4" x 28-3/8"	33	\$370	\$389
	94T-725-MOD OAK	94T-725-MOD MAP	67-3/4" x 24-3/8"	43	\$482	\$506
	94T-726-MOD OAK	94T-726-MOD MAP	67-3/4" x 28-3/8"	52	\$497	\$522
	94T-728-MOD OAK	94T-728-MOD MAP	79-3/4" x 24-3/8"	51	\$503	\$528
	94T-729-MOD OAK	94T-729-MOD MAP	79-3/4" x 28-3/8"	61	\$552	\$579
	94T-731-MOD OAK	94T-731-MOD MAP	85-3/4" x 24-3/8"	55	\$506	\$531
	94T-732-MOD OAK	94T-732-MOD MAP	85-3/4" x 28-3/8"	66	\$517	\$543
	94T-734-MOD OAK	94T-734-MOD MAP	91-3/4" x 24-3/8"	59	\$517	\$543
	94T-735-MOD OAK	94T-735-MOD MAP	91-3/4" x 28-3/8"	60	\$526	\$552

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.


## **General Specifications**

#### **TABLETOPS**


Tabletops are 1-3/16" thick, 3-ply, 45# density particleboard core with a .050" thick, high-pressure laminate top sheet and a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining. Edges are solid Northern-grown red oak. The external drop edge band is 5/8" thick x 1-5/8"W, externally banded to form a bullnose.

#### **LEGS**


Legs are glued up, 2-1/4" solid Northern-grown red oak, radiused 1/2" on vertical edges. Each leg has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick steel plate. The plate is attached to the leg by a 5/16" x 3" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded steel bushings in the underside of the tabletop. Leg plates are positioned behind, and hidden by the extended table edge band.



94T Series Drop Edge



94T Series External Edge Band



Round Table	Oak Catalog No. 94T-626-S00 OAK	Maple Catalog No. 94T-626-S00 MAP	Description  Round Table	HxWxD 16"Hx36" Diameter	Wt. (lbs.)	Oak Price \$1,279	Maple Price \$1,395
Square Table	94T-625-S00 OAK	94T-625-S00 MAP	Square Table	16" x 30" x 30"	51	\$913	\$994
Rectangular Table	94T-627-S00 OAK	94T-627-S00 MAP	Rectangular Table	16" x 24" x 48"	46	\$929	\$1,013
End Tables	94T-628-S00 OAK	94T-628-S00 MAP	End Table	22" x 24" x 24"	45	\$769	\$838
	94T-629-S00 OAK	94T-629-S00 MAP	End Table	22" x 30" x 24"	48	\$784	\$854

# Array Tables

### **General Specifications**

#### TABLETOP FOR WOOD VENEER

Tabletop will be 1" thick veneered particleboard, with .020" thick veneer on both faces. Wood veneer tops receive a 1/4" thick x 1"W wood (Maple, Oak or Walnut) edge band.

#### TABLETOP FOR THERMALLY-FUSED LAMINATE (TFL)

Tabletop will be 1" thick MDF, with .020" thick thermally-fused laminate on both faces. TFL tops receive a PVC edge band which will be flexible polyethylene, 2mm thick x 1"W.

#### TABLETOP FOR HIGH-PRESSURE LAMINATE (HPL)

Tabletop will be 1" thick particleboard, with .035" thick high-pressure laminate surface and .020" thick backing sheet for balanced construction. High-pressure laminate tops receive a PVC edge band which will be flexible polyethylene, 2mm thick x 1"W or a 5/8" thick x 1-1/16"W wood (Maple or Oak) edge band.

#### PATH LEGS (METAL)


Legs will be 2" x 2" steel square tubing with a wall thickness not less than 2mm. Legs are supplied with a standard glide insert. Metal legs attach to table top by means of a flange welded to the leg. Attachment flange will be 3-3/4" x 3-3/4" metal plate formed and welded on two sides to the leg. Each leg attachment flange is attached to the metal apron support frame using four #8 x 3/4" screws and then attached to the underneath of the tabletop by five #12 x 3/4" screws. Legs will be finished with electrostatic applied epoxy powder-coat paint.


#### **BLADE LEGS (METAL)**


Legs will be 1" x 3" steel rectangular tubing with a wall thickness not less than 2mm. Legs are supplied with a standard glide insert. Metal legs attach to table top by means of a flange welded to the leg. Attachment flange will be 3-3/4" x 3-3/4" metal plate formed and welded on two sides to the leg. Each leg attachment flange is attached to the metal apron support frame using four #8 x 3/4" screws and then attached to the underneath of the tabletop by five #12 x 3/4" screws. Legs will be finished with electrostatic applied epoxy powder-coat paint.

#### APRON SUPPORT FRAME


A metal frame 1"W x 2"H x 2mm thick in various lengths will be attached to underneath of the tabletop using #12 x 3/4" screws. Each leg attachment flange will be attached to the apron support frame using four #8 x 3/4" screws.













2MM PVC ON HPL Edge Detail





Path Legs Catalog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
Round Table with	Veneer Top and Ma	atching Wood Edge Band				Round Tabl
ARYP36RD30VOS	ARYB36RD30VOS	Veneer Oak Top/Edge Band	30"H x 36" Diameter	80	\$1,771	
ARYP36RD30VMS	ARYB36RD30VMS	Veneer Maple Top/Edge Band	30"H x 36" Diameter	80	\$1,857	
ARYP36RD30VWS	ARYB36RD30VWS	Veneer Walnut Top/Edge Band	30"H x 36" Diameter	80	\$1,991	
ARYP42RD30VOS	ARYB42RD30VOS	Veneer Oak Top/Edge Band	30"H x 42" Diameter	85	\$1,851	
ARYP42RD30VMS	ARYB42RD30VMS	Veneer Maple Top/Edge Band	30"H x 42" Diameter	85	\$1,937	
ARYP42RD30VWS	ARYB42RD30VWS	Veneer Walnut Top/Edge Band	30"H x 42" Diameter	85	\$2,071	J J
ARYP48RD30VOS	ARYB48RD30VOS	Veneer Oak Top/Edge Band	30"H x 48" Diameter	90	\$1,931	3
ARYP48RD30VMS	ARYB48RD30VMS	Veneer Maple Top/Edge Band	30"H x 48" Diameter	90	\$2,017	
ARYP48RD30VWS	ARYB48RD30VWS	Veneer Walnut Top/Edge Band	30"H x 48" Diameter	90	\$2,151	
ARYP60RD30VOS	ARYB60RD30VOS	Veneer Oak Top/Edge Band	30"Hx60" Diameter	95	\$2,083	with Path Leg
ARYP60RD30VMS	ARYB60RD30VMS	Veneer Maple Top/Edge Band	30"H x 60" Diameter	95	\$2,169	
ARYP60RD30VWS	ARYB60RD30VWS	Veneer Walnut Top/Edge Band	30"H x 60" Diameter	95	\$2,378	
ARYP36RD42VOS	ARYB36RD42VOS	Veneer Oak Top/Edge Band	42"H x 36" Diameter	90	\$1,771	TETT
ARYP36RD42VMS	ARYB36RD42VMS	Veneer Maple Top/Edge Band	42"H x 36" Diameter	90	\$1,857	
ARYP36RD42VWS	ARYB36RD42VWS	Veneer Walnut Top/Edge Band	42"H x 36" Diameter	90	\$1,991	
Please	specify Wood Finish for Tab	letop and Wood Edge Band (Table 1)	). Details can be found on p	age GEN 4.		
Round Table with	Solid Surface Top					J.
ARYP36RD30SSS	ARYB36RD30SSS	Solid Surface Top	30"H x 36" Diameter	C	all for Pricing	with Blade Leg
ARYP42RD30SSS	ARYB42RD30SSS	Solid Surface Top	30"H x 42" Diameter	Ca	all for Pricing	
ARYP48RD30SSS	ARYB48RD30SSS	Solid Surface Top	30"H x 48" Diameter	C	all for Pricing	
ARYP60RD30SSS	ARYB60RD30SSS	Solid Surface Top	30"H x 60" Diameter	C	all for Pricing	
ARYP36RD42SSS	ARYB36RD42SSS	Solid Surface Top	42"H x 36" Diameter	C	all for Pricing	
		Please call for details.				

30"H x 36" Diameter

30"H x 42" Diameter

30"H x 48" Diameter

30"H x 60" Diameter

42"H x 36" Diameter

\$1,169

\$1,229

\$1,298

\$1,441

\$1,169

80

85

90

95

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

TFL Top, PVC Edge Band

Round Table with TFL Top, PVC Edge Band

ARYB36RD30TPS

ARYB42RD30TPS

ARYB48RD30TPS

ARYB60RD30TPS

ARYB36RD42TPS

ARYP36RD30TPS

ARYP42RD30TPS

ARYP48RD30TPS

ARYP60RD30TPS

ARYP36RD42TPS

	Path Legs Catalog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Round Table	Round Table with	HPL Top, Maple or Oa	k Edge Band			
	ARYP36RD30HMS ARYP36RD30H0S	ARYB36RD30HMS ARYB36RD30HOS	HPL Top, Maple Edge Band HPL Top, Oak Edge Band	30"H x 36" Diameter 30"H x 36" Diameter	80 80	\$1,771 \$1,771
	ARYP42RD30HMS ARYP42RD30H0S	ARYB42RD30HMS ARYB42RD30HOS	HPL Top, Maple Edge Band HPL Top, Oak Edge Band	30"H x 42" Diameter 30"H x 42" Diameter	85 85	\$1,851 \$1,851
	ARYP48RD30HMS ARYP48RD30H0S	ARYB48RD30HMS ARYB48RD30HOS	HPL Top, Maple Edge Band HPL Top, Oak Edge Band	30"H x 48" Diameter 30"H x 48" Diameter	90 90	\$1,931 \$1,931
J	ARYP60RD30HMS ARYP60RD30H0S	ARYB60RD30HMS ARYB60RD30H0S	HPL Top, Maple Edge Band HPL Top, Oak Edge Band	30"H x 60" Diameter 30"H x 60" Diameter	95 95	\$2,083 \$2,083
with Path Legs	ARYP36RD42HMS ARYP36RD42H0S	ARYB36RD42HMS ARYB36RD42HOS	HPL Top, Maple Edge Band HPL Top, Oak Edge Band	42"H x 36" Diameter 42"H x 36" Diameter	90 90	\$1,771 \$1,771
	Please specify Lar	ninate Color (Tables 2 and 4)	and Metal Leg Color (Table 3).	Details can be found on pa	ges GEN 4 and	GEN 5.
	Round Table with	HPL Top, PVC Edge Ba	and			
	ARYP36RD30HPS	ARYB36RD30HPS	HPL Top, PVC Edge Band	30"H x 36" Diameter	80	\$1,280
n []	ARYP42RD30HPS	ARYB42RD30HPS	HPL Top, PVC Edge Band	30"H x 42" Diameter	85	\$1,360
J	ARYP48RD30HPS	ARYB48RD30HPS	HPL Top, PVC Edge Band	30"H x 48" Diameter	90	\$1,440
with Blade Legs	ARYP60RD30HPS	ARYB60RD30HPS	HPL Top, PVC Edge Band	30"H x 60" Diameter	95	\$1,592
ŭ	ARYP36RD42HPS	ARYB36RD42HPS	HPL Top, PVC Edge Band	42"H x 36" Diameter	90	\$1,280

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

with Blade Legs

	Price	Wt. (lbs.)	HxWxD	Description	Blade Legs Catalog No.	Path Legs Catalog No.
Square Table				latching Wood Edge Band	h Veneer Top and M	Square Table with
	\$1,348	90	30" x 30" x 30"	Veneer Oak Top/Edge Band	ARYB303030VOS	ARYP303030VOS
1	\$1,434	90	30" x 30" x 30"	Veneer Maple Top/ Edge Band	ARYB303030VMS	ARYP303030VMS
The state of the s	\$1,568	90	30" x 30" x 30"	Veneer Walnut Top/Edge Band	ARYB303030VWS	ARYP303030VWS
	\$1,512	100	30" x 42" x 42"	Veneer Oak Top/Edge Band	ARYB424230VOS	ARYP424230VOS
	\$1,598	100	30" x 42" x 42"	Veneer Maple Top/Edge Band	ARYB424230VMS	ARYP424230VMS
3	\$1,732	100	30" x 42" x 42"	Veneer Walnut Top/Edge Band	ARYB424230VWS	ARYP424230VWS
U U	\$1,612	110	30" x 48" x 48"	Veneer Oak Top/Edge Band	ARYB484830VOS	ARYP484830VOS
U	\$1,698	110	30" x 48" x 48"	Veneer Maple Top/Edge Band	ARYB484830VMS	ARYP484830VMS
with Path Legs	\$1,832	110	30" x 48" x 48"	Veneer Walnut Top/Edge Band	ARYB484830VWS	ARYP484830VWS
	\$1,512	105	36" x 42" x 42"	Veneer Oak Top/Edge Band	ARYB424236VOS	ARYP424236VOS
	\$1,598	105	36" x 42" x 42"	Veneer Maple Top/Edge Band	ARYB424236VMS	ARYP424236VMS
	\$1,732	105	36" x 42" x 42"	Veneer Walnut Top/Edge Band	ARYB424236VWS	ARYP424236VWS
	\$1,612	115	36" x 48" x 48"	Veneer Oak Top/Edge Band	ARYB484836VOS	ARYP484836VOS
	\$1,698	115	36" x 48" x 48"	Veneer Maple Top/Edge Band	ARYB484836VMS	ARYP484836VMS
	\$1,832	115	36" x 48" x 48"	Veneer Walnut Top/Edge Band	ARYB484836VWS	ARYP484836VWS
	\$1,348	100	42" x 30" x 30"	Veneer Oak Top/Edge Band	ARYB303042V0S	ARYP303042V0S
11	\$1,434	100	42" x 30" x 30"	Veneer Maple Top/Edge Band	ARYB303042VMS	ARYP303042VMS
	\$1,568	100	42" x 30" x 30"	Veneer Walnut Top/Edge Band	ARYB303042VWS	ARYP303042VWS

Square Table with	h Solid Surface Top			
ARYP303030SSS	ARYB303030SSS	Solid Surface Top	30" x 30" x 30"	Call for Pricing
ARYP424230SSS	ARYB424230SSS	Solid Surface Top	30" x 42" x 42"	Call for Pricing
ARYP484830SSS	ARYB484830SSS	Solid Surface Top	30" x 48" x 48"	Call for Pricing
ARYP424236SSS	ARYB424236SSS	Solid Surface Top	36" x 42" x 42"	Call for Pricing
ARYP484836SSS	ARYB484836SSS	Solid Surface Top	36" x 48" x 48"	Call for Pricing
ARYP303042SSS	ARYB303042SSS	Solid Surface Top	42" x 30" x 30"	Call for Pricing

Please call for details.

Square Table with TFL Top, PVC Edge Band									
ARYP303030TPS	ARYB303030TPS	TFL Top, PVC Edge Band	30" x 30" x 30"	90	\$1,073				
ARYP424230TPS	ARYB424230TPS	TFL Top, PVC Edge Band	30" x 42" x 42"	100	\$1,182				
ARYP484830TPS	ARYB484830TPS	TFL Top, PVC Edge Band	30" x 48" x 48"	110	\$1,282				
ARYP424236TPS	ARYB424236TPS	TFL Top, PVC Edge Band	36" x 42" x 42"	105	\$1,182				
ARYP484836TPS	ARYB484836TPS	TFL Top, PVC Edge Band	36" x 48" x 48"	115	\$1,282				
ARYP303042TPS	ARYB303042TPS	TFL Top, PVC Edge Band	42" x 30" x 30"	100	\$1,073				

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

	i util Logo	
	Catalog No.	Ca
Square Table	Square Table w	ith HPL
	ARYP303030HMS	AF
1	ARYP303030HOS	AF
TT	ARYP424230HMS	AF
1 // 1	ARYP424230HOS	AF
	ARYP484830HMS	AF
	ARYP484830HOS	AF
	ARYP424236HMS	AF
3	ARYP424236HOS	AF

with Path Legs



with Blade Legs

Path Legs Catalog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Square Table with	HPL Top, Maple or Oa	ak Edge Band			
ARYP303030HMS	ARYB303030HMS	HPL Top, Maple Edge Band	30" x 30" x 30"	90	\$1,348
ARYP303030H0S	ARYB303030H0S	HPL Top, Oak Edge Band	30" x 30" x 30"	90	\$1,348
ARYP424230HMS	ARYB424230HMS	HPL Top, Maple Edge Band	30" x 42" x 42"	100	\$1,512
ARYP424230HOS	ARYB424230HOS	HPL Top, Oak Edge Band	30" x 42" x 42"	100	\$1,512
ARYP484830HMS	ARYB484830HMS	HPL Top, Maple Edge Band	30" x 48" x 48"	110	\$1,612
ARYP484830HOS	ARYB484830HOS	HPL Top, Oak Edge Band	30" x 48" x 48"	110	\$1,612
ARYP424236HMS	ARYB424236HMS	HPL Top, Maple Edge Band	36" x 42" x 42"	105	\$1,512
ARYP424236HOS	ARYB424236HOS	HPL Top, Oak Edge Band	36" x 42" x 42"	105	\$1,512
ARYP484836HMS	ARYB484836HMS	HPL Top, Maple Edge Band	36" x 48" x 48"	115	\$1,612
ARYP484836HOS	ARYB484836HOS	HPL Top, Oak Edge Band	36" x 48" x 48"	115	\$1,612
ARYP303042HMS	ARYB303042HMS	HPL Top, Maple Edge Band	42" x 30" x 30"	100	\$1,348
ARYP303042H0S	ARYB303042H0S	HPL Top, Oak Edge Band	42" x 30" x 30"	100	\$1,348

Please specify Laminate Color (Tables 2 and 4) and Metal Leg Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Square Table with HPL Top, PVC Edge Band								
ARYP303030HPS	ARYB303030HPS	HPL Top, PVC Edge Band	30" x 30" x 30"	90	\$1,147			
ARYP424230HPS	ARYB424230HPS	HPL Top, PVC Edge Band	30" x 42" x 42"	100	\$1,311			
ARYP484830HPS	ARYB484830HPS	HPL Top, PVC Edge Band	30" x 48" x 48"	110	\$1,411			
ARYP424236HPS	ARYB424236HPS	HPL Top, PVC Edge Band	36" x 42" x 42"	105	\$1,311			
ARYP484836HPS	ARYB484836HPS	HPL Top, PVC Edge Band	36" x 48" x 48"	115	\$1,411			
ARYP303042HPS	ARYB303042HPS	HPL Top, PVC Edge Band	42" x 30" x 30"	100	\$1,147			

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

	Price	Wt. (lbs.)	HxWxD	Description	Blade Legs Catalog No.	Path Legs Catalog No.
Rectangular Tab				Matching Wood Edge Band	with Veneer Top and	Rectangular Table
	\$1,648	96	30" x 60" x 30"	Veneer Oak Top/Edge Band	ARYB306030VOS	ARYP306030VOS
	\$1,772	96	30" x 60" x 30"	Veneer Maple Top/Edge Band	ARYB306030VMS	ARYP306030V03
	\$1,772	96	30" x 60" x 30"	Veneer Walnut Top/Edge Band	ARYB306030VWS	ARYP306030VWS
N T	\$1,783	110	30" x 72" x 30"	Veneer Oak Top/Edge Band	ARYB307230VOS	ARYP307230VOS
11 (1)						ARYP307230V03
WW II /	\$1,907 \$2,041	110 110	30" x 72" x 30" 30" x 72" x 30"	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	ARYB307230VMS ARYB307230VWS	ARYP307230VWS
	\$1,948	120	30" x 90" x 30"	Veneer Oak Top/Edge Band	ARYB309030VOS	ARYP309030VOS
	\$2,072 \$2,206	120 120	30" x 90" x 30" 30" x 90" x 30"	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	ARYB309030VMS ARYB309030VWS	ARYP309030VMS ARYP309030VWS
U				· -		
with Path Le	\$1,717	104	30" x 60" x 36"	Veneer Oak Top/Edge Band	ARYB366030VOS	ARYP366030V0S
	\$1,846	104	30" x 60" x 36"	Veneer Maple Top/Edge Band	ARYB366030VMS	ARYP366030VMS
	\$1,986	104	30" x 60" x 36"	Veneer Walnut Top/Edge Band	ARYB366030VWS	ARYP366030VWS
	\$1,857	118	30" x 72" x 36"	Veneer Oak Top/Edge Band	ARYB367230VOS	ARYP367230VOS
	\$1,986	118	30" x 72" x 36"	Veneer Maple Top/Edge Band	ARYB367230VMS	ARYP367230VMS
14 1 1 11	\$2,126	118	30" x 72" x 36"	Veneer Walnut Top/Edge Band	ARYB367230VWS	ARYP367230VWS
	\$2,029	128	30" x 90" x 36"	Veneer Oak Top/Edge Band	ARYB369030VOS	ARYP369030VOS
	\$2,158	128	30" x 90" x 36"	Veneer Maple Top/Edge Band	ARYB369030VMS	ARYP369030VMS
11 11 11 11	\$2,130	128	30" x 90" x 36"	Veneer Walnut Top/Edge Band	ARYB369030VWS	ARYP369030VWS
	\$1,830	110	30" x 60" x 42"	Veneer Oak Top/Edge Band	ARYB426030VOS	ARYP426030VOS
<u> </u>	\$1,968	110	30" x 60" x 42"	Veneer Maple Top/Edge Band	ARYB426030VMS	ARYP426030VMS
with Blade Le	\$1,700	110	30" x 60" x 42"	Veneer Walnut Top/Edge Band	ARYB426030VWS	ARYP426030VWS
	\$1,980	124	30" x 72" x 42"	Veneer Oak Top/Edge Band	ARYB427230VOS	ARYP427230VOS
				1 0		
	\$2,117	124	30" x 72" x 42"	Veneer Maple Top/Edge Band	ARYB427230VMS	ARYP427230VMS
	\$2,266	124	30" x 72" x 42"	Veneer Walnut Top/Edge Band	ARYB427230VWS	ARYP427230VWS
	\$2,163	135	30" x 90" x 42"	Veneer Oak Top/Edge Band	ARYB429030VOS	ARYP429030VOS
	\$2,300	135	30" x 90" x 42"	Veneer Maple Top/Edge Band	ARYB429030VMS	ARYP429030VMS
	\$2,450	135	30" x 90" x 42"	Veneer Walnut Top/Edge Band	ARYB429030VWS	ARYP429030VWS
	\$2,487	145	30" x 108" x 42"	Veneer Oak Top/Edge Band	ARYB4210830VOS	ARYP4210830VOS
	\$2,587	145	30" x 108" x 42"	Veneer Maple Top/Edge Band	ARYB4210830VMS	ARYP4210830VMS
	\$2,727	145	30" x 108" x 42"	Veneer Walnut Top/Edge Band	ARYB4210830VWS	ARYP4210830VWS
	\$2,626	155	30" x 120" x 42"	Veneer Oak Top/Edge Band	ARYB4212030VOS	ARYP4212030VOS
	\$2,803	155	30" x 120" x 42"	Veneer Maple Top/Edge Band	ARYB4212030VMS	ARYP4212030VMS
	\$2,927	155	30" x 120" x 42"	Veneer Walnut Top/Edge Band	ARYB4212030VWS	ARYP4212030VWS
		85	36" x 48" x 24"	Veneer Oak Top/Edge Band	ARYB244836VOS	ARYP244836VOS
	\$1 441					ARYP244836VMS
	\$1,441 \$1.540			Vencer Manle Ton / Edge Rand		
	\$1,549	85 85	36" x 48" x 24" 36" x 48" x 24"	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	ARYB244836VMS ARYB244836VWS	ARYP244836VWS
	\$1,549 \$1,666	85 85	36" x 48" x 24" 36" x 48" x 24"	Veneer Walnut Top/Edge Band	ARYB244836VWS	ARYP244836VWS
	\$1,549 \$1,666 \$1,516	85 85 96	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band	ARYB244836VWS ARYB246036VOS	ARYP244836VWS ARYP246036VOS
	\$1,549 \$1,666 \$1,516 \$1,630	85 85 96 96	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS	ARYP244836VWS ARYP246036VOS ARYP246036VMS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754	85 85 96 96 96	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 60" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS	ARYP244836VWS ARYP246036VOS ARYP246036VMS ARYP246036VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640	85 85 96 96 96	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band	ARYB244836VWS ARYB246036V0S ARYB246036VMS ARYB246036VWS ARYB247236VOS	ARYP244836VWS ARYP246036VOS ARYP246036VMS ARYP246036VWS ARYP247236VOS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754	85 85 96 96 96 110	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VMS	ARYP244836VWS ARYP246036VOS ARYP246036VMS ARYP246036VWS ARYP247236VOS ARYP247236VMS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640	85 85 96 96 96	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band	ARYB244836VWS ARYB246036V0S ARYB246036VMS ARYB246036VWS ARYB247236VOS	ARYP244836VWS ARYP246036VOS ARYP246036VMS ARYP246036VWS ARYP247236VOS ARYP247236VMS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754	85 85 96 96 96 110	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VMS	ARYP244836VWS ARYP246036VOS ARYP246036VMS ARYP246036VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878	85 85 96 96 96 110 110	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VMS ARYB247236VWS	ARYP244836VWS ARYP246036VMS ARYP246036VWS ARYP246036VWS ARYP247236VMS ARYP247236VWS ARYP247236VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792	85 85 96 96 96 110 110 110	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VWS ARYB247236VWS ARYB249036VOS	ARYP244836VWS ARYP246036VMS ARYP246036VWS ARYP247236VOS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP247036VWS ARYP249036VMS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792 \$1,906	85 85 96 96 96 110 110 110 120 120	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24" 36" x 90" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VWS ARYB247236VWS ARYB247236VWS ARYB249036VOS ARYB249036VMS	ARYP244836VWS ARYP246036VOS ARYP246036VMS ARYP246036VWS ARYP247236VOS ARYP247236VMS ARYP247236VWS ARYP249036VOS ARYP249036VWS ARYP249036VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792 \$1,906 \$2,030 \$1,648	85 85 96 96 96 110 110 110 120 120	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24" 36" x 90" x 24" 36" x 90" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB2446036VWS ARYB247236VOS ARYB247236VMS ARYB247236VWS ARYB249036VOS ARYB249036VMS ARYB249036VWS	ARYP244836VWS ARYP246036VOS ARYP246036VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP249036VOS ARYP249036VWS ARYP249036VWS ARYP249036VWS ARYP249036VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792 \$1,906 \$2,030	85 85 96 96 96 110 110 110 120 120 120	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VMS ARYB247236VWS ARYB249036VOS ARYB249036VMS ARYB249036VWS ARYB249036VWS ARYB306036VOS	ARYP244836VWS ARYP246036VMS ARYP246036VWS ARYP246036VWS ARYP247236VMS ARYP247236VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792 \$1,906 \$2,030 \$1,648 \$1,772 \$1,907	85 85 96 96 96 110 110 110 120 120 120 100 100	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24" 36" x 90" x 24" 36" x 60" x 30" 36" x 60" x 30" 36" x 60" x 30"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VMS ARYB247236VWS ARYB249036VWS ARYB249036VWS ARYB249036VWS ARYB306036VMS ARYB306036VWS	ARYP244836VWS ARYP246036VMS ARYP246036VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP249036VWS ARYP249036VWS ARYP249036VWS ARYP306036VWS ARYP306036VWS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792 \$1,906 \$2,030 \$1,648 \$1,772 \$1,907 \$1,783	85 85 96 96 96 110 110 110 120 120 120 100 100 100	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24" 36" x 90" x 24" 36" x 60" x 30" 36" x 60" x 30" 36" x 60" x 30" 36" x 72" x 30"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VWS ARYB247236VWS ARYB247236VWS ARYB249036VWS ARYB249036VWS ARYB249036VWS ARYB306036VWS ARYB306036VWS ARYB306036VWS ARYB307236VOS	ARYP244836VWS ARYP246036VMS ARYP246036VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP249036VWS ARYP249036VWS ARYP249036VWS ARYP306036VWS ARYP306036VWS ARYP306036VWS ARYP306036VWS ARYP307236VOS
	\$1,549 \$1,666 \$1,516 \$1,630 \$1,754 \$1,640 \$1,754 \$1,878 \$1,792 \$1,906 \$2,030 \$1,648 \$1,772 \$1,907	85 85 96 96 96 110 110 110 120 120 120 100 100	36" x 48" x 24" 36" x 48" x 24" 36" x 60" x 24" 36" x 60" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 72" x 24" 36" x 90" x 24" 36" x 90" x 24" 36" x 60" x 30" 36" x 60" x 30" 36" x 60" x 30"	Veneer Walnut Top/Edge Band Veneer Oak Top and Edge Band Veneer Maple Top and Edge Band Veneer Walnut Top and Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band Veneer Walnut Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band Veneer Maple Top/Edge Band	ARYB244836VWS ARYB246036VOS ARYB246036VMS ARYB246036VWS ARYB247236VOS ARYB247236VMS ARYB247236VWS ARYB249036VWS ARYB249036VWS ARYB249036VWS ARYB306036VMS ARYB306036VWS	ARYP244836VWS ARYP246036VMS ARYP246036VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP247236VWS ARYP249036VWS ARYP249036VWS ARYP249036VWS ARYP306036VWS ARYP306036VWS

 $Please\ specify\ Wood\ Finish\ for\ Tabletop\ and\ Wood\ Edge\ Band\ (Table\ 1).\ Details\ can\ be\ found\ on\ page\ GEN\ 4.$ 

	Path Legs Catalog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Rectangular Table	Rectangular Table	e with Veneer Top and	d Matching Wood Edge Bar	nd		
	ARYP309036V0S	ARYB309036VOS	Veneer Oak Top/Edge Band	36" x 90" x 30"	125	\$1,948
T	ARYP309036VMS	ARYB309036VMS	Veneer Maple Top/Edge Band	36" x 90" x 30"	125	\$2,072
	ARYP309036VWS	ARYB309036VWS	Veneer Walnut Top/Edge Band	36" x 90" x 30"	125	\$2,206
	ARYP426036V0S	ARYB426036VOS	Veneer Oak Top/Edge Band	36" x 60" x 42"	115	\$1,830
11 11 11	ARYP426036VMS	ARYB426036VMS	Veneer Maple Top/Edge Band	36" x 60" x 42"	115	\$1,968
1 0	ARYP426036VWS	ARYB426036VWS	Veneer Walnut Top/Edge Band	36" x 60" x 42"	115	\$2,117
0	ARYP427236VOS	ARYB427236VOS	Veneer Oak Top/Edge Band	36" x 72" x 42"	129	\$1,980
W.	ARYP427236VMS	ARYB427236VMS	Veneer Maple Top/Edge Band	36" x 72" x 42"	129	\$2,117 \$2,244
U	ARYP427236VWS	ARYB427236VWS	Veneer Walnut Top/Edge Band	36" x 72" x 42"	129	\$2,266
with Path Legs	ARYP429036VOS	ARYB429036VOS	Veneer Oak Top/Edge Band	36" x 90" x 42"	140	\$2,163
	ARYP429036VMS ARYP429036VWS	ARYB429036VMS ARYB429036VWS	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	36" x 90" x 42" 36" x 90" x 42"	140 140	\$2,300 \$2,450
	AR1P429030VW3	AK10429030VW3				•
THE THE	ARYP4210836VOS	ARYB4210836VOS	Veneer Oak Top/Edge Band	36" x 108" x 42"	150	\$2,487
	ARYP4210836VMS ARYP4210836VWS	ARYB4210836VMS ARYB4210836VWS	Veneer Maple Top/Edge Band	36" x 108" x 42"	150 150	\$2,587 \$2,727
			Veneer Walnut Top/Edge Band	36" x 108" x 42"		•
	ARYP4212036V0S	ARYB4212036VOS	Veneer Oak Top/Edge Band	36" x 120" x 42"	160	\$2,626
	ARYP4212036VMS ARYP4212036VWS	ARYB4212036VMS ARYB4212036VWS	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	36" x 120" x 42" 36" x 120" x 42"	160 160	\$2,803 \$2,927
Ú.						•
	ARYP244842VOS	ARYB244842VOS	Veneer Oak Top/Edge Band	42" x 48" x 24"	90	\$1,441
vith Blade Legs	ARYP244842VMS ARYP244842VWS	ARYB244842VMS ARYB244842VWS	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	42" x 48" x 24" 42" x 48" x 24"	90 90	\$1,549 \$1,666
J						•
	ARYP246042VOS ARYP246042VMS	ARYB246042VOS	Veneer Oak Top/Edge Band	42" x 60" x 24"	101 101	\$1,441 \$1,540
	ARYP246042VWS	ARYB246042VMS ARYB246042VWS	Veneer Maple Top/Edge Band Veneer Walnut Top/Edge Band	42" x 60" x 24" 42" x 60" x 24"	101	\$1,549 \$1,666
						•
	ARYP247242VOS ARYP247242VMS	ARYB247242VOS ARYB247242VMS	Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band	42" x 72" x 24" 42" x 72" x 24"	115 115	\$1,640 \$1,754
	ARYP247242VWS	ARYB247242VWS	Veneer Walnut Top/Edge Band	42" x 72" x 24"	115	\$1,734
	ARYP249042VOS	ARYB249042VOS	· -	42" x 90" x 24"	125	•
	ARYP249042VMS	ARYB249042VMS	Veneer Oak Top/Edge Band Veneer Maple Top/Edge Band	42 x 90 x 24 42" x 90" x 24"	125	\$1,792 \$1,906
	ARYP249042VWS	ARYB249042VWS	Veneer Walnut Top/Edge Band	42" x 90" x 24"	125	\$2,030
	Please s	pecify Wood Finish for Tableto	op and Wood Edge Band (Table 1). De	etails can be found on p	page GEN 4	1.
		0.000				
	Rectangular with ARYP306030SSS	ARYB306030SSS	Solid Surface Top	30" x 60" x 30"		Call for Pricing
	ARYP307230SSS	ARYB307230SSS	Solid Surface Top	30" x 72" x 30"		Call for Pricing
	ARYP309030SSS	ARYB309030SSS	Solid Surface Top	30" x 90" x 30"		Call for Pricing
	ARYP366030SSS	ARYB366030SSS	Solid Surface Top	30" x 60" x 36"		Call for Pricing
	ARYP367230SSS	ARYB367230SSS	Solid Surface Top	30" x 72" x 36"		Call for Pricing
	ARYP369030SSS	ARYB369030SSS	Solid Surface Top	30" x 90" x 36"		Call for Pricing
	ARYP426030SSS	ARYB426030SSS	Solid Surface Top	30" x 60" x 42"		Call for Pricing
	ARYP427230SSS	ARYB427230SSS	Solid Surface Top	30" x 72" x 42"		Call for Pricing
	ARYP429030SSS	ARYB429030SSS	Solid Surface Top	30" x 90" x 42"		Call for Pricing
	ARYP4210830SSS	ARYB4210830SSS	Solid Surface Top	30" x 108" x 42"		Call for Pricing
	AIN 1 F 4 Z 1 U 0 3 U 3 3 3	UU1045 10090999	Julia Juliace Tup	JU X 100 X 4Z		Jan 101 PHUING

Please call for details.

Solid Surface Top

Solid Surface Top

Solid Surface Top

Solid Surface Top

30" x 120" x 42"

36" x 48" x 24"

36" x 60" x 24"

36" x 72" x 24"

**Call for Pricing** 

**Call for Pricing** 

**Call for Pricing** 

**Call for Pricing** 

ARYB4212030SSS

ARYB244836SSS

ARYB246036SSS

ARYB247236SSS

ARYP4212030SSS

ARYP244836SSS

ARYP246036SSS

ARYP247236SSS

h Legs talog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
ctangular with	Solid Surface Top				
P249036SSS	ARYB249036SSS	Solid Surface Top	36" x 90" x 24"		Call for Pricing
P306036SSS	ARYB306036SSS	Solid Surface Top	36" x 60" x 30"		Call for Pricing
307236SSS	ARYB307236SSS	Solid Surface Top	36" x 72" x 30"		Call for Pricing
2309036SSS	ARYB309036SSS	Solid Surface Top	36" x 90" x 30"		Call for Pricing
426036SSS	ARYB426036SSS	Solid Surface Top	36" x 60" x 42"		Call for Pricing
P427236SSS	ARYB427236SSS	Solid Surface Top	36" x 72" x 42"		Call for Pricing
P429036SSS	ARYB429036SSS	Solid Surface Top	36" x 90" x 42"		Call for Pricing
P4210836SSS	ARYB4210836SSS	Solid Surface Top	36" x 108" x 42"		Call for Pricing
P4212036SSS	ARYB4212036SSS	Solid Surface Top	36" x 120" x 42"		Call for Pricing
244842SSS	ARYB244842SSS	Solid Surface Top	42" x 48" x 24"		Call for Pricing
P246042SSS	ARYB246042SSS	Solid Surface Top	42" x 60" x 24"		Call for Pricing
P247242SSS	ARYB247242SSS	Solid Surface Top	42" x 72" x 24"		Call for Pricing
249042SSS	ARYB249042SSS	Solid Surface Top	42" x 90" x 24"		Call for Pricing
		Please call for details.			
angular Table	e with TFL Top, PVC E	Edge Band			
306030TPS	ARYB306030TPS	TFL Top, PVC Edge Band	30" x 60" x 30"	96	\$1,246
307230TPS	ARYB307230TPS	TFL Top, PVC Edge Band	30" x 72" x 30"	110	\$1,317
2309030TPS	ARYB309030TPS	TFL Top, PVC Edge Band	30" x 90" x 30"	120	\$1,462
P366030TPS	ARYB366030TPS	TFL Top, PVC Edge Band	30" x 60" x 36"	104	\$1,298
367230TPS	ARYB367230TPS	TFL Top, PVC Edge Band	30" x 72" x 36"	118	\$1,372
369030TPS	ARYB369030TPS	TFL Top, PVC Edge Band	30" x 90" x 36"	128	\$1,523
P426030TPS	ARYB426030TPS	TFL Top, PVC Edge Band	30" x 60" x 42"	110	\$1,384
P427230TPS	ARYB427230TPS	TFL Top, PVC Edge Band	30" x 72" x 42"	124	\$1,463
9429030TPS	ARYB429030TPS	TFL Top, PVC Edge Band	30" x 90" x 42"	135	\$1,624
P4210830TPS	ARYB4210830TPS	TFL Top, PVC Edge Band	30" x 108" x 42"	145	\$1,866
P4212030TPS	ARYB4212030TPS	TFL Top, PVC Edge Band	30" x 120" x 42"	155	\$1,998
P244836TPS	ARYB244836TPS	TFL Top, PVC Edge Band	36" x 48" x 24"	85	\$1,089
P246036TPS	ARYB246036TPS	TFL Top, PVC Edge Band	36" x 60" x 24"	96	\$1,146
P247236TPS	ARYB247236TPS	TFL Top, PVC Edge Band	36" x 72" x 24"	110	\$1,212
P249036TPS	ARYB249036TPS	TFL Top, PVC Edge Band	36" x 90" x 24"	120	\$1,345
P306036TPS	ARYB306036TPS	TFL Top, PVC Edge Band	36" x 60" x 30"	100	\$1,246
P307236TPS	ARYB307236TPS	TFL Top, PVC Edge Band	36" x 72" x 30"	115	\$1,317
/P309036TPS	ARYB309036TPS	TFL Top, PVC Edge Band	36" x 90" x 30"	125	\$1,462
P426036TPS	ARYB426036TPS	TFL Top, PVC Edge Band	36" x 60" x 42"	115	\$1,384
P427236TPS	ARYB427236TPS	TFL Top, PVC Edge Band	36" x 72" x 42"	129	\$1,463
P429036TPS	ARYB429036TPS	TFL Top, PVC Edge Band	36" x 90" x 42"	140	\$1,624
1210836TPS	ARYB4210836TPS	TFL Top, PVC Edge Band	36" x 108" x 42"	150	\$1,866

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

#### Rectangular Table



Path Legs	Blade Legs			Wt.				
Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price			
Rectangular Table with TFL Top, PVC Edge Band								
ARYP4212036TPS	ARYB4212036TPS	TFL Top, PVC Edge Band	36" x 120" x 42"	160	\$1,998			
ARYP244842TPS	ARYB244842TPS	TFL Top, PVC Edge Band	42" x 48" x 24"	90	\$1,089			
ARYP246042TPS	ARYB246042TPS	TFL Top, PVC Edge Band	42" x 60" x 24"	101	\$1,146			
ARYP247242TPS	ARYB247242TPS	TFL Top, PVC Edge Band	42" x 72" x 24"	115	\$1,212			
ARYP249042TPS	ARYB249042TPS	TFL Top, PVC Edge Band	42" x 90" x 24"	125	\$1,345			

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

Note: Edge Band Color does NOT have to match Laminate Color. GEN 5.

with Path Legs



Rectangular Table	e with HPL Top, Maple	e or Oak Edge Band			
ARYP306030HMS	ARYB306030HMS	HPL Top, Maple Edge Band	30" x 60" x 30"	96	\$1,648
ARYP306030HOS	ARYB306030H0S	HPL Top, Oak Edge Band	30" x 60" x 30"	96	\$1,648
ARYP307230HMS	ARYB307230HMS	HPL Top, Maple Edge Band	30" x 72" x 30"	110	\$1,783
ARYP307230H0S	ARYB307230H0S	HPL Top, Oak Edge Band	30" x 72" x 30"	110	\$1,783
ARYP309030HMS	ARYB309030HMS	HPL Top, Maple Edge Band	30" x 90" x 30"	120	\$1,948
ARYP309030H0S	ARYB309030H0S	HPL Top, Oak Edge Band	30" x 90" x 30"	120	\$1,948
ARYP366030HMS	ARYB366030HMS	HPL Top, Maple Edge Band	30" x 60" x 36"	104	\$1,717
ARYP366030HOS	ARYB366030H0S	HPL Top, Oak Edge Band	30" x 60" x 36"	104	\$1,717
ARYP367230HMS	ARYB367230HMS	HPL Top, Maple Edge Band	30" x 72" x 36"	118	\$1,857
ARYP367230HOS	ARYB367230H0S	HPL Top, Oak Edge Band	30" x 72" x 36"	118	\$1,857
ARYP369030HMS	ARYB369030HMS	HPL Top, Maple Edge Band	30" x 90" x 36"	128	\$2,029
ARYP369030HOS	ARYB369030H0S	HPL Top, Oak Edge Band	30" x 90" x 36"	128	\$2,029
ARYP426030HMS	ARYB426030HMS	HPL Top, Maple Edge Band	30" x 60" x 42"	110	\$1,830
ARYP426030HOS	ARYB426030H0S	HPL Top, Oak Edge Band	30" x 60" x 42"	110	\$1,830
ARYP427230HMS	ARYB427230HMS	HPL Top, Maple Edge Band	30" x 72" x 42"	124	\$1,980
ARYP427230HOS	ARYB427230H0S	HPL Top, Oak Edge Band	30" x 72" x 42"	124	\$1,980
ARYP429030HMS	ARYB429030HMS	HPL Top, Maple Edge Band	30" x 90" x 42"	135	\$2,163
ARYP429030H0S	ARYB429030H0S	HPL Top, Oak Edge Band	30" x 90" x 42"	135	\$2,163
ARYP4210830HMS	ARYB4210830HMS	HPL Top, Maple Edge Band	30" x 108" x 42"	145	\$2,487
ARYP4210830H0S	ARYB4210830H0S	HPL Top, Oak Edge Band	30" x 108" x 42"	145	\$2,487
ARYP4212030HMS	ARYB4212030HMS	HPL Top, Maple Edge Band	30" x 120" x 42"	155	\$2,626
ARYP4212030H0S	ARYB4212030H0S	HPL Top, Oak Edge Band	30" x 120" x 42"	155	\$2,626
ARYP244836HMS	ARYB244836HMS	HPL Top, Maple Edge Band	36" x 48" x 24"	85	\$1,441
ARYP244836HOS	ARYB244836H0S	HPL Top, Oak Edge Band	36" x 48" x 24"	85	\$1,441
ARYP246036HMS	ARYB246036HMS	HPL Top, Maple Edge Band	36" x 60" x 24"	96	\$1,516
ARYP246036H0S	ARYB246036H0S	HPL Top, Oak Edge Band	36" x 60" x 24"	96	\$1,516
ARYP247236HMS	ARYB247236HMS	HPL Top, Maple Edge Band	36" x 72" x 24"	110	\$1,640
ARYP247236H0S	ARYB247236H0S	HPL Top, Oak Edge Band	36" x 72" x 24"	110	\$1,640
ARYP249036HMS	ARYB249036HMS	HPL Top, Maple Edge Band	36" x 90" x 24"	120	\$1,792
ARYP249036H0S	ARYB249036H0S	HPL Top, Oak Edge Band	36" x 90" x 24"	120	\$1,792
ARYP306036HMS	ARYB306036HMS	HPL Top, Maple Edge Band	36" x 60" x 30"	100	\$1,648
ARYP306036H0S	ARYB306036H0S	HPL Top, Oak Edge Band	36" x 60" x 30"	100	\$1,648
ARYP307236HMS	ARYB307236HMS	HPL Top, Maple Edge Band	36" x 72" x 30"	115	\$1,783
ARYP307236H0S	ARYB307236H0S	HPL Top, Oak Edge Band	36" x 72" x 30"	115	\$1,783
ARYP309036HMS	ARYB309036HMS	HPL Top, Maple Edge Band	36" x 90" x 30"	125	\$1,948
ARYP309036H0S	ARYB309036H0S	HPL Top, Oak Edge Band	36" x 90" x 30"	125	\$1,948

Please specify Laminate Color (Tables 2 and 4) and Metal Leg Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Path Legs Catalog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
Rectangular Table	e with HPL Top, Mapl	e or Oak Edge Band				Rectangular Table
ARYP426036HMS	ARYB426036HMS	HPL Top, Maple Edge Band	36" x 60" x 42"	115	\$1,830	
ARYP426036H0S	ARYB426036H0S	HPL Top, Oak Edge Band	36" x 60" x 42"	115	\$1,830	
ARYP427236HMS	ARYB427236HMS	HPL Top, Maple Edge Band	36" x 72" x 42"	129	\$1,980	
ARYP427236HOS	ARYB427236HOS	HPL Top, Oak Edge Band	36" x 72" x 42"	129	\$1,980	
ARYP429036HMS	ARYB429036HMS	HPL Top, Maple Edge Band	36" x 90" x 42"	140	\$2,163	
ARYP429036HOS	ARYB429036HOS	HPL Top, Oak Edge Band	36" x 90" x 42"	140	\$2,163	
ARYP4210836HMS	ARYB4210836HMS	HPL Top, Maple Edge Band	36" x 108" x 42"	150	\$2,487	U U
ARYP4210836H0S	ARYB4210836H0S	HPL Top, Oak Edge Band	36" x 108" x 42"	150	\$2,487	
ARYP4212036HMS	ARYB4212036HMS	HPL Top, Maple Edge Band	36" x 120" x 42"	160	\$2,626	with Path Legs
ARYP4212036H0S	ARYB4212036H0S	HPL Top, Oak Edge Band	36" x 120" x 42"	160	\$2,626	
ARYP244842HMS	ARYB244842HMS	HPL Top, Maple Edge Band	42" x 48" x 24"	90	\$1,441	7.1
ARYP244842HOS	ARYB244842HOS	HPL Top, Oak Edge Band	42" x 48" x 24"	90	\$1,441	
ARYP246042HMS	ARYB246042HMS	HPL Top, Maple Edge Band	42" x 60" x 24"	101	\$1,516	
ARYP246042HOS	ARYB246042HOS	HPL Top, Oak Edge Band	42" x 60" x 24"	101	\$1,516	
ARYP247242HMS	ARYB247242HMS	HPL Top, Maple Edge Band	42" x 72" x 24"	115	\$1,640	
ARYP247242HOS	ARYB247242HOS	HPL Top, Oak Edge Band	42" x 72" x 24"	115	\$1,640	
ARYP249042HMS	ARYB249042HMS	HPL Top, Maple Edge Band	42" x 90" x 24"	125	\$1,792	
ARYP249042HOS	ARYB249042HOS	HPL Top, Oak Edge Band	42" x 90" x 24"	125	\$1,792	
Please specify La	minate Color (Tables 2 and 4	) and Metal Leg Color (Table 3).	Details can be found on p	oages GEN 4 and	d GEN 5.	with Blade Legs

Rectangul	or Toble	a with UD	I Ton	DI/C Edgo	Rand

ARYP306030HPS	ARYB306030HPS	HPL Top, PVC Edge Band	30" x 60" x 30"	96	\$1,375
ARYP307230HPS	ARYB307230HPS	HPL Top, PVC Edge Band	30" x 72" x 30"	110	\$1,490
ARYP309030HPS	ARYB309030HPS	HPL Top, PVC Edge Band	30" x 90" x 30"	120	\$1,636
ARYP366030HPS	ARYB366030HPS	HPL Top, PVC Edge Band	30" x 60" x 36"	104	\$1,432
ARYP367230HPS	ARYB367230HPS	HPL Top, PVC Edge Band	30" x 72" x 36"	118	\$1,552
ARYP369030HPS	ARYB369030HPS	HPL Top, PVC Edge Band	30" x 90" x 36"	128	\$1,704
ARYP426030HPS	ARYB426030HPS	HPL Top, PVC Edge Band	30" x 60" x 42"	110	\$1,527
ARYP427230HPS	ARYB427230HPS	HPL Top, PVC Edge Band	30" x 72" x 42"	124	\$1,654
ARYP429030HPS	ARYB429030HPS	HPL Top, PVC Edge Band	30" x 90" x 42"	135	\$1,816
ARYP4210830HPS	ARYB4210830HPS	HPL Top, PVC Edge Band	30" x 108" x 42"	145	\$2,080
ARYP4212030HPS	ARYB4212030HPS	HPL Top, PVC Edge Band	30" x 120" x 42"	155	\$2,237
ARYP244836HPS	ARYB244836HPS	HPL Top, PVC Edge Band	36" x 48" x 24"	85	\$1,202
ARYP246036HPS	ARYB246036HPS	HPL Top, PVC Edge Band	36" x 60" x 24"	96	\$1,265
ARYP247236HPS	ARYB247236HPS	HPL Top, PVC Edge Band	36" x 72" x 24"	110	\$1,371
ARYP249036HPS	ARYB249036HPS	HPL Top, PVC Edge Band	36" x 90" x 24"	120	\$1,505
ARYP306036HPS	ARYB306036HPS	HPL Top, PVC Edge Band	36" x 60" x 30"	100	\$1,375
ARYP307236HPS	ARYB307236HPS	HPL Top, PVC Edge Band	36" x 72" x 30"	115	\$1,490
ARYP309036HPS	ARYB309036HPS	HPL Top, PVC Edge Band	36" x 90" x 30"	125	\$1,636
ARYP426036HPS	ARYB426036HPS	HPL Top, PVC Edge Band	36" x 60" x 42"	115	\$1,527
ARYP427236HPS	ARYB427236HPS	HPL Top, PVC Edge Band	36" x 72" x 42"	129	\$1,654

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

	Path Legs Catalog No.	Blade Legs Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Rectangular Table	Rectangular Table	e with HPL Top, PVC Ed	dge Band			
	ARYP429036HPS	ARYB429036HPS	HPL Top, PVC Edge Band	36" x 90" x 42"	140	\$1,816
7	ARYP4210836HPS	ARYB4210836HPS	HPL Top, PVC Edge Band	36" x 108" x 42"	150	\$2,080
T	ARYP4212036HPS	ARYB4212036HPS	HPL Top, PVC Edge Band	36" x 120" x 42"	160	\$2,237
	ARYP244842HPS	ARYB244842HPS	HPL Top, PVC Edge Band	42" x 48" x 24"	90	\$1,202
\\ u	ARYP246042HPS	ARYB246042HPS	HPL Top, PVC Edge Band	42" x 60" x 24"	101	\$1,265
0	ARYP247242HPS	ARYB247242HPS	HPL Top, PVC Edge Band	42" x 72" x 24"	115	\$1,371
U	ARYP249042HPS	ARYB249042HPS	HPL Top, PVC Edge Band	42" x 90" x 24"	125	\$1,505

with Path Legs

Please specify Laminate Color (Tables 2 and 4), Edge Band Color (Table 4) and Metal Leg Color (Table 3).

Details can be found on pages GEN 4 and GEN 5.

**Note:** Edge Band Color does NOT have to match Laminate Color.



**-ARY 12-** F11-1-19G-ARY

## The mTable<sup>TM</sup> Collection

### **General Specifications**

#### **TABLETOP**

Tabletop is 1-3/16" thick, 9-ply solid hardwood plywood or 3-ply 45# density particleboard, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Edges are solid Northern-grown Red Oak or maple. Top receives an external solid drop edge Northern-grown Red Oak or maple band 5/8" x 1-5/8" thick, radiused to form a bullnose.

#### APRON (Optional)

A 1-3/4" W x 25/32" Northern-grown Red Oak or maple apron is fitted between the legs and behind the extended tabletop edge band. A 1/4" styling line, routed into the apron, highlights the tabletop and legs. The bottom edge and both ends of each apron receive a 1/2" radius. Aprons are attached to the table using wood cleats screwed to the underside of the tabletop. Aprons on round tables go straight between the legs.

#### **LEGS**


Legs are 2-3/8" round steel tubing with a wall thickness not less than .64". Legs are finished with electrostatically applied epoxy powder paint. Legs are supplied with a standard glide insert. Lockable caster inserts interchange with the glide insert on any leg. Table legs are attached to the tabletop by means of a flange welded to the leg tube. The attachment flange is 4-5/8" in diameter formed and welded on two sides. The leg flange is attached to the tabletop by six (6) 1/4"-20 x 1" bolts engaging 1/4" internally and externally threaded bushings embedded in the underside of the tabletop.

#### CASTERS (Optional)


When specified, a three-inch black nylon hooded twin-wheel caster with a brake is supplied. Lockable caster inserts interchange with the glide insert on any leg. Add one caster per table leg (sold each).

#### TABLETOP SUPPORT


For maximum rigidity, rectangular tables 60" wide or more receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 90" or wider receive two extra legs located under the center of the table to provide added support.



MT Series Drop Edge



mTable Leg Detail



MT-109-S00 OAK MT-109-S02 OAK MT-109	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price	
MT-Y09-S00 OAK MT-Y09-S02 OAK busenile Table	Round Oak Tabl	<u>'e</u>						Round Table
MT-J09-S00 OAK MT-J29-S00 AM M	MT-109-S00 OAK	MT-109-S02 OAK	Adult Table	29"H x 36" Diameter	100	\$1,866	\$1,640	
MT-129-S00 OAK MT-129-S02 OAK MT-129	MT-Y09-S00 OAK	MT-Y09-S02 OAK	Youth Table	27-1/2"H x 36" Diameter	100	\$1,866	\$1,640	
MT-Y29-S00 OAK	MT-J09-S00 OAK	MT-J09-S02 OAK	Juvenile Table	25"H x 36" Diameter	100	\$1,866	\$1,640	
MT-Y29-S00 OAK	MT-129-S00 OAK	MT-129-S02 OAK	Adult Table	29"H x 42" Diameter	110	\$1.998	\$1.771	
MT-129-S00 OAK MT-141-S02 OAK MT-141-S00 OAK MT-141-S02 OAK MT-141								
MIT-V41-SOO OAK	MT-J29-S00 OAK	MT-J29-S02 OAK	Juvenile Table	25"H x 42" Diameter	110			
MIT-V41-SQO OAK	MT-141-S00 OAK	MT-141-S02 OAK	Adult Table	29"H x 48" Diameter	120	\$1,998	\$1,771	
### MT-109-S00 MAP MT-109-S02 MAP Vouth Table	MT-Y41-S00 OAK	MT-Y41-S02 OAK	Youth Table	27-1/2"H x 48" Diameter	120	-	\$1,771	
MT-109-S00 MAP MT-90-S02 MAP MT-90-S02 MAP MT-90-S02 MAP Wouth Table 27-1/2"H x36" Diameter 100 \$2,034 \$1,788 MT-90-S00 MAP MT-90-S02 MAP WT-90-S02 MAP MT-90-S02 MAP MT-90-S02 MAP MT-90-S00 MAP MT-90-S02 MAP MT-90-S02 MAP MT-90-S00 MAP MT-9	MT-J41-S00 OAK	MT-J41-S02 OAK	Juvenile Table	25"H x 48" Diameter	120	\$1,998	\$1,771	
MT-YO9-S00 MAP MT-YO9-S02 MAP Juvenile Table Juvenile Table 27-1/2"Hx 36" Diameter 100 \$2,034 \$1,788 MT-19-S00 MAP MT-19-S02 MAP Juvenile Table 25"Hx 36" Diameter 100 \$2,034 \$1,788 MT-19-S00 MAP MT-19-S02 MAP Adult Table 29"Hx 42" Diameter 110 \$2,178 \$1,931 MT-19-S00 MAP MT-19-S02 MAP Juvenile Table 25"Hx 42" Diameter 110 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Adult Table 25"Hx 42" Diameter 110 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Adult Table 27-1/2"Hx 42" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 42" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 48" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 48" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25" X30" X30" 110 \$1,647 \$1,405 MT-191-S00 OAK MT-191-S02 OAK MT-191-S02 OAK Juvenile Table 25" X30" X30" 110 \$1,647 \$1,405 MT-191-S00 OAK MT-191-S02 OAK MT-191-S02 OAK MT-191-S02 OAK MT-191-S02 OAK MT-191-S00 OAK MT-191-S02 MAP MT-191-S02	Round Maple Ta	<u>able</u>						
MT-J09-S00 MAP MT-J09-S02 MAP Juvenile Table 25"Hx 36" Diameter 100 \$2,034 \$1,788 MT-J29-S00 MAP MT-J29-S02 MAP Juvenile Table 29"Hx 42" Diameter 110 \$2,178 \$1,931 MT-J29-S00 MAP MT-J29-S02 MAP Juvenile Table 27-1/2"Hx 42" Diameter 110 \$2,178 \$1,931 MT-J29-S00 MAP Juvenile Table 27-1/2"Hx 42" Diameter 110 \$2,178 \$1,931 MT-J41-S00 MAP MT-J29-S00 MAP Juvenile Table 27-1/2"Hx 48" Diameter 110 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 29"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,931 MT-J41-S00 MAP MT-J41-S02 MAP Juvenile Table 27-1/2"Hx 48" Diameter 120 \$2,178 \$1,405 MT-J91-S00 QAK MT-J91-S02 QAK Juvenile Table 27-1/2"X42" X30" X30" 110 \$1,647 \$1,405 MT-J91-S00 QAK MT-J37-S02 QAK Juvenile Table 25" X42" X42" 110 \$1,778 \$1,537 MT-J37-S00 QAK MT-J37-S02 QAK Juvenile Table 27-1/2" X42" X42" 110 \$1,778 \$1,537 MT-J37-S00 QAK MT-J37-S02 QAK Juvenile Table 27-1/2" X48" X48" 110 \$1,925 \$1,684 MT-J54-S02 QAK MT-J54-S02 QAK Juvenile Table 27-1/2" X48" X48" 110 \$1,925 \$1,684 MT-J54-S02 QAK MT-J54-S02 QAK MT-J54-S02 QAM MT-J54-S02 MAP MT-J91-S02	MT-109-S00 MAP	MT-109-S02 MAP	Adult Table	29"H x 36" Diameter	100	\$2,034	\$1,788	
MT-129-S00 MAP MT-129-S02 MAP Adult Table 29"Hx 42" Diameter 110 \$2,178 \$1,931 MT-129-S00 MAP MT-129-S02 MAP Juvenile Table 25"Hx 42" Diameter 110 \$2,178 \$1,931 MT-129-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 42" Diameter 110 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Adult Table 29"Hx 48" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 48" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 48" Diameter 120 \$2,178 \$1,931 MT-141-S00 MAP MT-141-S02 MAP Juvenile Table 25"Hx 48" Diameter 120 \$2,178 \$1,931 MT-191-S00 OAK MT-191-S02 MAP Juvenile Table 29" x80" x30" 110 \$1,795 \$1,532 MT-191-S00 MAP MT-191-S02 MAP MT-191-S02 MAP Juvenile Table 29" x42" x42" 110 \$1,939 \$1,675 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 29" x42" x42" 110 \$1,939 \$1,675 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 29" x48" x48" 110 \$1,939 \$1,675 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 29" x48" x48" 110 \$1,939 \$1,675 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 29" x48" x48" 110 \$1,939 \$1,675 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 27-1/2" x48" x48" 110 \$1,939 \$1,675 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 27-1/2" x48" x48" 110 \$1,939 \$1,675	MT-Y09-S00 MAP	MT-Y09-S02 MAP	Youth Table	27-1/2"H x 36" Diameter	100	-	\$1,788	
MT-Y29-S00 MAP MT-Y29-S02 MAP Junchi Table Z5"H x 42" Diameter 110 \$2,178 \$1,931	MT-J09-S00 MAP	MT-J09-S02 MAP	Juvenile Table	25"H x 36" Diameter	100		\$1,788	
MT-Y29-S00 MAP MT-Y29-S02 MAP Junenile Table 27-1/2"Hx 42" Diameter 110 \$2,178 \$1,931 MT-19-S00 MAP MT-19-S02 MAP	MT-129-S00 MAP	MT-129-S02 MAP	Adult Table	29"H x 42" Diameter	110	\$2,178	\$1,931	
MT-141-S00 MAP MT-141-S02 MAP MT-141	MT-Y29-S00 MAP	MT-Y29-S02 MAP	Youth Table	27-1/2"H x 42" Diameter	110	\$2,178	\$1,931	
MT-Y41-S00 MAP MT-J41-S02 MAP MT-J41	MT-J29-S00 MAP	MT-J29-S02 MAP	Juvenile Table	25"H x 42" Diameter	110	\$2,178	\$1,931	
MT-Y41-S00 MAP MT-Y41-S02 MAP MT-J41-S02 MAR MT-J41	MT-141-S00 MAP	MT-141-S02 MAP	Adult Table	29"H x 48" Diameter	120	\$2,178	\$1,931	
Square Oak Table	MT-Y41-S00 MAP	MT-Y41-S02 MAP	Youth Table	27-1/2"H x 48" Diameter	120		•	
MT-191-S00 OAK MT-191-S02 OAK Adult Table 29"x30"x30" 110 \$1,647 \$1,405 MT-191-S00 OAK MT-191-S02 OAK Youth Table 27-1/2"x30"x30" 110 \$1,647 \$1,405 MT-191-S00 OAK MT-191-S02 OAK Juvenile Table 25"x30"x30" 110 \$1,647 \$1,405 MT-191-S00 OAK MT-191-S02 OAK Adult Table 29"x42"x42" 110 \$1,778 \$1,537 MT-137-S00 OAK MT-137-S02 OAK Juvenile Table 27-1/2"x42"x42" 110 \$1,778 \$1,537 MT-137-S00 OAK MT-137-S02 OAK Juvenile Table 27-1/2"x42"x42" 110 \$1,778 \$1,537 MT-154-S00 OAK MT-154-S02 OAK Adult Table 29"x42"x42" 110 \$1,778 \$1,537 MT-154-S00 OAK MT-154-S02 OAK Juvenile Table 29"x48"x48" 110 \$1,925 \$1,684 MT-154-S02 OAK MT-154-S02 OAK Juvenile Table 25"x48"x48" 110 \$1,925 \$1,684 MT-154-S02 OAK MT-154-S02 OAK Juvenile Table 25"x48"x48" 110 \$1,925 \$1,684 MT-154-S02 OAK MT-154-S02 OAK MT-154-S02 OAK Juvenile Table 29"x30"x30" 110 \$1,795 \$1,532 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-191-S00 MAP MT-191-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-137-S00 MAP MT-137-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-137-S00 MAP MT-137-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-137-S00 MAP MT-154-S02 MAP Juvenile Table 27-1/2"x42"x42" 110 \$1,939 \$1,675 MT-154-S00 MAP MT-154-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-154-S00 MAP MT-154-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-154-S00 MAP MT-154-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-154-S00 MAP MT-154-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-154-S00 MAP MT-154-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-154-S00 MAP MT-154-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835	MT-J41-S00 MAP	MT-J41-S02 MAP	Juvenile Table	25"H x 48" Diameter	120	\$2,178	\$1,931	
MT-191-S00 OAK MT-191-S02 OAK Adult Table 29"x30"x30" 110 \$1,647 \$1,405 MT-Y91-S00 OAK MT-Y91-S02 OAK Youth Table 27-1/2"x30"x30" 110 \$1,647 \$1,405 MT-J91-S00 OAK MT-J91-S02 OAK Adult Table 25"x30"x30" 110 \$1,647 \$1,405 MT-J91-S00 OAK MT-J91-S02 OAK Adult Table 25"x30"x30" 110 \$1,778 \$1,537 MT-J37-S00 OAK MT-J37-S02 OAK Adult Table 27-1/2"x42"x42" 110 \$1,778 \$1,537 MT-J37-S00 OAK MT-J37-S02 OAK Adult Table 27-1/2"x42"x42" 110 \$1,778 \$1,537 MT-J37-S00 OAK MT-J37-S02 OAK Adult Table 27-1/2"x42"x42" 110 \$1,778 \$1,537 MT-J37-S00 OAK MT-J54-S02 OAK Adult Table 29"x48"x48" 110 \$1,925 \$1,684 MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 27-1/2"x48"x48" 110 \$1,925 \$1,684 MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 25"x48"x48" 110 \$1,925 \$1,684 MT-J91-S00 MAP MT-J91-S02 MAP Youth Table 27-1/2"x30"x30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25"x30"x30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J54-S02 MAP Juvenile Table 25"x42"x42" 110 \$1,939 \$1,675 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25"x48"x48" 110 \$2,099 \$1,835								
MT-Y91-S00 OAK MT-J91-S02 OAK MT-J91-S02 OAK MT-J91-S02 OAK MT-J91-S00 OAK MT-J91-S00 OAK MT-J91-S02 MAP MT-J91	Square Oak Tab	<u>le</u>						Square Table
MT-J91-S00 OAK MT-J91-S02 OAK Juvenile Table 25" x 30" x 30" 110 \$1,647 \$1,405 MT-137-S00 OAK MT-137-S02 OAK Adult Table 29" x 42" x 42" 110 \$1,778 \$1,537 MT-J37-S00 OAK MT-J37-S02 OAK Juvenile Table 25" x 42" x 42" 110 \$1,778 \$1,537 MT-J37-S00 OAK MT-J37-S02 OAK Juvenile Table 25" x 42" x 42" 110 \$1,778 \$1,537 MT-J54-S00 OAK MT-J54-S02 OAK Adult Table 29" x 48" x 48" 110 \$1,925 \$1,684 MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 25" x 48" x 48" 110 \$1,925 \$1,684 MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 25" x 48" x 48" 110 \$1,925 \$1,684 MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 25" x 48" x 48" 110 \$1,925 \$1,684 MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 29" x 30" x 30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25" x 30" x 30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 30" x 30" 110 \$1,795 \$1,532 MT-J37-S00 MAP MT-J37-S02 MAP MT-J37-S02 MAP Juvenile Table 29" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 27-1/2" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 27-1/2" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J54-S02 MAP Juvenile Table 27-1/2" x 42" x 42" 110 \$1,939 \$1,675 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 27-1/2" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 2								
MT-137-S00 OAK MT-137-S02 OAK Adult Table 29" x 42" x 42" 110 \$1,778 \$1,537 MT-137-S00 OAK MT-137-S02 OAK Youth Table 25" x 42" x 42" 110 \$1,778 \$1,537 MT-154-S00 OAK MT-154-S02 OAK Juvenile Table 25" x 42" x 42" 110 \$1,778 \$1,537 MT-154-S00 OAK MT-154-S02 OAK Adult Table 29" x 48" x 48" 110 \$1,925 \$1,684 MT-154-S00 OAK MT-154-S02 OAK								
MT-Y37-S00 OAK MT-Y37-S02 MAP MT-Y37	M1-J91-S00 OAK	M1-J91-S02 OAK	Juvenile l'able	25" x 30" x 30"	110	\$1,647	\$1,405	
MT-J37-S00 OAK MT-J37-S02 OAK Juvenile Table 25" x 42" x 42" 110 \$1,778 \$1,537 MT-154-S00 OAK MT-154-S02 OAK MT-154-S02 OAK MT-Y54-S00 MAP MT								
MT-154-S00 OAK MT-154-S02 OAK MT-154-S02 OAK MT-Y54-S02 OAK MT-Y54-S02 OAK MT-Y54-S00 OAK MT-Y54-S02 MAP MT-Y54								
MT-Y54-S00 OAK MT-Y54-S02 OAK Youth Table 27-1/2" x 48" x 48" 110 \$1,925 \$1,684  MT-J54-S00 OAK MT-J54-S02 OAK Juvenile Table 25" x 48" x 48" 110 \$1,925 \$1,684   Square Maple Table  MT-191-S02 MAP MT-191-S02 MAP Adult Table 29" x 30" x 30" 110 \$1,795 \$1,532 MT-Y91-S00 MAP MT-Y91-S02 MAP Juvenile Table 25" x 30" x 30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25" x 30" x 30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-137-S02 MAP Adult Table 29" x 42" x 42" 110 \$1,795 \$1,532 MT-Y37-S00 MAP MT-Y37-S02 MAP Youth Table 27-1/2" x 42" x 42" 110 \$1,939 \$1,675 MT-Y37-S00 MAP MT-Y37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 29" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835	WII-J37-S00 OAK	WII-J37-SU2 UAK	Juvenile lable	25" X 42" X 42"	110	\$1,778	\$1,537	
MT-J54-S00 OAK         MT-J54-S02 OAK         Juvenile Table         25" x 48" x 48"         110         \$1,925         \$1,684           Square Maple Table         MT-191-S00 MAP         MT-191-S02 MAP         Adult Table         29" x 30" x 30"         110         \$1,795         \$1,532           MT-Y91-S00 MAP         MT-Y91-S02 MAP         Youth Table         27-1/2" x 30" x 30"         110         \$1,795         \$1,532           MT-J91-S00 MAP         MT-J91-S02 MAP         Juvenile Table         25" x 30" x 30"         110         \$1,795         \$1,532           MT-137-S00 MAP         MT-J37-S02 MAP         Adult Table         29" x 42" x 42"         110         \$1,939         \$1,675           MT-Y37-S00 MAP         MT-Y37-S02 MAP         Youth Table         27-1/2" x 42" x 42"         110         \$1,939         \$1,675           MT-J37-S00 MAP         MT-J37-S02 MAP         Juvenile Table         25" x 42" x 42"         110         \$1,939         \$1,675           MT-154-S00 MAP         MT-154-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S02 MAP         Juven						-	•	
Square Maple Table           MT-191-S00 MAP         MT-191-S02 MAP         Adult Table         29" x 30" x 30"         110         \$1,795         \$1,532           MT-Y91-S00 MAP         MT-Y91-S02 MAP         Youth Table         27-1/2" x 30" x 30"         110         \$1,795         \$1,532           MT-J91-S00 MAP         MT-J91-S02 MAP         Juvenile Table         25" x 30" x 30"         110         \$1,795         \$1,532           MT-137-S00 MAP         MT-137-S02 MAP         Adult Table         29" x 42" x 42"         110         \$1,939         \$1,675           MT-Y37-S00 MAP         MT-Y37-S02 MAP         Youth Table         27-1/2" x 42" x 42"         110         \$1,939         \$1,675           MT-J37-S00 MAP         MT-J37-S02 MAP         Juvenile Table         25" x 42" x 42"         110         \$1,939         \$1,675           MT-154-S00 MAP         MT-154-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-Y54-S00 MAP         MT-Y54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog N								
MT-191-S00 MAP MT-191-S02 MAP Adult Table 29" x 30" x 30" 110 \$1,795 \$1,532 MT-Y91-S00 MAP MT-Y91-S02 MAP Youth Table 27-1/2" x 30" x 30" 110 \$1,795 \$1,532 MT-J91-S00 MAP MT-J91-S02 MAP Juvenile Table 25" x 30" x 30" 110 \$1,795 \$1,532 MT-J37-S00 MAP MT-137-S02 MAP Adult Table 29" x 42" x 42" 110 \$1,939 \$1,675 MT-Y37-S00 MAP MT-Y37-S02 MAP Youth Table 27-1/2" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-T54-S00 MAP MT-T54-S02 MAP Adult Table 29" x 48" x 48" 110 \$2,099 \$1,835 MT-Y54-S00 MAP MT-Y54-S02 MAP Youth Table 27-1/2" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835	MT-J54-S00 OAK	MT-J54-S02 OAK	Juvenile Table	25" x 48" x 48"	110	\$1,925	\$1,684	
MT-Y91-S00 MAP         MT-Y91-S02 MAP         Youth Table         27-1/2" x 30" x 30"         110         \$1,795         \$1,532           MT-J91-S00 MAP         MT-J91-S02 MAP         Juvenile Table         25" x 30" x 30"         110         \$1,795         \$1,532           MT-137-S00 MAP         MT-137-S02 MAP         Adult Table         29" x 42" x 42"         110         \$1,939         \$1,675           MT-Y37-S00 MAP         MT-Y37-S02 MAP         Youth Table         27-1/2" x 42" x 42"         110         \$1,939         \$1,675           MT-J37-S00 MAP         MT-J37-S02 MAP         Juvenile Table         25" x 42" x 42"         110         \$1,939         \$1,675           MT-J54-S00 MAP         MT-J54-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price	Square Maple T	able						
MT-J91-S00 MAP         MT-J91-S02 MAP         Juvenile Table         25" x 30" x 30"         110         \$1,795         \$1,532           MT-137-S00 MAP         MT-137-S02 MAP         Adult Table         29" x 42" x 42"         110         \$1,939         \$1,675           MT-Y37-S00 MAP         MT-Y37-S02 MAP         Youth Table         27-1/2" x 42" x 42"         110         \$1,939         \$1,675           MT-J37-S00 MAP         MT-J37-S02 MAP         Juvenile Table         25" x 42" x 42"         110         \$1,939         \$1,675           MT-154-S00 MAP         MT-154-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-Y54-S00 MAP         MT-Y54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price	MT-191-S00 MAP	MT-191-S02 MAP	Adult Table	29" x 30" x 30"	110	\$1,795	\$1,532	
MT-137-S00 MAP MT-137-S02 MAP Adult Table 29" x 42" x 42" 110 \$1,939 \$1,675 MT-Y37-S00 MAP MT-Y37-S02 MAP Youth Table 27-1/2" x 42" x 42" 110 \$1,939 \$1,675 MT-J37-S00 MAP MT-J37-S02 MAP Juvenile Table 25" x 42" x 42" 110 \$1,939 \$1,675 MT-154-S00 MAP MT-154-S02 MAP Adult Table 29" x 48" x 48" 110 \$2,099 \$1,835 MT-Y54-S00 MAP MT-Y54-S02 MAP Youth Table 27-1/2" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835 MT-J54-S00 MAP MT-J54-S02 MAP Juvenile Table 25" x 48" x 48" 110 \$2,099 \$1,835								
MT-Y37-S00 MAP         MT-Y37-S02 MAP         Youth Table         27-1/2" x 42" x 42"         110         \$1,939         \$1,675           MT-J37-S00 MAP         MT-J37-S02 MAP         Juvenile Table         25" x 42" x 42"         110         \$1,939         \$1,675           MT-154-S00 MAP         MT-J54-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-Y54-S00 MAP         MT-Y54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price	MT-J91-S00 MAP	MT-J91-S02 MAP	Juvenile Table	25" x 30" x 30"	110	\$1,795	\$1,532	
MT-J37-S00 MAP         MT-J37-S02 MAP         Juvenile Table         25" x 42" x 42"         110         \$1,939         \$1,675           MT-154-S00 MAP         MT-154-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-Y54-S00 MAP         MT-Y54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price	MT-137-S00 MAP	MT-137-S02 MAP	Adult Table	29" x 42" x 42"	110	\$1,939	\$1,675	
MT-154-S00 MAP         MT-154-S02 MAP         Adult Table         29" x 48" x 48"         110         \$2,099         \$1,835           MT-Y54-S00 MAP         MT-Y54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price		MT-Y37-S02 MAP					•	
MT-Y54-S00 MAP         MT-Y54-S02 MAP         Youth Table         27-1/2" x 48" x 48"         110         \$2,099         \$1,835           MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price	MT-J37-S00 MAP	MT-J37-S02 MAP	Juvenile Table	25" x 42" x 42"	110	\$1,939	\$1,675	
MT-J54-S00 MAP         MT-J54-S02 MAP         Juvenile Table         25" x 48" x 48"         110         \$2,099         \$1,835           Catalog No.         Description         Price	MT-154-S00 MAP	MT-154-S02 MAP	Adult Table	29" x 48" x 48"	110	\$2,099	\$1,835	
Catalog No. Description Price	MT-Y54-S00 MAP	MT-Y54-S02 MAP	Youth Table				· ·	
	MT-J54-S00 MAP	MT-J54-S02 MAP	Juvenile Table	25" x 48" x 48"	110	\$2,099	\$1,835	
ANT CASTED. Control of the state of the stat	Catalog No.	Description					Price	
•	MT-CASTER		,				\$28	Casters
3-inch black nylon hooded twin-wheel caster with a brake.  Add one caster per table leg (sold each).		-		ter with a brake.				

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: Optional Wood Aprons for Tables are located on page MTA 6.

	Plywood Core Catalog No.	Particleboard Core Catalog No.	Description	HxWxD	Wt. (lbs.)	Plywood Core Price	Particleboard Core Price
Four-Reader	Four-Reader Re	ctangular Oak Ta	<u>ble</u>				
Rectrangular Table	MT-194-S00 OAK	MT-194-S02 OAK	Adult Table	29" x 60" x 30"	120	\$1,664	\$1,442
	MT-Y94-S00 OAK	MT-Y94-S02 OAK	Youth Table	27-1/2" x 60" x 30"	120	\$1,664	\$1,442
	MT-J94-S00 OAK	MT-J94-S02 OAK	Juvenile Table	25" x 60" x 30"	120	\$1,664	\$1,442
	MT-195-S00 OAK	MT-195-S02 OAK	Adult Table	29" x 72" x 30"	140	\$1,844	\$1,603
	MT-Y95-S00 OAK	MT-Y95-S02 OAK	Youth Table	27-1/2" x 72" x 30"	140	\$1,844	\$1,603
	MT-J95-S00 OAK	MT-J95-S02 OAK	Juvenile Table	25" x 72" x 30"	140	\$1,844	\$1,603
	Four-Reader Re	ctangular Maple	Table				
	MT-194-S00 MAP	MT-194-S02 MAP	Adult Table	29" x 60" x 30"	120	\$1,813	\$1,572
	MT-Y94-S00 MAP	MT-Y94-S02 MAP	Youth Table	27-1/2" x 60" x 30"	120	\$1,813	\$1,572
	MT-J94-S00 MAP	MT-J94-S02 MAP	Juvenile Table	25" x 60" x 30"	120	\$1,813	\$1,572
	MT-195-S00 MAP	MT-195-S02 MAP	Adult Table	29" x 72" x 30"	140	\$2,011	\$1,747
	MT-Y95-S00 MAP	MT-Y95-S02 MAP	Youth Table	27-1/2" x 72" x 30"	140	\$2,011	\$1,747
	MT-J95-S00 MAP	MT-J95-S02 MAP	Juvenile Table	25" x 72" x 30"	140	\$2,011	\$1,747
	Siv.Paadar Pac	tangular Oak Tabi	le.				
Rectrangular Table	MT-144-S00 OAK	MT-144-S02 OAK	Adult Table	29" x 60" x 36"	120	\$1,752	\$1,530
3	MT-Y44-S00 OAK	MT-Y44-S02 OAK	Youth Table	27-1/2" x 60" x 36"	120	\$1,752 \$1,752	\$1,530 \$1,530
	MT-J44-S00 OAK	MT-J44-S02 OAK	Juvenile Table	25" x 60" x 36"	120	\$1,752 \$1,752	\$1,530 \$1,530
	MT-138-S00 OAK	MT-138-S02 OAK	Adult Table	29" x 72" x 36"	140	\$1,932	\$1,691
	MT-Y38-S00 OAK	MT-Y38-S02 OAK	Youth Table	27-1/2" x 72" x 36"	140	\$1,932	\$1,691
•	MT-J38-S00 OAK	MT-J38-S02 OAK	Juvenile Table	25" x 72" x 36"	140	\$1,932	\$1,691
*	MT-145-S00 OAK	MT-145-S02 OAK	Adult Table	29" x 72" x 48"	170	\$2,108	\$1,881
	MT-Y45-S00 OAK	MT-Y45-S02 OAK	Youth Table	27-1/2" x 72" x 48"	170	\$2,108	\$1,881
	MT-J45-S00 OAK	MT-J45-S02 OAK	Juvenile Table	25" x 72" x 48"	170	\$2,108	\$1,881
	Six-Reader Rec	tangular Maple Ta	able				
	MT-144-S00 MAP	MT-144-S02 MAP	Adult Table	29" x 60" x 36"	120	\$1,909	\$1,667
	MT-Y44-S00 MAP	MT-Y44-S02 MAP	Youth Table	27-1/2" x 60" x 36"	120	\$1,909	\$1,667
						÷ -,, · • ·	,

Catalog No. Description Price

Juvenile Table

Adult Table

Youth Table

Adult Table

Youth Table

Juvenile Table

Juvenile Table

MT-J44-S02 MAP

MT-138-S02 MAP

MT-Y38-S02 MAP

MT-J38-S02 MAP

MT-145-S02 MAP

MT-Y45-S02 MAP

MT-J45-S02 MAP

25" x 60" x 36"

29" x 72" x 36"

27-1/2" x 72" x 36"

25" x 72" x 36"

29" x 72" x 48"

27-1/2" x 72" x 48"

25" x 72" x 48"

120

140

140

140

170

170

170

\$1,909

\$2,106

\$2,106

\$2,106

\$2,298

\$2,298

\$2,298

\$1,667

\$1,843

\$1,843

\$1,843 \$2,051

\$2,051

\$2,051

\$28



Casters

MT-J44-S00 MAP

MT-138-S00 MAP

MT-Y38-S00 MAP

MT-J38-S00 MAP

MT-145-S00 MAP

MT-Y45-S00 MAP

MT-J45-S00 MAP

MT-CASTER

Caster add-on to make any table mobile.

3-inch black nylon hooded twin-wheel caster with a brake.

Add one caster per table leg (sold each).

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: Optional Wood Aprons for Tables are located on page MTA 6.

	rticleboard Core Price	Plywood Core Pa Price	Wt. (lbs.)	HxWxD	Description	Particleboard Core Catalog No.	Plywood Core Catalog No.
Rectangular Table wit				<u>egs</u>	er Support Le	k Table with Cento	Rectangular Oa
Center Support Leg	\$2,181	\$2,517	165	29" x 90" x 30"	Adult Table	MT-198-S02 OAK	VIT-198-S00 OAK
	\$2,181	\$2,517	165	27-1/2" x 90" x 30"	Youth Table	MT-Y98-S02 OAK	MT-Y98-S00 OAK
	\$2,181	\$2,517	165	25" x 90" x 30"	Juvenile Table	MT-J98-S02 OAK	VIT-J98-S00 OAK
	\$2,269	\$2,606	165	29" x 90" x 36"	Adult Table	MT-146-S02 OAK	VIT-146-S00 OAK
	\$2,269	\$2,606	165	27-1/2" x 90" x 36"	Youth Table	MT-Y46-S02 OAK	MT-Y46-S00 OAK
•	\$2,269	\$2,606	165	25" x 90" x 36"	Juvenile Table	MT-J46-S02 OAK	VIT-J46-S00 OAK
	\$2,423	\$2,781	185	29" x 90" x 48"	Adult Table	MT-134-S02 OAK	VIT-134-S00 OAK
	\$2,423	\$2,781	185	27-1/2" x 90" x 48"	Youth Table	MT-Y34-S02 OAK	VIT-Y34S00 OAK
	\$2,423	\$2,781	185	25" x 90" x 48"	Juvenile Table	MT-J34-S02 OAK	MT-J34-S00 OAK
				<u>Legs</u>	nter Support	ple Table with Ce	Rectangular Ma
	\$2,377	\$2,744	165	29" x 90" x 30"	Adult Table	MT-198-S02 MAP	MT-198-S00 MAP
	\$2,377	\$2,744	165	27-1/2" x 90" x 30"	Youth Table	MT-Y98-S02 MAP	MT-Y98-S00 MAP
	\$2,377	\$2,744	165	25" x 90" x 30"	Juvenile Table	MT-J98-S02 MAP	MT-J98-S00 MAP
	\$2,473	\$2,841	165	29" x 90" x 36"	Adult Table	MT-146-S02 MAP	MT-146-S00 MAP
	\$2,473	\$2,841	165	27-1/2" x 90" x 36"	Youth Table	MT-Y46-S02 MAP	MT-Y46-S00 MAP
	\$2,473	\$2,841	165	25" x 90" x 36"	Juvenile Table	MT-J46-S02 MAP	MT-J46-S00 MAP
	\$2,641	\$3,032	185	29" x 90" x 48"	Adult Table	MT-134-S02 MAP	MT-134-S00 MAP
	\$2,641	\$3,032	185	27-1/2" x 90" x 48"	Youth Table	MT-Y34-S02 MAP	MT-Y34S00 MAP
	\$2,641	\$3,032	185	25" x 90" x 48"	Juvenile Table	MT-J34-S02 MAP	MT-J34-S00 MAP

Catalog No.	Description	Price	
MT-CASTER	Caster add-on to make any table mobile.	\$28	Casters

3-inch black nylon hooded twin-wheel caster with a brake. Add one caster per table leg (sold each).



Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: Optional Wood Aprons for Tables are located on page MTA 6.

## **Optional Wood Apron for Reading Tables**

Note: A 1-3/4" W x 25/32" Northern-grown Red Oak or maple apron is fitted between the legs and behind the extended tabletop edge band. A 1/4" styling line, routed into the apron, highlights the tabletop and legs. The bottom edge and both ends of each apron receive a 1/2" radius. Aprons are attached to the table using wood cleats screwed to the underside of the tabletop. Aprons on round tables go straight between the legs.

0ak	Maple		Wt.	0ak	Maple
Catalog No.	Catalog No.	Description	(lbs.)	Price	Price
109-AK-S00 OAK	109-AK-S00 MAP	For 36" Diameter Table	5	\$208	\$228
129-AK-S00 OAK	129-AK-S00 MAP	For 42" Diameter Table	5	\$208	\$228
141-AK-S00 OAK	141-AK-S00 MAP	For 48" Diameter Table	5	\$215	\$234
191-AK-S00 OAK	191-AK-S00 MAP	For 30" Square Table	5	\$146	\$159
137-AK-S00 OAK	137-AK-S00 MAP	For 42" Square Table	5	\$155	\$168
154-AK-S00 OAK	154-AK-S00 MAP	For 48" Square Table	5	\$170	\$185
194-AK-S00 OAK	194-AK-S00 MAP	For 30" x 60" Table	5	\$175	\$190
195-AK-S00 OAK	195-AK-S00 MAP	For 30" x 72" Table	5	\$190	\$207
198-AK-S00 OAK	198-AK-S00 MAP	For 30" x 90" Table	5	\$194	\$211
144-AK-S00 OAK	144-AK-S00 MAP	For 36" x 60" Table	8	\$181	\$197
138-AK-S00 OAK	138-AK-S00 MAP	For 36" x 72" Table	8	\$198	\$216
146-AK-S00 OAK	146-AK-S00 MAP	For 36" x 90" Table	10	\$198	\$216
145-AK-S00 OAK	145-AK-S00 MAP	For 48" x 72" Table	10	\$208	\$228
134-AK-S00 OAK	134-AK-S00 MAP	For 48" x 90" Table	12	\$215	\$234

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

## **General Specifications**

#### **TABLETOPS**

Tabletop is 1-3/16" thick, 3-ply 45# density particle board, with a high-pressure laminate top surface .050" thick and a backing sheet .020" thick for balanced construction. Edges are solid Northern-grown Red Oak or maple. Top receives an external solid drop edge Northern-grown Red Oak or maple band 5/8" x 1-5/8" thick, radiused to form a bullnose.

Note: Standing Height Tables are Apron construction.

#### **TABLE SUPPORT**

For maximum rigidity, rectangular tables 60" or more wide receive a V-shaped, 14-gauge steel keel securely fastened to the underside of the tabletop. Tables 48"D and more than 60"W, receive two steel keels parallel to the length of the table. Tables 72" or wider receive two extra legs located under the center of the table to provide added support.

#### LFGS

Legs are 2-3/8" round steel tubing with a wall thickness not less than .64". Legs are finished with electrostatically applied epoxy-powder paint. Legs are supplied with a standard glide insert. Lockable caster inserts interchange with the glide insert on any leg. Table legs are attached to the tabletop by means of a flange welded to the leg tube. The attachment flange is 4-5/8" in diameter formed and welded on two sides. The leg flange is attached to the tabletop by six (6) 1/4" - 20 x 1" bolts engaging 1/4" internally and externally threaded bushings embedded in the underside of the tabletop.

#### **CASTER (OPTIONAL)**

When specified, a three-inch black nylon hooded twin-wheel caster with a brake is supplied. Lockable caster inserts interchange with the glide insert on any leg. Add one caster per table leg (sold each).

#### **PRIVACY PANEL**

Privacy panels are 10"H, constructed of 1" thick, 3-ply veneered particleboard. Exposed edges are banded with 1.6mm oak or maple edge bands. The privacy panel attaches securely to the tabletop by screws passing through the tabletop and into the privacy panels. The privacy panel is finished to match the table and designed to obscure wires exiting computer equipment, to eliminate incidental tampering and create defined patron space.


**Note**: 72"W and 90"W tables with privacy panels have additional legs for added support.

#### APRON (OPTIONAL)


A 1-3/4"W x 25/32" solid Northern-grown Red Oak or maple apron is fitted between the legs and behind the extended tabletop edge band. A 1/4" styling line, routed into the apron, highlights the tabletop and legs. The bottom edge and both ends of each apron receive a 1/2" radius. Aprons are attached to the table using wood cleats screwed to the underside of the tabletop. Aprons on round tables go straight between the legs.

#### **ELECTRICAL**


Each position on a Computer Table receives one 3" diameter grommet for wire passage and J-channel wire manager to hold excess wires. Grommets are ABS black plastic with notched removable cap. J-channel is 18-guage steel with electro-statically applied black powder paint and is mounted to the underside of the tabletop.



MT Series Drop Edge



mTable Leg Detail



	Oak Catalog No.	Maple Catalog No.	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
One Position Computer Tables	MT-645-S00 OAK	MT-645-S00 MAP	27-1/2" x 30" x 24"	80	\$1,434	\$1,563
	MT-665-S00 OAK	MT-665-S00 MAP	27-1/2" x 30" x 30"	80	\$1,524	\$1,661
Two Position Computer Tables	MT-649-S00 OAK	MT-649-S00 MAP	27-1/2" x 60" x 24"	110	\$2,049	\$2,233
	MT-669-S00 OAK	MT-669-S00 MAP	27-1/2" x 60" x 30"	110	\$2,196	\$2,394
One Position Computer Table with 10"H Privacy Panel	MT-643-S00 OAK	MT-643-S00 MAP	27-1/2" x 36" x 24"	70	\$1,786	\$1,948
	MT-663-S00 OAK	MT-663-S00 MAP	27-1/2" x 36" x 36"	80	\$1,932	\$2,107
Two Position Computer Table with 10"H Privacy Panel	MT-642-S00 OAK	MT-642-S00 MAP	27-1/2" x 72" x 24"	150	\$2,401	\$2,616
	MT-662-S00 OAK	MT-662-S00 MAP	27-1/2" x 72" x 36"	150	\$2,547	\$2,776
Three Position Computer Table with 10"H Privacy Panel	MT-644-S00 OAK	MT-644-S00 MAP	27-1/2" x 90" x 24"	180	\$3,272	\$3,566
	MT-664-S00 OAK	MT-664-S00 MAP	27-1/2" x 90" x 36"	170	\$3,418	\$3,726

Please specify Wood Finish (Table 1), High-Pressure Laminate (Table 2) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

**-MTA 8 -** F11-1-19G-MTA

## Mobile Tables

Mobile Tables Mobile Tables

### **General Specifications**

#### **TABLETOP**

Tabletop will be 1-3/16" thick, 3-ply 45# density particleboard, with .050" thick high-pressure laminate surface and .020" thick backing sheet for balanced construction. Edges will be flexible polyethylene tee mold, 5/16" thick x 1-1/4" wide. Core material receives a 5/64" x 3/8" route to receive tee mold. Tee mold is applied to core material after the laminate and backer sheet.

#### LEGS (WOOD)

Legs are 2-1/2" round solid Northern-grown red oak. Bottom edges of legs are radiused 1/8". Each leg has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of a counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to tabletops by means of a 5" square x 5/16" thick steel plate. The plate is attached to the leg by a 5/16" x 2-1/2" machine bolt engaging a 5/8" diameter barrel nut inserted into the leg. The steel plate is attached to the tabletop by five 5/16" x 1" machine bolts engaging internally and externally threaded bushings in the underside of the tabletop.

#### **CASTER (FOR WOOD LEG)**


When specified, a 3" black nylon hooded twin-wheel caster with a brake is supplied. Add one caster per table leg (sold each).

#### LEGS (METAL)


Legs will be 2-3/8" round steel tubing with a wall thickness not less than .64". Legs are supplied with a standard glide insert. Lockable caster inserts interchange with the glide insert on any leg. Table legs will be attached to the tabletop by means of a flange welded to the leg tube. The attachment flange will be 4-5/8" in diameter formed and welded on two sides. The leg flange is attached to the tabletop by six (6) 1/4"-20 x 1" bolts engaging 1/4" internal and external threaded bushings embedded in the underside of the tabletop. Legs will be finished with electrostatic applied epoxy powder-coat paint.


#### CASTER (FOR METAL LEG)

When specified, a 2-1/4" black nylon hooded twin-wheel caster with a brake is supplied. Lockable caster inserts interchange with the glide insert on any leg. Add one caster per table leg (sold each).



**Edge Detail** 





Note: Tables come equipped with two lockable casters, additional casters (below) can be ordered for other legs.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Wood Leg Price	Metal Leg Price	
60-768-M00	Adult Table	29" x 55-1/4" x 50"	110	\$884	\$884	Gumdrop Table
60-Y68-M00	Youth Table	27-1/2" x 55-1/4" x 50"	110	\$884	\$884	
60-J68-M00	Juvenile Table	25" x 55-1/4" x 50"	110	\$884	\$884	
60-799-M00	Adult Table	29" x 45" x 36"	105	\$981	\$981	Boat Table
60-Y99-M00	Youth Table	27-1/2" x 45" x 36"	105	\$981	\$981	
60-J99-M00	Juvenile Table	25" x 45" x 36"	105	\$981	\$981	
60-763-M00	Adult Table	29" x 45" x 39-3/4"	110	\$872	\$872	Triangular Table
						3
60-J63-M00	Juvenile Table	25" x 45" x 39-3/4"	110	\$872	\$872	
60-778-M00	Adult Table	29" x 53-5/8" x 51-3/8"	105	\$1,302	\$1,302	Pentagon Table
60-Y78-M00	Youth Table	27-1/2" x 53-5/8" x 51-3/8"	105	\$1,302	\$1,302	
60-J78-M00	Juvenile Table			\$1,302	\$1,302	
	60-768-M00 60-Y68-M00 60-J68-M00 60-799-M00 60-Y99-M00 60-J99-M00 60-Y63-M00 60-J63-M00 60-J63-M00 60-J63-M00	60-768-M00 Adult Table 60-Y68-M00 Youth Table 60-J68-M00 Juvenile Table 60-799-M00 Adult Table 60-Y99-M00 Youth Table 60-J99-M00 Juvenile Table 60-763-M00 Adult Table 60-Y63-M00 Youth Table 60-J63-M00 Juvenile Table 60-778-M00 Adult Table 700-778-M00 Youth Table 700-778-M00 Youth Table	60-768-M00	60-768-M00 Adult Table 29" x 55-1/4" x 50" 110 60-Y68-M00 Youth Table 27-1/2" x 55-1/4" x 50" 110 60-J68-M00 Juvenile Table 25" x 55-1/4" x 50" 110  60-799-M00 Adult Table 29" x 45" x 36" 105 60-Y99-M00 Youth Table 27-1/2" x 45" x 36" 105 60-J99-M00 Juvenile Table 25" x 45" x 36" 105  60-763-M00 Adult Table 29" x 45" x 39-3/4" 110 60-Y63-M00 Juvenile Table 27-1/2" x 45" x 39-3/4" 110 60-J63-M00 Juvenile Table 25" x 45" x 39-3/4" 110 60-J63-M00 Juvenile Table 25" x 45" x 39-3/4" 110	60-768-M00 Adult Table 29" x 45" x 36" 110 \$884 60-Y68-M00 Juvenile Table 27-1/2" x 55-1/4" x 50" 110 \$884 60-J68-M00 Juvenile Table 25" x 55-1/4" x 50" 110 \$884 60-J68-M00 Juvenile Table 25" x 55-1/4" x 50" 110 \$884 60-J68-M00 Juvenile Table 25" x 45" x 36" 105 \$981 60-Y99-M00 Youth Table 27-1/2" x 45" x 36" 105 \$981 60-J99-M00 Juvenile Table 25" x 45" x 36" 105 \$981 60-J99-M00 Juvenile Table 25" x 45" x 36" 105 \$981 60-J63-M00 Youth Table 27-1/2" x 45" x 39-3/4" 110 \$872 60-Y63-M00 Juvenile Table 25" x 45" x 39-3/4" 110 \$872 60-J63-M00 Juvenile Table 25" x 45" x 39-3/4" 110 \$873 60-J63-M00 Juvenile Table 25" x 45" x 39-3/4" 110 \$873 60-J63-M00 Juvenile Table 25" x 45" x 39-3/4" 110 \$873 60-J63-M00 Juvenile Table 25	60-768-M00 Adult Table 29" x 55-1/4" x 50" 110 \$884 \$884 60-768-M00 Youth Table 27-1/2" x 55-1/4" x 50" 110 \$884 \$884 60-768-M00 Juvenile Table 25" x 55-1/4" x 50" 110 \$884 \$884 60-768-M00 Juvenile Table 25" x 55-1/4" x 50" 110 \$884 \$884 \$884 \$884 \$884 \$884 \$884 \$88

Catalog No.	Description	Price		
MT-CASTER	Caster for Metal Leg	\$28		Casters
	2-1/4" black nylon hooded twin-wheel caster with a brake. Add one caster per table leg (sold each).			
LG-CST-S00	Caster for Wood Leg 3" black nylon hooded twin-wheel caster with a brake. Add one caster per table leg (sold each).	\$84		
	γ,		Metal Leg Caster	Wood Leg Caster

Please specify Laminate Color (Tables 2 and 4), T-Mold Color (Table 4), Leg Type (Oak or Metal) and Wood Leg Finish (Table 1) or Metal Leg Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: T-Mold Color does NOT have to match Laminate Color.

Mobile Tables

Note: Tables come equipped with two lockable casters, additional casters (below) can be ordered for other legs.

	Oak Wood Leg Catalog No.	Metal Leg Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Wood Leg Price	Metal Leg Price
Small Free Form Table	60-780-W00	60-780-M00	Adult Table	29" x 68-3/4" x 52-1/2"	100	\$1,101	\$1,101
	60-Y80-W00	60-Y80-M00	Youth Table	27-1/2" x 68-3/4" x 52-1/2"	100	\$1,101	\$1,101
	60-J80-W00	60-J80-M00	Juvenile Table	25" x 68-3/4" x 52-1/2"	100	\$1,101	\$1,101
Medium Free Form Table	60-774-W00	60-774-M00	Adult Table	29" x 75-1/2" x 64-7/8"	140	\$1,373	\$1,373
	60-Y74-W00	60-Y74-M00	Youth Table	27-1/2" x 75-1/2" x 64-7/8	140	\$1,373	\$1,373
	60-J74-W00	60-J74-M00	Juvenile Table	25" x 75-1/2" x 64-7/8	140	\$1,373	\$1,373
Large Free Form Table	60-776-W00	60-776-M00	Adult Table	29" x 85-1/2" x 53"	125	\$1,373	\$1,373
	60-Y76-W00	60-Y76-M00	Youth Table	27-1/2" x 85-1/2" x 53"	125	\$1,373	\$1,373
	60-J76-W00	60-J76-M00	Juvenile Table	25" x 85-1/2" x 53"	125	\$1,373	\$1,373
Extra Large Free Form Table	60-781-W00	60-781-M00	Adult Table	29" x 78-1/2" x 41"	120	\$1,523	\$1,523
	60-Y81-W00	60-Y81-M00	Youth Table	27-1/2" x 78-1/2" x 41"	120	\$1,523	\$1,523
	60-J81-W00	60-J81-M00	Juvenile Table	25" x 78-1/2" x 41"	120	\$1,523	\$1,523
	Catalog No.	Descripti	on				Price
Casters	MT-CASTER		ack nylon hooded tw	in-wheel caster with a brake. Add or	ne caster p	er table leg (sold each)	<b>\$28</b> ).
Metal Leg Caster Wood Leg Caster	LG-CST-S00	Caster for N 3" black n		neel caster with a brake. Add one cas	ster per tal	ole leg (sold each).	\$84

Please specify Laminate Color (Tables 2 and 4), T-Mold Color (Table 4), Leg Type (Oak or Metal) and Wood Leg Finish (Table 1) or Metal Leg Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: T-Mold Color does NOT have to match Laminate Color.

**- MOB 4 -** F11-1-19G-MOB

# Sync Tables

## **General Specifications**

#### **TABLETOP**


Tabletop will be 1-3/16" thick, 3-ply 45# density particleboard, with .050" thick high-pressure laminate surface and .020" thick backing sheet for balanced construction. Edges will be flexible polyethylene tee mold, 5/16" thick x 1-1/4" wide. Core material receives a 5/64" x 3/8" route to receive tee mold. Tee mold is applied to core material after the laminate and backer sheet.

#### LEGS (METAL)


Legs will be 2-3/8" round steel tubing with a wall thickness not less than .64". Legs are supplied with a standard glide insert. Lockable caster inserts interchange with the glide insert on any leg. Table legs will be attached to the tabletop by means of a flange welded to the leg tube. The attachment flange will be 4-5/8" in diameter formed and welded on two sides. The leg flange is attached to the tabletop by six (6) 1/4"-20 x 1" bolts engaging 1/4" internal and external threaded bushings embedded in the underside of the tabletop. Legs will be finished with electrostatic applied epoxy powder-coat paint.

#### **CASTER**

When specified, a 2-1/4" black nylon hooded twin-wheel caster with a brake is supplied. Lockable caster inserts interchange with the glide insert on any leg. Add one caster per table leg (sold each).



**Edge Detail** 



MTCASTER

Note: Tables come equipped with two lockable casters, additional casters (below) can be ordered for other legs.

	Price	Wt. (lbs.)	HxWxD	Description	Catalog No.
Hourglass Tab	\$905	90	29" x 45" x 36"	Adult Table	MST45HG29ARMMS
	\$905	90	27-1/2" x 45" x 36"	Youth Table	VIST45HG27ARMMS
	\$905	90	25" x 45" x 36"	Juvenile Table	MST45HG25ARMMS
	\$1,120	100	29" x 53" x 43"	Adult Table	//ST53HG29ARMMS
\\    *	\$1,120	100	27-1/2" x 53" x 43"	Youth Table	/IST53HG27ARMMS
₩    ₩	\$1,120	100	25" x 53" x 43"	Juvenile Table	/IST53HG25ARMMS
В	ψ1,120	100	20 800 810	Satorino rasio	io i do i
Round Tab	\$905	90	29" x 48" x 48"	Adult Table	MST48RD29ARMMS
	\$905	90	27-1/2" x 48" x 48"	Youth Table	MST48RD27ARMMS
	\$905	90	25" x 48" x 48""	Juvenile Table	/IST48RD25ARMMS
3					
Docking Tab	\$905	80	29" x 48" x 24"	Adult Table	MST48DT29ARMMS
	\$905	80	27-1/2" x 48" x 24"	Youth Table	MST48DT27ARMMS
	\$905	80	25" x 48" x 24"	Juvenile Table	MST48DT25ARMMS
Semi-Circle Tab	\$882	100	29" x 60" x 31-5/8"	Adult Table	MST60SC29ARMMS
Seriii Sirdic Tab	\$882	100	27-1/2" x 60" x 31-5/8"	Youth Table	MST60SC27ARMMS
	\$882	100	25" x 60" x 31-5/8"	Juvenile Table	MST60SC25ARMMS
	φ <b>0</b> 02	100	23 800 831-370	Juverine rable	VISTOUSUZSAKIVIIVIS
Trapezoid Tab	\$1,068	90	29" x 64" x 38"	Adult Table	MST64TR29ARMMS
	\$1,068	90	27-1/2" x 64" x 38"	Youth Table	MST64TR27ARMMS
	\$1,068	90	25" x 64" x 38"	Juvenile Table	MST64TR25ARMMS
1000	Price			Description	Catalog No.
Caste	\$28			Metal Leg Caster	MT-CASTER
		dd one caster per ta	oded twin-wheel caster with a brake. A		

Note: T-Mold Color does NOT have to match Laminate Color.

Note: Tables come equipped with two lockable casters, additional casters (below) can be ordered for other legs.

	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
Fan Table	MST65FT29ARMMS	Adult Table	29" x 65" x 37-3/4"	100	\$1,027
	MST65FT27ARMMS MST65FT25ARMMS	Youth Table Juvenile Table	27-1/2" x 65" x 37-3/4" 25" x 65" x 37-3/4"	100 100	\$1,027 \$1,027
	WST03I 123ANWW3	Sure line Table	25 805 837-574	100	Ψ1,02 <i>1</i>
Star Table	60793M00	Adult Table	29" x 46-7/32" x 44-5/8"	90	\$1,149
	60Y93M00 60J93M00	Youth Table Juvenile Table	27-1/2" x 46-7/32" x 44-5/8" 25" x 46-7/32" x 44-5/8"	90 90	\$1,149 \$1,149
Shell Table	60794M00	Adult Table	29" x 54-19/32" x 51-13/32"	90	\$1,209
	60Y94M00 60J94M00	Youth Table Juvenile Table	27-1/2" x 54-19/32" x 51-13/32" 25" x 54-19/32" x 51-13/32"	90 90	\$1,209 \$1,209
					V.,
Pod Table	60795M00	Adult Table	29" x 54-1/4" x 23-3/4"	80	\$918
	60Y95M00 60J95M00	Youth Table Juvenile Table	27-1/2" x 54-1/4" x 23-3/4 25" x 54-1/4" x 23-3/4	80 80	\$918 \$918
	Catalog No.	Description			Price
Casters	MT-CASTER	Metal Leg Caster			\$28
		2-1/4" black nylon hood	ded twin-wheel caster with a brake. Add one c	aster per table leg (sold	each).

Please specify Laminate Color (Tables 2 and 4), T-Mold Color (Table 4) and Metal Leg Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: T-Mold Color does NOT have to match Laminate Color.


# Collection Accessories

XX-193-S00 39"H Double Action Gate

XX-E93-S00 32"H Double Action Gate



XX-342-S00 Mobile Printer Stand



XX-914-S00 Depressible Receiving Truck for 32"H Units

XX-914-S02 Depressible Receiving Truck for 32"H Units w/Rubber Bumpers




XX-915-S00 Depressible Receiving Truck for 39"H Units

XX-915-S02 Depressible Receiving Truck for 39"H Units w/Rubber Bumpers



Catalog No.	Description	Wt. (lbs.)	Price
Accessories In O	ak Wood		
T0-193-S00	39"H Double Action Gate	42	\$1,107
TO-E93-S00	32"H Double Action Gate	40	\$988
TO-342-S00	Mobile Printer Stand	50	\$1,759
TO-914-S00	Depressible Receiving Truck for 32"H Units	100	\$1,557
T0-914-S02	Depressible Receiving Truck for 32"H Units w/Rubber Bumpers	100	\$1,695
T0-915-S00	Depressible Receiving Truck for 39"H Units	100	\$1,812
T0-915-S02	Depressible Receiving Truck for 39"H Units w/Rubber Bumpers	100	\$1,957
TO-025-S00	Knee Space Hang A Drawer without Lock (No image)	18	\$337
T0-025-S02	Knee Space Hang A Drawer with Lock (No image)	18	\$379
Accessories In M	Taple Wood		
M0-193-S00	39"H Double Action Gate	42	\$1,206
MO-E93-S00	32"H Double Action Gate	40	\$1,078
M0-342-S00	Mobile Printer Stand	50	\$1,917
M0-914-S00	Depressible Receiving Truck for 32"H Units	100	\$1,696
M0-914-S02	Depressible Receiving Truck for 32"H Units w/Rubber Bumpers	100	\$1,848
M0-915-S00	Depressible Receiving Truck for 39"H Units	100	\$1,975
M0-915-S02	Depressible Receiving Truck for 39"H Units w/Rubber Bumpers	100	\$2,133
M0-025-S00	Knee Space Hang A Drawer without Lock (No image)	18	\$367
M0-025-S02	Knee Space Hang A Drawer with Lock (No image)	18	\$413
Accessories In C	herry Wood		
CO-193-S00	39"H Double Action Gate	42	\$1,328
CO-E93-S00	32"H Double Action Gate	40	\$1,187
CO-342-S00	Mobile Printer Stand	50	\$2,110
CO-914-S00	Depressible Receiving Truck for 32"H Units	100	\$1,867
CO-914-S02	Depressible Receiving Truck for 32"H Units w/Rubber Bumpers	100	\$2,034
CO-915-S00	Depressible Receiving Truck for 39"H Units	100	\$2,175
CO-915-S02	Depressible Receiving Truck for 39"H Units w/Rubber Bumpers	100	\$2,349
CO-025-S00	Knee Space Hang A Drawer without Lock (No image)	18	\$404
C0-025-S02	Knee Space Hang A Drawer with Lock (No image)	18	\$456


Please specify Wood Finish (Table 1) . Details can be found on page GEN 4.




Catalog No.	Description	Wt. (lbs.)	Price
Mobile Pedestal	s In Oak Wood		
T0-019-S00	33"H Open Shelf/Computer Unit with Casters	115	\$1,395
TO-E19-S00	25-1/2"H Open Shelf/Computer Unit with Casters	100	\$1,246
TO-E19-S01	23-1/4"H Open Shelf/Computer Unit with Nail Glides	100	\$1,246
TO-020-S00	33"H Cupboard Unit with Caster	120	\$2,010
TO-E20-S00	25-1/2"H Cupboard Unit with Caster	105	\$1,818
TO-E20-S01	23-1/4"H Cupboard Unit with Nail Glides	105	\$1,818
TO-021-S00	33"H 3 Drawer Unit with Caster	170	\$1,790
TO-E21-S00	25-1/2"H 2 Drawer Unit with Casters	150	\$1,608
TO-E21-S01	25-1/2"H 2 Drawer Unit with Nail Glides	150	\$1,608
Mobile Pedestal	s In Maple Wood		
M0-019-S00	33"H Open Shelf/Computer Unit with Casters	115	\$1,522
M0-E19-S00	25-1/2"H Open Shelf/Computer Unit with Casters	100	\$1,358
M0-E19-S01	23-1/4"H Open Shelf/Computer Unit with Nail Glides	100	\$1,358
M0-020-S00	33"H Cupboard Unit with Caster	120	\$2,190
M0-E20-S00	25-1/2"H Cupboard Unit with Caster	105	\$1,982
M0-E20-S01	23-1/4"H Cupboard Unit with Nail Glides	105	\$1,982
M0-021-S00	33"H 3 Drawer Unit with Caster	170	\$1,952
M0-E21-S00	25-1/2"H 2 Drawer Unit with Casters	150	\$1,753
M0-E21-S01	25-1/2"H 2 Drawer Unit with Nail Glides	150	\$1,753
Mobile Pedestal	s In Cherry Wood		
CO-019-S00	33"H Open Shelf/Computer Unit with Casters	115	\$1,675
CO-E19-S00	25-1/2"H Open Shelf/Computer Unit with Casters	100	\$1,495
CO-E19-S01	23-1/4"H Open Shelf/Computer Unit with Nail Glides	100	\$1,495
CO-020-S00	33"H Cupboard Unit with Caster	120	\$2,411
CO-E20-S00	25-1/2"H Cupboard Unit with Caster	105	\$2,181
CO-E20-S01	23-1/4"H Cupboard Unit with Nail Glides	105	\$2,181
CO-021-S00	33"H 3 Drawer Unit with Caster	170	\$2,148
CO-E21-S00	25-1/2"H 2 Drawer Unit with Casters	150	\$1,931
CO-E21-S01	25-1/2"H 2 Drawer Unit with Nail Glides	150	\$1,931


Please specify Wood Finish (Table 1) . Details can be found on page GEN 4.

Basic Keyboard Pullout



Articulating Keyboard Pullout with Swing A Mouse





Catalog No.	Description	Wt. (lbs.)	Price
Computer Acc	<u>essories</u>		
60-464-000	Basic Keyboard Pullout, Black	15	\$187
60-465-000	Articulating Keyboard Pullout, Black	13	\$455
60-465-002	Swing A Mouse, Black	2	\$166
73-105-S00	Metal Adjustable CPU Holder	7	\$331

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Movable Pri	nter Shelf for PA	C Stations				
64-694-S00 OAK	64-694-S00 MAP	Printer Shelf Shelf mounts on top vertical panels. Shel attach to panels. It r removed or relocate Usable shelf size is 1	f does not nay be completely d at any time.	10	\$510	\$556

# Classic Shelving

# **General Specifications**

#### CONSTRUCTION

Shelving construction is modular type, utilizing all natural hardwoods. No particleboard or synthetic materials will be used. Shelving units are designed with the starter and adder concept and measure 36-3/16" from center to center of the uprights. Oak and Maple are the standard wood species for Brodart shelving.

#### **END PANELS**

End panels are 1" thick, 9-ply Formaldehyde-free hardwood veneer core plywood. All exposed vertical and top edges are banded with matching solid Northern-grown Oak or Maple hardwood. Edges are square, but eased. Vertical rows of holes are drilled near the front and rear of each panel for shelf adjustment on 32mm centers. Panels are drilled at front, rear, top, and bottom for embedding internal and external threaded bushings. Tops and bases are attached to end panels with 5/16" - 18 x 2" hex-head bolts and washers. Lag bolts or wood screws are not used. Clip and metal strip style shelf attachments are available if specified.

#### INTERMEDIATE UPRIGHTS

Intermediate uprights are 1" thick, 9-ply Formaldehyde-free hardwood veneer core plywood. All exposed vertical and top edges are banded with matching solid Northern-grown Oak or Maple hardwood. Edges are square, but eased. Shelf pinholes are bored on both sides of the panel but staggered so that pins can be deeply seated. Panels are drilled through at front, rear, top, and bottom for attachment of tops and bases with 5/16" - 18 x 4-1/2" hex-head bolts, nuts, and washers. Clip and metal strip style shelf attachments are available if specified.

#### **BASE**

The base front is 4"H X 3/4" thick solid Northern-grown Oak or Maple hardwood. A 2" x 3/4" rail is tenoned full-length to the inside of the front. Bolting cleats 1-1/4" x 1-1/4" are glued and stapled perpendicular at the ends of the rail and drilled to allow assembly bolts to pass through. A second full-length rail is glued and stapled to the rear of the bolting cleats for support and proper alignment. Bases are manufactured so the base shelf rests on the bolting cleats set behind and flush with the top of the base front.

#### **ATTACHMENT**


Four bolts are used to attach each single-faced base or top, except for 16"D single-faced units, on which six bolts are used. Eight bolts are used to attach each double-faced base or top, except for 32"D double-faced units, on which twelve bolts are used. All hardware is concealed from view after assembly. Each single-faced unit is supplied with a metal bracket, lead anchor, and screws for fastening to the wall. Double-faced ranges that do not have partitions receive two steel sway bars per range, 46-7/8" long and 5/16" square. These attach to the starter panel at both sides of the range and the adjoining intermediate panel with screws.

#### **BACKS AND PARTITIONS**

Backs and partitions are constructed of 3-ply or 5-ply furniture-grade Oak or Maple veneered plywood finished to match shelving. Backs are finished on one side and used with single-faced shelving. Partitions are used with double-faced shelving, and therefore finished on both sides. Economical painted backs and partitions are also available upon request.

Note: Backs and partitions do not function with "Book Stop" shelving.

Note: Clip and Strip shelving is available for Wood Shelf units ONLY and can be ordered by changing the S1 prefix on the starter unit to S3, and changing the S2 prefix on the adder unit to S4. i.e.: S3-861-S00 or S4-861-S00.



Starter
Includes two end panels, shelf pin and joining holes on inside only.
37-3/16"W overall

Includes one intermediate upright with shelf pin and joining holes on both sides. 36-3/16"W overall

# **General Specifications - Tops**

#### WOOD SHELVING TOPS

Cornice tops have a 2-1/8" fascia, 3/4" thick, of solid Northern-grown Oak or Maple hardwood banded to a 3/4" 7-ply hardwood plywood panel of specified depth. The top front corner of the fascia has a 1/8" radius. On the inside surface of the top at each end, butted to the fascia, are solid hardwood bolting cleats 1-1/4" x 1-1/4" that are both glued and stapled. For additional strength, a 4" cleat is added at the intersection of the fascia and top panel. Bolting cleats are drilled to allow assembly bolts to pass through.

Note: Tops on 72"H, 82"H, and 90"H units are inverted.

#### SUB TOPS FOR CONTINUOUS SHELVING TOPS

Sub tops are constructed using solid hardwood cleats and plywood components. Tops have a 2-1/8" facia, 3/4" thick, of solid Northerngrown Oak or Maple hardwood banded to the front.

Note: Sub-tops for shelving (to accept continuous HPL Tops - sold separately ) are available and can be ordered by changing the S00 extension on the catalog number to S02. i.e.: S1-861-S02.

#### INDIVIDUAL HIGH-PRESSURE LAMINATE TOPS

Cornice tops have a 2-1/8" facia, 3/4" thick, of solid Northern-grown Oak or Maple hardwood banded to a 3/4" 3-ply 45# density particleboard panel of specified depth, that consists of a top surface of .050" thick high-pressure laminate, with a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards.


Note: Individual HPL tops for shelving are available and can be ordered by changing the S00 extension on the catalog number to S03. i.e.: S1-861-S03.


# SHELVING TOPS (High-Pressure Laminate and Continuous)

To order wood shelving with individual high-pressure laminate tops use the standard shelving part number, changing the S00 to S03. Tops are available in 42" and 60-1/2"H units. If 72" or 82" is required, order as M03.

To order wood shelving with sub tops for use with continuous shelving tops, use the standard shelving part number changing the S00 to S02. The sub tops are available in 42", 48", and 60-1/2"H units.

Note: Continuous tops must be ordered separately.





Individual High-Pressure Laminate Top



Shelving Starter/Adder with Sub-Top and Continuous Top

# **General Specifications - Shelves & Mobile Units**

#### WOOD SHELVES

Shelves are 3/4" thick, glued-up solid Northern-grown Oak or Maple hardwood. Random widths no more than 4" or less than 1-1/2" are used. To ensure adequate support for heavy volumes, no substitute for solid hardwood is permitted. Adjustable shelves are grooved 11/32" diameter half round on the underside to set firmly on 1" long, 5/16" diameter threaded shelf pins, cadmium-plated. Shelf depths are nominal.

#### **OMEGA (STEEL) SHELVES**

Omega (steel) shelves are designed to fit Brodart's wood shelving units. These shelves are 18-gauge steel stamped with notches in the bottom edge to fit over shelf pins. The front and back edges are triple bent for strength and to eliminate sharp edges. Shelves are electrostatic powder-coat painted with epoxy paint and oven cured. Shelf accepts spring-type overhead wire book support. Units are supplied with a wood base shelf. Omega shelves are available in many standard and optional colors - please call for selection.

#### OMEGA "BOOK STOP" STEEL SHELVES

Omega "Book Stop" steel shelves are designed to fit Brodart's wood shelving units. These shelves are 18-gauge steel stamped with notches in the bottom edge to fit over shelf pins. The front and back edges are triple bent for strength and to eliminate sharp edges. The back edge of the shelf is bent upward to form a 90° angle, 1-5/8"H above the shelf surface to function as a book stop. Shelves are electrostatic powder-coat painted with epoxy paint and oven cured. Units are supplied with a metal base shelf. Omega shelves are available in many standard and optional colors - please call for selection.

Note: Backs and partitions do not function with "Book Stop" shelving.

#### MOBILE SHELVING UNITS

Mobile Shelving is available on 42", 48", and 60-1/2" units. Shelving construction is the same as the standard shelving with the exception of the base. The base facing is 4-3/8"H, receives four reinforced 14-gauge corner brackets with four 2-1/2" heavy-duty swivel casters attached to a 14-gauge caster bracket. Corner brackets are attached to the end panel and the base facing. The caster assembly is hidden within the base, giving the appearance of standard unit. All mobile units receive partitions, with the exception of Omega Book Stop units, which receive sway braces. Units are offered as starter or starter/adder only.

#### PICTURE BOOK SHELVING SHELVES

Picture Book Shelving is 12"D with six (6) hardboard dividers per shelf. A 2"H, solid wood back keeps dividers in place.

#### **GLASS DOOR SHELVING**

Each unit has sliding 1/4" thick laminated glass doors to protect shelved items. A solid back and door lock ensures safe storage. Door pulls are provided. Doors slide smoothly in aluminum tracks at top and bottom. Wood shelves are 9"D.

#### TILT AND STORE SHELVING


Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

#### METAL PICTURE BOOK SHELVING

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.

#### PERIODICAL SHELVING

Periodical shelving can display any type of media such as CD's, videocassettes, books and magazines. The shelf can be divided with the six dividers provided with each shelf. Each sloping display shelf will have a 13-3/4"H clear display area.



Omega Book Stop Shelf



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Jan State of the S
5 Adjustabl	le Shelves, 1 Fi.	xed Shelf and 1	Base Shelf				90"H Wood Shelves
S1-960-S00	1S-960-S00	S/F Starter	90" x 37-3/16" x 10"	103	\$1,462	\$1,535	
S2-960-S00	2S-960-S00	S/F Adder	90" x 36-3/16" x 10"	90	\$1,113	\$1,169	
S1-967-S00	1S-967-S00	S/F Starter	90" x 37-3/16" x 12"	122	\$1,577	\$1,656	
S2-967-S00	2S-967-S00	S/F Adder	90" x 36-3/16" x 12"	102	\$1,199	\$1,259	
S1-673-S00	1S-673-S00	S/F Starter	90" x 37-3/16" x 16"	127	\$1,755	\$1,843	
S2-673-S00	2S-673-S00	S/F Adder	90" x 36-3/16" x 16"	107	\$1,376	\$1,445	
4 Adjustabl	le Shelves, 1 Fi.	xed Shelf and 1	Base Shelf				82"H Wood Shelves
S1-976-S00	1S-976-S00	S/F Starter	82" x 37-3/16" x 10"	93	\$1,333	\$1,401	
S2-976-S00	2S-976-S00	S/F Adder	82" x 36-3/16" x 10"	80	\$1,011	\$1,061	
S1-977-S00	1S-977-S00	S/F Starter	82" x 37-3/16" x 12"	112	\$1,440	\$1,513	
S2-977-S00	2S-977-S00	S/F Adder	82" x 36-3/16" x 12"	92	\$1,092	\$1,147	
S1-679-S00	1S-679-S00	S/F Starter	82" x 37-3/16" x 16"	117	\$1,602	\$1,682	
S2-679-S00	2S-679-S00	S/F Adder	82" x 36-3/16" x 16"	97	\$1,254	\$1,317	
4 Adjustabl	le Shelves and	1 Base Shelf					72"H Wood Shelves
S1-861-S00	1S-861-S00	S/F Starter	72" x 37-3/16" x 10"	88	\$1,215	\$1,276	
S2-861-S00	2S-861-S00	S/F Adder	72" x 36-3/16" x 10"	75	\$919	\$965	
S1-863-S00	1S-863-S00	S/F Starter	72" x 37-3/16" x 12"	102	\$1,316	\$1,382	
S2-863-S00	2S-863-S00	S/F Adder	72" x 36-3/16" x 12"	87	\$994	\$1,044	
S1-675-S00	1S-675-S00	S/F Starter	72" x 37-3/16" x 16"	107	\$1,439	\$1,511	
S2-675-S00	2S-675-S00	S/F Adder	72" x 36-3/16" x 16"	92	\$1,139	\$1,196	
4 Adjustabl	le Shelves and	1 Base Shelf					60-1/2"H Wood Shelves
S1-979-S00	1S-979-S00	S/F Starter	60-1/2" x 37-3/16" x 10"	75	\$1,098	\$1,153	
S2-979-S00	2S-979-S00	S/F Adder	60-1/2" x 36-3/16" x 10"	65	\$829	\$871	
S1-988-S00	1S-988-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	96	\$1,189	\$1,249	
S2-988-S00	2S-988-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	81	\$899	\$945	
S1-678-S00	1S-678-S00	S/F Starter	60-1/2" x 37-3/16" x 16"	101	\$1,307	\$1,372	
S2-678-S00	2S-678-S00	S/F Adder	60-1/2" x 36-3/16" x 16"	86	\$1,023	\$1,074	

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

 $For details \ regarding \ Clip \ \& \ Strip \ Shelving, \ Sub \ Tops \ or \ Individual \ HPL \ Tops, \ please \ reference \ the \ Modifications \ \& \ Up \ Charges \ Section \ located \ on \ page \ MOD \ 8.$ 

M. M. Tanana	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
48"H Wood Shelves	2 Adjustabl	e Shelves and	1 Base Shelf				
	S1-761-S00	1S-761-S00	S/F Starter	48" x 37-3/16" x 10"	71	\$907	\$952
	S2-761-S00	2S-761-S00	S/F Adder	48" x 36-3/16" x 10"	63	\$656	\$689
	S1-762-S00	1S-762-S00	S/F Starter	48" x 37-3/16" x 12"	84	\$967	\$1,016
	S2-762-S00	2S-762-S00	S/F Adder	48" x 36-3/16" x 12"	74	\$693	\$728
	S1-676-S00	1S-676-S00	S/F Starter	48" x 37-3/16" x 16"	89	\$1,048	\$1,100
	S2-676-S00	2S-676-S00	S/F Adder	48" x 36-3/16" x 16"	79	\$771	\$809
	32-070-300	23-070-300	37 F Addel	46 1 30-3/10 110	19	\$//1	<b>\$00</b> 7
12"H Wood Shalvas				46 830-3710 810	19	\$//1	<b>400</b> 7
12"H Wood Shelves	2 Adjustabl	e Shelves and	1 Base Shelf		19		
12"H Wood Shelves	<i>2 Adjustabl</i> S1-981-S00	e <i>Shelves and</i> 1S-981-S00	<i>1 Base Shelf</i> S/F Starter	42" x 37-3/16" x 10"	61	\$857	\$901
12"H Wood Shelves	2 Adjustabl	e Shelves and	1 Base Shelf				\$901
12"H Wood Shelves	<i>2 Adjustabl</i> S1-981-S00	e <i>Shelves and</i> 1S-981-S00	<i>1 Base Shelf</i> S/F Starter	42" x 37-3/16" x 10"	61	\$857	\$901 \$643
12"H Wood Shelves	2 Adjustable S1-981-S00 S2-981-S00	e Shelves and 1S-981-S00 2S-981-S00	1 Base Shelf S/F Starter S/F Adder	42" x 37-3/16" x 10" 42" x 36-3/16" x 10"	61 53	\$857 \$612	\$901 \$643 \$958
42"H Wood Shelves	2 Adjustable \$1-981-\$00 \$2-981-\$00 \$1-989-\$00	e Shelves and 15-981-500 25-981-500 15-989-500	1 Base Shelf  S/F Starter S/F Adder  S/F Starter	42" x 37-3/16" x 10" 42" x 36-3/16" x 10" 42" x 37-3/16" x 12"	61 53 74	\$857 \$612 \$913	\$901 \$643 \$958 \$675

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price		THE REAL PROPERTY.
<u> 5 Adjustabl</u>	le Shelves, 1 Fix	xed Shelf and 1	Base Shelf per Side				90"	H Wood Shelves
S1-969-S00	1S-969-S00	D/F Starter	90" x 37-3/16" x 20"	185	\$2,561	\$2,689		
S2-969-S00	2S-969-S00	D/F Adder	90" x 36-3/16" x 20"	153	\$2,023	\$2,124		
C4 070 C00	46 070 600	D /F Ctt	0011 - 27 2 /4 / 11 - 2 4 11	224	<b>\$0.774</b>	<b>#0.000</b>		
S1-973-S00 S2-973-S00	1S-973-S00 2S-973-S00	D/F Starter D/F Adder	90" x 37-3/16" x 24" 90" x 36-3/16" x 24"	224 188	\$2,771 \$2,153	\$2,909		
32-973-300	23-973-300	D/ F Addel	90 130-3/10 124	100	\$2,133	\$2,260		
S1-683-S00	1S-683-S00	D/F Starter	90" x 37-3/16" x 32"	239	\$3,079	\$3,233		
S2-683-S00	2S-683-S00	D/F Adder	90" x 36-3/16" x 32"	203	\$2,470	\$2,594		
							0.144	
<u> 4 Adjustabl</u>	le Shelves, 1 Fix	xed Shelf and 1	Base Shelf per Side				82"	H Wood Shelves
S1-983-S00	1S-983-S00	D/F Starter	82" x 37-3/16" x 20"	175	\$2,393	\$2,513		
S2-983-S00	2S-983-S00	D/F Adder	82" x 36-3/16" x 20"	143	\$1,863	\$1,956		
S1-990-S00	1S-990-S00	D/F Starter	82" x 37-3/16" x 24"	214	\$2,609	\$2,740		
S2-990-S00	2S-990-S00	D/F Adder	82" x 36-3/16" x 24"	178	\$2,007	\$2,107		
C4 (00 C00	46 (00 600	D /F Charles	0011 - 27 2 (4 ( 11 - 2011	222	<b>#0.000</b>	<b>60.04</b> E		
S1-689-S00 S2-689-S00	1S-689-S00 2S-689-S00	D/F Starter D/F Adder	82" x 37-3/16" x 32" 82" x 36-3/16" x 32"	229 193	\$2,899 \$2,304	\$3,045 \$2,419		
4 Adjustabl	le Shelves and	1 Base Shelf pe	<u>r Side</u>				72"	H Wood Shelves
C1 04F C00	1S-865-S00	D/F Starter						ii wood Siicives
. DUC-COS-1 c.		D/F Statiet	72" x 37-3/16" x 20"	160	\$2.274	\$1.747		TI WOOD Shelves
\$1-865-\$00 \$2-865-\$00	2S-865-S00	D/F Adder	72" x 37-3/16" x 20" 72" x 36-3/16" x 20"	160 128	\$2,274 \$2,388	\$1,747 \$1,834		The Wood Shelves
	2S-865-S00			160 128	\$2,274 \$2,388	\$1,747 \$1,834		T WOOD SHELVES
S2-865-S00	2S-865-S00 1S-866-S00		72" x 36-3/16" x 20" 72" x 37-3/16" x 24"					Two districts
		D/F Adder	72" x 36-3/16" x 20"	128	\$2,388	\$1,834		TWOOD SHEWES
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00	1S-866-S00 2S-866-S00	D/F Adder  D/F Starter  D/F Adder	72" x 36-3/16" x 20" 72" x 37-3/16" x 24" 72" x 36-3/16" x 24"	128 199 163	\$2,388 \$2,453 \$1,891	\$1,834 \$2,576 \$1,985		TWOOD SHEWES
S2-865-S00 S1-866-S00	1S-866-S00	D/F Adder D/F Starter	72" x 36-3/16" x 20" 72" x 37-3/16" x 24"	128 199	\$2,388 \$2,453	\$1,834 \$2,576		Wood Sileives
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00	1S-866-S00 2S-866-S00 1S-685-S00	D/F Adder  D/F Starter  D/F Adder  D/F Starter	72" x 36-3/16" x 20"  72" x 37-3/16" x 24"  72" x 36-3/16" x 24"  72" x 37-3/16" x 32"	128 199 163 214	\$2,388 \$2,453 \$1,891 \$2,602	\$1,834 \$2,576 \$1,985 \$2,732		TWOOD SHEWES
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00	1S-866-S00 2S-866-S00 1S-685-S00 2S-685-S00	D/F Adder  D/F Starter  D/F Adder  D/F Starter	72" x 36-3/16" x 20"  72" x 37-3/16" x 24"  72" x 36-3/16" x 24"  72" x 37-3/16" x 32"  72" x 36-3/16" x 32"	128 199 163 214	\$2,388 \$2,453 \$1,891 \$2,602	\$1,834 \$2,576 \$1,985 \$2,732	60-1/2"	H Wood Shelves
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00	1S-866-S00 2S-866-S00 1S-685-S00 2S-685-S00	D/F Adder  D/F Starter  D/F Adder  D/F Starter  D/F Adder	72" x 36-3/16" x 20"  72" x 37-3/16" x 24"  72" x 36-3/16" x 24"  72" x 37-3/16" x 32"  72" x 36-3/16" x 32"	128 199 163 214	\$2,388 \$2,453 \$1,891 \$2,602 \$2,167	\$1,834 \$2,576 \$1,985 \$2,732 \$2,275	60-1/2"	
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00 \$4 Adjustable \$1-985-\$00	1\$-866-\$00 2\$-866-\$00 1\$-685-\$00 2\$-685-\$00	D/F Adder  D/F Starter  D/F Adder  D/F Starter  D/F Adder	72" x 36-3/16" x 20"  72" x 37-3/16" x 24"  72" x 36-3/16" x 32"  72" x 36-3/16" x 32"  72" x 36-3/16" x 32"	128 199 163 214 178	\$2,388 \$2,453 \$1,891 \$2,602	\$1,834 \$2,576 \$1,985 \$2,732	60-1/2"	
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00	1\$-866-\$00 2\$-866-\$00 1\$-685-\$00 2\$-685-\$00	D/F Adder  D/F Starter D/F Adder  D/F Starter D/F Adder  1 Base Shelf pe	72" x 36-3/16" x 20"  72" x 37-3/16" x 24"  72" x 36-3/16" x 32"  72" x 36-3/16" x 32"  72" x 36-3/16" x 32"  ***T Side**  60-1/2" x 37-3/16" x 20"	128 199 163 214 178	\$2,388 \$2,453 \$1,891 \$2,602 \$2,167 \$2,154 \$1,633	\$1,834 \$2,576 \$1,985 \$2,732 \$2,275 \$2,261 \$1,715	60-1/2"	
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00 \$1-985-\$00 \$2-985-\$00 \$1-986-\$00	1S-866-S00 2S-866-S00 1S-685-S00 2S-685-S00 2S-985-S00 2S-985-S00 1S-986-S00	D/F Adder  D/F Starter D/F Adder  D/F Starter D/F Adder  1 Base Shelf pe	72" x 36-3/16" x 24" 72" x 37-3/16" x 24" 72" x 36-3/16" x 32" 72" x 36-3/16" x 32" 72" x 36-3/16" x 32"  ***T Side** 60-1/2" x 37-3/16" x 20" 60-1/2" x 37-3/16" x 20" 60-1/2" x 37-3/16" x 20"	128 199 163 214 178 139 115	\$2,388 \$2,453 \$1,891 \$2,602 \$2,167 \$2,154 \$1,633 \$2,293	\$1,834 \$2,576 \$1,985 \$2,732 \$2,275 \$2,261 \$1,715 \$2,407	60-1/2"	
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00 \$4.40justabl \$1-985-\$00 \$2-985-\$00	1S-866-S00 2S-866-S00 1S-685-S00 2S-685-S00 2S-985-S00 2S-985-S00	D/F Adder  D/F Starter D/F Adder  D/F Starter D/F Adder  1 Base Shelf pe	72" x 36-3/16" x 24" 72" x 36-3/16" x 24" 72" x 36-3/16" x 32" 72" x 36-3/16" x 32" 72" x 36-3/16" x 32"  ***T Side** 60-1/2" x 37-3/16" x 20" 60-1/2" x 36-3/16" x 20"	128 199 163 214 178	\$2,388 \$2,453 \$1,891 \$2,602 \$2,167 \$2,154 \$1,633	\$1,834 \$2,576 \$1,985 \$2,732 \$2,275 \$2,261 \$1,715	60-1/2"	
\$2-865-\$00 \$1-866-\$00 \$2-866-\$00 \$1-685-\$00 \$2-685-\$00 \$1-985-\$00 \$1-985-\$00 \$1-986-\$00	1S-866-S00 2S-866-S00 1S-685-S00 2S-685-S00 2S-985-S00 2S-985-S00 1S-986-S00	D/F Adder  D/F Starter D/F Adder  D/F Starter D/F Adder  1 Base Shelf pe	72" x 36-3/16" x 24" 72" x 37-3/16" x 24" 72" x 36-3/16" x 32" 72" x 36-3/16" x 32" 72" x 36-3/16" x 32"  ***T Side** 60-1/2" x 37-3/16" x 20" 60-1/2" x 37-3/16" x 20" 60-1/2" x 37-3/16" x 20"	128 199 163 214 178 139 115	\$2,388 \$2,453 \$1,891 \$2,602 \$2,167 \$2,154 \$1,633 \$2,293	\$1,834 \$2,576 \$1,985 \$2,732 \$2,275 \$2,261 \$1,715 \$2,407	60-1/2"	

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

 $For details \ regarding \ Clip \ \& \ Strip \ Shelving, \ Sub \ Tops \ or \ Individual \ HPL \ Tops, \ please \ reference \ the \ Modifications \ \& \ Up \ Charges \ Section \ located \ on \ page \ MOD \ 8.$ 

TWO IS NOT THE OWNER.	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
B"H Wood Shelves			1 Base Shelf per	<u>Side</u>			
	S1-765-S00	1S-765-S00	D/F Starter	48" x 37-3/16" x 20"	111	\$1,642	\$1,724
	S2-765-S00	2S-765-S00	D/F Adder	48" x 36-3/16" x 20"	96	\$1,232	\$1,294
	S1-766-S00	1S-766-S00	D/F Starter	48" x 37-3/16" x 24"	134	\$1,717	\$1,803
	S2-766-S00	2S-766-S00	D/F Adder	48" x 36-3/16" x 24"	111	\$1,317	\$1,383
	S1-686-S00	1S-686-S00	D/F Starter	48" x 37-3/16" x 32"	145	\$1,860	\$1,953
	S2-686-S00	2S-686-S00	D/F Adder	48" x 36-3/16" x 32"	122	\$1,464	\$1,53{
2"H Wood Shelves			D/F Adder 1 Base Shelf per		122	\$1,464	\$1,538
2"H Wood Shelves					122	\$1,464 \$1,512	\$1,538
2"H Wood Shelves	2 Adjustabl	e Shelves and	1 Base Shelf per	<u>Side</u>			
2"H Wood Shelves	2 Adjustabl \$1-987-\$00	e <i>Shelves and</i> 1S-987-S00	<i>1 Base Shelf per</i> D/F Starter	<i>Side</i> 42" x 37-3/16" x 20"	101	\$1,512	\$1,588
2"H Wood Shelves	2 Adjustable \$1-987-\$00 \$2-987-\$00	e <i>Shelves and</i> 1S-987-S00 2S-987-S00	<b>1 Base Shelf per</b> D/F Starter D/F Adder	<b>Side</b> 42" x 37-3/16" x 20" 42" x 36-3/16" x 20"	101 86	\$1,512 \$1,130	\$1,588 \$1,186 \$1,652
2"H Wood Shelves	2 Adjustable \$1-987-\$00 \$2-987-\$00 \$1-991-\$00	e Shelves and 1S-987-S00 2S-987-S00 1S-991-S00	1 Base Shelf per  D/F Starter  D/F Adder  D/F Starter	Side 42" x 37-3/16" x 20" 42" x 36-3/16" x 20" 42" x 37-3/16" x 24"	101 86 124	\$1,512 \$1,130 \$1,573	\$1,588 \$1,186


 $For details \ regarding \ Clip \ \& \ Strip \ Shelving, \ Sub \ Tops \ or \ Individual \ HPL \ Tops, \ please \ reference \ the \ Modifications \ \& \ Up \ Charges \ Section \ located \ on \ page \ MOD \ 8.$ 

#### Picture Book Shelving


Picture Book Shelving is 12"D with six (6) hardboard dividers per shelf. A 2"H, solid wood back keeps dividers in place.




0ak	Maple				0ak	Maple	
Catalog No.	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Price	
2 Adjustable	e Picture Book	with Divider Sh	elves and 1 Base Shelf				60-1/2"H Wood Picture Book Shelves
S1-931-S00	1S-931-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	105	\$1,276	\$1,340	
S2-931-S00	2S-931-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	90	\$920	\$966	



<u> 1 Adjustabl</u>	e Picture Book	with Divider Sh	nelves and 1 Base Shelf				48"H Wood
S1-929-S00	1S-929-S00	S/F Starter	48" x 37-3/16" x 12"	86	\$1,182	\$1,241	Picture Book Shelves
S2-929-S00	2S-929-S00	S/F Adder	48" x 36-3/16" x 12"	76	\$882	\$926	



1 Adjustabl	e Picture Book	with Divider She	elves and 1 Base Shelf				42"H Wood
S1-932-S00	1S-932-S00	S/F Starter	42" x 37-3/16" x 12"	78	\$982	\$1,031	Picture Book Shelves
S2-932-S00	2S-932-S00	S/F Adder	42" x 36-3/16" x 12"	68	\$703	\$739	



Please specify Wood Finish (Table 1). Details can be found on page GEN 4.


For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.




#### Picture Book Shelving

Picture Book Shelving is 12"D with six (6) hardboard dividers per shelf. A 2"H, solid wood back keeps dividers in place.


	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
60-1/2"H Wood Picture Book Shelves	<u> 2 Adjustabl</u>	e Picture Book	with Divider Sh	nelves and 1 Base Shelf	per Side		
	\$1-933-\$00 \$2-933-\$00	1S-933-S00 2S-933-S00	D/F Starter D/F Adder	60-1/2" x 37-3/16" x 24" 60-1/2" x 36-3/16" x 24"	180 152	\$2,430 \$1,780	\$2,551 \$1,869



48"H Wood	<u>1 Adjustabl</u>	e Picture Book	with Divider Sh	elves and 1 Base Shelf p	oer Side		
Picture Book Shelves	S1-930-S00	1S-930-S00	D/F Starter	48" x 37-3/16" x 24"	149	\$1,887	\$1,981
	S2-930-S00	2S-930-S00	D/F Adder	48" x 36-3/16" x 24"	130	\$1,449	\$1,522



42"H Wood	<u>1 Adjustabl</u>	e Picture Book	with Divider Sh	nelves and 1 Base Shelf	oer Side		
Picture Book Shelves	S1-934-S00	1S-934-S00	D/F Starter	42" x 37-3/16" x 24"	130	\$1,684	\$1,768
	S2-934-S00	2S-934-S00	D/F Adder	42" x 36-3/16" x 24"	110	\$1,373	\$1,442



Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

#### **Glass Door Shelving**

Each unit has sliding 1/4" thick laminated glass doors to protect shelved items. A solid back and door lock ensures safe storage. Door pulls are provided. Doors slide smoothly in aluminum tracks at top and bottom. Wood shelves are 9"D.



		Maple	0ak Drigo	W# (lbo)	HxWxD	Description	Maple Catalog No.	Oak
		Price	Price	Wt. (lbs.)	HXWXD	Description	Catalog No.	Catalog No.
82"H Wood Shelves	82"				1 Base Shelf	red Shelf and	e Shelves, 1 Fix	<u>4 Adjustabl</u>
	TETTO	\$5,542	\$5,278	290	82" x 37-3/16" x 12"	S/F Starter	1S-950-S00	S1-950-S00
	灵姜	\$4,869	\$4,637	260	82" x 36-3/16" x 12"	S/F Adder	2S-950-S00	S2-950-S00
	7							
	<b>当</b> 夏							

1 Adiustahl	e Shelves and	1 Rasa Shalf					72"	H Wood Shelves
\$1-885-\$00 \$2-885-\$00	1S-885-S00 2S-885-S00	S/F Starter S/F Adder	72" x 37-3/16" x 12" 72" x 36-3/16" x 12"	270 240	\$4,855 \$4,266	\$5,098 \$4,479		

4 Adjustable	e Shelves and	1 Base Shelf					60-1/2"	H Wood Shelves
S1-954-S00 S2-954-S00	1S-954-S00 2S-954-S00	S/F Starter S/F Adder	60-1/2" x 37-3/16" x 12" 60-1/2" x 36-3/16" x 12"	230 200	\$4,466 \$3,960	\$4,690 \$4,158		

2 Adjustabl	e Shelves and	1 Base Shelf					48"H Wood Shelves	
S1-955-S00	1S-955-S00	S/F Starter	48" x 37-3/16" x 12"	200	\$4,015	\$4,216		
S2-955-S00	2S-955-S00	S/F Adder	48" x 36-3/16" x 12"	160	\$3,571	\$3,750		

2 Adjustable Shelves and 1 Base Shelf									
S1-680-S00	1S-680-S00	S/F Starter	42" x 37-3/16" x 12"	180	\$3,563	\$3,742			
S2-680-S00	2S-680-S00	S/F Adder	42" x 36-3/16" x 12"	140	\$3,188	\$3,348			

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.







#### **Glass Door Shelving**

Each unit has sliding 1/4" thick laminated glass doors to protect shelved items. A solid back and door lock ensures safe storage. Door pulls are provided. Doors slide smoothly in aluminum tracks at top and bottom. Wood shelves are 9"D.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
82"H Wood Shelves	4 Adjustable	Shelves, 1 Fi.	xed Shelf and	1 Base Shelf per Side			
	\$1-690-\$00 \$2-690-\$00	1S-690-S00 2S-690-S00	D/F Starter D/F Adder	82" x 37-3/16" x 24" 82" x 36-3/16" x 24"	551 494	\$9,060 \$8,605	\$9,513 \$9,035

#### 72"H Wood Shelves



#### 4 Adjustable Shelves and 1 Base Shelf per Side

S1-886-S00	1S-886-S00	D/F Starter	72" x 37-3/16" x 24"	513	\$8,153	\$8,560
S2-886-S00	2S-886-S00	D/F Adder	72" x 36-3/16" x 24"	456	7,744	\$8,131

# 60-1/2"H Wood Shelves



#### 4 Adjustable Shelves and 1 Base Shelf per Side

S1-691-S00	1S-691-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	437	\$7,377	\$7,746
S2-691-S00	2S-691-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	380	\$6,958	\$7,306

#### 48"H Wood Shelves



#### 2 Adjustable Shelves and 1 Base Shelf per Side

S1-682-S00	1S-682-S00	D/F Starter	48" x 37-3/16" x 24"	380	\$6,778	\$7,117
S2-682-S00	2S-682-S00	D/F Adder	48" x 36-3/16" x 24"	304	\$6.494	\$6.819

# 42"H Wood Shelves



#### 2 Adjustable Shelves and 1 Base Shelf per Side

S1-681-S00	1S-681-S00	D/F Starter	42" x 37-3/16" x 24"	342	\$6,075	\$6,379
S2-681-S00	2S-681-S00	D/F Adder	42" x 36-3/16" x 24"	266	\$5,818	\$6,109

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
5 Sloping Sl	helves, 4 Flat S	helves (1 Fixe	d Shelf) and 1 Base	Shelf .		
S1-918-S00	1S-918-S00	S/F Starter	82" x 37-3/16" x 12"	120	\$2,009	\$2,109
S2-918-S00	2S-918-S00	S/F Adder	82" x 36-3/16" x 12"	100	\$1,528	\$1,604



82"H Wood Periodical Display Shelves



# 4 Sloping Shelves, 3 Flat Shelves and 1 Base Shelf


S1-875-S00	1S-875-S00	S/F Starter	72" x 37-3/16" x 12"	114	\$1,743	\$1,830
S2-875-S00	2S-875-S00	S/F Adder	72" x 36-3/16" x 12"	95	\$1,304	\$1,369






#### 3 Sloping Shelves, 2 Flat Shelves and 1 Base Shelf


S1-920-S00	1S-920-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	105	\$1,473	\$1,547
S2-920-S00	2S-920-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	90	\$1,080	\$1,134



#### 2 Sloping Shelves, 1 Flat Shelf and 1 Base Shelf

S1-919-S00	1S-919-S00	S/F Starter	48" x 37-3/16" x 12"	90	\$1,290	\$1,354
S2-919-S00	2S-919-S00	S/F Adder	48" x 36-3/16" x 12"	80	\$996	\$1,046





#### 2 Sloping Shelves, 1 Flat Shelf and 1 Base Shelf

S1-921-S00	1S-921-S00	S/F Starter	42" x 37-3/16" x 12"	80	\$1,113	\$1,169
S2-921-S00	2S-921-S00	S/F Adder	42" x 36-3/16" x 12"	70	\$913	\$958

42"H Wood Periodical Display Shelves



Please specify Wood Finish (Table 1). Details can be found on page GEN 4. For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

Wt.

0ak

Maple




#### Periodical Display Shelving

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system splay shelf has a 13-3/4"H clear display area.

	but they do not tilt. Each slopi	ng display
	Oak Catalog No.	Maple Catalog
82"H Wood Periodical Display Sh	nelves <u>5 Sloping</u> S	Shelves,
	\$1,922,500	15-922

-	5		=
=	4		=
	4	=	
	6	-	
	4		
	3	-	

Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
5 Sloping S	helves, 4 Fla	t Shelves (1 F	Fixed Shelf) and 1 Bas	e Shelf pe	er Side	
S1-922-S00	1S-922-S00	D/F Starter	82" x 37-3/16" x 24"	230	\$3,644	\$3,826
S2-922-S00	2S-922-S00	D/F Adder	82" x 36-3/16" x 24"	194	\$3,068	\$3,222



4 Sloping S	Shelves, 3 Fla	t Shelves an	d 1 Base Shelf per Side	<u>9</u>		
S1-876-S00	1S-876-S00	D/F Starter	72" x 37-3/16" x 24"	210	\$3,316	\$3,482
S2-876-S00	2S-876-S00	D/F Adder	72" x 36-3/16" x 24"	180	\$2,793	\$2,932



3 Sloping S	helves, 2 Fla	t Shelves ar	nd 1 Base Shelf per Side			
S1-923-S00	1S-923-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	185	\$2,624	\$2,755
S2-923-S00	2S-923-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	157	\$2,060	\$2,163



2 Sloping Shelves, 1 Flat Shelf and 1 Base Shelf per Side									
S1-925-S00	1S-925-S00	D/F Starter	48" x 37-3/16" x 24"	150	\$2,362	\$2,480			
S2-925-S00	2S-925-S00	D/F Adder	48" x 36-3/16" x 24"	130	\$1,794	\$1,883			



2 Sloping Shelves, 1 Flat Shelf and 1 Base Shelf per Side									
0 \$2,106 \$2,211 1 \$1.528 \$1.604									
3									


Please specify Wood Finish (Table 1). Details can be found on page GEN 4. For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

#### Tilt and Store Shelving

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

Note: Tilt and Store Shelving is available in 16" depth ONLY.

Oak	Maple				Oak	Maple
Catalog No.	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Price
5 Tilting She	elves, 4 Flat Sl	helves (1 Fixed	d Shelf) and 1 Base S	helf		
S1-935-S00	1S-935-S00	S/F Starter	82" x 37-3/16" x 16"	250	\$2,432	\$2,553
S2-935-S00	2S-935-S00	S/F Adder	82" x 36-3/16" x 16"	214	\$1,956	\$2,054



82"H Wood Tilt & Store Shelves



# 4 Tilting Shelves, 3 Flat Shelves and 1 Base Shelf

S1-880-S00	1S-880-S00	S/F Starter	72" x 37-3/16" x 16"	220	\$2,213	\$2,324
S2-880-S00	2S-880-S00	S/F Adder	72" x 36-3/16" x 16"	180	\$1,780	\$1,869





#### 3 Tilting Shelves, 2 Flat Shelves and 1 Base Shelf

S1-936-S00	1S-936-S00	S/F Starter	60-1/2" x 37-3/16" x 16"	180	\$1,876	\$1,970
S2-936-S00	2S-936-S00	S/F Adder	60-1/2" x 36-3/16" x 16"	130	\$1,426	\$1,497





## 2 Tilting Shelves, 1 Flat Shelf and 1 Base Shelf

S1-938-S00	1S-938-S00	S/F Starter	48" x 37-3/16" x 16"	120	\$1,634	\$1,716
S2-938-S00	2S-938-S00	S/F Adder	48" x 36-3/16" x 16"	110	\$1,251	\$1,314


48"H Wood Tilt & Store Shelves



#### 2 Tilting Shelves, 1 Flat Shelf and 1 Base Shelf


S1-937-S00	1S-937-S00	S/F Starter	42" x 37-3/16" x 16"	100	\$1,391	\$1,460
S2-937-S00	2S-937-S00	S/F Adder	42" x 36-3/16" x 16"	90	\$1,075	\$1,129

42"H Wood Tilt & Store Shelves



Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.




#### Tilt and Store Shelving

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

Note: Tilt and Store Shelving is available in 16" depth ONLY.

82"H Wood Tilt & Sto	re Shelves



Uak	iviapie				Uak	iviapie
Catalog No.	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Price
5 Tilting She	lves, 4 Flat Sh	nelves and 1 B	Base Shelf per Side			
S1-945-S00	1S-945-S00	D/F Starter	82" x 37-3/16" x 32"	450	\$4,379	\$4,596
S2-945-S00	2S-945-S00	D/F Adder	82" x 36-3/16" x 32"	385	\$3,521	\$3,698

#### 72"H Wood Tilt & Store Shelves



4 Tilting Shelves, 3 Flat Shelves and 1 Base Shelf per Side									
S1-840-S00	1S-840-S00	D/F Starter	72" x 37-3/16" x 32"	396	\$3,985	\$4,183			
S2-840-S00	2S-840-S00	D/F Adder	72" x 36-3/16" x 32"	324	\$3,203	\$3,364			

#### 60-1/2"H Wood Tilt & Store Shelves



3 Tilting Shelves, 2 Flat Shelves and 1 Base Shelf per Side										
S1-946-S00	1S-946-S00	D/F Starter	60-1/2" x 37-3/16" x 32"	324	\$3,377	\$3,546				
S2-946-S00	2S-946-S00	D/F Adder	60-1/2" x 36-3/16" x 32"	234	\$2,565	\$2,694				

#### 48"H Wood Tilt & Store Shelves



S1-948-S00	1S-948-S00	D/F Starter	48" x 37-3/16" x 32"	216	\$2,940	\$3,088
S2-948-S00	2S-948-S00	D/F Adder	48" x 36-3/16" x 32"	198	\$2,250	\$2,364

#### 42"H Wood Tilt & Store Shelves



2 Tilting Shelves,	1 Flat Shelf an	d 1 Base Shelf	per Side
			•

2 Tilting Shelves, 1 Flat Shelf and 1 Base Shelf per Side

S1-947-S00	1S-947-S00	D/F Starter	42" x 37-3/16" x 32"	180	\$2,504	\$2,629
S2-947-S00	2S-947-S00	D/F Adder	42" x 36-3/16" x 32"	162	\$1,934	\$2,033

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Ans son
5 Adjustable	e Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Wood Base	e Shelf			90"H Omega Shelves
S5-960-S00	5S-960-S00	S/F Starter	90" x 37-3/16" x 10"	103	\$1,238	\$1,301	
S6-960-S00	6S-960-S00	S/F Adder	90" x 36-3/16" x 10"	90	\$938	\$985	
S5-967-S00	5S-967-S00	S/F Starter	90" x 37-3/16" x 12"	122	\$1,393	\$1,463	
S6-967-S00	6S-967-S00	S/F Adder	90" x 36-3/16" x 12"	102	\$1,002	\$1,052	

4 Adjustable	e Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Wood Base	<u>Shelf</u>			82"H (	Omega Shelves
S5-976-S00	5S-976-S00	S/F Starter	82" x 37-3/16" x 10"	93	\$1,130	\$1,186	TET	9
S6-976-S00	6S-976-S00	S/F Adder	82" x 36-3/16" x 10"	80	\$858	\$901		
S5-977-S00	5S-977-S00	S/F Starter	82" x 37-3/16" x 12"	112	\$1,268	\$1,331		
S6-977-S00	6S-977-S00	S/F Adder	82" x 36-3/16" x 12"	92	\$929	\$975		

4 Adjustabl	e Metal Shelve	s and 1 Wood B	ase Shelf				72"H Omega Shelve
S5-861-S00	5S-861-S00	S/F Starter	72" x 37-3/16" x 10"	88	\$1,031	\$1,082	
S6-861-S00	6S-861-S00	S/F Adder	72" x 36-3/16" x 10"	75	\$787	\$826	
S5-863-S00	5S-863-S00	S/F Starter	72" x 37-3/16" x 12"	102	\$1,156	\$1,214	
S6-863-S00	6S-863-S00	S/F Adder	72" x 36-3/16" x 12"	87	\$862	\$905	

4 Adjustable	e Metal Shelve	s and 1 Wood E	Base Shelf				60-1/2"H Omega Shelve
S5-979-S00	5S-979-S00	S/F Starter	60-1/2" x 37-3/16" x 10"	75	\$933	\$979	
S6-979-S00	6S-979-S00	S/F Adder	60-1/2" x 36-3/16" x 10"	65	\$714	\$750	
S5-988-S00	5S-988-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	96	\$1,046	\$1,098	
S6-988-S00	6S-988-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	81	\$794	\$833	

Ane on	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
48"H Omega Shelves	2 Adjustabl	e Metal Shelve	es and 1 Wood Ba	se Shelf			
	S5-761-S00	5S-761-S00	S/F Starter	48" x 37-3/16" x 10"	71	\$801	\$840
	S6-761-S00	6S-761-S00	S/F Adder	48" x 36-3/16" x 10"	63	\$584	\$614
	S5-762-S00	5S-762-S00	S/F Starter	48" x 37-3/16" x 12"	84	\$851	\$894
	S6-762-S00	6S-762-S00	S/F Adder	48" x 36-3/16" x 12"	74	\$613	\$644

42"H Omega Shelves	2 Adjustabl	e Metal Shelve	s and 1 Wood B	ase Shelf			
	S5-981-S00	5S-981-S00	S/F Starter	42" x 37-3/16" x 10"	61	\$765	\$803
	S6-981-S00	6S-981-S00	S/F Adder	42" x 36-3/16" x 10"	53	\$551	\$578
	S5-989-S00	5S-989-S00	S/F Starter	42" x 37-3/16" x 12"	74	\$802	\$842
	S6-989-S00	6S-989-S00	S/F Adder	42" x 36-3/16" x 12"	64	\$568	\$597

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Three 3th
5 Adjustable	Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Wood Base	e Shelf per Si	<u>de</u>		90"H Omega Shelves
S5-969-S00	5S-969-S00	D/F Starter	90" x 37-3/16" x 20"	185	\$2,080	\$2,184	
S6-969-S00	6S-969-S00	D/F Adder	90" x 36-3/16" x 20"	153	\$1,565	\$1,644	
S5-973-S00	5S-973-S00	D/F Starter	90" x 37-3/16" x 24"	224	\$2,493	\$2,618	
S6-973-S00	6S-973-S00	D/F Adder	90" x 36-3/16" x 24"	188	\$1,731	\$1,818	
						Į	

4 Adjustable	e Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Wood Base	Shelf per S	<u>ide</u>		82"	H Omega Shelves
S5-983-S00	5S-983-S00	D/F Starter	82" x 37-3/16" x 20"	175	\$1,976	\$2,075		
S6-983-S00	6S-983-S00	D/F Adder	82" x 36-3/16" x 20"	143	\$1,518	\$1,594		
S5-990-S00	5S-990-S00	D/F Starter	82" x 37-3/16" x 24"	214	\$2,325	\$2,442		
S6-990-S00	6S-990-S00	D/F Adder	82" x 36-3/16" x 24"	178	\$1,675	\$1,758		

4 Adjustabl	Adjustable Metal Shelves and 1 Wood Base Shelf per Side							Omega Shelves
S5-865-S00	5S-865-S00	D/F Starter	72" x 37-3/16" x 20"	160	\$1,876	\$1,970		
66-865-S00	6S-865-S00	D/F Adder	72" x 36-3/16" x 20"	128	\$1,471	\$1,545		
S5-866-S00	5S-866-S00	D/F Starter	72" x 37-3/16" x 24"	199	\$2,171	\$2,279		
S6-866-S00	6S-866-S00	D/F Adder	72" x 36-3/16" x 24"	163	\$1,620	\$1,701		

4 Adjustabl	e Metal Shelve	s and 1 Wood E	Base Shelf per Side				60-1/2"H	Omega Shelve
S5-985-S00	5S-985-S00	D/F Starter	60-1/2" x 37-3/16" x 20"	139	\$1,779	\$1,868		
S6-985-S00	6S-985-S00	D/F Adder	60-1/2" x 36-3/16" x 20"	115	\$1,425	\$1,496		
S5-986-S00	5S-986-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	170	\$2,015	\$2,116		
S6-986-S00	6S-986-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	142	\$1,563	\$1,642		

Tro SAN	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price				
48"H Omega Shelves	2 Adjustabl	e Metal Shelve	s and 1 Wood Ba	se Shelf per Side							
	S5-765-S00	5S-765-S00	D/F Starter	48" x 37-3/16" x 20"	111	\$1,405	\$1,475				
	S6-765-S00	6S-765-S00	D/F Adder	48" x 36-3/16" x 20"	96	\$1,031	\$1,082				
	S5-766-S00	5S-766-S00	D/F Starter	48" x 37-3/16" x 24"	134	\$1,518	\$1,594				
	S6-766-S00	6S-766-S00	D/F Adder	48" x 36-3/16" x 24"	111	\$1,138	\$1,195				

42"H Omega Shelves	2 Adjustabl	le Metal Shelve	es and 1 Wood B	ase Shelf per Side							
	S5-987-S00	5S-987-S00	D/F Starter	42" x 37-3/16" x 20"	101	\$1,311	\$1,376				
	S6-987-S00	6S-987-S00	D/F Adder	42" x 36-3/16" x 20"	86	\$933	\$979				
	S5-991-S00	5S-991-S00	D/F Starter	42" x 37-3/16" x 24"	124	\$1,393	\$1,463				
	S6-991-S00	6S-991-S00	D/F Adder	42" x 36-3/16" x 24"	105	\$1,032	\$1,083				

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Ime in
5 Adjustable	e Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Metal Base	e Shelf			90"H Omega
S7-960-S00	7S-960-S00	S/F Starter	90" x 37-3/16" x 10"	103	\$1,238	\$1,301	Book Stop Shelves
S8-960-S00	8S-960-S00	S/F Adder	90" x 36-3/16" x 10"	90	\$938	\$985	
S7-967-S00	7S-967-S00	S/F Starter	90" x 37-3/16" x 12"	122	\$1,393	\$1,463	
S8-967-S00	85-967-S00	S/F Adder	90" x 36-3/16" x 12"	102	\$1,002	\$1,052	

<u> 4 Adjustable</u>	Metal Shelves,	1 Fixed Metal She	lf and 1 Metal Base St	<u>nelf</u>		
S7-976-S00	7S-976-S00	S/F Starter	82" x 37-3/16" x 10"	93	\$1,265	\$1,328
S8-976-S00	8S-976-S00	S/F Adder	82" x 36-3/16" x 10"	80	\$985	\$1,034
S7-977-S00	7S-977-S00	S/F Starter	82" x 37-3/16" x 12"	112	\$1,425	\$1,496
S8-977-S00	8S-977-S00	S/F Adder	82" x 36-3/16" x 12"	92	\$1,059	\$1,111



4 Adjustable Metal Shelves and 1 Metal Base Shelf								
S7-861-S00	7S-861-S00	S/F Starter	72" x 37-3/16" x 10"	88	\$1,133	\$1,190		
S8-861-S00	8S-861-S00	S/F Adder	72" x 36-3/16" x 10"	75	\$884	\$928		
S7-863-S00	7S-863-S00	S/F Starter	72" x 37-3/16" x 12"	102	\$1,295	\$1,359		
S8-863-S00	8S-863-S00	S/F Adder	72" x 36-3/16" x 12"	87	\$960	\$1,008		

Во	ook Stop Shelve
TET	-

72"H Omega

4 Adjustable Metal Shelves and 1 Metal Base Shelf								
S7-979-S00	7S-979-S00	S/F Starter	60-1/2" x 37-3/16" x 10"	75	\$1,002	\$1,052		
S8-979-S00	8S-979-S00	S/F Adder	60-1/2" x 36-3/16" x 10"	65	\$784	\$823		
S7-988-S00	7S-988-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	96	\$1,165	\$1,223		
S8-988-S00	8S-988-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	81	\$861	\$904		




Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Shelving Backs and Partitions CANNOT be used with Omega Book Stop Shelving.




48"H Omega Book Stop Shelves



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
2 Adjustable	e Metal Shelves	s and 1 Metal Ba	se Shelf			
S7-761-S00	7S-761-S00	S/F Starter	48" x 37-3/16" x 10"	71	\$843	\$885
S8-761-S00	8S-761-S00	S/F Adder	48" x 36-3/16" x 10"	63	\$627	\$658
S7-762-S00	7S-762-S00	S/F Starter	48" x 37-3/16" x 12"	84	\$914	\$959
S8-762-S00	8S-762-S00	S/F Adder	48" x 36-3/16" x 12"	74	\$661	\$694

42"H Omega Book Stop Shelves



2 Adjustable Metal Shelves and 1 Metal Base Shelf								
S7-981-S00	7S-981-S00	S/F Starter	42" x 37-3/16" x 10"	61	\$804	\$844		
S8-981-S00	8S-981-S00	S/F Adder	42" x 36-3/16" x 10"	53	\$587	\$617		
S7-989-S00	7S-989-S00	S/F Starter	42" x 37-3/16" x 12"	74	\$851	\$894		
S8-989-S00	8S-989-S00	S/F Adder	42" x 36-3/16" x 12"	64	\$613	\$644		

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 


Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Shelving Backs and Partitions CANNOT be used with Omega Book Stop Shelving.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	Ino
5 Adjustabl	le Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Metal Base	Shelf per Sid	<u>de</u>		90"H Omega
S7-969-S00	7S-969-S00	D/F Starter	90" x 37-3/16" x 20"	185	\$2,420	\$2,541	Book Stop Shelves
S8-969-S00	8S-969-S00	D/F Adder	90" x 36-3/16" x 20"	153	\$1,883	\$1,977	
S7-973-S00	7S-973-S00	D/F Starter	90" x 37-3/16" x 24"	224	\$2,847	\$2,990	
S8-973-S00	8S-973-S00	D/F Adder	90" x 36-3/16" x 24"	188	\$2,057	\$2,159	
4 Adjustabl	le Metal Shelve	s, 1 Fixed Metal	Shelf and 1 Metal Base	Shelf per Sig	<u>de</u>		82"H Omega
S7-983-S00	7S-983-S00	D/F Starter	82" x 37-3/16" x 20"	175	\$2,243	\$2,355	Book Stop Shelves
S8-983-S00	8S-983-S00	D/F Adder	82" x 36-3/16" x 20"	143	\$1,771	\$1,859	
\$7-990-\$00 \$8-990-\$00	7S-990-S00 8S-990-S00	D/F Starter D/F Adder	82" x 37-3/16" x 24" 82" x 36-3/16" x 24"	214 178	\$2,601 \$1,927	\$2,730 \$2,023	
4 Adjustabl	le Metal Shelve	s and 1 Metal Ba	ase Shelf per Side				72"H Omega Book Stop Shelves
S7-865-S00	7S-865-S00	D/F Starter	72" x 37-3/16" x 20"	160	\$2,079	\$2,183	DOOK Stop Shelves
S8-865-S00	8S-865-S00	D/F Adder	72" x 36-3/16" x 20"	128	\$1,665	\$1,748	
S7-866-S00	7S-866-S00	D/F Starter	72" x 37-3/16" x 24"	199	\$2,377	\$2,496	
S8-866-S00	8S-866-S00	D/F Adder	72" x 36-3/16" x 24"	163	\$1,805	\$1,895	
4 Adjustabl	le Metal Shelve	s and 1 Metal Ba	ase Shelf per Side				60-1/2"H Omega
S7-985-S00	7S-985-S00	D/F Starter	60-1/2" x 37-3/16" x 20"	139	\$1,914	\$2,009	Book Stop Shelves
S8-985-S00	8S-985-S00	D/F Adder	60-1/2" x 36-3/16" x 20"	115	\$1,561	\$1,639	
S7-986-S00	7S-986-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	170	\$2,149	\$2,256	
\$8-986-\$00	8S-986-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	142	\$1,685	\$1,769	

Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Shelving Backs and Partitions CANNOT be used with Omega Book Stop Shelving.




48"H Omega Book Stop Shelves



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
2 Adjustable	e Metal Shelve	s and 1 Metal Ba	ase Shelf per Side			
S7-765-S00	7S-765-S00	D/F Starter	48" x 37-3/16" x 20"	111	\$1,493	\$1,568
S8-765-S00	8S-765-S00	D/F Adder	48" x 36-3/16" x 20"	96	\$1,119	\$1,175
S7-766-S00	7S-766-S00	D/F Starter	48" x 37-3/16" x 24"	134	\$1,605	\$1,685
S8-766-S00	8S-766-S00	D/F Adder	48" x 36-3/16" x 24"	111	\$1,224	\$1,285

42"H Omega Book Stop Shelves



2 Adjustable Metal Shelves and 1 Metal Base Shelf per Side							
S7-987-S00	7S-987-S00	D/F Starter	42" x 37-3/16" x 20"	101	\$1,389	\$1,458	
S8-987-S00	8S-987-S00	D/F Adder	42" x 36-3/16" x 20"	86	\$1,009	\$1,059	
S7-991-S00	7S-991-S00	D/F Starter	42" x 37-3/16" x 24"	124	\$1,470	\$1,544	
S8-991-S00	8S-991-S00	D/F Adder	42" x 36-3/16" x 24"	105	\$1,109	\$1,165	

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.

Note: Each metal display shelf receives 6 metal dividers per shelf.




Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price		
5 Display M	letal Shelves, 3	Adjustable Me	tal Shelves, 1 Fixed	Metal Shelf a	and 1 Wood Ba	ase Shelf	82"	H Omega Periodical
S7-918-S00	7S-918-S00	S/F Starter	82" x 37-3/16" x 12"	120	\$1,949	\$2,047		Display Shelves
S8-918-S00	8S-918-S00	S/F Adder	82" x 36-3/16" x 12"	100	\$1,483	\$1,557		TIT

4 Display Metal Shelves, 3 Adjustable Metal Shelves and 1 Wood Base Shelf

 \$7.875-\$00
 7\$-875-\$00
 \$\$/F Starter
 72" x 37-3/16" x 12"
 270
 \$1,691
 \$1,776

 \$8-875-\$00
 \$5/F Adder
 72" x 36-3/16" x 12"
 240
 \$1,266
 \$1,329

72"H Omega Periodical Display Shelves




3 Display Metal Shelves, 2 Adjustable Metal Shelves and 1 Wood Base Shelf

 \$7.920-\$00
 7\$-920-\$00
 \$/F Starter
 60-1/2" x 37-3/16" x 12"
 230
 \$1,431
 \$1,502

 \$8.920-\$00
 \$5/F Adder
 60-1/2" x 36-3/16" x 12"
 200
 \$1,048
 \$1,100

60-1/2"H Omega Periodical Display Shelves






Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.



Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.


Note: Each metal display shelf receives 6 metal dividers per shelf.

48"H Omega Periodical
Display Shelves



Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
2 Display Me	etal Shelves, 1	Adjustable Me	etal Shelf and 1 Woo	nd Base Shel	f	
\$7-919-\$00 \$8-919-\$00	7S-919-S00 8S-919-S00	S/F Starter S/F Adder	48" x 37-3/16" x 12" 48" x 36-3/16" x 12"	200 160	\$1,251 \$967	\$1,314 \$1,016

# 42"H Omega Periodical Display Shelves



<u> 2 Display M</u>	2 Display Metal Shelves, 1 Adjustable Metal Shelf and 1 Wood Base Shelf									
S7-921-S00	7S-921-S00	S/F Starter	42" x 37-3/16" x 12"	180	\$1,079	\$1,133				
002-150-92	95-021-500	S /E Addor	12" v 26_2 /16" v 12"	1//0	4994	¢03U				

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.

Note: Each metal display shelf receives 6 metal dividers per shelf.




Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
	letal Shelves, 3 d Base Shelf pe		etal Shelves, 1 Fixed	d Metal Shelf			82"H Omega Periodical Display Shelves
\$7-922-\$00 \$8-922-\$00	7S-922-S00 8S-922-S00	D/F Starter D/F Adder	82" x 37-3/16" x 24" 82" x 36-3/16" x 24"	230 194	\$3,536 \$2,977	\$3,713 \$3,126	

S7-876-S00	7S-876-S00	D/F Starter	72" x 37-3/16" x 24"	210	\$3,217	\$3,378	Display Shelves
S8-876-S00	8S-876-S00	D/F Adder	72" x 36-3/16" x 24"	180	\$2,709	\$2,845	

3 Dispiay IVI	<u>etai Sneives, 2</u>	<u> Adjustable l</u>	Metal Shelves and 1 Wo	od Base S	<u>sneit per Siae</u>		60-1/2"H Omega Periodical
S7-923-S00	7S-923-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	185	\$2,546	\$2,673	Display Shelves
\$8-923-\$00	8S-923-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	157	\$1,999	\$2,099	


 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 



Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.


Note: Each metal display shelf receives 6 metal dividers per shelf.

48"H Omega Periodical	
Display Shelves	



	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
	2 Display Me	etal Shelves,	1 Adjustable Me	etal Shelf and 1 Woo	od Base Shel	f per side	
<b>-</b> 1	\$7-925-\$00 \$8-925-\$00	7S-925-S00 8S-925-S00	D/F Starter D/F Adder	48" x 37-3/16" x 24" 48" x 36-3/16" x 24"	150 130	\$2,292 \$1,740	\$2,406 \$1,827

# 42"H Omega Periodical Display Shelves



<u> 2 Display M</u>	<u>etal Shelves, 1</u>	Adjustable M	<u>letal Shelf and 1 Woo</u>	d Base She	elf per side	
S7-924-S00	7S-924-S00	D/F Starter	42" x 37-3/16" x 12"	130	\$2,044	\$2,146
S8-924-S00	8S-924-S00	D/F Adder	42" x 36-3/16" x 12"	111	\$1,483	\$1,557


Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

#### Metal Tilt and Store Shelving

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

Note: Tilt and Store Shelving is available in 16" depth ONLY.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
5 Tilting Me	tal Shelves, 4 F	lat Wood Shelv	ves and 1 Wood Base	<u>Shelf</u>		
\$7-935-\$00 \$8-935-\$00	7S-935-S00 8S-935-S00	S/F Starter S/F Adder	82" x 37-3/16" x 16" 82" x 36-3/16" x 16"	250 214	\$2,520 \$2,116	\$2,646 \$2,222





82"H Omega Tilt & Store Shelves



#### 4 Tilting Metal Shelves, 3 Flat Wood Shelves and 1 Wood Base Shelf

S7-880-S00	7S-880-S00	S/F Starter	72" x 37-3/16" x 16"	220	\$2,390	\$2,509
S8-880-S00	8S-880-S00	S/F Adder	72" x 36-3/16" x 16"	180	\$1,879	\$1,973






# 3 Tilting Metal Shelves, 2 Flat Wood Shelves and 1 Wood Base Shelf

S7-936-S00	7S-936-S00	S/F Starter	60-1/2" x 37-3/16" x 16"	180	\$2,260	\$2,373
S8-936-S00	8S-936-S00	S/F Adder	60-1/2" x 36-3/16" x 16"	130	\$1,639	\$1,721

60-1/2"H Omega Tilt & Store Shelves



2 Tilting Metal Shelves,	1 Flat Wood Shelves and 1 Wood Base Shelf
--------------------------	---

S7-938-S00	7S-938-S00	S/F Starter	48" x 37-3/16" x 16"	120	\$2,016	\$2,117
S8-938-S00	8S-938-S00	S/F Adder	48" x 36-3/16" x 16"	110	\$1,543	\$1,620

48"H Omega Tilt & Store Shelves





#### 2 Tilting Metal Shelves, 1 Flat Wood Shelves and 1 Wood Base Shelf


S7-937-S00	7S-937-S00	S/F Starter	42" x 37-3/16" x 16"	100	\$1,773	\$1,861
S8-937-S00	8S-937-S00	S/F Adder	42" x 36-3/16" x 16"	90	\$1,445	\$1,518

42"H Omega Tilt & Store Shelves





Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.




#### Metal Tilt and Store Shelving

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.


Note: Tilt and Store Shelving is available in 16" depth ONLY.

001111	O	T:14 0	C+	Clark
8Z H	umeda	א זווו	Store	Shelves




Uak	iviapie				Uak	iviapie				
Catalog No.	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Price				
5 Tilting Metal Shelves, 4 Flat Wood Shelves and 1 Wood Base Shelf per Side										
S7-945-S00	7S-945-S00	D/F Starter	82" x 37-3/16" x 32"	450	\$4,535	\$4,763				
S8-945-S00	8S-945-S00	D/F Adder	82" x 36-3/16" x 32"	385	\$3,810	\$3,999				

# 72"H Omega Tilt & Store Shelves



4 Tilting Metal Shelves, 3 Flat Wood Shelves and 1 Wood Base Shelf per Side									
S7-840-S00	7S-840-S00	D/F Starter	72" x 37-3/16" x 32"	396	\$4,303	\$4,517			
S8-840-S00	8S-840-S00	D/F Adder	72" x 36-3/16" x 32"	324	\$3,381	\$3,551			

## 60-1/2"H Omega Tilt & Store Shelves



3 Tilting Metal Shelves, 2 Flat Wood Shelves and 1 Wood Base Shelf per Side								
S7-946-S00	7S-946-S00	D/F Starter	60-1/2" x 37-3/16" x 32"	324	\$4,068	\$4,271		
S8-946-S00	8S-946-S00	D/F Adder	60-1/2" x 36-3/16" x 32"	234	\$2,950	\$3,098		

#### 48"H Omega Tilt & Store Shelves





2 Hiting We	tai Sneives, T	FIAT WOOD SI	neives and T wood Bas	se Sneit pe	<u>er Siae</u>	
S7-948-S00	7S-948-S00	D/F Starter	48" x 37-3/16" x 32"	216	\$3,629	
S8-948-S00	8S-948-S00	D/F Adder	48" x 36-3/16" x 32"	198	\$2,777	

\$3,810

\$2,916

#### 42"H Omega Tilt & Store Shelves





2 Tilting Metal Shelves, 1 Flat Wood Shelves and 1 Wood Base Shelf per Side						
67.047.600	70 047 000	D /F Ct t	4011 27 2 /4 / 11 2011	100	<b>#0.400</b>	

 \$7-947-\$00
 7\$-947-\$00
 D/F Starter
 42" x 37-3/16" x 32"
 180
 \$3,190
 \$3,351

 \$8-947-\$00
 B\$-947-\$00
 D/F Adder
 42" x 36-3/16" x 32"
 162
 \$2,602
 \$2,732

Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.


Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.




Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	iviapie Price
4 Adjustable	e (1 Fixed) Pict	ure Book w/Di	vider Metal Shelves	and 1 Wood	Base Shelf	
S1-233-S00 S2-233-S00	1S-233-S00 2S-233-S00	S/F Starter S/F Adder	82" x 37-3/16" x 12" 82" x 36-3/16" x 12"	250 214	\$1,445 \$1,059	\$1,518 \$1,111




**Picture Book Shelves** 




4 Adjustable Picture Book w/Divider Metal Shelves and 1 Wood Base Shelf										
S1-237-S00	1S-237-S00	S/F Starter	72" x 37-3/16" x 12"	220	\$1,318	\$1,384				
\$2-237-\$00	25-237-500	S /E Addor	72" v 26_2 /16" v 12"	180	\$002	¢1 021				





<u>3 Aajustabie</u>	<u> Picture Book</u>	w/Divider ivie	<u>etai Sheives and 1 Woo</u>	<u>a Base Si</u>	<u>neir</u>	
S1-232-S00	1S-232-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	180	\$1,191	\$1,251
S2-232-S00	2S-232-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	130	\$906	\$951

60-1/2"H Omega Picture Book Shelves




Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.



Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.

	0ak	Maple		HxWxD	Wt. (lbs.)	0ak	Maple
	Catalog No.	Catalog No.	Description			Price	Price
48"H Omega Picture Book Shelves	2 Adjustab	le Picture Book	w/Divider Me	tal Shelves and 1 W	ood Base She	<u>If</u>	
	S1-238-S00	1S-238-S00	S/F Starter	48" x 37-3/16" x 12"	120	\$971	\$1,020
	S2-238-S00	2S-238-S00	S/F Adder	48" x 36-3/16" x 12"	110	\$700	\$735

#### 42"H Omega Picture Book Shelves



2 Adjustable Picture Book w/Divider Metal Shelves and 1 Wood Base Shelf							
S1-231-S00	1S-231-S00	S/F Starter	42" x 37-3/16" x 12"	100	\$914	\$959	
S2-231-S00	2S-231-S00	S/F Adder	42" x 36-3/16" x 12"	90	\$647	\$679	


 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.




82"H Omega

Oак Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	iviapie Price
4 Adjustable	e (1 Fixed) Pict	ure Book w/Di	vider Metal Shelves	and 1 Wood	Base Shelf p	er Side
S1-236-S00	1S-236-S00	D/F Starter	82" x 37-3/16" x 24"	450	\$2,653	\$2,785
S2-236-S00	2S-236-S00	D/F Adder	82" x 36-3/16" x 24"	385	\$1,909	\$2,004




4 Adjustable Picture Book w/Divider Metal Shelves and 1 Wood Base Shelf per Side								
S1-247-S00	1S-247-S00	D/F Starter	72" x 37-3/16" x 24"	396	\$2,475	\$2,599		
S2-247-S00	2S-247-S00	D/F Adder	72" x 36-3/16" x 24"	324	\$1,846	\$1,939		

72"H Omega Picture Book Shelves



<u>3 Aajustable</u>	<u>Picture Book vi</u>	<u>//Diviaer ivie</u>	etai Sheives and 1 Woo	a Base S	neit per Siae	
S1-235-S00	1S-235-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	324	\$2,297	\$2,411
S2-235-S00	2S-235-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	234	\$1,782	\$1,871

60-1/2"H Omega Picture Book Shelves




 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 



Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
48"H Omega Picture Book Shelves	2 Adjustable	Picture Book w	/Divider Meta	ol Shelves and 1 Wo	od Base Sheli	f per Side	
	S1-248-S00	1S-248-S00	D/F Starter	48" x 37-3/16" x 24"	216	\$1,730	\$1,817
	\$2-248-\$00	2S-248-S00	D/F Adder	48" x 36-3/16" x 24"	198	\$1,298	\$1,363

#### 42"H Omega Picture Book Shelves



# 2 Adjustable Picture Book w/Divider Metal Shelves and 1 Wood Base Shelf per Side S1-234-S00 1S-234-S00 D/F Starter 42" x 37-3/16" x 24" 180 \$1,587 \$1,667 S2-234-S00 2S-234-S00 D/F Adder 42" x 36-3/16" x 24" 162 \$1,178 \$1,236

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

2 Adjustable Shelves and 1 Base Shelf per Side

D/F Starter

D/F Starter

D/F Starter/Adder

D/F Starter/Adder

1S-765-S07

1S-765-S08

1S-766-S07

1S-766-S08

S1-765-S07

S1-765-S08

S1-766-S07

S1-766-S08

						Cas	ters Base
Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
4 Adjustable	e Shelves and	1 Base Shelf per	<u>Side</u>				60-1/2"H Wood Shelves
S1-985-S07	1S-985-S07	D/F Starter	60-1/2" x 37-3/16" x 20"	144	\$2,515	\$2,640	
S1-985-S08	1S-985-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 20"	268	\$4,527	\$4,753	
S1-986-S07	1S-986-S07	D/F Starter	60-1/2" x 37-3/16" x 24"	190	\$2,647	\$2,779	
S1-986-S08	1S-986-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 24"	352	\$4,765	\$5,003	

117

217

154

\$1,983

\$3,570

\$2,086

\$3,758

\$2,081

\$3,749

\$2,191

\$3,946

2 Adjustable Shelves and 1 Base Shelf per Side										
S1-987-S07	1S-987-S07	D/F Starter	42" x 37-3/16" x 20"	106	\$1,850	\$1,944				
S1-987-S08	1S-987-S08	D/F Starter/Adder	42" x 73-3/8" x 20"	204	\$3,328	\$3,494				
S1-991-S07	1S-991-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$1,948	\$2,046				
S1-991-S08	1S-991-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$3,503	\$3,678				

48" x 37-3/16" x 20"

48" x 73-3/8" x 20"

48" x 37-3/16" x 24"

48" x 73-3/8" x 24"



48"H Wood Shelves

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.
For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

Note: Partitions included for Mobile Units.




# **Casters Base**

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
60-1/2"H Wood Periodical Display Shelves	3 Sloping S	helves, 2 Flat	Shelves and 1 Woo	od Base Shelf per Side			
	S1-923-S07	1S-923-S07	D/F Starter	60-1/2" x 37-3/16" x 24"	190	\$3,891	\$4,085
	S1-923-S08	1S-923-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 24"	352	\$7,004	\$7,355



48"H Wood **Periodical Display Shelves** 






42"H Wood **Periodical Display Shelves** 

2 Sloping Sl	helves, 1 Flat S	Shelves and 1 Woo	d Base Shelf per Side			
S1-924-S07	1S-924-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$2,864	\$3,007
S1-924-S08	1S-924-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$5,149	\$5,407



Please specify Wood Finish (Table 1). Details can be found on page GEN 4. For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

Note: Partitions included for Mobile Units.




1 Adjustabl	le Picture Book	48"H Wood					
\$1-930-\$07 \$1-930-\$08	1S-930-S07 1S-930-S08	D/F Starter D/F Starter/Adder	48" x 37-3/16" x 24" 48" x 73-3/8" x 24"	154 285	\$2,252 \$4,051	\$2,365 \$4,253	Picture Book Shelves

<u> 1 Adjustabl</u>	42"H Wood Picture Book Shelves						
S1-934-S07	1S-934-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$2,056	\$2,158	Picture Book Sherves
S1-934-S08	1S-934-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$3,780	\$3,969	

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.
For details regarding Clip & Strip Shelving, Sub Tops or Individual HPL Tops, please reference the Modifications & Up Charges Section located on page MOD 8.

Note: Partitions included for Mobile Units.



Please specify Wood Finish (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

D/F Starter

D/F Starter/Adder

42" x 37-3/16" x 24"

42" x 73-3/8" x 24"

140

269

\$1,849

\$3,325

\$1,942

\$3,492

S5-991-S07

S5-991-S08

5S-991-S07

5S-991-S08

Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Partitions included for Mobile Units.

						Cas	ters Base
0ak	Maple				Oak	Maple	
Catalog No.	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Price	
4 Adjustabl	e Metal Shelve	es and 1 Metal Bas	se Shelf per Side				60-1/2"H Omega Book Stop Shelves
S7-985-S07	7S-985-S07	D/F Starter	60-1/2" x 37-3/16" x 20"	144	\$3,012	\$3,163	Book Stop Shelves
S7-985-S08	7S-985-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 20"	268	\$5,291	\$5,555	
S7-986-S07	7S-986-S07	D/F Starter	60-1/2" x 37-3/16" x 24"	190	\$3,085	\$3,240	
S7-986-S08	7S-986-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 24"	352	\$5,381	\$5,650	
2 Adjustabl	le Metal Shelve	es and 1 Metal Bas	se Shelf per Side				48"H Omega
S7-765-S07	7S-765-S07	D/F Starter	48" x 37-3/16" x 20"	117	\$2,216	\$2,327	Book Stop Shelves
S7-765-S08	7S-765-S08	D/F Starter/Adder	48" x 73-3/8" x 20"	217	\$3,822	\$4,014	
S7-766-S07	7S-766-S07	D/F Starter	48" x 37-3/16" x 24"	154	\$2,334	\$2,451	
\$7-766-\$08	7S-766-S08	D/F Starter/Adder	48" x 73-3/8" x 24"	285	\$4,024	\$4,225	
2 Adjustabl	e Metal Shelve	es and 1 Metal Bas	se Shelf per Side				(42"H Omega
S7-987-S07	7S-987-S07	D/F Starter	42" x 37-3/16" x 20"	106	\$1,996	\$2,096	Book Stop Shelves
S7-987-S08	7S-987-S08	D/F Starter/Adder	42" x 73-3/8" x 20"	204	\$3,577	\$3,756	
S7-991-S07	7S-991-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$2,101	\$2,206	
\$7-991-\$08	7S-991-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$3,766	\$3,954	

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Metal\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Shelving Backs and Partitions CANNOT be used with Omega Book Stop Shelving.

Sway Braces included.

# Classic Shelving

### **Shelving Backs**

Except where specified, all single-faced shelving is supplied without backs. When specified, single-faced shelving is supplied with full-height and full width plywood backs, 1/4" thick. Backs Partitions fit into rabbets in the end panels, intermediates, tops, and base, so that edges are concealed from view after installation.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Plywood with Veneer Face	SB-608-S00	BS-608-S00	S/F Back, 90"H	87-5/16" x 35-5/8" x 1/4"	24	\$182	\$191
Single-Faced Shelving Backs	SB-600-S00	BS-600-S00	S/F Back, 82"H	79-5/16" x 35-5/8" x 1/4"	22	\$176	\$184
	SB-620-S00	BS-620-S00	S/F Back, 72"H	69-5/16" x 35-5/8" x 1/4"	20	\$173	\$181
	SB-602-S00	BS-602-S00	S/F Back, 60-1/2"H	58-15/16" x 35-5/8" x 1/4"	18	\$169	\$177
	SB-606-S00	BS-606-S00	S/F Back, 48"H	46-7/16" x 35-5/8" x 1/4"	15	\$117	\$123
	SB-604-S00	BS-604-S00	S/F Back, 42"H	40-7/16" x 35-5/8" x 1/4"	12	\$105	\$110
Finished Two Sides	SB-608-S02	BS-608-S02	S/F Back, 90"H	87-5/16" x 35-5/8" x 1/4"	24	\$238	\$250
Plywood with Veneer Face	SB-600-S02	BS-600-S02	S/F Back, 82"H	79-5/16" x 35-5/8" x 1/4"	22	\$230	\$242
Single-Faced Shelving Backs	SB-620-S02	BS-620-S02	S/F Back, 72"H	69-5/16" x 35-5/8" x 1/4"	20	\$214	\$225
	SB-602-S02	BS-602-S02	S/F Back, 60-1/2"H	58-15/16" x 35-5/8" x 1/4"	18	\$198	\$208
	SB-606-S02	BS-606-S02	S/F Back, 48"H	46-7/16" x 35-5/8" x 1/4"	15	\$146	\$153
	SB-604-S02	BS-604-S02	S/F Back, 42"H	40-7/16" x 35-5/8" x 1/4"	12	\$134	\$141
	ı	<b>Note:</b> For use with she	elving with exposed backs. (I	Does not include finishing and band	ling back edge of s	shelving unit.)	
Painted	SB-940-S00	N/A	S/F Back, 90"H	87-5/16" x 35-5/8" x 1/4"	24	\$150	N/A
Single-Faced Shelving Backs	SB-939-S00	N/A	S/F Back, 82"H	79-5/16" x 35-5/8" x 1/4"	22	\$144	N/A
	SB-960-S00	N/A	S/F Back, 72"H	69-5/16" x 35-5/8" x 1/4"	20	\$141	N/A
	SB-942-S00	N/A	S/F Back, 60-1/2"H	58-15/16" x 35-5/8" x 1/4"	18	\$139	N/A
	SB-948-S00	N/A	S/F Back, 48"H	46-7/16" x 35-5/8" x 1/4"	15	\$96	N/A
	SB-943-S00	N/A	S/F Back, 42"H	40-7/16" x 35-5/8" x 1/4"	12	\$83	N/A

Please specify Wood Finish (Table 1) or Paint Color; if applicable (Table 3). Details can be found on pages GEN 4 and GEN 5.

# **Shelving Partitions**

Except where specified, all double-faced shelving is supplied without partitions. When specified, double-faced shelving is supplied with full-height and full width plywood partitions, 1/4" thick. Partitions fit into rabbets in the end panels, intermediates, tops, and base, so that edges are concealed from view after installation.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
SB-609-S00	BS-609-S00	D/F Partition, 90"H	87-5/16" x 35-5/8" x 1/4"	24	\$238	\$250	Plywood with Veneer Face
SB-601-S00	BS-601-S00	D/F Partition, 82"H	79-5/16" x 35-5/8" x 1/4"	22	\$230	\$242	Double-Faced
SB-621-S00	BS-621-S00	D/F Partition, 72"H	69-5/16" x 35-5/8" x 1/4"	20	\$214	\$225	Shelving Partitions
SB-603-S00	BS-603-S00	D/F Partition, 60-1/2"H	58-15/16" x 35-5/8" x 1/4"	18	\$198	\$208	
SB-607-S00	BS-607-S00	D/F Partition, 48"H	46-7/16" x 35-5/8" x 1/4"	15	\$146	\$153	
SB-605-S00	BS-605-S00	D/F Partition, 42"H	40-7/16" x 35-5/8" x 1/4"	12	\$134	\$141	
SB-941-S00	N/A	D/F Partition, 90''H	87-5/16" x 35-5/8" x 1/4"	24	\$177	N/A	Painted
SB-945-S00	N/A	D/F Partition, 82"H	79-5/16" x 35-5/8" x 1/4"	22	\$169	N/A	Double-Faced
SB-961-S00	N/A	D/F Partition, 72"H	69-5/16" x 35-5/8" x 1/4"	20	\$159	N/A	Shelving Partitions
SB-947-S00	N/A	D/F Partition, 60-1/2"H	58-15/16" x 35-5/8" x 1/4"	18	\$146	N/A	
SB-950-S00	N/A	D/F Partition, 48"H	46-7/16" x 35-5/8" x 1/4"	15	\$109	N/A	
SB-949-S00	N/A	D/F Partition, 42"H	40-7/16" x 35-5/8" x 1/4"	12	\$102	N/A	

# Classic Shelving

	Oak	Maple Cotolog No	Description	H.W.D	11/4 /lba \	0ak	Maple
Newspaper File Insert	Catalog No.	Catalog No. 1S-968-S00	Description	H x W x D 40-3/4" x 35-3/16"	Wt. (lbs.)	Price	Price
The waspaper Tile in series	31-908-300	15-908-500	Newspaper File Insert Unit fits into any 10" or insert is made of two (2) Cleats are attached to u (10) newspaper sticks.	"H or higher. File h ten (10) slots for files.	\$701	\$735	
Bulletin Board Insert	S1-862-S00	1S-862-S00	Bulletin Board Insert	21-3/8" x 35-1/16"	20	\$492	\$517
			Unit is of solid hardwood Inserted into the inside opiano hinge is attched to shelving top fascia. This pull knob is affixed to th catches secure the unit	е			
Pullout Reference Shelf	S6-120-S00 OAK	S6-120-S00 MAP	Pullout Reference Shelf Shelf and shelf front is c Shelf front receives two solid hardwood cleats 1 100 # full extension dra	\$597	\$627		
Pullout CD DVD Shelf	S6-122-S00 OAK	S6-122-S00 MAP	AP Pullout CD/DVD Shelf 6-1/4" x 35-1/8" x 11-1/4" 30 Drawer is constructed of solid hardwood with 1/4" thick wood panel bottom. Drawer has 7-ply hardwood plywood fronts with select face veneers and two (2) black wire drawer pulls. Drawer receives a set of solid hardwood cleats 1-1/4" x 1-1/4" for mounting to shelving unit and 100 # full extension drawer slides. Each unit contains five (5) storage compartments for CD/DVD storage. Each compartment is 4-3/4" H x 4-3/4" W x 9-1/2"D. Storage capacity is 21 CD jewel cases or 16 DVD cases per compartment.				\$885
Seismic Anchors			and depths. Each panel anchor hardware. Seism hot rolled steel angle bra	c anchoring will be provided in the shelving range will be nic anchoring consist of one acket, two (2) flathead sock to (2) hex nuts and one (1) Hi	required to receive seiso (1) 1/4" thick 10-gaug et cap bolts, two (2) flat	mic e washers,	,
H	EQSFSTART	N/A	S/F Starter per unit		1	\$162	N/A
STARTER ADDER	EQSFADD	N/A	S/F Adder per unit		1	\$133	N/A
	EQDFSTART EQDFADD	N/A N/A	D/F Starter per unit D/F Adder per unit		2 2	\$335 \$316	N/A N/A
Shelf Pins	73-009-001	N/A	Pack of Shelf Pins - 4 pe	er Pack		\$1	N/A

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ or\ Metal\ Color;\ if\ applicable\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price	
	J	Wood shelves are 3/4" thick, glued-up solid North hardwood. Random widths no more than 4" or less To ensure adequate support for heavy volumes, no is permitted. Adjustable shelves are grooved 11/3 underside to set firmly on 1" long, 5/16" diamete cadmium-plated. Shelf depths are nominal.  Note: Double-Faced shelving you must order one	nern-grown Oak or Mass than 1-1/2" are us substitute for solid h 2" diameter half rour threaded shelf pins	ed. ardwood nd on the	(	Wood Shelves/Base Shelf
		4440		***	40-	
PSO-AW16-S	PMS-AW16-S	16" Shelf Wood	8	\$92	\$97	
60-061-S00 OAK	60-061-S00 MAP	12" Shelf Wood	8	\$77	\$81	
60-060-S00 OAK	60-060-S00 MAP	10" Shelf Wood	7	\$72	\$76	
60-965-S00 OAK	60-965-S00 MAP	Sloping Wood Periodical Shelf	9	\$195	\$205	
60-062-S00 OAK	60-062-S00 MAP	12" Picture Book Shelf with	21	\$155	\$163	
00 002 300 OAK	00 002 300 171711	Hardboard Divders	21	Ψ100	Ψ103	
6096711	N/A	Hardboard Divders for Picture Book	1	\$6	N/A	
		Shelves (per divider)				
SHPICBKS00 OAK	SHPICBKS00 MAP	12" Picture Book Shelf with	25	\$366	\$384	
		Six 7-3/4"H x 3/4" Wood Dividers				
		0.75.4.41.5	4.0	****	***	
1836382 OAK	1836382 MAP	S/F 16" Base Shelf	10	\$102	\$107	
1836392 OAK	1836392 MAP	S/F 12" Base Shelf	9	\$89	\$94	
1836402 OAK	1836402 MAP	S/F 10" Base Shelf	8	\$82	\$86	
D1836382 OAK	D1836382 MAP	D/F 16" Base Shelf*	10	\$102	\$107	
DH836392 OAK	D836392 MAP	D/F 12" Base Shelf*	9	\$89	\$94	
DH836402 OAK	D836402 MAP	D/F 10" Base Shelf*	8	\$82	\$86	
21.000 102 01	2000 102 1111 11	*Double-Faced shelving you must order one base:	shelf per side of unit.		400	
		9,	•			
6096795 OAK	6096795 MAP	S/F 12" Picture Book Base Shelf	21	\$186	\$195	
6096790 OAK	6096790 MAP	D/F 12" Picture Book Base Shelf*	21	\$173	\$181	
		*Double-Faced shelving you must order one base	shelf per side of unit.			
		Note: Dividers must be ordered separately.				
1836397 OAK	1836397 MAP	S/F 12" Glass Door Base Shelf	9	\$173	\$181	

	Catalog No.	Description	HxW	Wt. (lbs.)	Price
Omega Flat Shelf	73-004-S00 73-003-S00	12" Omega Flat Shelf 10" Omega Flat Shelf		8 7	\$64 \$60
The same		Omega (steel) shelves are designed to fit Brodar shelving units. These shelves are 18-gauge steel with notches in the bottom edge to fit over shelf and back edges are triple bent for strength and t Shelves are electrostatic powder-coat painted w Shelf accepts spring-type overhead wire book suin many standard and optional colors - please ca	I stamped pins. The front to eliminate sharp edges. vith epoxy paint and oven cured. upport. Omega shelves are availal	ble	
Omega Book Stop Shelf	73-002-S00	12" Omega Book Stop Shelf		9	\$100
Amo	73-001-S00	10" Omega Book Stop Shelf Omega "Book Stop" steel shelves are designed These shelves are 18-gauge steel stamped with shelf pins. The front and back edges are triple be edges. The back edge of the shelf is bent upward the shelf surface to function as a book stop. She with epoxy paint and oven cured. Units are supp are available in many standard and optional colo	notches in the bottom edge to fit ent for strength and to eliminate s d to form a 90° angle, 1-5/8"H a dives are electrostatic powder-coa lied with a metal base shelf. Ome	8 nits. over sharp above at painted	\$93
Media Display Shelf with 6 Dividers	S6-102-S00	Metal Media Display Shelf with 6 Dividers. Shelves are made to fit any stashelving unit - pin and hole or clip & strip. Unit and are electrostatically powder painted with e oven cured. The shelf can be divided with six (6 are provided with each shelf.	s are 18-gauge steel poxy paint which is	20	\$219
Divider/Picture Book Shelf with 2 Dividers	S6-103-S00	Metal Divider/Picture Book Shelf with 2 Dividers. Shelves are made to fit 3 shelving unit - pin and hole only. Units are 18-with a 7"H book-stop back and are electrostat with epoxy paint which is oven cured. The shelf two (2) metal dividers which are provided with espaced at 1-1/4" intervals.	gauge steel, 10-1/2"D ically powder painted f can be divided with	20	\$173

Please specify Metal Color (Table 3). Details can be found on page GEN 5.

Note: Metal Divider/Picture Book Shelf CANNOT be used as a Base Shelf.

0ak	Maple			0ak	Maple
Catalog No.	Catalog No.	Description	Wt. (lbs.)	Price	Price
Shelving Tops (F	Please specify shelvin	g height that top is to be	used on.)		
1836311	1836311A	High 12" Top	9	\$243	\$255
1836321	1836321A	High 10" Top	8	\$225	\$236
1836281	1836281A	High 20'' Top	15	\$338	\$355
1836271	1836271A	High 24" Top	17	\$365	\$383
1836312	1836312A	Low 12" Top	9	\$243	\$255
1836322	1836322A	Low 10" Top	8	\$225	\$236
1836282	1836282A	Low 20" Top	15	\$338	\$355
1836272	1836272A	Low 24" Top	17	\$365	\$383
Shelving Base					
1836341	1836341A	16" Base	7	\$200	\$210
1836351	1836351A	12" Base	6	\$159	\$167
1836361	1836361A	10" Base	6	\$144	\$151
Shelving Slatwa	II End Panels				
60-040-S00 OAK	60-040-S00 MAP	42"Hx20"Dx1"	40	\$580	\$609
60-041-S00 OAK	60-041-S00 MAP	42"H x 24"D x 1"	45	\$587	\$617
60-098-S00 OAK	60-098-S00 MAP	48"Hx20"Dx1"	45	\$599	\$629
60-099-S00 OAK	60-099-S00 MAP	48''H x 24''D x 1''	50	\$609	\$640
60-042-S00 OAK	60-042-S00 MAP	60-1/2"H x 20"D x 1"	55	\$763	\$801
60-043-S00 OAK	60-043-S00 MAP	60-1/2"H x 24"D x 1"	65	\$783	\$822
60-096-S00 OAK	60-096-S00 MAP	72"Hx20"Dx1"	65	\$816	\$857
60-097-S00 OAK	60-097-S00 MAP	72"H x 24"D x 1"	75	\$837	\$879
60-044-S00 OAK	60-044-S00 MAP	82"Hx20"Dx1"	70	\$870	\$914
60-045-S00 OAK	60-045-S00 MAP	82"H x 24"D x 1"	80	\$889	\$933
60-046-S00 OAK	60-046-S00 MAP	90"Hx20"Dx1"	80	\$931	\$977
60-047-S00 OAK	60-047-S00 MAP	90"H x 24"D x 1"	90	\$950	\$998

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

**Note:** Slatwall End Panels are designed to be used in conjunction with existing end panels. Please use as an "ADD ON" feature only. Attaching hardware NOT INCLUDED.

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price
Shelving End I	Panels, Pin and Hol	<u>.                                    </u>			
2900210	2900210A	S/F 82"H x 12"D, Left	17	\$350	\$368
2900211	2900211A	S/F 82"H x 12"D, Right	. <i>.</i> 17	\$350	\$368
2900212	2900212A	S/F 82"H x 10"D, Left	15	\$321	\$338
2900213	2900213A	S/F 82"H x 10"D, Right	15	\$321	\$338
2900203	2900203A	D/F 82"H x 24"D	33	\$598	\$628
2900202	2900202A	D/F 82"H x 20"D	21	\$569	\$598
2900201	2900201A	D/F 82"H x 16"D	23	\$539	\$566
2900274	2900274A	S/F 72"H x 12"D, Left	15	\$336	\$353
2900275	2900275A	S/F 72"H x 12"D, Right	15	\$336	\$353
2900276	2900276A	S/F 72"H x 10"D, Left	13	\$289	\$303
2900277	2900277A	S/F 72"H x 10"D, Right	13	\$289	\$303
2900281	2900281A	D/F 72"H x 24"D	29	\$549	\$576
2900280	2900280A	D/F 72"H x 20"D	20	\$214	\$225
2900218	2900218A	S/F 60-1/2"H x 12"D, Left	13	\$269	\$282
2900219	2900219A	S/F 60-1/2"H x 12"D, Right	13	\$269	\$282
2900220	2900220A	S/F 60-1/2"H x 10"D, Left	11	\$256	\$269
2900221	2900221A	S/F 60-1/2"H x 10"D, Right	11	\$256	\$269
2900206	2900206A	D/F 60-1/2"H x 24"D	25	\$454	\$477
2900205	2900206A	D/F 60-1/2"H x 20"D	21	\$413	\$433
2900251	2900251A	S/F 48"H x 12"D, Left	12	\$219	\$230
2900252	2900252A	S/F 48"H x 12"D, Right	12	\$219	\$230
2900253	2900253A	S/F 48"H x 10"D, Left	10	\$204	\$215
2900254	2900254A	S/F 48"H x 10"D, Right	10	\$204	\$215
2900250	2900250A	D/F 48"H x 24"D	21	\$355	\$373
2900249	2900249A	D/F 48"H x 20"D	19	\$329	\$346
2900226	2900226A	S/F 42"H x 12"D, Left	10	\$198	\$208
2900227	2900227A	S/F 42"H x 12"D, Right	10	\$198	\$208
2900228	2900228A	S/F 42"H x 10"D, Left	9	\$183	\$192
2900229	2900229A	S/F 42"H x 10"D, Right	9	\$183	\$192
2900209	2900209A	D/F 42"H x 24"D	18	\$309	\$324
2900208	2900208A	D/F 42"H x 20"D	17	\$291	\$305

Classic Shelving

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

Note: All End and Intermediate Panels are drilled and/or bushed for use with Brodart Shelving Only..

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price
Shelving Inter	mediate Panels, Pi	n and Hole			
1836051	1836051A	S/F 82"H x 12"D	17	\$360	\$378
1836071	1836071A	S/F 82"H x 10"D	14	\$328	\$345
1835851	1835851A	D/F 82"Hx 24"D	33	\$627	\$658
1835871	1835871A	D/F 82"Hx 20"D	27	\$598	\$628
1836054	1836054A	S/F 72"H x 12"D	16	\$353	\$371
1836053	1836053A	S/F 72"H x 10"D	14	\$304	\$319
1835831	1835831A	D/F 72"H x 24"D	31	\$575	\$604
1835841	1835841A	D/F 72"H x 20"D	26	\$548	\$575
1836131	1836131A	S/F 60-1/2"Hx 12"D	15	\$277	\$291
1836151	1836151A	S/F 60-1/2"Hx 10"D	13	\$264	\$277
1835911	1835911A	D/F 60-1/2"H x 24"D	29	\$468	\$492
1835931	1835931A	D/F 60-1/2"H x 20"D	25	\$425	\$446
1836133	1836133A	S/F 48"H x 12"D	12	\$226	\$238
1836134	1836134A	S/F 48"H x 10"D	11	\$211	\$222
1835933	1835933A	D/F 48"H x 24"D	24	\$367	\$385
1835932	1835932A	D/F 48"H x 20"D	21	\$341	\$358
1836211	1836211A	S/F 42"H x 12"D	10	\$203	\$214
1836231	1836231A	S/F 42"H x 10"D	9	\$187	\$196
1835971	1835971A	D/F 42"H x 24"D	19	\$317	\$333
1835991	1835991A	D/F 42"H x 20"D	17	\$304	\$319

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

Note: All End and Intermediate Panels are drilled and/or bushed for use with Brodart Shelving Only..

**-CLA 48-** F11-1-19G-CLA

# Reprise Shelving

# **General Specifications**

#### CONSTRUCTION

Shelving construction is modular type, utilizing thermally-fused laminate panels. Shelving units are designed with the starter and adder concept and measure 36" from center to center of the uprights. Bannister Oak, Biltmore Cherry, Classic Maple, Canadian Gray, Classic Black and Bright White are the standard finishes for Reprise shelving uprights, tops and bases. Shelves are available in Orange, Red, Plum, Island Green and Lapis Blue in addition to the colors listed previously.

#### **END PANELS**

End panels are 1" thick thermally-fused laminate panels. All exposed vertical and top edges are banded with matching 2mm PVC edge banding. Edges are square, but eased. Vertical rows of holes are drilled near the front and rear of each panel for shelf adjustment on 32mm centers. Panels are drilled at front, rear, top, and bottom for embedding internal and external threaded bushings. Tops and bases are attached to end panels with 5/16" - 18 x 2" hex-head bolts and washers. Lag bolts or Laminate screws are not used. Clip and metal strip style shelf attachments are available if specified.

#### INTERMEDIATE UPRIGHTS

Intermediate uprights are 1" thick thermally-fused laminate panels. All exposed vertical and top edges are banded with matching 2mm PVC edge banding. Edges are square, but eased. Shelf pinholes are bored on both sides of the panel but staggered so that pins can be deeply seated. Panels are drilled through at front, rear, top, and bottom for attachment of tops and bases with 5/16"-18 x 4-1/2" hex-head bolts, nuts, and washers. Clip and metal strip style shelf attachments are available if specified.

#### **BASE**

The base front is 4"H x 3/4" thick thermally-fused laminate panel with matching 2mm PVC edge banding on top and bottom edges. A 2" x 3/4" rail is tenoned full-length to the inside of the front. Bolting cleats 1-1/4" x 1-1/4" are glued and stapled perpendicular at the ends of the rail and drilled to allow assembly bolts to pass through. A second full-length rail is glued and stapled to the rear of the bolting cleats for support and proper alignment. Bases are manufactured so the base shelf rests on the bolting cleats set behind and flush with the top of the base front.


#### **ATTACHMENT**

Four bolts are used to attach each single-faced base or top, except for 16"D single-faced units, on which six bolts are used. Eight bolts are used to attach each double-faced base or top, except for 32"D double-faced units, on which twelve bolts are used. All hardware is concealed from view after assembly. Each single-faced unit is supplied with a metal bracket, lead anchor, and screws for fastening to the wall. Double-faced ranges that do not have partitions receive two steel sway bars per range, 46-7/8" long and 5/16" square. These attach to the starter panel at both sides of the range and the adjoining intermediate panel with screws.

#### BACKS AND PARTITIONS

Backs and partitions are constructed with 1/4" thick thermally-fused laminate panels.

Note: Backs and partitions do not function with "Book Stop" shelving. Clip and Strip shelving is available for Laminate Shelf units ONLY and can be ordered by changing the RP1 prefix on the starter unit to RP3, and changing the RP2 prefix on the adder unit to RP4. i.e.: RP3-861-S00 or RP4-861-S00.



Starter
Includes two end panels,
shelf pin and joining holes
on inside only.
37-3/16"W overall

Includes one intermediate upright with shelf pin and joining holes on both sides. 36-3/16"W overall

# **General Specifications - Shelves & Shelving Tops**

#### LAMINATE SHELVES

Shelves are 3/4" thick, thermally-fused laminate, banded on front and back with matching 2mm PVC edgebanding. To ensure adequate support for heavy volumes, a 3/4" thick, 1-1/4" wide support member is attached to the back edge of the bottom of each shelf. Adjustable shelves are grooved 11/32" diameter half round on the underside to set firmly on 1" long, 5/16" diameter threaded shelf pins, cadmium-plated. Shelf depths are nominal.

#### **OMEGA (STEEL) SHELVES**

Omega (steel) shelves are designed to fit Brodart's Reprise shelving units. These shelves are 18-gauge steel stamped with notches in the bottom edge to fit over shelf pins. The front and back edges are triple bent for strength and to eliminate sharp edges. Shelves are electrostatic powder coat painted with epoxy paint and oven cured. Shelf accepts spring-type overhead wire book support. Units are supplied with a laminate base shelf. Omega shelves are available in many standard and optional colors - please call for selection.

#### OMEGA "BOOK STOP" STEEL SHELVES

Omega "Book Stop" steel shelves are designed to fit Brodart's Reprise shelving units. These shelves are 18-gauge steel stamped with notches in the bottom edge to fit over shelf pins. The front and back edges are triple bent for strength and to eliminate sharp edges. The back edge of the shelf is bent upward to form a 90° angle, 1-5/8"H above the shelf surface to function as a book stop. Shelves are electrostatic powder-coat painted with epoxy paint and oven cured. Units are supplied with a metal base shelf. Omega shelves are available in many standard and optional colors - please call for selection.

Note: Backs and partitions do not function with "Book Stop" shelving.

#### SHELVING TOPS

Cornice tops have a 1-3/8" fascia, constructed with 3/4" thick, thermally-fused laminate panel with matching 2mm PVC edge banding. On the inside surface of the top at each end, butted to the fascia, is a solid hardLaminate bolting cleat 1-1/4" x 1-1/4" that is both glued and stapled. Bolting cleats are drilled to allow assembly bolts to pass through.

Note: Tops on 72"H, 82"H, and 90"H units are inverted. Continuous tops must be ordered separately.

## PICTURE BOOK SHELVING

Picture Book Shelving is 12"D with six (6) hardboard dividers per shelf. A 2"H, solid wood back keeps dividers in place.

### METAL TILT AND STORE SHELVING

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

#### METAL PICTURE BOOK SHELVING

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each ivider to prevent removal.

#### PERIODICAL SHELVING

Periodical shelving can display any type of media such as CD's, videocassettes, books and magazines. The shelf can be divided with the six dividers provided with each shelf. Each sloping display shelf will have a 13-3/4"H clear display area.



Flat Laminate Shelf



Omega Flat Shelf



**Omega Book Stop Shelf** 



Shelving Starter/Adder with Continuous Top

# **General Specifications - Mobile Units**

### MOBILE SHELVING UNITS

Mobile Shelving is available on 42", 48", and 60-1/2" units. Shelving construction is the same as the standard shelving with the exception of the base. The base facing is 4-3/8"H, receives four reinforced 14 gauge corner brackets with four 2-1/2" heavy-duty swivel casters attached to a 14-gauge caster bracket. Corner brackets are attached to the end panel and the base facing. The caster assembly is hidden within the base, giving the appearance of standard unit. All mobile units receive partitions, with the exception of Omega Book Stop units, which receive sway braces. Units are offered as starter or starter/adder only.



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
5 Adjustable Sh	nelves, 1 Fixed Shelf	and 1 Base Shelf			90"H Laminate Shelves
RP1-960-S00	S/F Starter	90" x 37-3/16" x 10"	103	\$1,106	
RP2-960-S00	S/F Adder	90" x 36-3/16" x 10"	90	\$842	
RP1-967-S00	S/F Starter	90" x 37-3/16" x 12"	122	\$1,193	
RP2-967-S00	S/F Adder	90" x 36-3/16" x 12"	102	\$907	
RP1-673-S00	S/F Starter	90" x 37-3/16" x 16"	127	\$1,327	
RP2-673-S00	S/F Adder	90" x 36-3/16" x 16"	107	\$1,040	
4 Adjustable Sh	nelves, 1 Fixed Shelf	and 1 Base Shelf			82"H Laminate Shelves
RP1-976-S00	S/F Starter	82" x 37-3/16" x 10"	93	\$1,008	
RP2-976-S00	S/F Adder	82" x 36-3/16" x 10"	80	\$764	
RP1-977-S00	S/F Starter	82" x 37-3/16" x 12"	112	\$1,089	
RP2-977-S00	S/F Adder	82" x 36-3/16" x 12"	92	\$826	
RP1-679-S00	S/F Starter	82" x 37-3/16" x 16"	117	\$1,211	
RP2-679-S00	S/F Adder	82" x 36-3/16" x 16"	97	\$948	
4 Adjustable Sh	nelves and 1 Base Sh	<u>elf</u>			72"H Laminate Shelves
RP1-861-S00	S/F Starter	72" x 37-3/16" x 10"	88	\$919	1 1
RP2-861-S00	S/F Adder	72" x 36-3/16" x 10"	75	\$695	
RP1-863-S00	S/F Starter	72" x 37-3/16" x 12"	102	\$995	
RP2-863-S00	S/F Adder	72" x 36-3/16" x 12"	87	\$752	
RP1-675-S00	S/F Starter	72" x 37-3/16" x 16"	107	\$1,088	
RP2-675-S00	S/F Adder	72" x 36-3/16" x 16"	92	\$861	
4 Adjustable Sh	nelves and 1 Base Sh	n <u>elf</u>			60-1/2"H Laminate Shelves
RP1-979-S00	S/F Starter	60-1/2" x 37-3/16" x 10"	75	\$830	
RP2-979-S00	S/F Adder	60-1/2" x 36-3/16" x 10"	65	\$627	
RP1-988-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	96	\$899	
RP2-988-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	81	\$680	
RP1-678-S00	S/F Starter	60-1/2" x 37-3/16" x 16"	101	\$988	
RP2-678-S00	S/F Adder	60-1/2" x 36-3/16" x 16"	86	\$773	



	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
48"H Laminate Shelves	2 Adjustable Sh	nelves and 1 Base Sh	<u>elf</u>		
	RP1-761-S00	S/F Starter	48" x 37-3/16" x 10"	71	\$686
	RP2-761-S00	S/F Adder	48" x 36-3/16" x 10"	63	\$496
	RP1-762-S00	S/F Starter	48" x 37-3/16" x 12"	84	\$731
	RP2-762-S00	S/F Adder	48" x 36-3/16" x 12"	74	\$524
	RP1-676-S00	S/F Starter	48" x 37-3/16" x 16"	89	\$792
	RP2-676-S00	S/F Adder	48" x 36-3/16" x 16"	79	\$583

42"H Laminate Shelves	2 Adjustable Sh	2 Adjustable Shelves and 1 Base Shelf					
	RP1-981-S00	S/F Starter	42" x 37-3/16" x 10"	61	\$648		
	RP2-981-S00	S/F Adder	42" x 36-3/16" x 10"	53	\$463		
	RP1-989-S00	S/F Starter	42" x 37-3/16" x 12"	74	\$690		
	RP2-989-S00	S/F Adder	42" x 36-3/16" x 12"	64	\$486		
	RP1-677-S00	S/F Starter	42" x 37-3/16" x 16"	79	\$716		
	RP2-677-S00	S/F Adder	42" x 36-3/16" x 16"	68	\$508		

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
5 Adjustable Sh	nelves, 1 Fixed Sh	elf and 1 Base Shelf per Si	i <u>de</u>		90"H Laminate Shelves
RP1-969-S00	D/F Starter	90" x 37-3/16" x 20"	185	\$1,936	
RP2-969-S00	D/F Adder	90" x 36-3/16" x 20"	153	\$1,529	
RP1-973-S00	D/F Starter	90" x 37-3/16" x 24"	224	\$2,095	
RP2-973-S00	D/F Adder	90" x 36-3/16" x 24"	188	\$1,628	
RP1-683-S00	D/F Starter	90" x 37-3/16" x 32"	239	\$2,328	
RP2-683-S00	D/F Adder	90" x 36-3/16" x 32"	203	\$1,868	
4 Adjustable Sh	nelves, 1 Fixed Sh	elf and 1 Base Shelf per Si	i <u>de</u>		82"H Laminate Shelves
RP1-983-S00	D/F Starter	82" x 37-3/16" x 20"	175	\$1,809	
RP2-983-S00	D/F Adder	82" x 36-3/16" x 20"	143	\$1,409	
RP1-990-S00	D/F Starter	82" x 37-3/16" x 24"	214	\$1,973	
RP2-990-S00	D/F Adder	82" x 36-3/16" x 24"	178	\$1,517	
RP1-689-S00	D/F Starter	82" x 37-3/16" x 32"	229	\$2,192	
RP2-689-S00	D/F Adder	82" x 36-3/16" x 32"	193	\$1,742	
4 Adjustable Sh	nelves and 1 Base	Shelf per Side			72"H Laminate Shelves
RP1-865-S00	D/F Starter	72" x 37-3/16" x 20"	160	\$1,719	
RP2-865-S00	D/F Adder	72" x 36-3/16" x 20"	128	\$1,321	
RP1-866-S00	D/F Starter	72" x 37-3/16" x 24"	199	\$1,855	
RP2-866-S00	D/F Adder	72" x 36-3/16" x 24"	163	\$1,430	
RP1-685-S00	D/F Starter	72" x 37-3/16" x 32"	214	\$1,967	
RP2-685-S00	D/F Adder	72" x 36-3/16" x 32"	178	\$1,638	
<u>4 Adjustable Sh</u>	nelves and 1 Base	Shelf per Side			60-1/2"H Laminate Shelves
RP1-985-S00	D/F Starter	60-1/2" x 37-3/16" x 20"	139	\$1,628	
RP2-985-S00	D/F Adder	60-1/2" x 36-3/16" x 20"	115	\$1,235	
RP1-986-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	170	\$1,733	1
RP2-986-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	142	\$1,345	
RP1-688-S00	D/F Starter	60-1/2" x 37-3/16" x 32"	185	\$1,908	
RP2-688-S00	D/F Adder	60-1/2" x 36-3/16" x 32"	157	\$1,529	



HO IT LO	amına	te Si	nelves		
	1		B.	E	>
				1	
				\$	

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
2 Adjustable She	elves and 1 Base Shel	f per Side		
RP1-765-S00	D/F Starter	48" x 37-3/16" x 20"	111	\$1,241
RP2-765-S00	D/F Adder	48" x 36-3/16" x 20"	96	\$932
RP1-766-S00	D/F Starter	48" x 37-3/16" x 24"	134	\$1,298
RP2-766-S00	D/F Adder	48" x 36-3/16" x 24"	111	\$996
RP1-686-S00	D/F Starter	48" x 37-3/16" x 32"	145	\$1,406
RP2-686-S00	D/F Adder	48" x 36-3/16" x 32"	122	\$1,107

42"H Laminate Shelves	2 Adjustable Sh	2 Adjustable Shelves and 1 Base Shelf per Side					
	RP1-987-S00	D/F Starter	42" x 37-3/16" x 20"	101	\$1,143		
	RP2-987-S00	D/F Adder	42" x 36-3/16" x 20"	86	\$854		
	RP1-991-S00	D/F Starter	42" x 37-3/16" x 24"	124	\$1,190		
	RP2-991-S00	D/F Adder	42" x 36-3/16" x 24"	105	\$907		
	RP1-687-S00	D/F Starter	42" x 37-3/16" x 32"	135	\$1,245		
	RP2-687-S00	D/F Adder	42" x 36-3/16" x 32"	116	\$949		

#### Picture Book Shelving

Picture Book Shelving is 12"D with six (6) hardboard dividers per shelf. A 2"H, solid wood back keeps dividers in place.




48"H Laminate Picture Book Shelves

42"H Laminate

**Picture Book Shelves** 


Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
2 Adjustable Pict	ure Book with Div	ider Shelves and 1 Base Shel	<u>If</u>		60-1/2"H Laminate Picture Book Shelves
RP1-931-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	105	\$965	
RP2-931-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	90	\$695	



1 Adjustable Picture Book with Divider	r Shelves and 1 Base Shelf

 RP1-929-S00
 S/F Starter
 48" x 37-3/16" x 12"
 86
 \$893


 RP2-929-S00
 S/F Adder
 48" x 36-3/16" x 12"
 76
 \$667



## 1 Adjustable Picture Book with Divider Shelves and 1 Base Shelf

 RP1-932-S00
 S/F Starter
 42" x 37-3/16" x 12"
 78
 \$743

 RP2-932-S00
 S/F Adder
 42" x 36-3/16" x 12"
 68
 \$532




Please specify Laminate Finishes (Table 4). Details can be found on page GEN 5.
For details regarding Clip & Strip Shelving, please reference the Modifications & Up Charges Section located on page MOD 8.




#### Picture Book Shelving

Picture Book Shelving is 12"D with six (6) hardboard dividers per shelf. A 2"H, solid wood back keeps dividers in place.


	Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
60-1/2"H Laminate Picture Book Shelves	2 Adjustable Pid	cture Book with Divi	der Shelves and 1 Base Shelf	per Side	
	RP1-933-S00 RP2-933-S00	D/F Starter D/F Adder	60-1/2" x 37-3/16" x 24" 60-1/2" x 36-3/16" x 24"	180	\$1,837 \$1,346
	RP2-933-300	D/F Addel	00-1/2 X 30-3/10 X 24	152	\$1,340



48"H Laminate	1 Adjustable Picture Book with Divider Shelves and 1 Base Shelf per Side						
Picture Book Shelves	RP1-930-S00	D/F Starter	48" x 37-3/16" x 24"	149	\$1,427		
	RP2-930-S00	D/F Adder	48" x 36-3/16" x 24"	130	\$1,096		



42"H Laminate Picture Book Shelves	1 Adjustable Picture Book with Divider Shelves and 1 Base Shelf per Side						
	RP1-934-S00	D/F Starter	42" x 37-3/16" x 24"	130	\$1,273		
	RP2-934-S00	D/F Adder	42" x 36-3/16" x 24"	110	\$1,038		



Please specify Laminate Finishes (Table 4). Details can be found on page GEN 5. For details regarding Clip & Strip Shelving, please reference the Modifications & Up Charges Section located on page MOD 8.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Ano
5 Adjustable Me	etal Shelves, 1 Fixed	Shelf and 1 Thermally-Fus	ed Laminate Bas	se Shelf	90"H Omega Shelve
RP5-960-S00	S/F Starter	90" x 37-3/16" x 10"	103	\$1,030	
RP6-960-S00	S/F Adder	90" x 36-3/16" x 10"	90	\$780	
RP5-967-S00	S/F Starter	90" x 37-3/16" x 12"	122	\$1,158	
RP6-967-S00	S/F Adder	90" x 36-3/16" x 12"	102	\$833	

4 Adjustable Met	tal Shelves, 1 Fixed	d Shelf and 1 Thermally-Fuse	d Laminate Ba	se Shelf
RP5-976-S00	S/F Starter	82" x 37-3/16" x 10"	93	\$940
RP6-976-S00	S/F Adder	82" x 36-3/16" x 10"	80	\$714
RP5-977-S00	S/F Starter	82" x 37-3/16" x 12"	112	\$1,054
RP6-977-S00	S/F Adder	82" x 36-3/16" x 12"	92	\$772



<u> 4 Adjustable Me</u>	etal Shelves and 1 7	Thermally-Fused Laminate Ba	ise Shelf	
RP5-861-S00	S/F Starter	72" x 37-3/16" x 10"	88	\$857
RP6-861-S00	S/F Adder	72" x 36-3/16" x 10"	75	\$654
RP5-863-S00	S/F Starter	72" x 37-3/16" x 12"	102	\$961
RP6-863-S00	S/F Adder	72" x 36-3/16" x 12"	87	\$717

F	
5	


4 Adjustable Me	tal Shelves and 1	Thermally-Fused Laminate Bas	se Shelf	
RP5-979-S00	S/F Starter	60-1/2" x 37-3/16" x 10"	75	\$776
RP6-979-S00	S/F Adder	60-1/2" x 36-3/16" x 10"	65	\$594
RP5-988-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	96	\$870
RP6-988-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	81	\$660



Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.



48"H	<b>Omega</b>	Shelves



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
2 Adjustable Me	etal Shelves and 1 Th	ermally-Fused Laminate Base	e Shelf	
RP5-761-S00	S/F Starter	48" x 37-3/16" x 10"	65	\$665
RP6-761-S00	S/F Adder	48" x 36-3/16" x 10"	57	\$486
RP5-762-S00	S/F Starter	48" x 37-3/16" x 12"	78	\$708
RP6-762-S00	S/F Adder	48" x 36-3/16" x 12"	68	\$510

42"l	l Om	ega	Shel	ves	
	<u> </u>	7	1<		
L					

2 Adjustable Me	tal Shelves and 1 Ti	hermally-Fused Laminate Base :	Shelf	
RP5-981-S00	S/F Starter	42" x 37-3/16" x 10"	61	\$636
RP6-981-S00	S/F Adder	42" x 36-3/16" x 10"	53	\$458
RP5-989-S00	S/F Starter	42" x 37-3/16" x 12"	74	\$667
RP6-989-S00	S/F Adder	42" x 36-3/16" x 12"	64	\$473

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Anne on
5 Adjustable Me	etal Shelves, 1 Fixed	Shelf and 1 Thermally-Fus	sed Laminate Bas	se Shelf per Side	90"H Omega Shelves
RP5-969-S00	D/F Starter	90" x 37-3/16" x 20"	185	\$1,730	
RP6-969-S00	D/F Adder	90" x 36-3/16" x 20"	153	\$1,302	
RP5-973-S00	D/F Starter	90" x 37-3/16" x 24"	224	\$2,073	
RP6-973-S00	D/F Adder	90" x 36-3/16" x 24"	188	\$1,440	

4 Adjustable Me	iustable Metal Shelves, 1 Fixed Shelf and 1 Thermally-Fused Laminate Base Shelf per Side			82"H Omega Shelv	
RP5-983-S00	D/F Starter	82" x 37-3/16" x 20"	175	\$1,643	
RP6-983-S00	D/F Adder	82" x 36-3/16" x 20"	143	\$1,262	
RP5-990-S00	D/F Starter	82" x 37-3/16" x 24"	214	\$1,934	
RP6-990-S00	D/F Adder	82" x 36-3/16" x 24"	178	\$1,393	


RP5-865-S00       D/F Starter       72" x 37-3/16" x 20"       160       \$1,560         RP6-865-S00       D/F Adder       72" x 36-3/16" x 20"       128       \$1,223         RP5-866-S00       D/F Starter       72" x 37-3/16" x 24"       199       \$1,805         RP6-866-S00       D/F Adder       72" x 36-3/16" x 24"       163       \$1,347	
RP5-866-S00 D/F Starter 72" x 37-3/16" x 24" 199 \$1,805	
RP6-866-S00 D/F Adder 72" x 36-3/16" x 24" 163 \$1,347	

4 Adjustable Me	etal Shelves and 1	60-1/2"H Omega Shelves			
RP5-985-S00	D/F Starter	60-1/2" x 37-3/16" x 20"	139	\$1,479	
RP6-985-S00	D/F Adder	60-1/2" x 36-3/16" x 20"	115	\$1,185	
RP5-986-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	170	\$1,676	
RP6-986-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	142	\$1,300	

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.




48"H	<b>Omega</b>	Shelves



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
2 Adjustable Me	etal Shelves and 1 Th	nermally-Fused Laminate Ba	se Shelf per Side	
RP5-765-S00	D/F Starter	48" x 37-3/16" x 20"	111	\$1,168
RP6-765-S00	D/F Adder	48" x 36-3/16" x 20"	96	\$857
RP5-766-S00	D/F Starter	48" x 37-3/16" x 24"	134	\$1,262
RP6-766-S00	D/F Adder	48" x 36-3/16" x 24"	111	\$946

# 42"H Omega Shelves



etal Shelves and 1 Ti	hermally-Fused Laminate Bas	e Shelf per Side	
D/F Starter	42" x 37-3/16" x 20"	101	\$1,090
D/F Adder	42" x 36-3/16" x 20"	86	\$776
D/F Starter	42" x 37-3/16" x 24"	124	\$1,158
D/F Adder	42" x 36-3/16" x 24"	105	\$858
	D/F Starter D/F Adder D/F Starter	D/F Starter 42" x 37-3/16" x 20" D/F Adder 42" x 36-3/16" x 20"  D/F Starter 42" x 37-3/16" x 24"	D/F Adder 42" x 36-3/16" x 20" 86  D/F Starter 42" x 37-3/16" x 24" 124

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	Ime on
5 Adjustable Me	etal Shelves, 1 Fixed	l Metal Shelf and 1 Metal B	Base Shelf		90"H Omega
RP7-960-S00	S/F Starter	90" x 37-3/16" x 10"	103	\$1,030	Book Stop Shelves
RP8-960-S00	S/F Adder	90" x 36-3/16" x 10"	90	\$780	
RP7-967-S00	S/F Starter	90" x 37-3/16" x 12"	122	\$1,158	
RP8-967-S00	S/F Adder	90" x 36-3/16" x 12"	102	\$833	

4 Adjustable Me	etal Shelves, 1 Fixe	d Metal Shelf and 1 Metal Ba	82"H Omeg		
RP7-976-S00	S/F Starter	82" x 37-3/16" x 10"	93	\$1,052	Book Stop Shelves
RP8-976-S00	S/F Adder	82" x 36-3/16" x 10"	80	\$819	
RP7-977-S00	S/F Starter	82" x 37-3/16" x 12"	112	\$1,185	
RP8-977-S00	S/F Adder	82" x 36-3/16" x 12"	92	\$880	

4 Adjustable Me	tal Shelves and 1 N	Metal Base Shelf		
RP7-861-S00	S/F Starter	72" x 37-3/16" x 10"	88	\$942
RP8-861-S00	S/F Adder	72" x 36-3/16" x 10"	75	\$735
RP7-863-S00	S/F Starter	72" x 37-3/16" x 12"	102	\$1,077
RP8-863-S00	S/F Adder	72" x 36-3/16" x 12"	87	\$799

<u> 4 Adjustable Me</u>	tal Shelves and 1	elves and 1 Metal Base Shelf		
RP7-979-S00	S/F Starter	60-1/2" x 37-3/16" x 10"	75	\$833
RP8-979-S00	S/F Adder	60-1/2" x 36-3/16" x 10"	65	\$652
RP7-988-S00	S/F Starter	60-1/2" x 37-3/16" x 12"	96	\$969
RP8-988-S00	S/F Adder	60-1/2" x 36-3/16" x 12"	81	\$716

60-1/2"H Omega Book Stop Shelves

72"H Omega



Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.




## 48"H Omega Book Stop Shelves



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
2 Adjustable Meta	al Shelves and 1 Me	etal Base Shelf		
RP7-761-S00	S/F Starter	48" x 37-3/16" x 10"	71	\$701
RP8-761-S00	S/F Adder	48" x 36-3/16" x 10"	63	\$521
RP7-762-S00	S/F Starter	48" x 37-3/16" x 12"	84	\$760
RP8-762-S00	S/F Adder	48" x 36-3/16" x 12"	74	\$549

# 42"H Omega Book Stop Shelves



2 Adjustable Me	Adjustable Metal Shelves and 1 Metal Base Shelf			
RP7-981-S00	S/F Starter	42" x 37-3/16" x 10"	61	\$668
RP8-981-S00	S/F Adder	42" x 36-3/16" x 10"	53	\$488
RP7-989-S00	S/F Starter	42" x 37-3/16" x 12"	74	\$708
RP8-989-S00	S/F Adder	42" x 36-3/16" x 12"	64	\$510

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

	aaa Chalf mar Ci		Description	Catalog No.
	ase sneit per si	d Metal Shelf and 1 Metal B	etal Shelves, 1 Fixed	5 Adjustable Me
\$2,012	185	90" x 37-3/16" x 20"	D/F Starter	RP7-969-S00
\$1,566	153	90" x 36-3/16" x 20"	D/F Adder	RP8-969-S00
\$2,368	224	90" x 37-3/16" x 24"	D/F Starter	RP7-973-S00
\$1,710	188	90" x 36-3/16" x 24"	D/F Adder	RP8-973-S00
·				

4 Adjustable Metal Shelves, 1 Fixed Metal Shelf and 1 Metal Base Shelf per Side				
RP7-983-S00	D/F Starter	82" x 37-3/16" x 20"	175	\$1,865
RP8-983-S00	D/F Adder	82" x 36-3/16" x 20"	143	\$1,473
RP7-990-S00	D/F Starter	82" x 37-3/16" x 24"	214	\$2,162
RP8-990-S00	D/F Adder	82" x 36-3/16" x 24"	178	\$1,602

Book Stop Shelves

82"H Omega

72"H Omega

60-1/2"H Omega

4 Adjustable Metal Shelves and 1 Metal Base Shelf per Side				
RP7-865-S00	D/F Starter	72" x 37-3/16" x 20"	160	\$1,729
RP8-865-S00	D/F Adder	72" x 36-3/16" x 20"	128	\$1,384
RP7-866-S00	D/F Starter	72" x 37-3/16" x 24"	199	\$1,977
RP8-866-S00	D/F Adder	72" x 36-3/16" x 24"	163	\$1,501




4 Adjustable Metal Shelves and 1 Metal Base Shelf per Side				
RP7-985-S00	D/F Starter	60-1/2" x 37-3/16" x 20"	139	\$1,591
RP8-985-S00	D/F Adder	60-1/2" x 36-3/16" x 20"	115	\$1,298
RP7-986-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	170	\$1,787
RP8-986-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	142	\$1,401

Book Stop Shelves

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.




# 48"H Omega Book Stop Shelves



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
2 Adjustable Metal Shelves and 1 Metal Base Shelf per Side					
RP7-765-S00	D/F Starter	48" x 37-3/16" x 20"	111	\$1,242	
RP8-765-S00	D/F Adder	48" x 36-3/16" x 20"	96	\$931	
RP7-766-S00	D/F Starter	48" x 37-3/16" x 24"	134	\$1,335	
RP8-766-S00	D/F Adder	48" x 36-3/16" x 24"	111	\$1,018	

# 42"H Omega Book Stop Shelves



2 Adjustable Metal Shelves and 1 Metal Base Shelf per Side				
RP7-987-S00	D/F Starter	42" x 37-3/16" x 20"	101	\$1,155
RP8-987-S00	D/F Adder	42" x 36-3/16" x 20"	86	\$839
RP7-991-S00	D/F Starter	42" x 37-3/16" x 24"	124	\$1,223
RP8-991-S00	D/F Adder	42" x 36-3/16" x 24"	105	\$922

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

#### Periodical Display Shelving

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.

and the second second

Note: Each metal display shelf receives 6 metal dividers per shelf.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price		
5 Display Metal Laminate Base		ole Metal Shelves, 1 Fixed N	letal Shelf and	1 Thermally-Fused	82"H	Omega Periodical Display Shelves
RP7-918-S00 RP8-918-S00	S/F Starter S/F Adder	82" x 37-3/16" x 12" 82" x 36-3/16" x 12"	120 100	\$1,621 \$1,233		

4 Display Metal Shelves, 3 Adjustable Metal Shelves and 1 Thermally-Fused Laminate Base Shelf

RP7-875-S00 RP8-875-S00 S/F Starter S/F Adder 72" x 37-3/16" x 12" 72" x 36-3/16" x 12" \$1,**407** 95 **\$1,053** 






72"H Omega Periodical Display Shelves

3 Display Metal Shelves, 2 Adjustable Metal Shelves and 1 Thermally-Fused Laminate Base Shelf


**RP7-920-S00** S/F Starter **RP8-920-S00** S/F Adder

60-1/2" x 37-3/16" x 12" 60-1/2" x 36-3/16" x 12" 90 **\$1,190** 

60-1/2"H Omega Periodical Display Shelve



Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.




#### **Periodical Display Shelving**

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.


Note: Each metal display shelf receives 6 metal dividers per shelf.

48"H Omega Periodical
Display Shelves



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
2 Display Metal Base Shelf	Shelves, 1 Adjustab	ele Metal Shelf and 1 Therma	ally-Fused Lami	<u>nate</u>
RP7-919-S00	S/F Starter	48" x 37-3/16" x 12"	90	\$1,040
RP8-919-S00	S/F Adder	48" x 36-3/16" x 12"	80	\$804

#### 42"H Omega Periodical **Display Shelves**



#### 2 Display Metal Shelves, 1 Adjustable Metal Shelf and 1 Thermally-Fused Laminate Base Shelf

RP7-921-S00	S/F Starter	42" x 37-3/16" x 12"	80	\$898
RP8-921-S00	S/F Adder	42" x 36-3/16" x 12"	70	\$737

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

## Omega Periodical Display Shelves, Double-Faced

#### Periodical Display Shelving

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.

Note: Each metal display shelf receives 6 metal dividers per shelf.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price		
5 Display Metal Shelves, 3 Adjustable Metal Shelves, 1 Fixed Metal Shelf and 1 Thermally-Fused Laminate Base Shelf per Side						
RP7-922-S00	D/F Starter	82" x 37-3/16" x 24"	230	\$2,940		
RP8-922-S00	D/F Adder	82" x 36-3/16" x 24"	194	\$2,476		


82"H Omega Periodical **Display Shelves** 



#### 4 Display Metal Shelves, 3 Adjustable Metal Shelves and 1 Thermally-Fused Laminate Base Shelf per Side


RP7-876-S00 D/F Starter 72" x 37-3/16" x 24" 210 \$2,675 RP8-876-S00 D/F Adder 72" x 36-3/16" x 24" 180 \$2,253

#### 72"H Omega Periodical **Display Shelves**



#### 3 Display Metal Shelves, 2 Adjustable Metal Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

RP7-923-S00 D/F Starter 60-1/2" x 37-3/16" x 24" 185 \$2,117 RP8-923-S00 D/F Adder 60-1/2" x 36-3/16" x 24" 157 \$1,662 60-1/2"H Omega Periodical **Display Shelve** 



Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

HxWxD

Wt. (lbs.)

Price



#### **Periodical Display Shelving**


Catalog No.

Periodical Display Shelves are 13"H with a 3/4"H retaining lip. The display shelves are adjustable on a pin and hole system but they do not tilt. Each sloping display shelf has a 13-3/4"H clear display area.

Note: Each metal display shelf receives 6 metal dividers per shelf.

Description


48"H Omega Periodical
Display Shelves



00	
2 Dichley Matel Shalvac	1 Adulstahla Matal Shalt and 1 Thormally.Fusad Laminata
2 Display Metal Sileives,	1 Adjustable Metal Shelf and 1 Thermally-Fused Laminate
D 01 16 '1	
Base Shelf per side	
base shell per side	
-	

RP7-925-S00	D/F Starter	48" x 37-3/16" x 24"	150	\$1,906
RP8-925-S00	D/F Adder	48" x 36-3/16" x 24"	130	\$1,447

# 42"H Omega Periodical Display Shelves



#### 2 Display Metal Shelves, 1 Adjustable Metal Shelf and 1 Thermally-Fused Laminate Base Shelf per side


RP7-924-S00	D/F Starter	42" x 37-3/16" x 24"	130	\$1,701
RP8-924-S00	D/F Adder	42" x 36-3/16" x 24"	111	\$1,233

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

Note: Tilt and Store Shelving is available in 16" depth ONLY.

Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
5 Tilting Meta	l Shelves, 4 Flat W	ood Shelves and 1 Therma	ally-Fused Lamin	nate Base Shelf
RP7-935-S00	S/F Starter	82" x 37-3/16" x 16"	250	\$2,096
RP8-935-S00	S/F Adder	82" x 36-3/16" x 16"	214	\$1.760




82"H Omega Tilt & Store Shelves



#### 4 Tilting Metal Shelves, 3 Flat Wood Shelves and 1 Thermally-Fused Laminate Base Shelf

RP7-880-S00	S/F Starter	72" x 37-3/16" x 16"	220	\$1,987
RP8-880-S00	S/F Adder	72" x 36-3/16" x 16"	180	\$1,563


#### 72"H Omega Tilt & Store Shelves




#### 3 Tilting Metal Shelves, 2 Flat Wood Shelves and 1 Thermally-Fused Laminate Base Shelf

RP7-936-S00	S/F Starter	60-1/2" x 37-3/16" x 16"	180	\$1,879
RP8-936-S00	S/F Adder	60-1/2" x 36-3/16" x 16"	130	\$1,363

#### 60-1/2"H Omega Tilt & Store Shelves



 $Please\ specify\ Laminate\ Finishes\ (Table\ 4)\ and\ Metal\ Color\ (Table\ 5).\ Details\ can\ be\ found\ on\ page\ GEN\ 5.$ 



Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

Note: Tilt and Store Shelving is available in 16" depth ONLY.

#### 48"H Omega Tilt & Store Shelves





Catalog IVO.	Description	пхухр	wr. (ibs.)	Price
2 Tilting Metal S Base Shelf	Shelves, 1 Flat Woo	d Shelves and 1 Thermally-I	Fused Laminate	
RP7-938-S00	S/F Starter	48" x 37-3/16" x 16"	120	\$1,676
RP8-938-S00	S/F Adder	48" x 36-3/16" x 16"	110	\$1,283

#### 42"H Omega Tilt & Store Shelves





#### 2 Tilting Metal Shelves, 1 Flat Wood Shelves and 1 Thermally-Fused Laminate Base Shelf

RP7-937-S00	S/F Starter	42" x 37-3/16" x 16"	100	\$1,474
RP8-937-S00	S/F Adder	42" x 36-3/16" x 16"	90	\$1,202

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Catalog No.

Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

HxWxD


Wt. (lbs.)

Price

Note: Tilt and Store Shelving is available in 16" depth ONLY.

Description

			. ,	
5 Tilting Metal S per Side	Shelves, 4 Flat Wood	Shelves and 1 Thermally-Fu	used Laminate	e Base Shelf
RP7-945-S00	D/F Starter	82" x 37-3/16" x 32"	450	\$3,771
RP8-945-S00	D/F Adder	82" x 36-3/16" x 32"	385	\$3,168



82"H Omega Tilt & Store Shelves




# <u>4 Tilting Metal Shelves, 3 Flat Wood Shelves and 1 Thermally-Fused Laminate Base Shelf per Side</u>

 RP7-840-S00
 D/F Starter
 72" x 37-3/16" x 32"
 396
 \$3,578

 RP8-840-S00
 D/F Adder
 72" x 36-3/16" x 32"
 324
 \$2,812


#### 72"H Omega Tilt & Store Shelves




# 3 Tilting Metal Shelves, 2 Flat Wood Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

RP7-946-S00 D/F Starter 60-1/2" x 37-3/16" x 32" 324 \$3,383 RP8-946-S00 D/F Adder 60-1/2" x 36-3/16" x 32" 234 \$2,454

#### 60-1/2"H Omega Tilt & Store Shelves




Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.



Sloping display shelves have a 13"H clear display area and lift up to expose flat storage shelves via a pivot hinge. Storage space is concealed when display shelves are in normal position.

Note: Tilt and Store Shelving is available in 16" depth ONLY.

#### 48"H Omega Tilt & Store Shelves



Catalog No.	Description	пхихр	Wt. (IDS.)	Price
2 Tilting Metal S per Side	helves, 1 Flat Wood	Shelves and 1 Thermally-	Fused Laminate I	Base Shelf
RP7-948-S00 RP8-948-S00	D/F Starter D/F Adder	48" x 37-3/16" x 32" 48" x 36-3/16" x 32"	216 198	\$3,018 \$2,309

#### 42"H Omega Tilt & Store Shelves





#### 2 Tilting Metal Shelves, 1 Flat Wood Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

RP7-947-S00	D/F Starter	42" x 37-3/16" x 32"	180	\$2,653
RP8-947-S00	D/F Adder	42" x 36-3/16" x 32"	162	\$2,164


Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

#### **Metal Picture Book Shelving**

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
<u>4 Adjustable (</u> Base Shelf	1 Fixed) Picture Bo	ook w/Divider Metal Shelv	es and 1 Therm	ally-Fused Laminate	82"H Omega Picture Book Shelves
RP1-233-S00 RP2-233-S00	S/F Starter S/F Adder	82" x 37-3/16" x 12" 82" x 36-3/16" x 12"	200 163	\$1,202 \$880	




4 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate Base Shelf

RP1-237-S00 RP2-237-S00 S/F Starter S/F Adder

72" x 37-3/16" x 12" 72" x 36-3/16" x 12"

104 \$1,096 \$817 87

72"H Omega **Picture Book Shelves** 



3 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate Base Shelf

RP1-232-S00 RP2-232-S00 S/F Starter S/F Adder

60-1/2" x 37-3/16" x 12" 60-1/2" x 36-3/16" x 12"

132 \$991 105 \$753

60-1/2"H Omega **Picture Book Shelves** 



Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Wt. (lbs.)

Price




#### Metal Picture Book Shelving

Catalog No.

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.

Description


48"H Omega
40 IT Officya
Picture Book Shelves



2 Adjustable Pid Base Shelf	cture Book w/Divide	r Metal Shelves and 1 Thern	nally-Fused La	minate_
RP1-238-S00	S/F Starter	48" x 37-3/16" x 12"	79	\$808
RP2-238-S00	S/F Adder	48" x 36-3/16" x 12"	69	\$582

HxWxD

#### 42"H Omega Picture Book Shelves



#### 2 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate Base Shelf

RP1-231-S00	S/F Starter	42" x 37-3/16" x 12"	78	\$760
RP2-231-S00	S/F Adder	42" x 36-3/16" x 12"	58	\$538

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

#### Metal Picture Book Shelving

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.




Catalog No.	Description	HxWxD	Wt. (lbs.)	Price	
	•	ook w/Divider Metal Shelv	es and 1 Therma	ally-Fused Laminate	82"H Omega Picture Book Shelves
<u>Base Shelf pe</u>	<u>er Side</u>				T ICTUIC DOOK STICIVES
RP1-236-S00	D/F Starter	82" x 37-3/16" x 24"	333	\$2,206	
RP2-236-S00	D/F Adder	82" x 36-3/16" x 24"	269	\$1,587	

4 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

72"H Omega Picture Book Shelves


RP1-247-S00	D/F Starter	72" x 37-3/16" x 24"	199	\$2,058
RP2-247-S00	D/F Adder	72" x 36-3/16" x 24"	163	\$1,535



4 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

60-1/2"H Omega Picture Book Shelves

RP1-235-S00	D/F Starter	60-1/2" x 37-3/16" x 24"	231	\$1,910
RP2-235-S00	D/F Adder	60-1/2" x 36-3/16" x 24"	186	\$1,482



Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Wt. (lbs.)

Price



#### Metal Picture Book Shelving

Catalog No.

Metal Picture Book Shelves are 11"D x 7"H overall with two metal dividers per shelf. Dividers can be placed at 26 equal spaces along the width of each shelf. A steel cotter pin is provided with each divider to prevent removal.

Description


48"H Omega	
Picture Book Shelv	es

2 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate
Base Shelf per Side

HxWxD

RP1-248-S00 D/F Starter 48" x 37-3/16" x 24" 134 \$1,439 RP2-248-S00 D/F Adder 48" x 36-3/16" x 24" 111 \$1,079

#### 42"H Omega **Picture Book Shelves**



#### 2 Adjustable Picture Book w/Divider Metal Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

RP1-234-S00	D/F Starter	42" x 37-3/16" x 24"	168	\$1,320
RP2-234-S00	D/F Adder	42" x 36-3/16" x 24"	139	\$979

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.



	Price	Wt. (lbs.)	HxWxD	Description	Catalog No.
60-1/2"H Laminate Shelves	2	helf per Side	ally-Fused Laminate Base Sl	helves and 1 Therma	4 Adjustable S
	\$1,901	144	60-1/2" x 37-3/16" x 20"	D/F Starter	RP1-985-S07
	\$3,422	268	60-1/2" x 73-3/8" x 20"	D/F Starter/Adder	RP1-985-S08
	\$2,001	190	60-1/2" x 37-3/16" x 24"	D/F Starter	RP1-986-S07
	\$3,602	352	60-1/2" x 73-3/8" x 24"	D/F Starter/Adder	RP1-986-S08

minate Shel	48"H Lam	<u>e</u>	Shelf per Sid	ly-Fused Laminate Base S	helves and 1 Thermal	2 Adjustable S
		\$1,499	117	48" x 37-3/16" x 20"	D/F Starter	RP1-765-S07
		\$2,699	217	48" x 73-3/8" x 20"	D/F Starter/Adder	RP1-765-S08
		\$1,577	154	48" x 37-3/16" x 24"	D/F Starter	RP1-766-S07
		\$2,841	285	48" x 73-3/8" x 24"	D/F Starter/Adder	RP1-766-S08
<						


<u> 2 Adjustable S</u>	helves and 1 Therma	<u>lly-Fused Laminate Base S</u>	Shelf per Sid	<u>le</u>	42"H Laminate Shelves
RP1-987-S07	D/F Starter	42" x 37-3/16" x 20"	106	\$1,399	
RP1-987-S08	D/F Starter/Adder	42" x 73-3/8" x 20"	204	\$2,516	
RP1-991-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$1,473	
RP1-991-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$2,648	

Please specify Wood Finish (Table 1). Details can be found on page GEN 4. For details regarding Clip & Strip Shelving, please reference the Modifications & Up Charges Section located on page MOD 8.

Note: Partitions included for Mobile Units.



60-1/2"H Laminate
<b>Picture Book Shelves</b>



Catalog No.	Description	HXWXD	vvi. (IDS.)	PH
2 Adjustable	Picture Book w/Divider	Shelves and 1 Thermally-Fu	sed Laminate Bas	se

11...W...D


\#\ /Iba\

# Shelf per Side

Decembelon

RP1-933-S07	D/F Starter	60-1/2" x 37-3/16" x 24"	180	\$2,101
RP1-933-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 24"	352	\$3,704

48"H Laminate **Picture Book Shelves** 



1 Adjustable Picture Book w/Divider Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

RP1-930-S07	D/F Starter	48" x 37-3/16" x 24"	149	\$1,703
RP1-930-S08	D/F Starter/Adder	48" x 73-3/8" x 24"	285	\$3,062

42"H Laminatef **Picture Book Shelves** 



1 Adjustable Picture Book w/Divider Shelves and 1 Thermally-Fused Laminate Base Shelf per Side

RP1-934-S07	D/F Starter	42" x 37-3/16" x 24"	130	\$1,554
RP1.934.S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$2.858


Please specify Wood Finish (Table 1). Details can be found on page GEN 4. For details regarding Clip & Strip Shelving, please reference the Modifications & Up Charges Section located on page MOD 8.

Note: Partitions included for Mobile Units.




	Price	Wt. (lbs.)	HxWxD	Description	Catalog No.
60-1/2"H Omega Shelves	oer Side	Base Shelf p	Thermally-Fused Laminate	letal Shelves and 1 T	4 Adjustable M
	\$2,048	144	60-1/2" x 37-3/16" x 20"	D/F Starter	RP5-985-S07
	\$3,685	268	60-1/2" x 73-3/8" x 20"	D/F Starter/Adder	RP5-985-S08
	\$2,090	190	60-1/2" x 37-3/16" x 24"	D/F Starter	RP5-986-S07
	\$3,761	352	60-1/2" x 73-3/8" x 24"	D/F Starter/Adder	RP5-986-S08

2 Adjustable Metal Shelves and 1 Thermally-Fused Laminate Base Shelf per Side								
RP5-765-S07	D/F Starter	48" x 37-3/16" x 20"	117	\$1,615				
RP5-765-S08	D/F Starter/Adder	48" x 73-3/8" x 20"	217	\$2,907				
RP5-766-S07	D/F Starter	48" x 37-3/16" x 24"	154	\$1,647				
RP5-766-S08	D/F Starter/Adder	48" x 73-3/8" x 24"	285	\$2,967				



<u> 2 Adjustable N</u>	<u>Metal Shelves and 1 Tl</u>	<u>hermally-Fused Laminate</u>	Base Shelf	per Side	42"H Omega Shelves
RP5-987-S07	D/F Starter	42" x 37-3/16" x 20"	106	\$1,506	
RP5-987-S08	D/F Starter/Adder	42" x 73-3/8" x 20"	204	\$2,710	
RP5-991-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$1,538	
RP5-991-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$2,765	



 $Please\ specify\ Laminate\ Finishes\ (Table\ 4)\ and\ Metal\ Color\ (Table\ 5).\ Details\ can\ be\ found\ on\ page\ GEN\ 5.$ 

Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Partitions included for Mobile Units.



60-1/2"H Omega
<b>Book Stop Shelves</b>



Catalog No.	Description	HxWxD	Wt. (lbs.)	Price
4 Adjustable	Metal Shelves and 1 Met	al Base Shelf per Side		
RP7-985-S07	D/F Starter	60-1/2" x 37-3/16" x 20"	144	\$2,505
RP7-985-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 20"	268	\$4,400
RP7-986-S07	D/F Starter	60-1/2" x 37-3/16" x 24"	190	\$2,566
RP7-986-S08	D/F Starter/Adder	60-1/2" x 73-3/8" x 24"	352	\$4,475

#### 48"H Omega Book Stop Shelves



2 Adjustable	2 Adjustable Metal Shelves and 1 Metal Base Shelf per Side								
RP7-765-S07	D/F Starter	48" x 37-3/16" x 20"	117	\$1,843					
RP7-765-S08	D/F Starter/Adder	48" x 73-3/8" x 20"	217	\$3,179					
DD7 7// 007	D /F 01	4011 07 0 (4 ( 11 0 4 11	454	44.044					
RP7-766-S07	D/F Starter	48" x 37-3/16" x 24"	154	\$1,941					
RP7-766-S08	D/F Starter/Adder	48" x 73-3/8" x 24"	285	\$3,346					

#### (42"H Omega Book Stop Shelves



2 Adjustable	e Metal Shelves and 1	Metal Base Shelf per Side		
RP7-987-S07	D/F Starter	42" x 37-3/16" x 20"	106	\$1,660
RP7-987-S08	D/F Starter/Adder	42" x 73-3/8" x 20"	204	\$2,975
RP7-991-S07	D/F Starter	42" x 37-3/16" x 24"	140	\$1,747
RP7-991-S08	D/F Starter/Adder	42" x 73-3/8" x 24"	269	\$3.132

Please specify Laminate Finishes (Table 4) and Metal Color (Table 5). Details can be found on page GEN 5.

Note: Clip & Strip Shelving CANNOT be used with Omega Shelves. Shelving Backs and Partitions CANNOT be used with Book Stop Shelving.

Sway Braces included.

#### **Shelving Backs**

Except where specified, all single-faced shelving is supplied without backs. When specified, single-faced shelving is supplied with full-height and full-width 1/4" thick thermally-fused laminate panel. Backs Partitions fit into rabbets in the end panels, intermediates, tops, and base, so that edges are concealed from view after installation.

#### Shelving Partitions

Except where specified, all double-faced shelving is supplied without partitions. When specified, double-faced shelving is supplied with full-height and full-width 1/4" thick thermally-fused laminate panel. Partitions fit into rabbets in the end panels, intermediates, tops, and base, so that edges are concealed from view after installation.

	Price	Wt. (lbs.)	HxWxD	Description	Catalog No.
Shelving Backs/Partiti	\$180	24	87-5/16" x 35-5/8" x 1/4"	Back/Partition, 90"H	RPB-608-S00
	\$174	22	79-5/16" x 35-5/8" x 1/4"	Back/Partition, 82"H	RPB-600-S00
	\$162	20	69-5/16" x 35-5/8" x 1/4"	Back/Partition, 72"H	RPB-620-S00
	\$150	18	58-15/16" x 35-5/8" x 1/4"	Back/Partition, 60-1/2"H	RPB-602-S00
	\$111	15	46-7/16" x 35-5/8" x 1/4"	Back/Partition, 48"H	RPB-606-S00
	\$102	12	40-7/16" x 35-5/8" x 1/4"	Back/Partition, 42"H	RPB-604-S00

Please specify Laminate Finishes (Table 4). Details can be found on page GEN 5.

## **External Edge Banding**

Single-Faced Tops are banded on both ends and on the front edge only. Back edge is not banded. Double-Faced Tops are banded on both ends and on the front and back edges.

Catalog No.	Description	Wt. (lbs.)	Price
To Cover ONE UNIT			
RP-W10-S01	10"D, Single-Faced	11	\$118
RP-W12-S01	12"D, Single-Faced	14	\$122
RP-W20-S01	20"D, Double-Faced	23	\$176
RP-W24-S01	24"D, Double-Faced	27	\$199
To Cover TWO UNITS	;		
RP-W10-S02	10"D, Single-Faced	22	\$165
RP-W12-S02	12"D, Single-Faced	28	\$175
RP-W20-S02	20"D, Double-Faced	46	\$248
RP-W24-S02	24"D, Double-Faced	54	\$312
To Cover THREE UNI RP-W10-S03	10"D, Single-Faced	33	\$221
RP-W12-S03	12"D, Single-Faced	42	\$231
RP-W20-S03	20"D, Double-Faced	69	\$314
RP-W24-S03	24"D, Double-Faced	81	\$330
		01	4000
To Cover FOUR UNIT			
RP-W10-S04	10"D, Single-Faced	44	\$329
RP-W12-S04	12"D, Single-Faced	56	\$349
RP-W20-S04	20"D, Double-Faced	92	\$491
RP-W24-S04	24"D, Double-Faced	108	\$528
To Cover FIVE UNITS			
RP-W10-S05	10"D, Single-Faced	55	\$381
RP-W12-S05	12"D, Single-Faced	70	\$407
RP-W20-S05	20"D, Double-Faced	115	\$562
RP-W24-S05	24"D, Double-Faced	135	\$642
To Cover SIX UNITS			
RP-W10-S06	10"D, Single-Faced	66	\$430
RP-W12-S06	12"D, Single-Faced	84	\$461
RP-W20-S06	20"D, Double-Faced	138	\$626
RP-W24-S06	24"D, Double-Faced	162	\$660
To Cover SEVEN UNI	<u>TS</u>		
RP-W10-S07	10"D, Single-Faced	77	\$546
RP-W12-S07	12"D, Single-Faced	98	\$580
RP-W20-S07	20"D, Double-Faced	161	\$803
RP-W24-S07	24"D, Double-Faced	189	\$859
To Cover EIGHT UNIT	<u>rs</u>		
RP-W10-S08	10"D, Single-Faced	88	\$595
RP-W12-S08	12"D, Single-Faced	112	\$635
RP-W20-S08	20"D, Double-Faced	184	\$875
RP-W24-S08	24"D, Double-Faced	216	\$974
To Cover NINE UNITS	5		
RP-W10-S09	10"D, Single-Faced	99	\$645
RP-W12-S09	12"D, Single-Faced	126	\$691
RP-W20-S09	20"D, Double-Faced	207	\$941
RP-W24-S09	24"D, Double-Faced	243	\$990

Please specify Laminate Finishes (Table 4). Details can be found on page GEN 5.

# Seating

## **General Specifications**

#### **CHAIR FRAME**

The chair frame is constructed of 16-gauge steel tubing. All joints are mig welded. The front and back legs are 1-3/4" diameter, and the side and front stretchers are 1-1/2" x 3/4" rectangular tubing. The framing includes four metal brackets attached to the seat. The legs are equipped with rubber-cushioned glides.

#### **CHAIR SEAT**

Chair seats are 5/8" thick bent multi-ply faced with maple or rift-cutt red oak as specified.

#### **UPHOLSTERED SEAT**

Upholstered seats receive 1-1/2" thick HR-55, 2.8 density 55 ILD foam prior to being covered by a selected upholstery material that is wrapped around and stapled to the underside of the seat panel.

#### WOOD CHAIR BACKS

Chair backs are 5/8" thick, bent multi-ply faced with maple or rift-cut red oak as specified. Adult backs are 10"H x 19-1/2"W. Youth backs are 8"H x 15-1/2"W.

#### UPHOLSTERED CHAIR BACKS

Upholstered chair backs have a back platen of curved plywood and receive 1" thick 1835 FR, 1.8 density, 35 ILD foam prior to being covered by a selected upholstery material that is wrapped around and stapled to the back of the platen. This upholstered back platen is then screwed to the wood back from the rear support.

#### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

#### **GLIDES**

Each chair leg is equipped with a 7/8" diameter rubber-cushioned alide.

	Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Wood	Wood Seat a	and Back with I	Metal Frame Chair,	Oak V	lood					
Seat/Back Chair	AP2-571-S00	32-1/2"H Adult	18-1/2" x 20-1/2" x 17	" 25		\$718				
	AP2-561-S00	28-3/4"H Youth	16-1/2" x 17-1/2" x 15	" 25		\$718				
	Wood Seat a	and Back with I	Metal Frame Chair,	Maple	Wood					
	AP2-571-SMA	32-1/2"H Adult	18-1/2" x 20-1/2" x 17	" 25		\$775				
	AP2-561-SMA	28-3/4"H Youth	16-1/2" x 17-1/2" x 15	" 25		\$775				
Upholstered	<u>Upholstered</u>	Seat and Baci	k with Metal Frame	Chair,	Oak Woo	od				
Seat/Back Chair	AP2-574-S00	32-1/2"H Adult	18-1/2" x 20-1/2" x 17	" 25	\$818	\$816	\$1,020	\$1,052	\$1,191	\$1,261
	AP2-564-S00	28-3/4"H Youth	16-1/2" x 17-1/2" x 15	" 25	\$762	\$761	\$950	\$982	\$1,112	\$1,174

Please specify Wood Finish (Table 1), Metal Color (Table 3) and Upholstery; if applicable (Table 5). Details can be found on pages GEN 4 and GEN 5.

\$891

\$830

\$890

\$828

\$1,113

\$1,037

\$1,148

\$1,068

\$1,301

\$1,208

\$1,374

\$1,279

Upholstered Seat and Back with Metal Frame Chair, Maple Wood

Fabric Requirements: 1-1/2 yards per chair, Non-directional, 54" wide.

AP2-574-SMA 32-1/2"H Adult 18-1/2" x 20-1/2" x 17" 25

AP2-564-SMA 28-3/4"H Youth 16-1/2" x 17-1/2" x 15" 25

## **General Specifications**

#### CHAIR FRAME

Chair frame is 36" overall height and 18-5/8" overall width. The legs are 1-3/4" square. The back legs receive a 10° angle beginning at the top of the seat. Lower support stretcher braces will be positioned between the front and back leg 9" from the bottom and will be 1"H x 3/4" thick. There are two (2) horizontal stretchers between the support braces that measure 3/4"H x 1" thick. Seat rails are 1-1/4" x 1" thick. All joints shall be mortised, tenoned, and glued. All vertical and horizontal edges are eased.

#### CHAIR SEAT - WOOD

The wood seat is scooped solid wood, 1" thick, 19"W, 19"D, with notches cut in the two (2) back corners to fit around the back legs.

#### **CHAIR SEAT - UPHOLSTERED**

The chair seat is 3/4" thick plywood covered with 1-1/2" thick foam and covered with a selected upholstery material which will be wrapped around and stapled to the underside of the seat. The underside of the seat is covered with a black cambric material.

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

#### CHAIR BACKS

The seat backs are 16-gauge metal, curved to fit the contour of the top back rail of the chair which is solid wood, 1-1/4"H x 1" thick and curved at a 30" radius. The backs are attached to the chair using finished wood screws. The metal is available in 5 different laser cut patterns which are electrostatic powder painted with no bare metal or sharp edges.

#### CHAIR ARMS


The arm is 1-3/4" square. The arm is attached 2" back from the front of the arm to a J-shaped vertical arm support that is 1-3/4" square. Vertical arm support is attached to the side seat rail with a wood lag bolt and fastened with a washer and nut. The arm is attached to the back post with a wood screw. Screw head is counter-sunk and capped with a wooden cover and sanded flush.

#### **CHAIR GLIDES**

Each chair leg is equipped with a 7/8" diameter rubber cushioned nail glide. This chair has passed the ANSI/BIFMA X5.1-2002 Type III test.

#### METAL BACK DESIGNS

When ordered, one of the following back designs must be specified as part of the catalog number. I.e.: an All Wood Adult Height chair in Oak wood and with the "Horizontal Slat" back design would be BBH-551-S00



# Seating

When ordered, one of the following back designs must be specified as part of the catalog number. Example: an All Wood Adult Height chair in Oak wood with the "Horizontal Slats" back design would be BBH 551 S00.












Q - QUARTER CIRCLE

T - TRIANGLES

H - HORIZONTAL SLATS

	Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
All Wood Chair without Arms	All Wood Chair,	Oak Wood								
	BB551-S00 OAK	32-1/2"H Adult	18" x 19" x 19"	22		\$876				
	BB561-S00 OAK	28-3/4"H Youth	16" x 19" x 19"	21		\$876				
	All Wood Chair, I	<u> Maple Wood</u>								
	BB551-S00 MAP	32-1/2"H Adult	18" x 19" x 19"	22		\$876				
	BB561-S00 MAP	28-3/4"H Youth	16" x 19" x 19"	21		\$876				





Wood Framed Chair with Upholstered Seat, Oak Wood									
BB552-S00 OAK	32-1/2"H Adult	18" x 19" x 19"	22	\$1,002	\$997	\$1,201	\$1,241	\$1,455	\$1,540
BB562-S00 OAK	28-3/4"H Youth	16" x 19" x 19"	21	\$1,002	\$997	\$1,201	\$1,241	\$1,455	\$1,540
Wood Framed Ch BB552-S00 MAP BB562-S00 MAP	nair with Uphols 32-1/2"H Adult 28-3/4"H Youth	stered Seat, Ma 18" x 19" x 19" 16" x 19" x 19"	<b>аріе И</b> 22 21	\$1,002 \$1,002	\$997 \$997	\$1,201 \$1,201	\$1,241 \$1,241	\$1,455 \$1,455	\$1,540 \$1,540

Fabric Requirements: 1/2 yards per chair, Non-directional, 54" wide.

**All Wood Chair** with Arms



All Wood Chair with Arms	(Arm Height: 26-3/8" Adult, 24-3/8" Youth), Oak Wood

BB\_-581-S00 OAK 32-1/2"H Adult 18" x 19" x 19" 28 \$1,002 BB\_-591-S00 OAK 28-3/4"H Youth 16" x 19" x 19" 27 \$1,002

All Wood Chair with Arms (Arm Height: 26-3/8" Adult, 24-3/8" Youth), Maple Wood

18" x 19" x 19" BB\_-581-S00 MAP 32-1/2"H Adult \$1,002 28 BB\_-591-S00 MAP 28-3/4"H Youth \$1,002 16" x 19" x 19" 27

Upholstered Seat **Chair with Arms** 



#### Wood Framed Chair with Upholstered Seat and Arms (Arm Height: 26-3/8" Adult, 24-3/8" Youth), Oak Wood 18" x 19" x 19"

BB\_-582-S00 OAK 32-1/2"H Adult 28 \$1,114 \$1,110 \$1,336 \$1,382 \$1,619 \$1,712 BB\_-592-S00 OAK 28-3/4"H Youth 16" x 19" x 19" 27 \$1,114 \$1,110 \$1,336 \$1,382 \$1,619 \$1,712

#### Wood Framed Chair with Upholstered Seat and Arms (Arm Height: 26-3/8" Adult, 24-3/8" Youth), Maple Wood

BB\_-582-S00 MAP 32-1/2"H Adult 18" x 19" x 19" \$1,114 \$1,110 \$1,336 \$1,382 \$1,619 \$1,712 BB\_-592-S00 MAP 28-3/4"H Youth 16" x 19" x 19" 27 \$1,114 \$1,110 \$1,336 \$1,382 \$1,619 \$1,712

Fabric Requirements: 1/2 yards per chair, Non-directional, 54" wide.

Please specify Wood Finish (Table 1), Upholstery; if applicable (Table 5) and Back Design (Above). Details can be found on pages GEN 4 and GEN 5.

## **General Specifications**

#### CHAIR FRAMES

Each frame member is constructed from 1-1/4" hardwood. All frame joints are mortised, tenoned and glued. Legs, back posts, and stretchers are 1" x 2-3/16"W. Upper side rail is 1" x 3"W; lower side rail is 1" x 2-3/16"W. Front and back top rails are 1" x 2-1/2" shaped to receive seat. Tops of front and rear vertical post in side frames have a 3/4" radius, and the bottom of each leg receives a 3/4" radius. Front and back legs are coped with a 7/8" radius on the two outside edges. The top of the side seat rails, the top of the side stretchers and the top of the cross stretchers are also coped with a 7/8" radius.

All frames have a 3/4" solid hardwood support brace in each corner of the seat area to give added strength.

#### **CHAIR SEAT**

Standard adult wood seats are 3/4" thick, bent-plywood panel, faced with select hardwood veneers. Standard youth and juvenile wood seats are 1/2" thick bent plywood panel, faced with select hardwood veneers.

Note: Optional 3/4" thick, hardwood seats, (available at extra charge), are constructed of glued-up strips not less than 1" or more than 3"W. Seat panels are scooped for seating comfort.

Upholstered seats are constructed of 1/2" formed plywood. The plywood is covered with 2" thick foam prior to being covered by a selected upholstery material which is wrapped around and stapled to the underside of seat. The underside of the seat is covered with black cambric material.

#### CHAIR BACK

Chair back is 1"  $\times$  5" (youth & juvenile) or 6" H (adult) steam-bent, solid hardwood, screwed into vertical back posts on an 8û angle using four 2" joint connector bolts. Upholstered backs have a back platen which is curved plywood; prior to upholstery two tee-nuts are inserted into the platen. The platen is covered with 1" foam padding and upholstered with all edges wrapped and stapled to the back side of the platen. Upholstered platens are attached to the chair back by two machine bolts which pass through the solid chair back into the tee-nuts in the platen.

#### UPHOLSTERY MATERIALS AND FABRICS

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

#### **GLIDES**

Leg base chairs are equipped with rubber-cushioned glides.

#### **SLED BASE CHAIRS**

Sled base chairs are of the same construction as leg base chairs but receive two 1" x 2-3/16" rails tenoned and glued to the bottom of leg post to form a sled base. Sled base chairs do not receive glides.

	Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
All Wood Chair	All Wood Chair v	vith Plywood Sea	at, Oak Wood							
	B1-551-S00 OAK	-	18" x 18-3/4" x 18"	23		\$362				
·	B1-561-S00 OAK	27-3/8"H Youth	16" x 16" x 16"	23		\$362				
	B1-541-S00 OAK	25-3/8"H Juvenile		22		\$362				
	All Wood Chair v	vith Plywood Sea	at, Maple Wood	1						
	B1-551-S00 MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$384				
	B1-561-S00 MAP	27-3/8"H Youth	16" x 16" x 16"	23		\$384				
U	B1-541-S00 MAP	25-3/8"H Juvenile	e 14" x 16" x 16"	22		\$384				
	All Wood Chair v	vith Solid (Saddı	le) Seat, Oak W	ood						
	B1-551-0AK	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$383				
	B1-561-0AK	27-3/8"H Youth	16" x 16" x 16"	23		\$383				
	B1-541-0AK	25-3/8"H Juvenile	2 14" x 16" x 16"	22		\$383				
	All Wood Chair v	vith Solid (Saddı	le) Seat, Maple	Wood						
	B1-551-OAK MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$406				
	B1-561-0AK MAP	27-3/8"H Youth	16" x 16" x 16"	23		\$406				
	B1-541-0AK MAP	25-3/8"H Juvenile	e 14" x 16" x 16"	22		\$406				

Upholstered Back Chair



Wood Frame Cha	air with Upholstered Back and F	Plywoo	od Seat, Oa	k Wood				
B1-553-S00 OAK	32-3/8"H Adult 18" x 18-3/4" x 18"	23	\$413	\$412	\$433	\$448	\$601	\$635
B1-563-S00 OAK	27-3/8"H Youth 16" x 16" x 16"	23	\$413	\$412	\$433	\$448	\$601	\$635
B1-543-S00 OAK	25-3/8"H Juvenile 14" x 16" x 16"	22	\$413	\$412	\$433	\$448	\$601	\$635
Wood Frame Cha	air with Upholstered Back and F	Plywoo	od Seat, Ma	aple Wood	,			
B1-553-S00 MAP	32-3/8"H Adult 18" x 18-3/4" x 18"	23	\$438	\$437	\$458	\$475	\$638	\$675
B1-563-S00 MAP	27-3/8"H Youth 16" x 16" x 16"	23	\$438	\$437	\$458	\$475	\$638	\$675
B1-543-S00 MAP	25-3/8"H Juvenile 14" x 16" x 16"	22	\$438	\$437	\$458	\$475	\$638	\$675
Wood Frame Cha	air with Upholstered Back and S	Solid (	Saddle) Sea	at, Oak Wo	ood			
B1-553-OAK	32-3/8"H Adult 18" x 18-3/4" x 18"	23	\$430	\$429	\$451	\$469	\$626	\$662
B1-563-0AK	27-3/8"H Youth 16" x 16" x 16"	23	\$430	\$429	\$451	\$469	\$626	\$662
B1-543-0AK	25-3/8"H Juvenile 14" x 16" x 16"	22	\$430	\$429	\$451	\$469	\$626	\$662
Wood Frame Cha	air with Upholstered Back and S	Solid (	Saddle) Sea	at, Maple	<u>Wood</u>			
B1-553-OAK MAP	32-3/8"H Adult 18" x 18-3/4" x 18"	23	\$456	\$455	\$478	\$496	\$665	\$703
B1-563-0AK MAP	27-3/8"H Youth 16" x 16" x 16"	23	\$456	\$455	\$478	\$496	\$665	\$703
B1-543-0AK MAP	25-3/8"H Juvenile 14" x 16" x 16"	22	\$456	\$455	\$478	\$496	\$665	\$703

Fabric Requirements: Back 1/4 yards and Seat 1/2 yards per chair, Non-directional, 54" wide.

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery;\ if\ applicable\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Wood Frame Cha	air with Upholster	ed Seat, Oak	Wood							Upholstered Seat Chai
B1-552-S00 OAK	32-3/8"H Adult 18	3" x 18-3/4" x 18"	23	\$425	\$421	\$475	\$493	\$614	\$650	Scat Orial
B1-562-S00 OAK	27-3/8"H Youth	16" x 16" x 16"	23	\$425	\$421	\$475	\$493	\$614	\$650	
B1-542-S00 OAK	25-3/8"H Juvenile	14" x 16" x 16"	22	\$425	\$421	\$475	\$493	\$614	\$650	
Wood Frame Cha	air with Upholster	ed Seat, Map	le Woo	d						
B1-552-S00 MAP	32-3/8"H Adult 18	3" x 18-3/4" x 18"	23	\$451	\$447	\$504	\$523	\$651	\$689	
B1-562-S00 MAP	27-3/8"H Youth	16" x 16" x 16"	23	\$451	\$447	\$504	\$523	\$651	\$689	
B1-542-S00 MAP	25-3/8"H Juvenile	14" x 16" x 16"	22	\$451	\$447	\$504	\$523	\$651	\$689	

B1-554-S00 OAK	a <i>ir with Upholstered Seat and B</i> 32-3/8"H Adult 18" x 18-3/4" x 18"	23	\$488	\$479	\$601	\$619	\$701	\$741	Upholstered Seat/Back Chai
B1-564-S00 OAK	27-3/8"H Youth 16" x 16" x 16"	23	\$488	\$479	\$601	\$619	\$701	\$741	
B1-544-S00 OAK  Wood Frame Cha	25-3/8"H Juvenile 14" x 16" x 16"  air with Upholstered Seat and B	22 <b>ack, N</b>	\$488 <u>Maple Woo</u>	\$479 <u>d</u>	\$601	\$619	\$701	\$741	
B1-554-S00 MAP	32-3/8"H Adult 18" x 18-3/4" x 18"	23	\$517	\$509	\$638	\$657	\$743	\$786	
B1-564-S00 MAP	27-3/8"H Youth 16" x 16" x 16"	23	\$517	\$509	\$638	\$657	\$743	\$786	
B1-544-S00 MAP	25-3/8"H Juvenile 14" x 16" x 16"	22	\$517	\$509	\$638	\$657	\$743	\$786	

Please specify Wood Finish (Table 1) and Upholstery; if applicable (Table 5). Details can be found on pages GEN 4 and GEN 5.



	Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
All Wood Chair	All Wood Chair v	vith Plywood S	Seat, Oak Wood							
	B2-551-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23		\$362				
	B2-561-S00 OAK	27"H Youth	16" x 16" x 16"	23		\$362				
	B2-541-S00 OAK	25"H Juvenile	14" x 16" x 16"	22		\$362				
	All Wood Chair v	vith Plywood S	Seat, Maple Wood	<u>d</u>						
	B2-551-S00 MAP	32"H Adult	18" x 18-3/4" x 18"	23		\$384				
	B2-561-S00 MAP	27"H Youth	16" x 16" x 16"	23		\$384				
	B2-541-S00 MAP	25"H Juvenile	14" x 16" x 16"	22		\$384				
	All Wood Chair v	vith Solid (Sad	ldle) Seat, Oak W	<u>'ood</u>						
	B2-551-0AK	32"H Adult	18" x 18-3/4" x 18"	23		\$383				
	B2-561-0AK	27"H Youth	16" x 16" x 16"	23		\$383				
	B2-541-OAK	25"H Juvenile	14" x 16" x 16"	22		\$383				
	All Wood Chair v	vith Solid (Sad	ldle) Seat, Maple	Wood						
	B2-551-OAK MAP	32"H Adult	18" x 18-3/4" x 18"	23		\$406				
	B2-561-0AK MAP	27"H Youth	16" x 16" x 16"	23		\$406				
	B2-541-0AK MAP	25"H Juvenile	14" x 16" x 16"	22		\$406				

Upholstered	
Rack Chair	



Wood Frame Cha	air with Uphols	stered Back and F	<u> Yywo</u>	od Seat, Oal	k Wood				
B2-553-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23	\$413	\$412	\$433	\$448	\$601	\$635
B2-563-S00 OAK	27"H Youth	16" x 16" x 16"	23	\$413	\$412	\$433	\$448	\$601	\$635
B2-543-S00 OAK	25"H Juvenile	14" x 16" x 16"	22	\$413	\$412	\$433	\$448	\$601	\$635
Wood Frame Cha	air with Uphols	stered Back and F	lywo	od Seat, Ma	ple Wood				
B2-553-S00 MAP	32"H Adult	18" x 18-3/4" x 18"	23	\$438	\$437	\$458	\$475	\$638	\$675
B2-563-S00 MAP	27"H Youth	16" x 16" x 16"	23	\$438	\$437	\$458	\$475	\$638	\$675
B2-543-S00 MAP	25"H Juvenile	14" x 16" x 16"	22	\$438	\$437	\$458	\$475	\$638	\$675
Wood Frame Cha	air with Uphols	stered Back and S	Solid (	Saddle) Sea	at, Oak Wo	ood			
B2-553-0AK	32"H Adult	18" x 18-3/4" x 18"	23	\$430	\$429	\$451	\$469	\$626	\$662
B2-563-0AK	27"H Youth	16" x 16" x 16"	23	\$430	\$429	\$451	\$469	\$626	\$662
B2-543-0AK	25"H Juvenile	14" x 16" x 16"	22	\$430	\$429	\$451	\$469	\$626	\$662
						_			
Wood Frame Cha	<u>air with Uphols</u>	stered Back and S	Solid (	<u>(Saddle) Sea</u>	it, Maple I	<u>Wood</u>			
B2-553-OAK MAP	32"H Adult	18" x 18-3/4" x 18"	23	\$456	\$455	\$478	\$496	\$665	\$703
B2-563-OAK MAP	27"H Youth	16" x 16" x 16"	23	\$456	\$455	\$478	\$496	\$665	\$703
B2-543-0AK MAP	25"H Juvenile	14" x 16" x 16"	22	\$456	\$455	\$478	\$496	\$665	\$703

 $Please \ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery;\ if\ applicable\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

	Grade 5 Price	Grade 4 Price	Grade 3 Price	Grade 2 Price	Wood/G1 Price	COM Price	Wt. (lbs.)	Seat H x W x D	Description	Catalog No.
Upholster Seat Cha							<u>Wood</u>	stered Seat, Oak	air with Uphols	Wood Frame Cha
Seat One	\$650	\$614	\$493	\$475	\$421	\$425	23	18" x 18-3/4" x 18"	32"H Adult	B2-552-S00 OAK
	\$650	\$614	\$493	\$475	\$421	\$425	23	16" x 16" x 16"	27"H Youth	B2-562-S00 OAK
	\$650	\$614	\$493	\$475	\$421	\$425	22	14" x 16" x 16"	25"H Juvenile	B2-542-S00 OAK
						1	e Wood	stered Seat, Mapl	air with Uphols	Wood Frame Cha
	\$689	\$651	\$523	\$504	\$447	\$451	23	18" x 18-3/4" x 18"	32"H Adult	B2-552-S00 MAP
	\$689	\$651	\$523	\$504	\$447	\$451	23	16" x 16" x 16"	27"H Youth	B2-562-S00 MAP
	\$689	\$651	\$523	\$504	\$447	\$451	22	14" x 16" x 16"	25"H Juvenile	B2-542-S00 MAP

Wood Frame Cha	air with Uphols	stered Seat and B	ack, C	Dak Wood						Upholstered
B2-554-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23	\$488	\$479	\$601	\$619	\$701	\$741	Seat/Back Chair
B2-564-S00 OAK	27"H Youth	16" x 16" x 16"	23	\$488	\$479	\$601	\$619	\$701	\$741	(C)
B2-544-S00 OAK	25"H Juvenile	14" x 16" x 16"	22	\$488	\$479	\$601	\$619	\$701	\$741	:
Wood Frame Ch	air with Uphols	stered Seat and B	ack, I	Maple Woo	<u>d</u>					
B2-554-S00 MAP	32"H Adult	18" x 18-3/4" x 18"	23	\$517	\$509	\$638	\$657	\$743	\$786	
B2-564-S00 MAP	27"H Youth	16" x 16" x 16"	23	\$517	\$509	\$638	\$657	\$743	\$786	
B2-544-S00 MAP	25"H Juvenile	14" x 16" x 16"	22	\$517	\$509	\$638	\$657	\$743	\$786	

 $Please \ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery;\ if\ applicable\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

	Catalog No.	Description	Seat HxWxD	Arm Height	Wt. (lbs.)	COM V	Vood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
All Wood Chair	All Wood with	Arms and Plyn	vood Seat , Oak	Wood							
	B10ACP18S	-	18" x 18-3/4" x 18		28		\$586				
	All Wood with	Arms and Plvv	vood Seat , Mag	ole Woo	d						
	B1MACP18S	-	18" x 18-3/4" x 18		28		\$608				
	All Wood with	Arms and Soli	d (Saddle) Seat	. Oak W	lood						
	B10ACW18S		18" x 18-3/4" x 18		28		\$607				
U	All Wood with	Arms and Soli	d (Saddle) Seat	. Maple	Wood						
	B1MACW18S		18" x 18-3/4" x 18	-	28		\$631				
Upholstered Back	B10ACPUB18S	32-3/8"H Adult	d Upholstered E 18" x 18-3/4" x 18 d Upholstered E	3" 23	28	\$638	\$637	\$657	\$673	\$825	\$860
	B1MACPUB18S	32-3/8"H Adult	18" x 18-3/4" x 18	3" 23	28	\$662	\$661	\$683	\$699	\$862	\$899
	Wood Framed	with Arms and	l Upholstered E	Back/So	lid (Sad	dle) Seat	Oak Woo	<u>od</u>			
	B10ACWUB18S	32-3/8"H Adult	18" x 18-3/4" x 18	3" 23	28	\$654	\$653	\$676	\$693	\$851	\$887
U	Wood Framed	with Arms and	d Upholstered E	Back/So	lid (Sad	dle) Seat	. Maple VI	Vood			
			18" x 18-3/4" x 18		28	\$680	\$679	\$703	\$721	\$889	\$928
Upholstered Seat	B10ACUS18S	32-3/8"H Adult	1 Upholstered S 18" x 18-3/4" x 18 1 Upholstered S 18" x 18-3/4" x 18	3" 23 <b>Seat, M</b> a	28	\$650	\$646 \$671	\$699 \$728	\$717 \$748	\$838 \$875	\$874 \$913
Upholstered Seat and Back	B10ACUSB18S  Wood Framed B1MACUSB18S	32-3/8"H Adult <i>with Arms and</i> 32-3/8"H Adult	1 Upholstered S 18" x 18-3/4" x 18 1 Upholstered S 18" x 18-3/4" x 18 1 yards and Seat	3" 23 <b>Seat and</b> 3" 23	28 <b>1 Back, 1</b> 28	\$713 <i>Maple Wo</i> \$742	\$704 <b>pod</b> \$733	\$825 \$862 54" wide.	\$843 \$881	\$925 \$968	\$966 \$1,011

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery;\ if\ applicable\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Catalog No.	Description	Seat HxWxD	Arm Height	Wt. (lbs.)	COM Wo Price	ood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
All Wood with	Arms and Plvv	ood Seat , Oak	Wood								All Wood Chai
B20ACP18S	_	18" x 18-3/4" x 18		29		\$586					
All Wood with	Arms and Plvu	ood Seat , Map	le Woo	d							
B2MACP18S	-	18" x 18-3/4" x 18		29		\$608					
All Wood with	Arms and Solid	d (Saddle) Seat,	Oak W	lood							
B20ACW18S		18" x 18-3/4" x 18		29		\$607					
All Wood with	Arms and Solid	d (Saddle) Seat	Manle	Wood							
All Wood with Bamacw18S		<b>d (Saddle) Seat,</b> 18" x 18-3/4" x 18	-	<b>Wood</b> 29		\$631					
			-			\$631					Lipholetored Pace
B2MACW18S  Wood Framed	32-3/8"H Adult  with Arms and	18" x 18-3/4" x 18	" 23 ack/Ply	29	•	lood	4/57	4/72	4005	<b>*</b> 0/0	Upholstered Back
B2MACW18S  Wood Framed	32-3/8"H Adult  with Arms and	18" x 18-3/4" x 18	" 23 ack/Ply	29	<i>Seat, Oak W</i> \$638		\$657	\$673	\$825	\$860	Upholstered Baci
B2MACW18S  Wood Framed B20ACPUB18S  Wood Framed	32-3/8"H Adult  with Arms and 32-3/8"H Adult  with Arms and	18" x 18-3/4" x 18  I Upholstered B  18" x 18-3/4" x 18	" 23 ack/Ply " 23 ack/Ply	29 wood \$	\$638 Seat, Maple	<b>//ood</b> \$637	\$657	\$673	\$825	,,,,,	Upholstered Back
B2MACW18S  Wood Framed B20ACPUB18S  Wood Framed	32-3/8"H Adult  with Arms and 32-3/8"H Adult  with Arms and	18" x 18-3/4" x 18  1 Upholstered B  18" x 18-3/4" x 18	" 23 ack/Ply " 23 ack/Ply	29 wood \$	\$638	<b>//ood</b> \$637	\$657 \$683	\$673 \$699	\$825 \$862	\$860 \$899	Upholstered Baci
B2MACW18S  Wood Framed B20ACPUB18S  Wood Framed B2MACPUB18S	with Arms and 32-3/8"H Adult with Arms and 32-3/8"H Adult 432-3/8"H Adult	18" x 18-3/4" x 18  I Upholstered B  18" x 18-3/4" x 18	" 23 ack/Ply " 23 ack/Ply " 23	29  wood \$ 29  wood \$ 29	\$638 <b>Seat, Maple</b> \$662	//ood \$637 • Wood \$661	\$683			,,,,,	Upholstered Back
Wood Framed B20ACPUB18S Wood Framed B2MACPUB18S Wood Framed	with Arms and 32-3/8"H Adult with Arms and 32-3/8"H Adult with Arms and with Arms and 32-3/8"H Adult	18" x 18-3/4" x 18  1 Upholstered B  18" x 18-3/4" x 18  1 Upholstered B  18" x 18-3/4" x 18	" 23  ack/Ply " 23  ack/Ply " 23  ack/So	29  wood \$ 29  wood \$ 29	\$638 <b>Seat, Maple</b> \$662	//ood \$637 • Wood \$661	\$683			,,,,,	Upholstered Baci
Wood Framed B20ACPUB18S Wood Framed B2MACPUB18S Wood Framed B2MACPUB18S	with Arms and 32-3/8"H Adult	18" x 18-3/4" x 18  I Upholstered B 18" x 18-3/4" x 18 I Upholstered B 18" x 18-3/4" x 18	ack/Ply " 23 ack/Ply " 23 ack/Ply " 23 ack/So " 23	29  wood S 29  wood S 29  lid (Sac	\$638 <b>Seat, Maple</b> \$662 <b>Iddle) Seat, C</b> \$654	//ood \$637 • Wood \$661 Oak Woo \$653	\$683 <b>od</b> \$676	\$699	\$862	\$899	Upholstered Back

Wood Framed	Wood Framed with Arms and Upholstered Seat, Oak Wood									
B20ACUS18S	32-3/8"H Adult	18" x 18-3/4" x 18"	23	29	\$650	\$646	\$699	\$717	\$838	\$874
Wood Framed with Arms and Upholstered Seat, Maple Wood										
B2MACUS18S	32-3/8"H Adult	18" x 18-3/4" x 18"	23	29	\$676	\$671	\$728	\$748	\$875	\$913



Wood Framed	Nood Framed with Arms and Upholstered Seat and Back, Oak Wood									
B20ACUSB18S	32-3/8"H Adult	18" x 18-3/4" x 18"	23	29	\$713	\$704	\$825	\$843	\$925	\$966
Wood Framed with Arms and Upholstered Seat and Back, Maple Wood										
B2MACUSB18S	32-3/8"H Adult	18" x 18-3/4" x 18"	23	29	\$742	\$733	\$862	\$881	\$968	\$1,011

Upholstered Seat and Back

 $Please \ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery;\ if\ applicable\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

	Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Leg Base Stool	Leg Base Stool	with Upholste	red Seat, Oak Wo	<u>od</u>						
	B1-555-S00 OAK	Adult Height	18" x 18-3/4" x 18"	18	\$429	\$424	\$472	\$485	\$620	\$656
	B1-Y55-S00 OAK	Youth Height	16" x 16-1/16" x 16"	18	\$429	\$424	\$472	\$485	\$620	\$656
	B1-J55-S00 OAK	Juvenile Height	14" x 16-1/16" x 16'	18	\$429	\$424	\$472	\$485	\$620	\$656
	Leg Base Stool with Upholstered Seat, Maple Wood									
	B1-555-S00 MAP	Adult Height	18" x 18-3/4" x 18"	18	\$455	\$450	\$501	\$514	\$658	\$696
U	B1-Y55-S00 MAP	Youth Height	16" x 16-1/16" x 16"	18	\$455	\$450	\$501	\$514	\$658	\$696
	B1-J55-S00 MAP	Juvenile Height	14" x 16-1/16" x 16'	' 18	\$455	\$450	\$501	\$514	\$658	\$696
Sled Base Stool	Sled Base Stoo	l with Upholsto	ered Seat, Oak We	ood						
	B2-555-S00 OAK	Adult Height	18" x 18-3/4" x 18"	18	\$429	\$424	\$472	\$485	\$620	\$656
	B2-Y55-S00 OAK	Youth Height	16" x 16-1/16" x 16"		\$429	\$424	\$472			\$656
	B2-J55-S00 OAK	Juvenile Height	14" x 16-1/16" x 16'		\$429	\$424	\$472	\$485	\$620	\$656
	Sled Base Stool with Upholstered Seat, Maple Wood									
	B2-555-S00 MAP	Adult Height	18" x 18-3/4" x 18"	18	\$455	\$450	\$501	\$514	\$658	\$696
	B2-Y55-S00 MAP	Youth Height	16" x 16-1/16" x 16"	18	\$455	\$450	\$501	\$514	\$658	\$696
	B2-J55-S00 MAP	Juvenile Height	14" x 16-1/16" x 16'	18	\$455	\$450	\$501	\$514	\$485 \$620 \$485 \$620 \$485 \$620 \$485 \$620 \$485 \$658 \$514 \$658 \$514 \$658 \$514 \$658 \$514 \$658 \$514 \$658 \$514 \$658	\$696
Standing Height Sled Base Stool	Standing Heigh	t Sled Base St	tool with Upholste	red Sea	nt, Oak W	Vood				
	B2-655-S00 OAK	Standing Height	28" x 16" x 16-5/8"	20	\$494	\$492	\$546	\$560	\$717	\$759
	Standing Heigh	Standing Height Sled Base Stool with Upholstered Seat, Maple Wood								
	B2-655-S00 MAP	Standing Height	28" x 16" x 16-5/8"	20	\$524	\$522	\$574	\$594	\$761	\$805

Fabric Requirements: Seat 1/2 yards per chair, Non-directional, 54" wide.

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery;\ if\ applicable\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

## **General Specifications**

#### Calyx Chair

#### **FRAME**

The chair frame is constructed of 5/8" diameter, 13-gauge steel tubing with reinforcing rods inside the bends. Frames are BIFMA tested. Frames will have a bright chrome surface finish or can be finished with electrostatic applied epoxy powder-coat paint. The legs are equipped with heavy-duty nylon glides.

#### SHELL

Shells are 9-ply Beech or Birch heat induction pressed plywood. Shell dimensions are  $16\text{"W} \times 17\text{"D} \times 15\text{"H} \times 1/2\text{"}$  thick. Available in three surface materials: Polyester, HP Laminate and Veneer.

#### **GLIDES**

Each chair leg is equipped with a 5/8" diameter heavy-duty nylon glide that fits inside chair leg.

Note: Calyx chairs are stackable up to 5 high.



#### FRAME

The stool frame is constructed of 5/8" diameter, 13-gauge steel tubing with reinforcing rods inside the bends. Frames are BIFMA tested. Frames will have a bright chrome surface finish or can be finished with electrostatic applied epoxy powder-coat paint. The legs are equipped with heavy-duty nylon glides.

#### SHELL

Shells are 9-ply Beech or Birch heat induction pressed plywood. Shell dimensions are 16"W x 17"D x 15"H x 1/2" thick. Available in three surface materials: Polyester, HP Laminate and Veneer.

#### **GLIDES**

Each stool leg is equipped with a 5/8" diameter heavy-duty nylon glide that fits inside stool leg.

### Calyx Bar Height Stool

#### Frame

The stool frame is constructed of 1/2" diameter steel rod. Frames are BIFMA tested. Frames will have a bright chrome surface finish or can be finished with electrostatic applied epoxy powder-coat paint. The sled base frames are equipped with heavy-duty nylon glides.

#### SHELL

Shells are 9-ply Beech or Birch heat induction pressed plywood. Shell dimensions are 16"W x 17"D x 15"H x 1/2" thick. Available in three surface materials: Polyester, HP Laminate and Veneer.

#### **GLIDES**

Stool frames are equipped with external heavy-duty nylon glides that fit onto the sled base frame.







	Catalog No.	Description	Overall Height	Seat H x W x D	Wt. (lbs.)	Price
Polyester Face with	Polyester Face	e and Chrome Frame				
Chrome Frame Chair	CXPC18S	Adult Height	31"	18" x 16" x 17"	13	\$286
	CXPC16S	Youth Height	29"	16" x 16" x 17"	13	\$286

 $\label{thm:polyester} \textbf{Please specify Polyester Face Color: Red, Black or White}.$ 

#### Veneer Face with Chrome or Powder-Coat Frame Chair



Maple Veneer Fa	ace and Chrome Fram	<u>ne</u>			
CXVC18MAPS	Adult Height	31"	18" x 16" x 17"	13	\$452
CXVC16MAPS	Youth Height	29"	16" x 16" x 17"	13	\$452
Oak Veneer Face	e and Chrome Frame				
CXVC180AKS	Adult Height	31"	18" x 16" x 17"	13	\$452
CXVC160AKS	Youth Height	29"	16" x 16" x 17"	13	\$452
Maple Veneer Fa	ace and Powder-Coat	Frame			
CXVP18MAPS	Adult Height	31"	18" x 16" x 17"	13	\$477
CXVP16MAPS	Youth Height	29"	16" x 16" x 17"	13	\$477
Oak Veneer Face	e and Powder-Coat Fr	<u>ame</u>			
CXVP180AKS	Adult Height	31"	18" x 16" x 17"	13	\$477
CXVP160AKS	Youth Height	29"	16" x 16" x 17"	13	\$477

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Powder-Coated\ Metal\ Frame\ Color\ (Table\ 3).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

Catalog No.	Description	Overall Height	Seat H x W x D	Wt. (lbs.)	Price
Brodart Stand	ard Laminate Face and	Chrome Frame			
CXLC18S	Adult Height	31"	18" x 16" x 17"	13	\$333
CXLC16S	Youth Height	29"	16" x 16" x 17"	13	\$333
Brodart Stand	ard Laminate Face and	Powder-Coat Frame	<u>e</u>		
CXLP18S	Adult Height	31"	18" x 16" x 17"	13	\$358
CXLP16S	Youth Height	29"	16" x 16" x 17"	13	\$358

Brodart Standard Laminate Face with Chrome or Powder-Coat Frame Chair



Please specify Brodart Standard Laminate (Table 4) and Powder-Coated Metal Frame Color (Table 3). Details can be found on pages GEN 4 and GEN 5.


Customer Spe	cified Laminate Face and	d Chrome Frame			
CXCC18S	Adult Height	31"	18" x 16" x 17"	13	\$396
CXCC16S	Youth Height	29''	16" x 16" x 17"	13	\$396
Customer Spec CXCP18S CXCP16S	<b>cified Laminate Face and</b> Adult Height Youth Height	<b>d Powder-Coat Fra</b> 31" 29"	<u>ame</u> 18" x 16" x 17" 16" x 16" x 17"	13 13	\$421 \$421

Customer Specified Laminate Face with Chrome or Powder-Coat Frame Chair




Please specify any Grade 1 Wilsonart Laminate with -60 Finish (Table 2) and Powder-Coated Metal Frame Color (Table 3). Details can be found on pages GEN 4 and GEN 5. *Minimum Quantity 15*.

	Catalog No.	Description	Overall Height	Seat H x W x D	Wt. (lbs.)	Price
Polyester Face with Chrome Frame Stool	Polyester Face	e Chrome Frame				
Chilothe Frame 31001	CXPC30S	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$440
	CXPC24S	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$440



Please specify Polyester Face Color: Red, Black or White.

Veneer Face with Chrome or
Powder-Coat Frame Stool



Maple Veneer F.	ace and Chrome Frame				
CXVC30MAPS	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$606
CXVC24MAPS	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$606
Oak Veneer Fac	e and Chrome Frame				
CXVC300AKS	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$606
CXVC240AKS	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$606
Maple Veneer F.	ace and Powder-Coat Fra	<u>ıme</u>			
CXVP30MAPS	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$631
CXVP24MAPS	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$631
Oak Veneer Fac	e and Powder-Coat Fram	<u>e</u>			
CXVP300AKS	Bar Height Stool	43-1/4"	30" x 16" x 17"	17 3	\$631
CXVP240AKS	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$631

Please specify Wood Finish (Table 1) and Powder-Coated Metal Frame Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Brodart Standard Laminate Face with Chrome or Powder-Coat Frame Chair


Catalog No.	Description	Overall Height	Seat H x W x D	Wt. (lbs.)	Price
Brodart Standa	ard Laminate Face and Ch	rome Frame			
CXLC30S	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$487
CXLC24S	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$487
Brodart Standa	ard Laminate Face and Po	wder-Coat Fram	<u>e</u>		
CXLP30S	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$512
CXLP24S	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$512

Please specify Brodart Standard Laminate (Table 4) and Powder-Coated Metal Frame Color (Table 3). Details can be found on pages GEN 4 and GEN 5.



Customer Specified	d Laminate Face and Chron	me Frame							
CXCC30S	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$550				
CXCC24S	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$550				
Customer Specified	Customer Specified Laminate Face and Powder-Coat Frame								
CXCP30S	Bar Height Stool	43-1/4"	30" x 16" x 17"	17	\$575				
CXCP24S	Counter Height Stool	37-1/4"	24" x 16" x 17"	16	\$575				

Please specify any Grade 1 Wilsonart Laminate with -60 Finish (Table 2) and Powder-Coated Metal Frame Color (Table 3). Details can be found on pages GEN 4 and GEN 5. *Minimum Quantity 15.* 



Customer Specified Laminate Face with Chrome or

## **General Specifications**

#### **SHELL**

Shells are 9-ply Beech or Birch heat induction pressed 1/2" thick plywood. Shell dimensions are 16"W x 17"D x 15"H x 1/2" thick. Available in three surface materials: Polyester, HP Laminate and Veneer. Two options for mechanism — swivel or swivel tilt.

#### **FIVE STAR BASE**

Black nylon, five star. Pneumatic height adjustment, 5" range. Casters suitable for carpet or hard surfaces

Catalog No. Des	cription	Overall Height	Seat H x W x D	Wt. (lbs.)	Price	
Polyester Face with Bla	nck Five Star Bas	<u>se</u>				Polyester Face with Five Star Base
CXPBSWS Swin	rel	29-1/2"-34-1/2"	16"-21" x 16" x 17"	18	\$449	WILLI FIVE Stal Dase
CXPBSTS Swin	el Tilt	29-1/2"-34-1/2"	16"-21" x 16" x 17"	18	\$489	
Please specify Polyester Face Co	lor: Red, Black or Whi	ite.				
Maple Veneer Face with CXVBSWMAPS Swith		o <b>r Base</b> 29-1/2"-34-1/2"	16"-21" x 16" x 17"	18	\$596	Veneer Face Swivel Chair with Five Star Base
CXVBSTMAPS Swin	rel Tilt	29-1/2"-34-1/2"	16"-21" x 16" x 17"	18	\$636	
Oak Veneer Face with I	Black Five Star I	Rase				
CXVBSWOAKS Swin		29-1/2"-34-1/2"	16"-21" x 16" x 17"	18	\$596	
	el Tilt	29-1/2"-34-1/2"	16"-21" x 16" x 17"	18	\$636	
Please specify Wood Finish (Tab	e 1). Details can be fo	ound on page GEN 4.				
Brodart Standard Lami						Brodart Laminate Face with Five Star Base
CXLBSWS Swin	rel rel Tilt	29-1/2"-34-1/2" 29-1/2"-34-1/2"	16"-21" x 16" x 17" 16"-21" x 16" x 17"	18 18	\$477 \$517	with the star base
Please specify Brodart Standard	Laminate (Table 4). [	Details can be found on page (	GEN 4.			
Customer Specified La CXCBSWS Swiv		h Black Five Star Bas	e <u>e</u> 16"-21" x 16" x 17"	18	\$527	Brodart Laminate Face with Five Star Base

Please specify any Grade 1 Wilsonart Laminate with -60 Finish (Table 2). Details can be found on pages GEN 4. *Minimum Quantity 15.* 



### **CHAIR FRAME**

Front legs are 1-1/2" square at the top tapering to 1-3/8" square at the bottom. The back legs are 1-1/4" x 1" at the top tapering to 1-3/4" x 1" at the bottom. All vertical and horizontal edges are eased. Lower support stretcher brackets are positioned between the front and back legs and measure 1" x 3/4"; upper stretcher support brackets are located between the front legs and between the back legs and also measure 1 x 3/4". Seat rails are 2-1/4" x 3/4". All joints are mortised, tenoned, and glued.

### ALL WOOD CHAIR SEAT

The chair seat is 1" thick solid wood, constructed of glued-up strips not less than 1" or more than 3"W. Seat panels are scooped for seating comfort.

### CHAIR BACK

The chair back consists of a horizontal top and bottom rail, and four vertical slats positioned between the rails. The top horizontal rail is 3-1/4" x 3/4" at the center tapering to 2-1/4" x 3/4" at each end. The bottom vertical rail is positioned 1-1/4" above the seat and measures 1-1/2" x 3/4" at the center tapering to 2-1/4" x 3/4". The four vertical slats are positioned 1-5/8" apart and measure 1-1/2" x 3/8". The horizontal rails are mortised, tenoned, and glued into the back leg posts. The vertical slats are mortised, tenoned, and glued into the horizontal rails.

	Catalog No.	Description	Seat H x W x D	(lbs.)	Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Price
Slat Back Chair	All Wood, S.	lat Back Chair v	vithout Arms							
hann	CA-571-S00	34"H Adult	18" x 18-3/4" x 15-1/2	" 25		\$425				
	CA-561-S00	29-1/2"H Youth	16" x 15-1/2" x 14-1/2	" 25		\$401				

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

D Series Chairs Seating

# **General Specifications**

### **CHAIR FRAMES**

Each frame member is constructed from 1-1/4" hardwood. All frame joints are mortised, tenoned, and glued. Legs, back posts, and stretchers are 1" x 2-3/16"W. Upper side rail is 1" x 3"W; lower side rail is 1" x 2-3/16"W. Front and back top rails are 1" x 2-1/2" shaped to receive seat. The vertical back rails are dog legged for comfort. Tops of front and rear vertical post in side frames have a 3/4" radius, and the bottom of each leg receives a 3/4" radius. Front and back legs are coped with a 7/8" radius on the two outside edges only. The top of the side seat rails, the top of the side stretchers and the top of the cross stretchers are also be coped with a 7/8" radius.

All frames have a 3/4" solid hardwood support brace in each corner of the seat area to give added strength. All seats are fastened with six "Z" brackets routed into the front and back rail and screwed into the bottom of the seat.

### **CHAIR SEAT**

Standard wood seats are 1/2" (adult) or 3/4" (adult extra wide) thick, bent-plywood seat panel faced with select hardwood veneers.

Note: Optional 3/4" thick, hardwood seats, (available at extra charge), are constructed of glued-up strips not less than 1" or more than 3"W. Seat panels are scooped for seating comfort.

Upholstered seats are constructed of 1/2" formed plywood. The plywood is covered with 2" thick foam prior to being covered by a selected upholstery material which is wrapped around and stapled to the underside of seat. The underside of the seat is covered with a black cambric material.

### **CHAIR BACK**

All wood chair backs are 1" x 5" (adult) or 6" (adult extra wide) steam-bent, solid hardwood, screwed into vertical back posts on a 16° angle. The 5" back receives a 1/4" horizontal-design route at the center, creating an appearance of two 2-3/8" slats. The 6" back receives two 1/4" horizontal-design routes positioned to create the appearance of three 1-13/16" slats. Upholstered backs are a full wrap-around, upholstered, 3/4" steam-bent solid-wood panel with an 8"H crown. The back is attached to the chair with four machine screws which pass through the chair back posts.

### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

### **GLIDES**

Leg base chairs are equipped with rubber-cushioned glides.

### **SLED BASE CHAIRS**

Sled base chairs are of the same construction as leg base chairs but receive two 1" x 2-3/16" rails tenoned and glued to the bottom of leg post to form a sled base. Sled base chairs do not receive glides.

	Catalog No.	Description	Seat HxWxD	Wt. (lbs.)	COM V	lood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
All Wood Chair		<u> </u>			11100	11100	11100	11100	11100	
All Prood Criain		-	wood Seat , Oak W			¢470				
	D1-551-S00 OAK	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$470				
		-	wood Seat , Maple							
	D1-551-S00 MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$484				
			lid (Saddle) Seat, C		1					
	D1-551-OAK	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$486				
Ų			lid (Saddle) Seat, N	-	ood					
	D1-551-OAK MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23		\$501				
pholstered Back	Mood Framed w	ith Archad Unb	olotored Book and	Dhunoo	l Soot Oo	uk Waad				
	D1-553-S00 OAK	32-3/8"H Adult	o <i>lstered Back and</i> 18" x 18-3/4" x 18"	23	<i>seat, Oa</i> \$513	\$512	\$535	\$557	\$748	\$792
								4007	Ψ7.10	Ψ, , _
		-	olstered Back and	-		-		¢574	¢770	¢045
	D1-553-S00 MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23	\$529	\$528	\$551	\$574	\$770	\$815
		-	olstered Back and				<u>Vood</u>			
	D1-553-0AK	32-3/8"H Adult	18" x 18-3/4" x 18"	23	\$531	\$529	\$555	\$577	\$771	\$816
U	Wood Framed w	ith Arched Upho	olstered Back and	Solid (S.	addle) Se	at, Maple	e Wood			
	D1-553-OAK MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23	\$547	\$545	\$571	\$594	\$795	\$840
pholstered Seat	Wood Framed w	ith Slat Back an	nd Upholstered Sea	at. Oak W	/ood					
<b>P</b>	D1-552-S00 OAK	32-3/8"H Adult	18" x 18-3/4" x 18"	23	\$574	\$570	\$643	\$665	\$832	\$880
	Mood Framed w	ith Clat Book on	ed Umbalatarad Car	at Manla	Mood					
	<u>vvood Framed w.</u> D1-552-S00 MAP	32-3/8"H Adult	nd Upholstered Sea 18" x 18-3/4" x 18"	23	\$590	\$587	\$662	\$686	\$858	\$907
	D1 332 300 WWW	32 37 0 11 Addit	10 110 374 110	23	4370	<b>\$307</b>	\$00Z	4000	4030	<i>\$767</i>
Jpholstered Seat and Back		•	Seat and Back, Oa							
Sout and Buok	D1-554-S00 OAK	32-3/8"H Adult	18" x 18-3/4" x 18"	23	\$633	\$626	\$782	\$808	\$914	\$968
	Wood Framed w	ith Upholstered	Seat and Back, M.	aple Woo	<u>od</u>					
	D1-554-S00 MAP	32-3/8"H Adult	18" x 18-3/4" x 18"	23	\$652	\$646	\$805	\$833	\$943	\$997
	Fabric Requireme	nts: Back 1/4 yaı	rds and Seat 1/2 yaı	rds per ch	air, Non-di	rectional,	54" wide.			
	Please specify Wood Fi	nish (Table 1) and Up	holstery; if applicable (Ta	ble 5). Deta	ails can be fo	und on page	s GEN 4 and	GEN 5.		

Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
All Wood with Sla	at Back and P	lywood Seat , Oak W	ood							All Wood Chair
D2-551-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23		\$470					
All Wood with Sla	at Back and P	lywood Seat , Maple	Wood							
D2-551-S00 MAP	32"H Adult	18" x 18-3/4" x 18"	23		\$484					
All Wood with Sla	at Back and S	olid (Saddle) Seat, O	ak Woo	<u>d</u>						
D2-551-OAK	32"H Adult	18" x 18-3/4" x 18"	23		\$486					
All Wood with Sla	at Back and S	olid (Saddle) Seat, M	laple We	ood						
D2-551-OAK MAP	32"H Adult	18" x 18-3/4" x 18"	23		\$501					

Wood Framed wi	ith Arched Upl	holstered Back and F	Plvwo	od Seat. Oak	k Wood					Upholstered Back
D2-553-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23	\$513	\$512	\$535	\$557	\$748	\$792	
Wood Framed wi	ith Arched Upl	holstered Back and F	Plywoo	od Seat, Maj	ole Wood	!				
D2-553-S00 MAP	32"H Adult	18" x 18-3/4" x 18"	23	\$529	\$528	\$551	\$574	\$770	\$815	
Wood Framed wi	ith Arched Uni	holstered Back and S	Solid (	(Saddle) Sea	nt Oak W	and				
	•		•				±		+	
D2-553-OAK	32"H Adult	18" x 18-3/4" x 18"	23	\$531	\$529	\$555	\$577	\$771	\$816	
Wood Framed wi	ith Arched Upl	holstered Back and S	Solid (	Saddle) Sea	t, Maple	Wood				~
D2-553-OAK MAP	32"H Adult	18" x 18-3/4" x 18"	23	\$547	\$545	\$571	\$594	\$795	\$840	

Wood Framed wit	th Slat Back and	Upholstered Seat,	Oak Woo	<u>od</u>					
D2-552-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23	\$574	\$570	\$643	\$665	\$832	\$880
DZ 332 300 07110	32 II Addit	10 110 37 4 110	25	ψ57-7	ψ370	ΨΟΤΟ	Ψ005	ψ03 <u>2</u>	ΨΟΟΟ
		Unhalatorad Saat							
<u>wood Framed wit</u>	th Slat Back and	Upholstered Seat,	ıvıapıe vı	<u>100a</u>					
D2-552-S00 MAP	t <b>h Siat Back and</b> 32''H Adult	<u>Upholstered Seat,</u> 18" x 18-3/4" x 18"	<i>IVI<b>apie VV</b></i> 23	<u>′ooa</u> \$590	\$587	\$662	\$686	\$858	\$907

Upholstered Seat

Wood Framed wi	th Upholstered S	Seat and Back, Oak	( Wood						
D2-554-S00 OAK	32"H Adult	18" x 18-3/4" x 18"	23	\$633	\$626	\$782	\$808	\$914	\$968
Wood Framed wi	th Upholstered S 32"H Adult	<b>Seat and Back, Maj</b> 18" x 18-3/4" x 18"	<b>ple Wood</b> 23	<b>!</b> \$652	\$646	\$805	\$833	\$943	\$997

Upholstered Seat and Back, Sled Base

Fabric Requirements: Back 1/4 yards and Seat 1/2 yards per chair, Non-directional, 54" wide.

### CHAIR FRAME

The chair frame is constructed of commercial-grade engineered Beech hardwood with components being double-doweled, glued, stapled and screwed. Reinforcing corner blocks are glued and stapled to the front and side rails. The front legs are 1-5/8" x 1"W. The back legs are tapered one piece steam bent 1-1/2" x 3/4" at the top, 2" at the seat rail, and 1-1/4" at base. The front, back and side rails measure 1-3/4" x 1-3/4"W. The chair receives 1" x 3/4"W side stretchers and a center horizontal stretcher. The seat height is 19" from the floor. The overall chair dimension is 34"H x 22"W x 22-1/2"D.

### CHAIR SEAT - UPHOLSTERED

The upholstered chair seat is 1/2" thick multi-ply plywood. The seat receives Sytex 100% polyester sheet webbing applied with 1/2" staples at a 45° angle (minimum 3 staples per inch). A 2" thick, HR-55 high-resilient CFC-free, polyurethane foam is glued to the top surface of the seat then upholstered. Cambric material is applied to the bottom of the seat panel.

### **CHAIR BACK - UPHOLSTERED**

The upholstered back is 1/2" thick multi-ply plywood. The back receives a 1/2" thick, HR-55 high-resilient CFC-free, polyurethane foam glued to the top surface of the back panel, then upholstered. The back is inserted in routes in the back crown and seat rail. The back is offered in partial or full upholstered design.

### **CHAIR BACK - WOOD**

The back panel is 1/2" thick multi-ply plywood. The back is offered in exposed wood hourglass design.

### **CHAIR ARMS**

The chair arm is constructed of commercial-grade engineered Beech hardwood. The arm are 1-1/2" x 1"W. The arm is attached to the front leg and frame with metal to metal connection for long term secure fastening.

### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections, polyurethane foam and Sytex are CAL 117 fire rated.

### **CHAIR GLIDES**

Each chair leg is equipped with a 7/8" diameter rubber-cushioned glide.

	Catalog No.	Overall H x W x D	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Hourglass Back Chair without Arms	Wood Frame	d, Hourglass Bac	k and Upholstered S	eat Cha	ir witho	ut Arms				
Chair without Arms	ENTSC19HBS	34" x 22" x 22-1/2"	19" x 18-3/4" x 18-3/4"	31	\$978	\$929	\$975	\$1,197	\$1,357	\$1,439



Hourglass Back Chair with Arms

Wood Framed, Hourglass Back and Upholstered Seat Chair with Arms (Arm Height 25-3/4")

ENTAC19HBS 34" x 22" x 22-1/2" 19" x 18-3/4" x 18-3/4" 31 \$1,063 \$1,059 \$1,113 \$1,366 \$1,546 \$1,641



Fabric Requirements: 1-1/4 yards per chair, Non-directional, 54" wide.

Catalog No.	Overall H x W x D	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Wood Frame	ed, Partially Uphol	stered Back and Upl	nolster	ed Seat	Chair with	out Arms				Partially Upholstered Back
ENTSC19PBS	34" x 22" x 22-1/2"	19" x 18-3/4" x 18-3/4"	33	\$1,025	\$1,020	\$1,071	\$1,316	\$1,489	\$1,581	Chair without Arms



Wood Framed, Partially Upholstered Back and Upholstered Seat Chair with Arms (Arm Height 25-3/4")

ENTAC19PBS 34" x 22" x 22-1/2" 19" x 18-3/4" x 18-3/4" 35 \$1,228 \$1,223 \$1,285 \$1,577 \$1,785 \$1,895

Partially
Upholstered Back
Chair with Arms



Wood Framed, Fully Upholstered Back and Upholstered Seat Chair without Arms

ENTSC19FBS 34" x 22" x 22-1/2" 19" x 18-3/4" x 18-3/4" 34 \$1,032 \$1,026 \$1,078 \$1,325 \$1,499 \$1,591

Fully Upholstered Back Chair without Arms



Wood Framed, Fully Upholstered Back and Upholstered Seat Chair with Arms (Arm Height 25-3/4")

ENTAC19FBS 34" x 22" x 22-1/2" 19" x 18-3/4" x 18-3/4" 37 \$1,234 \$1,292 \$1,292 \$1,586 \$1,796 \$1,906

Fully Upholstered Back Chair with Arms

Fabric Requirements: 2 yards per chair, Non-directional, 54" wide.



### **CHAIR FRAME**

Chair frame is 36" overall height and 18-1/2" overall width. Front legs are 1-5/8" square at the top tapering to 1-3/8" square at the bottom. The back post is bent from selected hardwood and finished to a thickness of 1-1/4" and is routed to a proper depth to accept the seat and seat apron to ensure that the vertical sitting load is supported by these horizontal routes. The back top rail is 3-1/2" overall height and 1" thick, and is bent to a radius of 18".

### **BACK FRAME**

The top back rail is double doweled to the vertical back posts and reinforced with  $\#10 \times 1-1/4$ " wood screws. The Essex version with the accent hole gets a 2-1/4" diameter hole positioned on the centerline of top back rail.

On the Essex chair there are five vertical back slats, which are 1-1/2"W x 5/8" thick. The back slats are tenoned the glued into the top rail and bottom rail of the back frame. These slats are equally spaced.

The seat apron is bent from selected hardwood, finished to 7/8" thick by 1-5/8"W and is tenoned and glued to both the front legs and back posts. Side stretchers and cross stretchers are 1"W x  $^{3}4$ " thick. All joinery is mortised, tenoned, and glued. The cross stretchers at the connecting joint are reinforced with steel pin.

### **CHAIR SEAT - UPHOLSTERED**

The upholstered chair seat panel is 3/4" thick, curved 5-ply plywood. The seat receives 2" thick, HR-55 high-resilient polyurethane foam glued to the top surface of the seat panel, then upholstered. Cambric material is applied to the bottom of the seat panel. The seat rim rests on a horizontal notch in the back post and is attached to the frame by 11 wood screws that are screwed up through the seat apron into the bottom of the seat.

### **CHAIR SEAT - WOOD**

The all-wood seat is 1-1/4" thick, made from random width boards between 1" and 4"W, and scooped for seating comfort. The seat rim rests on a horizontal notch in the back post and is attached to the frame by 11 wood screws that are screwed up through the seat apron into the bottom of the seat.

### **CHAIR GLIDES**

Chairs are equipped with 7/8" diameter nylon glides.

### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics that meet Calif. Technical Bulletin #133 are available.

Catalog No.	Overall Height	Seat H x W x D	Wt. (lbs.)	COM \ Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
All Wood w	ith Vertic	al Back Slats, Scoop	ed Seat	with Solid	Top Slat					Scooped Seat Chair with Solid Top Slat
15-451-S00	36"	18" x 18-1/2" x 17-1/2"	30		\$626					T-



All Wood with Vertical Back Slats, Scooped Seat with Top Slat Cutout

**15-471-S00** 36" 18" x 18-1/2" x 17-1/2" 30 \$647

Scooped Seat Chair with Top Slat Cutout



Wood Framed with Vertical Back Slats, Upholstered Seat with Solid Top Slat

15.454.S00 36" 18" v 18 1/2" v 17 1/2" 30 \$656 \$652 \$786 \$813 \$051 \$1 007 with Solid Top Slat

15-454-S00 36" 18" x 18-1/2" x 17-1/2" 30 \$656 \$652 \$786 \$813 \$951 \$1,007

Wood Framed with Vertical Back Slats, Upholstered Seat with Top Slat Cutout

15-474-S00 36" 18" x 18-1/2" x 17-1/2" 30 \$677 \$673 \$812 \$837 \$982 \$1,040 with Top Slat Cutout

Fabric Requirements: 1/2 yards per chair, Non-directional, 54" wide.



### **CHAIR FRAME**

Front legs are 1-3/4" square at the top tapering to 1-1/4" square at the bottom and radiused on the front outside frame corner. The back post is 1-1/2" x 1" at the top opening to 2-1/4" x 1" at the widest point, just below the seat platen and tapering to 1-5/8" x 1" at the bottom. All vertical and horizontal edges are eased. The top of the back post receives a radius on the front and outside edges to match the radius of the top back rail.

Two lower support stretchers are positioned between the front and back legs and measure 1" x 3/4"; upper stretcher supports are located between the front legs and between the back legs and also measure 1" x 3/4". Seat rails are 2-1/4" x 3/4". All joints are mortised, tenoned, and glued.

### CHAIR SEAT- WOOD

The chair seat is 1" thick solid wood, constructed of glued-up strips not less than 1" or more than 3"W. Seat panels are scooped for seating comfort.

### CHAIR SEAT- UPHOLSTERED

The chair seat is 1/2" thick plywood with the front corners receiving a 1-1/2" radius and 1-1/2" thick, 1850 FR Density polyurethane foam. The standard fabric is Brodart's grade one. Brodart's fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

### **CHAIR BACK**

The chair back consists of a horizontal top and bottom rail and five vertical slats positioned between the rails. The top horizontal rail is  $4" \times 3/4"$ . The bottom horizontal rail measures  $3-1/2" \times 3/4"$ . The five vertical slats are positioned 1-1/4" apart and measure  $1-1/8" \times 1/2"$ . The horizontal rails are mortised, tenoned, and glued into the back leg posts. The vertical slats are mortised, tenoned, and glued into the horizontal rails.

### **CHAIR ARMS**

Arm is 2-3/8" x 1" at the front tapering to 1-1/4" x 1" at the back. The arm is attached 2" back from the front of the arm to a J-shaped vertical arm support that is 1-1/4" x 1" at the top, expanding to 1-5/8" x 1" at its connection point with the side seat rail. Vertical arm support is attached to the side seat rail with a wood lag bolt & fastened with a washer and nut. The arm is attached to the back post 7-1/2" above the seat platen with a wood screw. Screw head is counter-sunk and capped with a wooden cover.

### **CHAIR GLIDES**

Each chair leg is equipped with a 7/8" diameter rubber cushioned nail glide.

This chair has passed the ANSI/BIFMA X5.1-2002 Type III test.

Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
All Wood, Slat B	ack without Arı	ms, Oak Wood								All Wood Chai without Arms
ME-551-S00 OAK	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20		\$461					П
ME-561-S00 OAK	31"H Youth	16 x 17" x 15"	19		\$461					Пппппп
ME-541-S00 OAK	29''H Juvenile	14 x 17" x 15"	18		\$461					
All Wood, Slat B.	ack without Arı	ms, Maple Wood								
ME-551-S00 MAP	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20		\$532					
ME-561-S00 MAP	31"H Youth	16 x 17" x 15"	19		\$532					
ME-541-S00 MAP	29''H Juvenile	14 x 17" x 15"	18		\$532					

All Wood, Slat Ba	ack with Arms	(Arm Height: 26-3/16	Adult, 2	22-1/2" Youth, 20-1/2" Juvenile), Oak Wood
ME-581-S00 OAK	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20	\$557
ME-591-S00 OAK	31"H Youth	16 x 17" x 15"	19	\$557
ME-531-S00 OAK	29"H Juvenile	14 x 17" x 15"	18	\$557
All Wood, Slat Ba	ack with Arms	<u>(Arm Height: 26-3/16'</u>	'Adult, 2	22-1/2" Youth, 20-1/2" Juvenile), Maple Wood
All Wood, Slat Ba	ack with Arms 34-3/4"H Adult	(Arm Height: 26-3/16' 18 x 18-1/8" x 15-7/8"	<b>'<i>Adult, 2</i></b> 20	22-1/2" Youth, 20-1/2" Juvenile), Maple Wood \$628
•			•	
ME-581-S00 MAP	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20	\$628



Wood Framed, L	Upholstered S	eat and Slat Back wit	hout Ar	ms, Oak W	lood				
ME-552-S00 OAK	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20	\$533	\$532	\$659	\$850	\$910	\$974
ME-562-S00 OAK	31"H Youth	16 x 17" x 15"	19	\$533	\$532	\$659	\$850	\$910	\$974
ME-542-S00 OAK	29"H Juvenile	14 x 17" x 15"	18	\$533	\$532	\$659	\$850	\$910	\$974
Wood Framed, l	Upholstered S	eat and Slat Back wit	hout Ar	ms, Maple	Wood				
ME-552-S00 MAP	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20	\$608	\$606	\$752	\$969	\$1,038	\$1,110
ME-562-S00 MAP	31"H Youth	16 x 17" x 15"	19	\$608	\$606	\$752	\$969	\$1,038	\$1,110
ME-542-S00 MAP	29"H Juvenile	14 x 17" x 15"	18	\$608	\$606	\$752	\$969	\$1,038	\$1,110



		t and Slat Back with A	lrms (Al	rm Height: 2	26-3/16" Ad	dult, 22-1	//2" Youth	<b>↓</b>	
20-1/2" Juvenile)									
ME-582-S00 OAK	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20	\$623	\$621	\$770	\$993	\$1,061	\$1,135
ME-592-S00 OAK	31"H Youth	16 x 17" x 15"	19	\$623	\$621	\$770	\$993	\$1,061	\$1,135
ME-532-S00 OAK	29"H Juvenile	14 x 17" x 15"	18	\$623	\$621	\$770	\$993	\$1,061	\$1,135
Wood Framed, U 20-1/2" Juvenile)	,	eat and Slat Back wit	h Arms	(Arm Heigl	ht: 26-3/16	" Adult, 2	2-1/2" Yo	uth,	
ME-582-S00 MAP	34-3/4"H Adult	18 x 18-1/8" x 15-7/8"	20	\$693	\$690	\$856	\$1,103	\$1,180	\$1,263
ME-592-S00 MAP	31"H Youth	16 x 17" x 15"	19	\$693	\$690	\$856	\$1,103	\$1,180	\$1,263
ME-532-S00 MAP	29"H Juvenile	14 x 17" x 15"	18	\$693	\$690	\$856	\$1,103	\$1,180	\$1,263

Upholstered Seat Chair with Arms



Fabric Requirements: 1/2 yards per chair, Non-directional, 54" wide.

### **CHAIR FRAME**

Each frame member is constructed from 1-1/4" hardwoods. All frame joints are mortised, tenoned and glued. All frames have a 3/4" solid hardwood support brace in each corner to give the chair added strength. All seats are fastened with six "Z" brackets routed into the frame and screwed into the bottom of the seat.

### CHAIR SEAT

Chair seats are 1/2" thick bent multi-ply faced with select hardwood veneers.

### **UPHOLSTERED SEAT**

Upholstered seats receive 1-1/2" thick HR-55, 2.8 density 55 ILD foam prior to being covered by a selected upholstery material that is wrapped around and stapled to the underside of the seat panel.

### WOOD CHAIR BACKS

Chair backs are 5/8" thick bent multi-ply faced with select hardwood veneers. Adult backs are 6-1/2"H x 20-1/4"W. Youth backs are 5-7/8"H x 17-3/8"W.

### **UPHOLSTERED CHAIR BACKS**

Upholstered chair backs have a back platen of curved plywood and receive 1/2" thick 1835 FR, 1.8 density, 35 ILD foam prior to being covered by a selected upholstery material that is wrapped around and stapled to the back of the platen. This upholstered back platen is screwed to the wood back from the rear support.

### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics that meet Calif. Technical Bulletin #133 are available.

### **GLIDES**

Each chair leg is equipped with a 7/8" diameter rubber-cushioned alide.

	Catalog No.	Description	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
All Ash Wood Chair	All Ash Wood									
Trood Orian	G1-571-S00	31-1/4"H Adult	18" x 20" x 19-5/8"	23		\$476				
	G1-561-S00	28-1/4"H Youth	16" x 16" x 17-1/4"	22		\$476				

### Upholstered Seat/Back Chair



Ash Wood Fra	me with Upholste	red Seat and Back							
G1-574-S00	31-1/4"H Adult	18" x 20" x 19-5/8"	23	\$639	\$636	\$788	\$819	\$877	\$939
G1-564-S00	28-1 //\"H Vouth	16" v 16" v 17 <sub>-</sub> 1///"	22	\$630	\$636	\$788	\$210	\$277	\$030

Fabric Requirements: 1 yard per chair, Non-directional, 54" wide.

### **CHAIR FRAMES**

The chair frame is constructed of straight-grained hardwood. The back posts are cut into a unique curved shape design. The back is curved plywood 3/8" thick.

### WOOD CHAIR SEAT

The wood chair seat is hardwood veneer, curved plywood 1/2" thick.

### **UPHOLSTERED CHAIR SEAT**

The upholstered seat uses a 1/2" thick platen with 1-1/2" thick high-resilient polyurethane foam and fabric as selected.

### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

Catalog No	Overall H x D	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
All Wood										All Wood Chair
NE-571-S00	35" x 22"	18-1/2" x 18-1/2" x 17-3/4"	25		\$521					

 Wood Frame with Upholstered Seat
 Upholstered

 NE-572-S00
 35" x 22"
 19-1/4" x 18-3/4" x 17-3/4"
 25
 \$635
 \$632
 \$758
 \$788
 \$844
 \$904
 Seat Chair

Fabric Requirements: 1/2 yard per chair, Non-directional, 54" wide.



### **CHAIR FRAME**

Chair frame is 36" overall height and 18-1/2" overall width. Front legs are 1-5/8" square at the top tapering to 1-3/8" square at the bottom. The back post is bent from selected hardwood and finished to a thickness of 1-1/4" and is routed to a proper depth to accept the seat and seat apron to ensure that the vertical sitting load is supported by these horizontal routes. The back top rail is 3-1/2" overall height and 1" thick, and is bent to a radius of 18".

The Parallax chair is available with or without an accent hole in the back frame top rail, and with a wood seat or an upholstered seat.

### **BACK FRAME**

The top back rail is double doweled to the vertical back posts and reinforced with  $\#10 \times 1-1/4$ " wood screws. The Parallax version with the accent hole gets a 2-1/4" diameter hole positioned on the centerline of the top back rail.

On the Parallax chair there are five horizontal back slats, which are 1-1/2"W x 5/8" thick. The back slats are tenoned and glued into the side rails of the back frame. These slats are equally spaced.

The seat apron is bent from selected hardwood, finished to 7/8" thick by 1-5/8"W and is tenoned and glued to both the front legs and back posts. Side stretchers and cross stretchers are 1"W x 3/4" thick. All joinery is mortised, tenoned, and glued. The cross stretchers at the connecting joint are reinforced with a steel pin.

### CHAIR SEAT (UPHOLSTERED)

The upholstered chair seat panel is 3/4" thick 5-ply plywood. The seat receives a 2" thick, HR-55 high-resilient polyurethane foam glued to the top surface of the seat panel, then upholstered. Cambric material is applied to the bottom of the seat panel. The seat rim rests on a horizontal notch in the back post and is attached to the frame by 11 wood screws that are screwed up through the seat apron into the bottom of the seat.

### CHAIR SEAT (WOOD)

The all wood seat is 1-1/4" thick, made from random width boards between 1" and 4"W, and scooped for seating comfort. The seat rim rests on a horizontal notch in the back post and is attached to the frame by 11 wood screws that are screwed up through the seat apron into the bottom of the seat.

### **GLIDES**

Chairs are equipped with 7/8" diameter nylon glides.

### **UPHOLSTERY MATERIALS AND FABRICS**

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

15-551-S00

36"

	Overall	Seat	Wt.	COM	Wood/G1	Grade 2	Grade 3	Grade 4	Grade 5
Catalog No.	Height	HxWxD	(lbs.)	Price	Price	Price	Price	Price	Price

\$747

All Wood with Horizontal Back Slats, Scooped Seat with Solid Top Slat

18" x 18-1/2" x 17-1/2"

Scooped Seat Chair with Solid Top Slat



All Wood with Horizontal Back Slats, Scooped Seat with Top Slat Cutout

**15-571-S00** 36" 18" x 18-1/2" x 17-1/2" 30 \$781

Scooped Seat Chair with Top Slat Cutout



Wood Framed with Horizontal Back Slats, Upholstered Seat with Solid Top Slat

15-554-S00 36" 18" x 18-1/2" x 17-1/2" 30 \$904 \$895 \$1,093 \$1,135 \$1,223 \$1,316

Upholstered Seat Chair with Solid Top Slat



Wood Framed with Horizontal Back Slats, Upholstered Seat with Top Slat Cutout

15-574-S00 36" 18" x 18-1/2" x 17-1/2" 30 \$938 \$929 \$1,133 \$1,177 \$1,266 \$1,362

Upholstered Seat Chair with Top Slat Cutout

Fabric Requirements: 1/2 yards per chair, Non-directional, 54" wide.



# **General Specifications**

### CHAIR FRAME/LEGS

Chair frames are constructed of 7/8" diameter steel tubing. Cross frames are constructed of 1/2" diameter steel tubing. Front and Rear Cross frames will be bent to follow the seat profile. Frames to be finished with electrostatic applied epoxy powder-coat paint available in a wide range of colors. Legs are equipped with heavy-duty black ABS glide inserts.

### **CHAIR SEAT**

Chair seats are constructed of 1/2" thick molded plywood, faced with Maple, Oak or Walnut veneers. Chair seats measure 16-1/2"W at the front and taper back to 14"W x 18-1/4"D.

### **CHAIR BACK**

Chair backs are constructed of 1/2" thick molded plywood, faced with Maple, Oak or Walnut veneers. Chair backs measure 17-3/4"W x 10-1/4"H.

### **CHAIR ARMS**

Chair arms are constructed of 5/8" thick molded plywood, faced with Maple, Oak or Walnut veneers.

### **CHAIR GLIDES**

Chairs are equipped with 2-3/8"H x 7/8" diameter nylon glides.

Chairs stack four high.

Chairs pass all ANSI / Bifma tests.

	Catalog No.	Seat Height	HxWxD	Wt. (lbs.)	Price
Chair without Arms	Powder-Coated	Steel Frame without Arr	ms, Plywood Seats and Back Fac	ced with Oak Wood	
**13333	PELN180AKS	18"	29" x 20" x 23-1/2"	13	\$445
1	Powder-Coated S	Steel Frame without Arr	ms, Plywood Seats and Back Fac	eed with Maple Wood	
	PELN18MAPS	18"	29" x 20" x 23-1/2"	13	\$445
	<u>Powder-Coated :</u> on Walnut Wood		ms, Plywood Seats and Back Fac	ced Available Only with Clo	e <u>ar Finish</u>
0 0	PELN18WALS	18"	29" x 20" x 23-1/2"	13	\$445
H					



Chair with Arms

Powder-Coated Steel Frame with Arms, Plywood Seats and Back Faced with Oak Wood PELA180AKS 18" 29" x 25" x 23-1/2" 17 \$545 Powder-Coated Steel Frame with Arms, Plywood Seats and Back Faced with Maple Wood PELA18MAPS 18" 29" x 25" x 23-1/2" \$545 Powder-Coated Steel Frame with Arms, Plywood Seats and Back Faced Available Only with Clear Finish on Walnut Wood PELA18WALS 18" 29" x 25" x 23-1/2" 17 \$545

Please specify Wood Finish (Table 1). Details can be found on page GEN 4.

### **CHAIR FRAME**

Each frame member is constructed from solid hardwood. All frame joints are mortised and tenoned. Horizontal front and back seat rails are 1" thick x 2-1/2"W. The two bottom horizontal cross stretcher rails are 1" thick x 1-1/4"W. On the end frames, the front post is 1" thick x 2-3/16"W, the two back posts are 1" thick x 2-3/8"W, the top side seat rail are 1" thick x 3"W and the two bottom side rails are 2-3/16"W x 1" thick. The end frame is 18-1/8"W at seat level and 24-5/8"W at floor level

Four corner blocks of solid wood are glued and triple screwed to the end frames and the upper seat horizontal cross members the seats are attached with six metal "Z" brackets.

The bottom of the end frame is shaped so that the chair may sit level or be tilted back at a  $10^{\circ}$  angle.

### CHAIR SEAT - WOOD

Wood seat is 3/4" thick, bent-plywood seat panel faced with select hardwood veneer.

### CHAIR SEAT - UPHOLSTERED

Upholstered seat is constructed of formed 1/2" plywood and fitted with 1-1/2" thick foam prior to being covered with the selected upholstery material, which is wrapped around and stapled to the underside of the seat. The underside of the seat is covered with a black cambric material.

### CHAIR BACK - WOOD

Chair back is 1" thick x 6"H steam bent solid hardwood in an arched design. Back is attached to vertical back posts at an 8° angle using four 2" joint connector bolts that pass through the vertical back posts.

### CHAIR BACK - UPHOLSTERED

Upholstered Chair back is 3/4" steam-bent solid hardwood in an arched design. Back panel is fully wrapped with 1" thick foam prior to being covered by selected upholstery material. Back is attached to vertical back posts at an 8° angle using four 2" joint connector bolts that pass through the vertical back posts.

### UPHOLSTERY MATERIALS AND FABRICS

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

Catalog No.	Overall Height	Seat H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
All Wood withou	ıt Arms,	Oak Wood								All Wood Chair
2P-571-S00 OAK	32"	18" x 18-3/4" x 17-1/2"	27		\$455					
All Wood withou	ıt Arms, ı	Maple Wood								
2P-571-S00 MAP	32"	18" x 18-3/4" x 17-1/2"	27		\$455					

Wood Frame, Upl	nolstere	ed Seat and Back witho	ut Arn	ns, Oak Wood	<u>d</u>				
2P-574-S00 OAK	32"	18" x 18-3/4" x 17-1/2"	27	\$593	\$589	\$749	\$783	\$837	\$896
Wood Frame, Upl	nolstere	ed Seat and Back witho	ut Arn	ns, Maple Wo	ood				
2P-574-S00 MAP	32"	18" x 18-3/4" x 17-1/2"	27	\$665	\$660	\$839	\$876	\$938	\$1,004

Fabric Requirements: 1/2 yard per chair, Non-directional, 54" wide.

Seat/Back Chair

Upholstered

**- TWO 2 -** F11-1-19G-STG

# Lounge Furniture

### **FRAME**

End frame assemblies are constructed of 1" x 3"W solid red oak with outside edges bullnosed. All pieces are mortised, tenoned, and glued to form a solid frame. Leg type or sled type is available.

The front facing of 1" x 3-1/2"W solid oak and the back rail of 1" x 3-1/2" solid oak are mortised, tenoned and glued into the end frame assemblies. Solid hardwood corner blocks are positioned under the cushion frame and screwed to the end frame and the front and back rails.

### UPHOLSTERED SEAT/BACK PANEL

The seat and back frame are a single piece of 3/4" bent plywood. The seat portion is fitted with a Dimatrol Webbing and then covered with black cambric fabric for comfort. This is then covered with 3-1/2" thick foam, which is also used on the chair back. The foam is mitered at the jointure of both the seat and back. The entire seat and back assembly is covered with the specified upholstery fabric, except for the underside of the seat which is covered with black cambric fabric.

Brodart upholstery materials meet requirements of the following fire codes: Calif. Technical Bulletin #117 (Sec. E part 1); CS-191-53 class 1.

Fabrics which meet Calif. Technical Bulletin #133 are available.

L1 – Seating has passed the American National Standards Test X5.41983 (ANSI).

### **GLIDES**

Each end frame assembly receive two 1" diameter rubber-cushioned glides.

### BENCH - FRAME

End frame assemblies are constructed of 1" x 3"W or 5"W solid oak, with all edges heavily eased. Facing rails are 1" x 3"W solid oak. Bench seats are attached to end frame assemblies by bolting through solid hardwood bolting blocks into internally and externally threaded brass bushings embedded into end frames.

### **LOUNGE TABLES - FRAME**

See L1 Series Bench Frame Construction.

### **TABLETOP**

Tabletop is 3-ply construction consisting of 3/4" thick particleboard core and 3" wood facings, with a .50" thick, high-pressure laminate top sheet and a backing sheet not less than .20" thick for balanced construction. High-pressure laminate has a lo-glare finish resistent to scratches, fading, and staining.

L1-622-S00 OAK

L1-622-S00 MAP

17"

17"

Square Table, Maple Wood

N/A 17" x 29-1/2" x 30" 51

N/A 17" x 29-1/2" x 30" 51

Catalog No.	Seat Height	Arm Height	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
One Seat Chai	r, Oak V	<u>Vood</u>									Chair, Leg Base
L1-112-S00 OAK	17''	23''	31" x 26" x 25"	48	\$1,116	\$1,075	\$1,377	\$1,471	\$1,568	\$1,659	
One Seat Chai	r. Maple	e Wood	1								
L1-112-S00 MAP	17"	23"	31" x 26" x 25"	48	\$1,250	\$1,204	\$1,543	\$1,648	\$1,757	\$1,858	
Fabric Requirem	nents: 2	yards pe	er chair, Non-dir	ectiona	l, 54" wide	<u>,</u>					u U
Two Seat Chair	r, Oak V	Vood									Two Seat, Leg Base
L1-212-S00 OAK	17"	23"	31" x 50" x 25"	85	\$1,818	\$1,729	\$2,338	\$2,521	\$2,525	\$2,670	
Two Seat Chair	r. Maple	· Wood	,								
L1-212-S00 MAP	17''	23"	31" x 50" x 25"	85	\$2,037	\$1,937	\$2,619	\$2,823	\$2,827	\$2,990	
Fabric Requirem	nents: 4	yards pe	er chair, Non-dir	ectiona	l, 54" wide	<i>9.</i>					
Three Seat Cha	air, Oak	Wood									Three Seat, Leg Base
L1-312-S00 OAK	17''	23''	31" x 74" x 25"	117	\$2,668	\$2,533	\$3,446	\$3,721	\$3,698	\$3,913	
Three Seat Ch	air, Map	ole Woo	<u>od</u>							k	
L1-312-S00 MAP	17''	23''	31" x 74" x 25"	117	\$2,988	\$2,836	\$3,860	\$4,168	\$4,142	\$4,382	
Fabric Requirem	nents: 6 j	yards pe	er chair, Non-dir	ectiona	l, 54" wide	э.					
Bench, Oak Wo	ood										Bench, Leg Base
L1-502-S00 OAK	17''	N/A 1	8" x 47-1/2" x 20'	" 51	\$1,102	\$1,073	\$1,158	\$1,184	\$1,565	\$1,656	
Bench, Maple	Wood										
L1-502-S00 MAP	17''	N/A 1	8" x 47-1/2" x 20'	" 51	\$1,234	\$1,202	\$1,297	\$1,325	\$1,753	\$1,854	r la
Fabric Requirem	nents: 2	yards pe	er bench, Non-d	irection	al, 54" wid	de.					
Rectangular Ta	ahla Os	ak Waa	d								Rectangular Table, Leg Base
L1-612-S00 OAK	17"		<b>u</b> 7'' x 47-1/2'' x 20'	" 46		\$1,074					
Rectangular Ta	able. Ma	aple W	ood								
L1-612-S00 MAP	17"		7'' x 47-1/2'' x 20'	" 46		\$1,201					
Square Table,	Oak Wo	ood									Square Table, Leg Base
11 422 COO OAV	17"		7" , 20 1 /2" , 20	II E4		¢1 024					

Please specify Wood Finish (Table 1) and Upholstery; if applicable (Table 5). Details can be found on pages GEN 4 and GEN 5.

\$1,024

\$1,148

	Catalog No.	Seat	Arm Height	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Chair, Sled Base	<u> </u>			IIAWAD	(103.)	11100	11100	11100	11100	11100	
oriany oroa Bass	One Seat Chair										
	L1-111-S00 OAK	17''	23''	31" x 26" x 25"	48	\$1,116	\$1,075	\$1,377	\$1,471	\$1,568	\$1,659
	One Seat Chair	r, Maple	e Wood	!							
	L1-111-S00 MAP	17"	23"	31" x 26" x 25"	48	\$1,250	\$1,204	\$1,543	\$1,648	\$1,757	\$1,858
	Fabric Requirem	ents: 2	yards pe	er chair, Non-di	rectiona	al, 54" wide	<u>.</u>				
Two Seat, Sled Base	Two Seat Chair	r, Oak V	<u>Vood</u>								
	L1-211-S00 OAK	17"	23"	31" x 50" x 25"	85	\$1,818	\$1,729	\$2,338	\$2,521	\$2,525	\$2,670
	Two Soat Chair	r Manle	. 1/1/000	,							
8	Two Seat Chair L1-211-S00 MAP	17"	23"	? 31" x 50" x 25"	85	\$2,037	\$1,937	\$2,619	\$2,823	\$2,827	\$2,990
0	L1-211-300 WAP	17	23	31 830 823	65	\$Z,U37	\$1,737	\$2,017	\$2,023	<b>ΦΖ,ΟΖ</b> /	\$2,770
4	Fabric Requirem	ents: 4 j	yards pe	er chair, Non-di	rectiona	al, 54" wide	<u>.</u>				
Three Seat, Sled Base	Three Seat Cha	air, Oak	Wood								
	L1-311-S00 OAK	17"	23"	31" x 74" x 25"	117	\$2,668	\$2,533	\$3,446	\$3,721	\$3,698	\$3,913
	Three Seat Cha	air Mar	do Ma	nd							
	L1-311-S00 MAP	17"	23"	31" x 74" x 25"	117	\$2,988	\$2,836	\$3,860	\$4,168	\$4,142	\$4,382
	Fabric Requirem	ents: 6 j		er chair, Non-di	rectiona	al, 54" wide	).				
Bench, Sled Base	Bench, Oak Wo	ood									
	L1-501-S00 OAK	17''	N/A 1	8" x 47-1/2" x 20	" 51	\$1,102	\$1,073	\$1,158	\$1,184	\$1,565	\$1,656
	Bonch Manla	Mood									
	Bench, Maple L1-501-S00 MAP	17"	NI/A 1	8" x 47-1/2" x 20	ı" 51	\$1,234	\$1,202	\$1,297	\$1,325	\$1,753	\$1,854
	L 1-50 1-300 IVIAP	17	IV/A	0 147-172 120	) )]	<b>Φ1,234</b>	\$1,202	<b>Φ1,297</b>	<b>Φ1,32</b> 3	\$1,755	<b>\$1,034</b>
	Fabric Requirem	ents: 2	yards pe	er bench, Non-a	direction	nal, 54" wid	le.				
Rectangular Table, Sled Base	Rectangular Ta	able, Oa	ak Woo	<u>d</u>							
	L1-611-S00 OAK	17"		7" x 47-1/2" x 20	" 46		\$1,074				
	Rectangular Ta	able III	anlo III	and .							
	L1-611-S00 MAP	17"	-	<i>000</i>  7" x 47-1/2" x 20	ı" Δ6		\$1,201				
	21 011 300 1411	.,	14771	7 172 120	40		Ψ1,201				
Square Table, Sled Base	Square Table,	Oak Wo	ood								
1	L1-621-S00 OAK	17"		7" x 29-1/2" x 30	" 51		\$1,024				
	Square Table,	<i>Maple</i> I	Nood								
	L1-621-S00 MAP	17"		7" x 29-1/2" x 30	ı" 51		\$1,148				

### **BRODART'S CONNECTING MODULAR LOUNGE SYSTEM**

Lounge chairs are supplied either with arms on the left side only or the right side only as well as without arms. Individual chairs may be held in position with heavy-duty steel brackets which are provided with each chair.

### **FRAME**

End frame assemblies will be constructed of 1" x 3" wide solid r ed oak with outside edges bullnosed. All pieces will be mortised, tenoned, and glued to form a solid frame. Leg type and sled type available.

The front facing of 1"  $\times$  3-1/2" wide solid oak and the back rail of 1"  $\times$  3-1/2" solid oak will be mortised, tenoned and glued into the end frame assemblies. Solid hardwood corner blocks will be positioned under the cushion frame and screwed to the end frame and the front and back rails.

### UPHOLSTERED SEAT/BACK PANEL

The seat and back frame are a single piece of 3/4" bent plywood. The seat portion is fitted with a Flex-O-Lator perma mesh system and then covered with black cambric fabric for comfort. This is then covered with 3-1/2" thick foam, which is also used on the chair back. The foam is mitered at the jointure of both the seat and back. The entire seat and back assembly is covered with the specified upholstery fabric, except for the underside of the seat which is covered with black cambric fabric.

Brodart upholstery materials meet requirements of the following fire codes: Calif. Technical Bulletin #117 (Sec. E part 1); CS-191-53 class 1.

Fabrics which meet Calif. Technical Bulletin #133 are available.

### **GLIDES**

Each end frame will receive two adjustable nickel/chrome floor glides.

### **TABLETOPS**

Tabletop will be 1-1/4" thick, particleboard core with solid-wood edges, surfaced with .050 high-pressure laminate and backed with .020 phenolic sheeting. Tops is 14" high.

The Top rests on the top edge of the adjoining end frames and is held securely in place with heavy-duty steel brackets, mechanically fastened to the underside of the top.

# Lounge Furniture

	Catalog No.	Seat Height	Arm Height	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Left Arm Chair					(103.)	11100	11100	11100	11100	11100	11100
	Left Arm Chai		_								
	L1-702-S00 OAK	17"	23''	31" x 26" x 25"	40	\$1,725	\$1,797	\$2,264	\$2,423	\$2,623	\$2,773
	Left Arm Chai	r with L	eg Base	e, Maple Woo	<u>od</u>						
	L1-702-S00 MAP	17"	23"	31" x 26" x 25"	40	\$1,933	\$2,012	\$2,536	\$2,713	\$2,938	\$3,105
	Fabric Requiren	nents: 2	yards pe	er chair, Non-di	irectiona	l, 54" wide	<u>.</u>				
Right Arm Chair	Right Arm Cha	air with	Leg Bas	se, Oak Wood	<u></u>						
	L1-712-S00 OAK	17"	23"	31" x 26" x 25"	40	\$1,725	\$1,797	\$2,264	\$2,423	\$2,623	\$2,773
	District Assess Obs		/ D -	44/14/-							
	Right Arm Cha		_			¢1 022	¢2.012	<b>#2.52</b> /	¢2.742	¢2.020	£2.10F
	L1-712-S00 MAP	17"	23''	31" x 26" x 25"	40	\$1,933	\$2,012	\$2,536	\$2,713	\$2,938	\$3,105
	Fabric Requiren	nents: 2	yards pe	er chair, Non-di	irectiona	l, 54" wide	<u>,</u>				
Center (Armless) Chair	Center Armles	ss Chair	with Le	eg Base, Oak	Wood						
	L1-722-S00 OAK		N/A	31" x 26" x 25"	35	\$1,676	\$1,745	\$2,201	\$2,353	\$2,549	\$2,694
	Center Armles						44.004			40.074	
	L1-722-S00 MAP	17"	N/A	31" x 26" x 25"	35	\$1,877	\$1,954	\$2,464	\$2,636	\$2,854	\$3,018
	Fabric Requiren	nents: 2	yards pe	er chair, Non-di	irectiona	l, 54" wide	<u>.</u>				
Left Arm Chair	Left Arm Chai	r with S	led Bas	se, Oak Wood	1						
	L1-701-S00 OAK	17"	23"	31" x 26" x 25"	40	\$1,759	\$1,832	\$2,309	\$2,468	\$2,675	\$2,829
	1 - St A Ob - 5		// D		1						
	Left Arm Chai			-		¢4.070	<b>#0.05</b> 2	40 505	40.7/5	<b>#0.00</b> /	<b>#2.470</b>
	L1-701-S00 MAP	17"	23"	31" x 26" x 25"	40	\$1,970	\$2,053	\$2,585	\$2,765	\$2,996	\$3,169
	Fabric Requiren	nents: 2	yards pe	er chair, Non-di	irectiona	l, 54" wide	<u>)</u>				
Right Arm Chair	Right Arm Cha	air with	Sled Ba	se. Oak Woo	od						
	L1-711-S00 OAK		23"	31" x 26" x 25"	40	\$1,759	\$1,832	\$2,309	\$2,468	\$2,675	\$2,829
						-	-	•	-	•	-
	Right Arm Cha			-							
	L1-711-S00 MAP	17"	23"	31" x 26" x 25"	40	\$1,970	\$2,053	\$2,585	\$2,765	\$2,996	\$3,169
	Fabric Requiren	ments: 2	yards pe	er chair, Non-di	irectiona	l, 54" wide	<u>.</u>				
Center (Armless) Chair	Center Armles	ss Chair	with S	led Base. Oal	k Wood						
	L1-721-S00 OAK		N/A		35	\$1,714	\$1,786	\$2,250	\$2,410	\$2,608	\$2,759
	Contact form	oo Ch = '		lad Daas ##	nle 147:	a d					
	Center Armles						<b>#0</b> 551	40 500	40.755	0.000	40.555
	L1-721-S00 MAP	17"	N/A	31" x 26" x 25"	35	\$1,920	\$2,001	\$2,520	\$2,698	2,921	\$3,090
	Fabric Requirer	nents: 2	yards pe	er chair, Non-di	irectiona	l, 54" wide	2,				
<b>V</b> I Dlo	ase specify Wood Finish	(Table 1) a	nd Unhole	tery: if annlicable	(Table 5) 「	etails can b	e found on nac	ies GFN 4 and	d GFN 5		
rie	aso specify wood i iilisii	(IUNIC I) a	na opnois	ioi j, ii appiicable	(Table J). L	otans tan Di	o rouria oi i pag	JOS OLIV 4 dill	JLIV J.		

Oak Catalog No.	Maple Catalog No.	Description	Wt. (lbs.)	Oak Price	Maple Price	
L1-705-S00 OAK	L1-705-S00 MAP	90° Inside Corner Tabletop	32	\$656	\$714	90° Inside Corner
		This top also receives a matching woo fastened to the tabletop.	d leg in the back corr	er which is also	mechanically	Tabletop
L1-706-S00 OAK	L1-706-S00 MAP	90° Outside Corner Tabletop	26	\$653	\$711	90° Outside Corner Tabletop
L1-707-S00 OAK	L1-707-S00 MAP	Straight Tabletop	23	\$815	\$889	Straight Tabletop
L1-708-S00 OAK	L1-708-S00 MAP	45° Inside Corner Tabletop	26	\$923	\$1,012	45° Inside Corner Tabletop



### **END FRAME ASSEMBLY**

End frames are 24-1/4"H x 26-5/8"D x 2-1/2" thick skeletal type construction. The arm is 24-1/4" high at the front and arches down with a 71" radius to 20-3/4" high at the rear of the arm. The arm assembly receives a 1/4" polyurethane 1240 FR density foam wrap and is fully upholstered. When specified only, the end frame assembly will receive a 1" thick solid wood top cap of either red oak or maple as specified. The wood cap is 3-3/8" wide. The arm assembly on the bottom surface will receive two-nickel chrome plated nail glides.

### UPHOLSTERED SEAT AND BACK

The seat and back frame are a single piece of 3/4" bent-plywood. The seat portion is fitted with a Dimatrol Webbing and then covered with black cambric fabric for comfort. This is then covered with 3-1/2" thick foam, which is also used on the chair back. The entire seat and back assembly are covered with the specified upholstery fabric except for the underside of the seat which is covered with a black cambric fabric.

Brodart upholstery materials meet requirements of the following fire codes: Calif. Technical Bulletin #117 (sec. E part 1); CS-191-53 class 1.

Fabrics which meet Calif. Technical Bulletin #133 are available.

Seat height at front – 17" Arm height – 24-9/32."

### SEAT TO ARM STRETCHER RAIL

The front rail is 24-3/4" long x 3-1/2" wide and wrapped with the same 1/4" foam as the ends and upholstery. The seat support rail is 24-3/4" long x 3-1/2" wide and is not upholstered. The rear rail is 24-3/4" long x 11-7/8" wide and is wrapped with the same 1/4" foam as the ends, and is upholstered. All rails are bolted with 1/4"- 20 bolts through metal brackets into metal bushings inserted in the arm assemblies.

Fabric Requirements: 6-1/2 yards per chair, Non-directional, 54" wide.

Catalog No.	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Fully Uphols	tered Lounge Chair								Fully Upholstered Chair
L4-121-S00  Fabric Require	31-3/8" x 30-5/8" x 28-7/16" ements: 6-1/2 yards per chair,	55 <i>Non-dir</i>	\$2,425 ectional,	\$2,354 54" wide.	\$2,631	\$2,935	\$3,438	\$3,636	
<u>Upholstered</u>	Lounge Chair with Curved	Oak Ar	m Caps						Upholstered w/Arm Caps
L4-122-S00	31-3/8" x 30-5/8" x 28-7/16"	55	\$2,669	\$2,593	\$2,897	\$3,245	\$3,786	\$4,004	
<u>Upholstered</u>	Lounge Chair with Curved	<u>Maple</u>	Arm Ca <sub>l</sub>	<u>2S</u>					
L4-122-S02	31-3/8" x 30-5/8" x 28-7/16"	55	\$2,716	\$2,641	\$2,949	\$3,291	\$3,855	\$4,077	

### **END FRAME ASSEMBLY**

End frames are constructed of legs that are 1" thick x 3"W, a bottom stretcher rail 1" thick x 2-1/4"W and a top arm rail 2-1/2"W x 1" thick that is arched to match the radius of the arm. All parts are constructed from solid red oak. All joints are mortised, tenoned, and glued to form a solid unit.

The arm is 1" thick x 3-3/8"W at the front and tapers to a width of 2-5/8" at the back. The arm is constructed of solid red oak which has been steam bent to a 72" radius.

The front stretcher and front seat rail are  $3"W \times 1"$  thick solid red oak. The back seat rail is 2-3/4"W by 1" thick solid red oak. The cross stretcher and seat rails are mortised, tenoned, and glued into the side frames.

### UPHOLSTERED SEAT AND BACK

The seat and back frame are a single piece of 3/4" bent-plywood. The seat portion is fitted with a Dimatrol Webbing and then covered with black cambric fabric for comfort. This is then covered with 3-1/2" thick foam, which is also used on the chair back. The entire seat and back assembly are covered with the specified upholstery fabric except for the underside of the seat which is covered with a black cambric fabric.

Brodart upholstery materials meet requirements of the following fire codes: Calif. Technical Bulletin #117 (sec. E part 1); CS-191-53 class 1.

Fabrics which meet Calif. Technical Bulletin #133 are available.

Seat height at front – 16-3/4." Arm height – 24-9/32."

### WOOD PLATEN FOR SIDE FRAME (OPTIONAL)

A 1/4" thick wood platen can be inserted into the side frame at the time of manufacture. This frame is constructed of 1/4" veneered plywood and is mortised into the adjoining frame members.

### **UPHOLSTERED SIDE FRAME (OPTIONAL)**

The side frame is upholstered using 1/4" fire-resistant polyurethane foam over a 1/4" platen and covered with the selected upholstery material.

Catalog No.	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
One Seat Loun	ge Chair with Open Fr	ame. Oal	k Wood						One Seat
L5-102-S00 OAK	31-3/8" x 31" x 28-3/8"	45	\$1,766	\$1,746	\$2,065	\$2,164	\$2,551	\$2,696	with Open Frame
One Seat Loun	ge Chair with Open Fr	ame, Ma <sub>l</sub>	ple Wood	1					
L5-102-S00 MAP	31-3/8" x 31" x 28-3/8"	45	\$1,978	\$1,955	\$2,313	\$2,424	\$2,857	\$3,020	
Fabric Requirem	ents: 2 yards per chair, l	Non-directi	ional, 54"	wide.					
One Seat Loun	ge Chair with Wood In	sert, Oal	k Wood						One Seat
L5-103-S00 OAK	31-3/8" x 31" x 28-3/8"	47	\$2,037	\$1,977	\$2,296	\$2,393	\$2,887	\$3,054	with Wood Insert
One Seat Loun	ge Chair with Wood In	sert, Ma <sub>l</sub>	ple Wood	1					
L5-103-S00 MAP	31-3/8" x 31" x 28-3/8"	47	\$2,281	\$2,214	\$2,571	\$2,680	\$3,233	\$3,420	
Fabric Requirem	ents: 3 yards per chair, l	Non-directi	ional, 54"	wide.					
One Seat Loun	ge Chair with Upholst	ered Inse	ert, Oak l	<u>Vood</u>					One Seat
L5-104-S00 OAK	31-3/8" x 31" x 28-3/8"	47	\$2,172	\$2,085	\$2,420	\$2,521	\$3,045	\$3,221	with Upholstered Insert
One Seat Loun	ge Chair with Upholst	ered Inse	ert, Maple	e Wood					
L5-104-S00 MAP	31-3/8" x 31" x 28-3/8"	47	\$2,433	\$2,335	\$2,710	\$2,823	\$3,410	\$3,608	
Fabric Requirem	ents: 4 yards per chair, l	Von-directi	ional, 54"	wide.					

# Lounge Furniture

	Catalog No.	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Two Seat	Two Soot Lound	ro Chair with Open Fram	o Ook	Mood					
with Open Frame	L5-212-S00 OAK	ge Chair with Open Frame 31-3/8" x55-1/4" x28-3/8"	80	\$2,773	\$2,648	\$3,288	\$3,478	\$3,867	\$4,089
	L3-212-300 OAK	31-3/0 833-1/4 820-3/0	80	<b>Φ</b> Ζ,113	\$2,040	<b>Φ3,200</b>	φ3,470	\$3,00 <i>1</i>	\$4,007
	Two Seat Loung	ge Chair with Open Fram	e, <i>Map</i>	le Wood	1				
	L5-212-S00 MAP	31-3/8" x 55-1/4" x 28-3/8""	80	\$3,105	\$2,965	\$3,683	\$3,896	\$4,331	\$4,580
U	Fabric Requireme	ents: 4 yards per chair, Non-	directio	nal, 54"	wide.				
Two Seat	Two Seat Loung	ge Chair with Wood Inser	t, Oak	Wood					
with Wood Insert	L5-213-S00 OAK	31-3/8" x 55-1/4" x 28-3/8"	82	\$3,255	\$3,078	\$3,716	\$3,908	\$4,493	\$2,708
	Two Soat Loung	ge Chair with Wood Inser	+ Man	la Waar	,				
	L5-213-S00 MAP	31-3/8" x 55-1/4" x 28-3/8"	<u>t, мар</u> 82	\$3,646	<u>*</u> \$3,446	\$4,163	\$4,377	\$5,032	\$3,034
	L3-2 13-300 IVIAP	31-3/0 833-1/4 820-3/0	02	<b>\$3,040</b>	<b>\$3,440</b>	<b>Φ4,103</b>	φ4,3 <i>11</i>	\$3,032	\$3,U34
	Fabric Requireme	ents: 5 yards per chair, Non-	directio	nal, 54"	wide.				
Two Seat with Upholstered Insert	Two Seat Loung	ge Chair with Upholstere	d Inser	t, Oak l	<b>Vood</b>				
with opnoistered insert	L5-214-S00 OAK	31-3/8" x 55-1/4" x 28-3/8"	82	\$3,464	\$3,272	\$3,926	\$4,127	\$4,776	\$5,052
	Two Seat Lound	ge Chair with Upholstere	d Insei	t. Maple	e Wood				
	L5-214-S00 MAP	31-3/8" x 55-1/4" x 28-3/8"	82	\$3,880	\$3,665	\$4,397	\$4,622	\$5,349	\$5,658
	Fabric Requireme	ents: 6 yards per chair, Non-	directio	nal, 54"	wide.				
Three Seat	Three Seat Lou	nge Chair with Open Frai	me, Oa	k Wood	1				
with Open Frame	L5-312-S00 OAK	31-3/8" x 79-5/8" x 28-3/8"	115	\$3,685	\$3,497	\$4,454	\$4,742	\$5,105	\$5,398
	There - C 4 1	Ob-iith O F			1				
		nge Chair with Open Frai		-		<b>#4.000</b>	<b>AF 242</b>	φE 740	<b>*</b> / <b>0</b> 4/
	L5-312-S00 MAP	31-3/8" x 79-5/8" x 28-3/8"	115	\$4,127	\$3,917	\$4,989	\$5,312	\$5,718	\$6,046
	Fabric Requireme	ents: 6 yards per chair, Non-	directio	nal, 54"	wide.				
Three Seat	Three Seat Lou	nge Chair with Wood Ins	ert, Oa	k Wood	!				
with Wood Insert	L5-313-S00 OAK	31-3/8" x 79-5/8" x 28-3/8"	117	\$4,160	\$3,893	\$4,851	\$5,139	\$5,684	\$6,010
	Three Seat Lou	nge Chair with Wood Ins	ert. Ma	aple Wo	od				
	L5-313-S00 MAP	31-3/8" x 79-5/8" x 28-3/8"	117	\$4,658	\$4,360	\$5,434	\$5,756	\$6,365	\$6,731
		ents: 7 yards per chair, Non-		-		75,151	75/122	7-7	7-7
Three Seat	Three Seat Loui	nge Chair with Upholstei	red Ins	ert, Oak	( Wood				
with Upholstered Insert	L5-314-S00 OAK	31-3/8" x 79-5/8" x 28-3/8"	117	\$4,357	\$4,074	\$5,046	\$5,332	\$5,948	\$6,290
	Three Seat Loui	nge Chair with Upholstei	red Ins	ert. Mai	ple Wood				
	L5-314-S00 MAP	31-3/8" x 79-5/8" x 28-3/8"	117	\$4,880	\$4,563	\$5,651	\$5,972	\$6,663	\$7,045
	Fabric Requireme	ents: 8 yards per chair, Non-	directio	nal, 54"	wide.				
Plea	se specify Wood Finish (Ta	able 1) and Upholstery; if applicable	e (Table 5	). Details c	an be found on	pages GEN 4 a	and GEN 5.		

### **TABLETOPS**

Tabletops are 1-3/16" thick, 3-ply, 45# density particleboard core with a .050" thick, high-pressure laminate top sheet and a backing sheet not less than .020" thick for balanced construction. High-pressure laminate has a lo-glare finish resistant to scratches, fading, and staining. Edges are solid Northern-grown red oak. The edge band is applied before the top laminate sheet constituting an internal edge band.

### **APRON**

A 3-1/2"W x 1" thick solid Northern-grown red oak apron is fitted between the legs, and behind the extended tabletop edge band. Bottom edge and both ends of each apron receive a 1/2" radius. Aprons are secured to the tabletop by attaching hardwood cleats to the inside surface of the aprons and screwing through the cleats into the underside of the tabletop.

### **LEGS**

Legs are glued up, 2-1/4" solid Northern-grown red oak. All vertical edges of legs receive a 1/2" radius. Bottom edges of legs are radiused 1/8". Each leg has a 2" diameter, adjustable glide mounted in a recessed tee-nut. The glide is further recessed into the leg by means of counter-sunk boring which accepts the upper two-thirds of the glide. Legs attach to the aprons by means of formed 14-gauge steel corner brackets. Each leg is bolted to the corner bracket with two 5/16"-hex-head bolts per leg.

	Maple Price	Oak Price	Wt. (lbs.)	HxWxD	Description	Maple Catalog No.	Oak Catalog No.
Roun	\$1,643	\$1,467	66	16-3/16" x 36" Diameter	Round Table	LX-626-S00 MAP	LX-626-S00 OAK
Squar	\$1,366	\$1,220	51	16-3/16" x 30" x 30"	Square Table	LX-625-S00 MAP	LX-625-S00 OAK
Rectangula	\$1,444	\$1,291	46	16-3/8" x 48" x 24"	Rectangular Table	LX-627-S00 MAP	LX-627-S00 OAK

D-S00 OAK 1-S00 OAK 2-S00 OAK	LX-620-S00 MAP LX-621-S00 MAP	Cylinder Table	18" x 18" Diameter	20	A4 404	
	LX-621-S00 MAP			20	\$1,121	\$1,256
2-S00 OAK		Cylinder Table	18" x 24" Diameter	31	\$1,385	\$1,552
	LX-622-S00 MAP	Cylinder Table	18" x 30" Diameter	42	\$1,581	\$1,771
	LX-610-S00 MAP	Cube Table	18" x 18" x 18"	50	\$1,442	\$1,615
	LX-611-S00 MAP LX-612-S00 MAP	Cube Table Cube Table	18" x 24" x 24" 18" x 30" x 30"	100	\$1,611 \$1,857	\$1,804 \$2,079
	0-S00 OAK 1-S00 OAK 2-S00 OAK	1-S00 OAK LX-611-S00 MAP	1-S00 OAK LX-611-S00 MAP Cube Table 2-S00 OAK LX-612-S00 MAP Cube Table	1-S00 OAK LX-611-S00 MAP Cube Table 18" x 24" x 24" 2-S00 OAK LX-612-S00 MAP Cube Table 18" x 30" x 30"	1-S00 OAK         LX-611-S00 MAP         Cube Table         18" x 24" x 24"         73           2-S00 OAK         LX-612-S00 MAP         Cube Table         18" x 30" x 30"         100	1-S00 OAK LX-611-S00 MAP Cube Table 18" x 24" x 24" x 24" 73 \$1,611

### **FRAME**

Frame members are constructed from premium hardwood plywood and rails, posts, and other main frame parts are of lumber not less than 5/4" thick kiln dried to a moisture content of 6-8%. All lumber is of sound stock, without knots, shakes or other defects which affect appearance and/or performance. All main frame joints are puzzle-joint construction with overlapped and notched hardwood plywood components. In addition, the frame is glued, stapled, and wood screws are used where necessary for further structural integrity.

### **UPHOLSTERY CONSTRUCTION**

The seat platform is constructed with sinuous 7.5-gauge steel wire springs firmly attached to the front and back rails. Springs are installed on 5" c/c. A spring unit surface is attained by attaching two (2) 16 gauge insulated steel tie wires (#F16SW) to each spring with Hartco clips running the entire length of the seat. A Flex-O-Lator unit is laid over the springs. The surface is covered with a layer of woven polypropylene matting and five (5) inches of Ultracel premium polyurethane foam.

The back receives Universal sinuous 7.5-gauge steel wire springs firmly attached to the top and bottom rails. Springs are installed on 5" c/c. A spring unit surface is attained by attaching two (2) 16-gauge insulated steel tie wires (#F16SW) to each spring with Hartco clips running the entire length of the back. A 2-1/2" layer of premium ultracel polyurethane foam with a compression of 20 pounds is covered with a layer of polyester fiber. The surface is covered with a layer of woven polypropylene matting and 2-1/2" Ultracel premium polyurethane foam.

Arm sides are covered with furniture grade paperboard. The tops of the arms receive a contoured H.D. bonded foam insert for softness and a final layer of 1/2" foam is applied over the top and sides of the arms.

### **TABLET ARM**

Standard tablet arm is bow front laminate top with black T-mold. WilsonArt laminates available for the laminate surface. Tablet is mounted to the right arm in the seated position. Standard bow front design is 22"W x 13"D. Tablet arm available in optional left arm seated position.

Note: WilsonArt Black 1595-60 laminate is the standard on tablet arm. Please designate the WilsonArt laminate to be provided.

### CASTERS (OPTIONAL)

Front casters are locking hard wheel with a load rating of 110 lbs. Mounting height is 2-1/2", wheel diameter is 55mm and cup diameter is 45mm.

### FINAL ASSEMBLY

The underside bottom of the chair is covered with a sheet of cambric for dust protection. The base frame of the chair receives four extruded plastic legs. Legs measure 2-1/2"H and are 2" diameter. Chairs are packed using padding and shrink wrap to minimize movement during shipping.

### WOOD FINISH

Exposed wood is of Beech construction and machine sanded and stained. Wood is then sealed and finished with a conversion varnish topcoat.

### C.O.M. FABRIC

For C.O.M. fabric on multiple rolls, add an additional yard of fabric per roll to the yardage requirements. Multiple rolls have shorter pieces of fabric and do not allow nesting or stacking to achieve the best yield which may result in yardage shortages. Request for additional fabric from the client may delay the order. Yardage should be added to the roll and not provided separately.

Brodart upholstery materials meet requirements of the following fire codes: Calif. Technical Bulletin #117 (Sec. E part 1); CS-191-53 class 1.

Fabrics which meet Calif. Technical Bulletin #133 are available.

# Lounge Furniture

	Catalog No.	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price			
Lounge Chair	<u>Upholstered Loun</u>	ge Chair, No Wood A	rm Cap	s, No Cas	sters							
	ENGLNG1SS	32-1/2" x 31-1/2" x 30"	65	\$2,756	\$2,676	\$2,890	\$3,317	\$3,907	\$4,120			
	<u>Upholstered Lounge Chair with Wood Arm Caps, No Casters</u>											
	ENGLNG1SWAS	32-1/2" x 31-1/2" x 30"	65	\$3,122	\$3,031	\$3,273	\$3,758	\$4,425	\$4,668			
	<u>Upholstered Lounge Chair with Casters, No Wood Arm Caps</u>											
	ENGLNG1SFCS	32-1/2" x 31-1/2" x 30"	65	\$2,937	\$2,851	\$3,078	\$3,536	\$4,162	\$4,391			
	Upholstered Lounge Chair with Wood Arm Caps and Casters											
	ENGLNG1SWAFCS	32-1/2" x 31-1/2" x 30"	65	\$3,303	\$3,206	\$3,463	\$3,976	\$4,681	\$4,938			
	Note: All Lounge Chairs h	nave a 18-1/2 Seat Height and	la 24-1/2	'' Arm Height	t.							
	Fabric Requirements	s: 4-1/2 yards per chair	, Non-dir	rectional, s	54" wide.							

Lounge Chair	Upholstered Loung	ge Chair with Tablet,	No W	ood Arm Ca	ps, No Ca	sters			·			
with Tablet Arm	ENGLNG1SRTS	32-1/2" x 31-1/2" x 30"	75	\$3,128	\$3,037	\$3,280	\$3,766	\$4,434	\$4,677			
	<u>Upholstered Loung</u>	ge Chair with Tablet,	Wood	Arm Caps,	No Caste	<u>rs</u>						
	ENGLNG1SRTWAS	32-1/2" x 31-1/2" x 30"	75	\$3,494	\$3,393	\$3,664	\$4,205	\$4,952	\$5,223			
	Upholstered Lounge Chair with Tablet, Casters, No Wood Arm Caps											
	ENGLNG1SRTFCS	32-1/2" x 31-1/2" x 30"	75	\$3,309	\$3,212	\$3,469	\$3,983	\$4,690	\$4,947			
	<u>Upholstered Loung</u>	Upholstered Lounge Chair with Tablet, Wood Arm Caps and Casters										
	ENGLNG1SRTWAFCS	32-1/2" x 31-1/2" x 30"	75	\$3,675	\$3,568	\$3,853	\$4,425	\$5,209	\$5,494			

Note: All Lounge Chairs have a 18-1/2 Seat Height and a 24-1/2" Arm Height.

Fabric Requirements: 4-1/2 yards per chair, Non-directional, 54" wide.

Loveseat	<u>Upholstered Lo</u> u	veseat, No Wood Arm C	aps, N	o Casters							
	ENGLNG2SS	32-1/2" x 53-1/2" x 30"	90	\$3,951	\$3,837	\$4,144	\$4,758	\$5,601	\$5,907		
	<u>Upholstered Lo</u> u	Upholstered Loveseat with Wood Arm Caps and No Casters									
	ENGLNG2SWAS	32-1/2" x 53-1/2" x 30"	90	\$4,317	\$4,191	\$4,528	\$5,198	\$6,120	\$6,456		
	Note: All Lounge Chair	s have a 18-1/2 Seat Height and	a 24-1/2	2'' Arm Height.							

Fabric Requirements: 8 yards per chair, Non-directional, 54" wide.

Please specify Wood Finish (Table 1), High-Pressure Laminate; if applicable (Table 2) and Upholstery (Table 5).

Details can be found on pages GEN 4 and GEN 5.

### INNER CORE

Inner core is constructed using High-Density compressed foam.

### **BASE**

Base is constructed using 1/2" thick Birch Support Board.

### **GLIDES**

Seats are equipped with 1/4" thick x 7/8" diameter nylon glides.


### UPHOLSTERY MATERIALS AND FABRICS

Brodart fabric selections and polyurethane foam are fire rated.

Fabrics which meet Calif. Technical Bulletin #133 are available.

WxD (lbs.)	Price	Grade 1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
v 10" v 16" 10	¢EOE	\$5.42	\$702	\$000	¢077	\$1.068
	x 18" x 16" 10	(17)				

Fabric Requirements: 3 yards per ottoman, Non-directional, 54" wide.



**Rectangle Ottoman** 

<u>Crescent Ottoman</u>
BR0F003S 17-1/4" x 18" x 18" 10 \$585 \$542 \$792 \$882 \$977 \$1,068

Fabric Requirements: 3 yards per ottoman, Non-directional, 54" wide.



 Round Ottoman

 BROF005S
 17-1/4" x 18" x 18"
 10
 \$585
 \$542
 \$792
 \$882
 \$977
 \$1,068

Fabric Requirements: 3 yards per ottoman, Non-directional, 54" wide.



Please specify Upholstery (Table 5). Details can be found on page GEN 5.

	Catalog No.	Overall H x W x D	Wt. (lbs.)	COM Price	Grade 1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price
Pentagon Ottoman	Pentagon Ottoman BR0F007S	17-1/4" x 26" x 24"	15	\$877	\$817	\$1,117	\$1,214	\$1,364	\$1,531
	Fabric Requirements: 4	4 yards per ottoman	, Non-dire	ctional, 54	1" wide.				
Bench	<u>Bench</u>								
	BR0F009S	17-1/4" x 48" x 18"	26	\$1,537	\$1,447	\$1,777	\$1,904	\$2,084	\$2,281
Quarter Round Ottoman	Fabric Requirements:  Quarter Round Otto. BR0F011S		15	\$1,249	\$1,189	\$1,489	\$1,586	\$1,736	\$1,903
	Fabric Requirements:	3 yards per ottomar	n, Non-dire	ectional, 54	4" wide.				
Half Round Ottoman	Half Round Ottomai	1							
	BR0F013S	17-1/4" x 54" x 18"	25	\$2,272	\$2,137	\$2,737	\$3,012	\$3,232	\$3,377
	Fabric Requirements:	6 yards per ottomar	n, Non-dire	ectional, 54	4" wide				
Arc Ottoman	Arc Ottoman								
	BROF015S	17-1/4" x 38" x 18"	15	\$1,505	\$1,410	\$1,740	\$1,867	\$2,047	\$2,244
	Fabric Requirements:	4 yards per ottomar	n, Non-dire	ectional, 54	4" wide.				

Please specify Upholstery (Table 5). Details can be found on page GEN 5.

	Grade 5 Price	Grade 4 Price	Grade 3 Price	Grade 2 Price	Grade 1 Price	COM Price	Wt. (lbs.)	Overall H x W x D	Catalog No.
Daisy Set									
(24" Center Round	\$5,499	\$5,249	\$4,949	\$4,549	\$3,599	\$3,949	60	17-1/4" x 60" x 60"	BR0F038S
with 5 Crescents)									

Fabric Requirements: 18 yards per Ccomplete Daisy Set, Non-directional, 54" wide.



**- CIR 4 -** F11-1-19G-LGE

# **Cabinets**

# **General Specifications**

### **TOPS**

When specified, optional tops will be 1-3/16" thick, 3-ply 45# particleboard grade M2 or better with a top surface of .050" thick, high-pressure laminate and a backing sheet not less than .020" thick for balanced construction. High-pressure laminate will be lo-glare finish resistant to scratches, fading, and staining that meets or exceeds NEMA standards. Top will receive bands on one long and two short edges. Edges will be solid Northern-grown Red Oak or Maple. The edge band will be a flush design 5/8" thick x 1-3/16", of specified profile design, externally banded with a 1/4" radius at corners.

### **SUBTOP**

The cabinet will receive two (2) 3/4" x 6" 7-ply, furniture grade veneer-core hardwood plywood rails in the top (front and rear) of the cabinet. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet. The sub top rails will anchor the top to the cabinet.

### **END PANEL**

End panels will be 3/4" thick, 7-ply, furniture grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges are externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or Maple veneer edge band. When specified, the end panel receives 32mm boring for shelf adjustment. The end panels and sub top will be joined with dowel pin construction and pocket screws. Each panel will receive two (2) 3/4" nylon nail glides.

### **BASE**

The cabinet will receive a 3/4" Thick x 4" high 7-ply, furniture-grade veneer-core hardwood plywood base rail in the front and rear of the cabinet. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet. Exposed edges will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or maple veneer edge band. Base rails will be positioned inside the end panels of the cabinet.

## **BACK PANEL**

The back panel will be 3/4" thick, 7-ply furniture-grade plywood with plain sliced Northern-grown Red Oak or Maple veneers. The top and end panels will receive a dado which captures the back panel on three sides. The back will receive six (6) 5/8"-#8 Philips pan head screws fastened to the hanger rails and end panels. The back panel will rest on the base rail.

### **DOOR**

When specified, doors will be 3/4" thick, 7-ply furniture-grade veneer-core hardwood plywood with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or maple veneer edge band. Each door receives two (2) European hinges and one four inch flat black wire pull. A solid oak or maple door stop, 3/4" thick x 2-1/8"H is placed at the top and bottom of the wardrobe and runs the entire width of the cabinet. Doors will be 3/4" half overlay in the cabinet.

#### SHFI VES

When specified, shelves will be 3/4" thick, 7-ply, furniture-grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges are externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or maple veneer edge band.

### **SPACER RAIL**

When specified, cabinets with drawers will receive spacer rails placed between drawers for structural support and as a drawer stop. Rails are 1" thick furniture-grade veneer-core hardwood plywood. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet.

## **HANGER RAIL**

The cabinet will receive a 3/4" x 4" 7-ply, furniture-grade veneer-core hardwood plywood rail in the top, bottom and middle rear of the cabinet. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet. Hanger rails will be positioned inside the end panels of the desk module.

### **DRAWER**

When specified, drawers will be constructed of solid hardwood with 1/4" thick wood bottom panel. Drawers will have 3-ply particleboard fronts with select Northern-grown Red Oak or Maple face veneer. Drawers will receive full extension slides with 100# load capacity and one four inch flat black wire pull.

	Maple	0ak	Wt.			Maple	Oak
	Price	Price	(lbs.)	HxWxD	Description	Catalog No.	Catalog No.
1 Door Cabine					Adjustable Shelf	Door with Lock, 1	32"H Unit with 1
	\$1,225	\$1,124	116	32" x 18" x 24"	Cabinet with Right Opening Door	CBM241832DRS	CB0241832DRS
	\$1,225	\$1,124	116	32" x 18" x 24"	Cabinet with Left Opening Door	CBM241832DLS	CB0241832DLS

32"H Unit with 2	2 Doors with Lock,	<u> 1 Adjustable Shelf</u>				
CB0242432DS	CBM242432DS	Cabinet with 2 Doors	32" x 24" x 24"	134	\$1,368	\$1,491
CB0243032DS	CBM243032DS	Cabinet with 2 Doors	32" x 30" x 24"	134	\$1,445	\$1,576
CB0243632DS	CBM243632DS	Cabinet with 2 Doors	32" x 36" x 24"	134	\$1,549	\$1,688
CB0244232DS	CBM244232DS	Cabinet with 2 Doors	32" x 42" x 24"	134	\$1,617	\$1,762



32"H Unit with 1 Pull Out Drawer and 1 Door with Lock, 1 Adjustable Shelf								
CB0241832PDDRS CBM241832PDDRS	Cabinet with Pull Out Drawer,	32" x 18" x 24"	136	\$1,455	\$1,586			
CBO241832PDDLS CBM241832PDDLS	Right Opening Door Cabinet with Pull Out Drawer,	32" x 18" x 24"	136	\$1,455	\$1.586			
CD0241032FDDL3 CDIVIZ41032FDDL3	Left Opening Door	JZ X 10 XZ4	130	φ1, <del>4</del> 33	φ1,300			



32"H Unit with 2	32"H Unit with 2 Pull Out Drawers and 2 Doors									
CB0242432PDDS	CBM242432PDDS	Cabinet with 2 Pull Out Drawers, 2 Doors	32" x 24" x 24"	134	\$1,999	\$2,179				
CB0243032PDDS	CBM243032PDDS	Cabinet with 2 Pull Out Drawers, 2 Doors	32" x 30" x 24"	134	\$2,180	\$2,376				
CB0243632PDDS	CBM243632PDDS	Cabinet with 2 Pull Out Drawers, 2 Doors	32" x 36" x 24"	134	\$2,313	\$2,521				



Work Surface for Base Cabinets with Subtop			Work Surface for
Work Surface per Square Foot	\$58	\$64	Base Cabinets with Subtop
Mitered Corner per Corner	\$409	\$446	

 $\textbf{Note:} \ \ \textbf{Price listed is for any standard Brodart 5/8" flush edge band profile.} \ \ \textbf{Please specify on order.}$ 

Cabinets Wall Cabinets

# **General Specifications**

# **TOPS**

Standard top will be 3/4" thick, 7-ply furniture-grade veneer-core hardwood plywood with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or maple veneer edge band.

### **END PANEL**

End panel will be 3/4" thick, 7-ply, furniture-grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or Maple veneer edge band. The end panel will receive 32mm boring for shelf adjustment. The end panels, top and base will be joined with dowel pin construction and pocket screws.

### **BASE**

Standard base will be 3/4" thick, 7-ply furniture-grade veneer-core hardwood plywood with plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or maple veneer edge band.

### **BACK PANEL**

The back panel will be 1/4" thick, 3-ply furniture-grade plywood with plain sliced Northern-grown Red Oak or maple veneers. The top, base and end panels will receive a dado which captures the back panel on four sides. The back will be glued and pin tacked to the hanger rails.

### HANGER RAIL

The cabinet will receive 3/4" x 4" 7-ply, furniture-grade veneer-core hardwood plywood rail in the top, middle and bottom rear of the cabinet. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet. Hanger rails will be positioned inside the end panels of the desk module.

### DOOR

When specified, doors will be 3/4" thick, 7-ply furniture-grade veneer-core hardwood plywood with plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or maple veneer edge band. Each door will receive two (2) European hinges and one four inch flat black wire pull. A solid oak or maple door stop, 3/4" thick x 2-1/8"H will be placed at the top and bottom of the wardrobe and run the entire width of the cabinet. Doors will be 3/4" half overlay in the cabinet.

### **SHELVES**

Shelves will be 3/4" thick, 7-ply, furniture-grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or maple veneer edge band.

	Maple Price	Oak Price	Wt. (lbs.)	HxWxD	Description	Maple Catalog No.	Oak Catalog No.
1 Door Wall Cabin					Adjustable Shelf	Door with Lock, 1	24"H Unit with 1
	\$1,343	\$1,232	48	24" x 18" x 12-3/4"	Cabinet with Right Opening Door	CWM121824DRS	CW0121824DRS
-	\$1,343	\$1,232	48		Cabinet with Left Opening Door	CWM121824DLS	CW0121824DLS
					<u>Adjustable Shelf</u>	Door with Lock, 1	30"H Unit with 1
	\$1,413	\$1,296	48	30" x 18" x 12-3/4"	Cabinet with Right Opening Door	CWM121830DRS	CW0121830DRS
	\$1,413	\$1,296	48	30" x 18" x 12-3/4"	Cabinet with Left Opening Door	CWM121830DLS	CW0121830DLS
2 Door Wall Cabin					Adjustable Shelf	Doors with Lock, 1	24"H Unit with 2
	<b>\$4.000</b>	44.074	F0	0411 0411 40 0 /411	•		
	\$1,389	\$1,274 \$1,537	59	24" x 24" x 12-3/4"	Cabinet with 2 Doors	CWM122424DS	CW0122424DS
	\$1,665 \$1,822	\$1,527 \$1,671	70 81	24" x 30" x 12-3/4" 24" x 36" x 12-3/4"	Cabinet with 2 Doors Cabinet with 2 Doors	CWM123024DS CWM123624DS	CW0123024DS CW0123624DS
	\$1,022	\$1,071	01	24 830 812-3/4	Cabinet with 2 Doors	CWWIIZ30Z4D3	CWO123024D3
PE .					Adjustable Shelf	Doors with Lock, 1	30"H Unit with 2
	\$1,462	\$1,341	59	30" x 24" x 12-3/4"	Cabinet with 2 Doors	CWM122430DS	CW0122430DS
	\$1,739	\$1,595	70	30" x 30" x 12-3/4"	Cabinet with 2 Doors	CWM123030DS	CW0123030DS
	\$1,872	\$1,717	81	30" x 36" x 12-3/4"	Cabinet with 2 Doors	CWM123630DS	CW0123630DS
Open Wall Cabin					oor, 1 Adjustable Shelf	Cabinet without Do	24"H Open Wall
	\$954	\$875	39	24" x 18" x 12"	Cabinet without Doors	CWM121824S	CW0121824S
	\$993	\$911	49	24" x 24" x 12"	Cabinet without Doors	CWM122424S	CW0122424S
	\$1,090	\$999	59	24" x 30" x 12"	Cabinet without Doors	CWM123024S	CW0123024S
	\$1,135	\$1,042	69	24" x 36" x 12"	Cabinet without Doors	CWM123624S	CW0123624S
					oor, 1 Adjustable Shelf	Cabinet without Do	30"H Open Wall
SCHOOL ST.	\$1,022	\$938	44	30" x 18" x 12"	Cabinet without Doors	CWM121830S	CW0121830S
	\$1,063	\$975	54	30" x 24" x 12"	Cabinet without Doors	CWM122430S	CW0122430S
	\$1,146	\$1,052	64	30" x 30" x 12"	Cabinet without Doors	CWM123030S	CW0123030S
	\$1,140	Ψ1/00 <u>=</u>	01		oubmot mimout boord		

# **General Specifications**

### **TOPS**

Standard top will be 3/4" thick, 7-ply furniture-grade veneer-core hardwood plywood with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or Maple veneer edge band. Top will be positioned over and flush with the outside edges of the end panels.

### **END PANEL**

End panel will be 3/4" thick, 7-ply, furniture-grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or maple veneer edge band. The end panels and top will be joined with 12-gauge angled metal brackets 3/4" x 3/4" screwed to the inside surface of the panel and top. Each panel will receive two (2) 3/4" nylon nail glides.

### INTERMEDIATE PANEL

When specified, intermediate panel will be 3/4" thick, 7-ply, furniture-grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edges will be externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or Maple veneer edge band.

#### **BASE**

The cabinet base will receive a 3/4" x 4" 7-ply, furniture-grade veneer-core hardwood plywood rail in the front and rear of the cabinet. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet. Exposed edges will be externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or maple veneer edge band. Base rails will be positioned inside the end panels of the desk module.

### **BACK PANEL**

The back panel will be 1/4" thick, 3-ply furniture-grade plywood with plain sliced Northern-grown Red Oak or Maple veneers. The top and end panels will receive a dado which captures the back panel on three sides. The back will receive ten (10) 5/8"-#8 Philips pan head screws fastened to the hanger rails and end panels. The back panel will rest on the base rail.

### **SHELF**

Shelf will be 3/4" thick, 7-ply, furniture-grade veneer-core hardwood plywood, with plain-sliced slip matched Northern-grown Red Oak or maple veneer on both sides. Exposed edge on the front side of the shelf will be externally banded with a 3/4" x 1.5mm solid, Northern-grown Red Oak or Maple veneer edge band. The shelf will be secured with 12-gauge angled metal brackets 3/4" x 3/4" screwed to the inside surface of the panel and top.

## **CLOTHES BAR**

When specified, a solid 1-1/4" diameter Birch dowel rod clothes bar will be placed below the fixed shelf and spans the full width of the wardrobe. The bar will be secured by two (2) 2-1/2" x 2-7/32" round pole sockets. The sockets will be fastened to the end panel with wood screws.

### HANGER RAIL

The cabinet will receive a 3/4" x 4" 7-ply, furniture-grade veneer-core hardwood plywood rail in the top, bottom and middle rear of the cabinet. The rails will be doweled and pocket screwed to the end panels to complete construction of the cabinet. Hanger rails will be positioned inside the end panels of the desk module.

#### DOORS

Doors will be 3/4" thick, 7-ply furniture-grade veneer-core hardwood plywood with plain-sliced slip matched Northern-grown Red Oak or Maple veneer on both sides. Exposed edges opposite the hinges will be externally banded with a 3/4" x 1.5mm thick solid, Northern-grown Red Oak or Maple veneer edge band. Each door will receive three (3) black five knuckle institutional hinges and one four inch flat black wire pull. A solid oak or maple door stop, 3/4" thick x 2-1/8"H will be placed at the top and bottom of the wardrobe and runs the entire width of the cabinet. Doors will be inset in the cabinet.

Oak	Maple			Wt.	0ak	Maple	
Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price	
82"H Unit with	4 Adjustable Shelve	es and 1 Fixed Shelf					Storage Cabine
CS0242482DS	CSM242482DS	Cabinet with 2 Doors & Locks	82" x 24" x 24"	234	\$2,626	\$2,863	
CS0243082DS	CSM243082DS	Cabinet with 2 Doors & Locks	82" x 30" x 24"	266	\$3,046	\$3,319	
CS0243682DS	CSM243682DS	Cabinet with 2 Doors & Locks	82" x 36" x 24"	298	\$3,206	\$3,494	
72"H Unit with	4 Adjustable Shelve	es and 1 Fixed Shelf					it.
CS0242472DS	CSM242472DS	Cabinet with 2 Doors & Locks	72" x 24" x 24"	226	\$2,522	\$2,748	
S0243072DS	CSM243072DS	Cabinet with 2 Doors & Locks	72" x 30" x 24"	258	\$2,924	\$3,187	
CS0243672DS	CSM243672DS	Cabinet with 2 Doors & Locks	72" x 36" x 24"	290	\$3,078	\$3,355	

82"H Unit with 2	82"H Unit with 2 Adjustable Shelves and Coat Rod									
CS0242482SCDS	CSM242482SCDS	Cabinet with 2 Doors & Locks	82" x 24" x 24"	201	\$2,465	\$2,687				
701111111111111111111111111111111111111	Adicatable Chalces	and Coat Dad								
/2"H Unit With 2	Adjustable Shelves	s and Coat Rod								
CS0242472SCDS	CSM242472SCDS	Cabinet with 2 Doors & Locks	72" x 24" x 24"	193	\$2,366	\$2,579				



<u>"H Unit with Partitions, 3 Adjusta</u>	able Shelves, 1 Fixed She	If and Coat Rod				Storage Cabinet with Partiti
D242482SPCDS CSM242482SPCDS	Cabinet with 2 Doors & Locks	82" x 24" x 24"	241	\$2,854	\$3,111	
0243082SPCDS CSM243082SPCDS	Cabinet with 2 Doors & Locks	82" x 30" x 24"	273	\$3,403	\$3,710	
0243682SPCDS	Cabinet with 2 Doors & Locks	82" x 36" x 24"	306	\$3,524	\$3,841	
Williait with Dantitians 2 Adives	ahla Shalvas 1 Fivad Sha	If and Coat Pod				111
<u>"H Unit with Partitions, 3 Adjusta</u>	able Sherves, TTIXed She.	n and coat Rod				
D242472SPCDS CSM242472SPCDS	·	72" x 24" x 24"	233	\$2,740	\$2,987	
	Cabinet with 2 Doors & Locks			\$2,740 \$3,267	\$2,987 \$3,561	

**-CAB 8 -** F11-1-19G-CAB

# Display Furniture

# Display Furniture

	0ak	Maple			Wt.	0ak	Maple
	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
A-Frame Shelving	60-048-S00 OAK	60-048-S00 MAP	Single-Faced Starter	42" x 37-1/8" x 16-3/4"	107	\$1,753	\$1,911
	60-049-S00 OAK	60-049-S00 MAP	Single-Faced Adder	42" x 36-3/16" x 16-3/4"	107	\$1,528	\$1,665
	60-050-S00 OAK	60-050-S00 MAP	Single-Faced Starter	60-1/2" x 37-1/8" x 16-3/4"	148	\$2,119	\$2,310
	60-051-S00 OAK	60-051-S00 MAP	Single-Faced Adder	60-1/2" x 36-3/16" x 16-3/4"	148	\$1,801	\$1,963
	60-022-S00 OAK	60-022-S00 MAP	Double-Faced Starter	42" x 37-1/8" x 33-5/8"	214	¢2 02E	¢2 100
	60-023-S00 OAK	60-023-S00 MAP	Double-Faced Starter  Double-Faced Adder	42" x 36-3/16" x 33-5/8"	184	\$2,925 \$2,648	\$3,188 \$2,886
	11					, ,	, ,
	60-024-S00 OAK	60-024-S00 MAP	Double-Faced Starter	60-1/2" x 37-1/8" x 33-5/8"	296	\$3,733	\$4,069
	60-025-S00 OAK	60-025-S00 MAP	Double-Faced Adder	60-1/2" x 36-3/16" x 33-5/8"	248	\$3,001	\$3,270
			3-ply veneered particleb edge banding. Shelves a	apered for style and made of 1" thick, oard with solid oak or maple hardwoo are 3/4" thick, 10"D solid oak or map es adjust on clip-and-strip hardware a e rear.	d le		
Slatwall End Panels	60-245-S00 OAK	60-245-S00 MAP	Slatwall End Panel For Double-Faced A-Fran	42" x 41-7/8" x 33-1/2" me Display	60	\$1,023	\$1,115
	60-246-S00 OAK	60-246-S00 MAP	Slatwall End Panel	60-1/2" x 60-3/8" x 33-1/2"	65	¢1 117	¢1 210
	60-246-300 UAK	60-246-300 IVIAP	For Double-Faced A-Frar		00	\$1,117	\$1,218
			Panel is construced of 3,	/4" thick slatwall with 1/4" thick soli	d wood trim	1.	
Mobile Bookstore Displayer	60-056-S00 OAK	60-056-S00 MAP	Mobile Bookstore Displayer with Storage U	54" x 39-3/16" x 55-5/8"	289	\$5,669	\$6,180
with Storage			Displayer with Storage o	unt			
			The flat base area is 11" The ends of the display a	ving is constructed using quality wood 'D and can be used as an additional di Ire provided with slatwall panels. The u /4"H x 10"D, two fixed top shelves an	splay area. nit includes	S	
Double-Faced A-Frame Stawall	60-738-S00 OAK	60-738-S00 MAP	Double-Faced Frame Slatwall with Casters	54" x 39-3/16" x 55-5/8"	289	\$3,434	\$3,744
	60-739-S00 OAK	60-739-S00 MAP	Double-Faced Frame	54" x 39-3/16" x 55-5/8"	289	\$3,106	\$3,386
			Slatwall without Casters				•
			or maple hardwood edge	ure-grade veneered 3-ply wood with so e banding. Slatwall panels are 47-3/4 Hblack toe kick is on two long sides.		/2"H	
	Please	snecify Wood Finish (Table	e 1). Details can be found o	nn nage GFN 4			

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
60-452-S00 OAK 60-453-S00 OAK	60-452-S00 MAP 60-453-S00 MAP	Classic Display Case Classic Display Case	82" x 48" x 20" 72" x 48" x 20"	400 380	\$10,373 \$10,027	\$11,307 \$10,929	Classic Display Case
		Freestanding case has adjustable t doors, with lock. Base of unit featur are tenoned together to ensure stal	res a lockable storage com	partment 17'	•	•	
60-456-S00 OAK	60-456-S00 MAP	Optional Lighting		5	\$789	\$860	
		Wood construction finished to mate and an on-off switch mounted into		cent lamp, pla	istic diffuser p	anel,	
60-168-S00 OAK	60-168-S00 MAP	Leg Base Exhibit Case with 3 adjustable shelves.	82" x 48" x 20"	320	\$8,193	\$8,930	Leg Base Exhibit Case and Cube Display Case
		This case has lockable sliding door glass; doors include a lock. Shelve					
60-169-S00 OAK	60-169-S00 MAP	Cube Display Case	82" x 24" x 24"	185	\$5,654	\$6,162	
		Solid frames are tenoned together laminated glass; shelves are 1/4" The shelves are adjustable on a pin Both are constructed of solid wood at the bottom and includes an adju	thick tempered glass. The one can determine the care of the care o	door incorpora flexibility.	ates a lock for	1111	
60-166-S00 OAK	60-166-S00 MAP	Horizontal Exhibit Case, 8''H Display	37" x 72" x 36"	200	\$5,951	\$6,486	Horizontal Exhibit Case
60-167-S00 OAK	60-167-S00 MAP	Horizontal Exhibit Case, 14"H Display	43" x 72" x 36"	220	\$6,363	\$6,936	ZATION GUSE
		This case is constructed of solid wo bottom and includes an adjustable with three stationary panels constru	leveling glide. The case off	fers lockable s	sliding doors o	on one side alon	
60-454-S00 OAK	60-454-S00 MAP	Horizontal Classic Exhibit Case, 8"H Display	37" x 72" x 36"	200	\$5,817	\$6,340	
		Construction is of solid wood. Fram radiused 1/2". Legs are 2-1/4" so adjustable leveling glides. Top of ca felt covered. Lockable sliding glass	quare with a 1/4" radius o ase and four sides are temp	n all four corn pered glass, w	ers, and are s rith the display	upplied with	
60-333-S00 OAK	60-333-S00 MAP	Horizontal Flip Top Exhibit Case,	37" x 72" x 36"	210	\$6,887	\$7,507	Horizontal Exhibit Case
60-334-S00 OAK	60-334-S00 MAP	8"H Display Horizontal Flip Top Exhibit Case, 14"H Display	43" x 72" x 36"	240	\$7,321	\$7,981	LATION Gase
		Unit is constructed of solid wood le 1" thick x 4"W pieces of solid woo				cted of framed-t	up I

\$240

# **General Specifications**

### **BOOK SHELF UNIT**

Shelves are constructed of 18-gauge metal. Book shelves are flat and 10"D. All units come with an acrylic signage display area at the top of the unit. The viewable display area is 3-1/4"H x 48"W.

### MEDIA SHELF UNIT

Shelves are constructed of 18-gauge metal. Media shelves are set at an angle for easy viewing and are 6-1/2"D. Nickel plated wire metal dividers are available for the media shelves and can be inserted in 1-3/4" increments. Media shelves also come with a 1/8" thick acrylic lip that runs the length of the shelf and protrudes above the base of the shelf 2-1/4".

### **END PANELS**

End panels are available in both solid and slatwall configurations. Panels are constructed of 3/4" Veneered Particleboard and banded with 1.6mm edge banding. The panels are mounted to the unit via two 14-gauge metal brackets.

### DOUBLE-FACED CAPACITY:

CD:	1200	Elementary Books: 320
DVD:	960	Picture Books: 450
CD w/Security:	1,000	Adult Books: 270
DVD w/Security:	800	

Note: Units 25% longer than traditional display units.

	0ak	Maple			Wt.	0ak	Maple
	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
Book Unit with 8 Book Shelves,	Double-Faced A	A-Frame Book	Unit with Eight (8) 9" Book S	Shelves, Anti-Sway Ba	r and Sigi	n Holder	
Anit-Sway Bar and Sign Holder	GMDDFBS67S	N/A	Double-Faced Starter	67" x 50" x 30"	270	\$3,987	N/A
	GMDDFBA67S	N/A	Double-Faced Adder	67" x 48" x 30"	270	\$3,172	N/A


CD/DVD Unit with 10 DVD/CD Shelves, 90 Wire Dividers, Anit-SwayBar and Sign Holder



# Double-Faced A-Frame Unit with Ten (10) DVD/CD Shelves, 90 Wire Dividers and Anti-Sway Bar and Sign Holder

GMDDFMS67S N/A **Double-Faced Starter** 67" x 50" x 30" 270 \$4,583 N/A GMDDFMA67S **Double-Faced Adder** 67" x 48" x 30" 270 \$3,767 N/A

**End Panels and Back Panels** 



End Panels and Back Panels

GMD0DFPP67S **GMDMDFPP67S** Double-Faced Solid End Panel 270 \$1,156 \$1,260 GMD0DFSP67S GMDMDFSP67S Double-Faced Slatwall End Panel 270 \$1,770 \$1,929 GMD0BP67S GMDMBP67S End Panel for 67"H Unit 270 \$220

Please specify Wood Finish; if applicable (Table 1) and Metal Color (Table 3). Details can be found on pages GEN 4 and GEN 5.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price		
64-100-S00 OAK	60-100-S00 MAP	Label Holder for Shelving Top	5-7/8" x 9" x 2-7/8"	1	\$93	\$101		End of Range
64-101-S00 OAK	60-101-S00 MAP	Label Holder for Shelving End Panel	5-1/4"H x 9"W	1	\$59	\$63		Signage
63ALH107S	N/A	Acrylic Label Holder	7-1/2"H x 10"W	1	\$73	N/A		
60-013-S00 OAK	60-013-S00 MAP	Book Displayer	59" x 19-3/8" x 16"	163	\$1,669	\$1,818		End of Range
55 C 16 555 57 II	00010000111111	Has five sloping shelf spaces for display shelves are 9"D. End panels are 3/4" equipped with adjustable leveling glide edges.	ying books spine out at an a thick, veneered particleboar	ngle for eas	sy access. <i>F</i> ded edges	Adjustable and are		Displayers
60-115-S00 OAK	60-115-S00 MAP	Magazine/Newspaper Displayer	59" x 19-3/8" x 16"	125	\$1,669	\$1,818		
		Displayer provides seven tiers in black v magazines. Pockets are 1-1/2"D. End with banded edges and are equipped w shelf are painted black, with a 15-1/2"	panels are 3/4" thick, vene vith adjustable leveling glide	eered partic es. Back and	leboard			
S1-114-S00	1S-114-S00	42"H Shelving has 4 shelves	42" x 20" x 12"	91	\$932	\$1,016		End of Range
S1-115-S00	1S-115-S00	42"H Shelving has 4 shelves	42" x 24" x 12"	114	\$944	\$1,030		Shelving
S1-116-S00	1S-116-S00	48"H Shelving has 4 shelves	48" x 20" x 12"	101	\$958	\$1,045		
S1-117-S00	1S-117-S00	48"H Shelving has 4 shelves	48" x 24" x 12"	124	\$971	\$1,059		
S1-118-S00	1S-118-S00	60-1/2"H Shelving has 4 shelves	60-1/2" x 20" x 12"	129	\$1,268	\$1,382		
S1-119-S00	1S-119-S00	60-1/2"H Shelving has 4 shelves	60-1/2" x 24" x 12"	160	\$1,280	\$1,395		
S1-120-S00	1S-120-S00	82"H Shelving has 5 shelves	82" x 20" x 12"	165	\$1,372	\$1,495		
S1-121-S00	1S-121-S00	82"H Shelving has 5 shelves  This standard construction shelving is d are 12"D and constructed of solid h pin-and-hole system to support the woo	nardwood. The upright end p		_	-		
60-052-S00 OAK	60-052-S00 MAP	Computer Station for Wood Shelving	82" x 24" x 12"	125	\$1,973	\$2,151		End of Range
60-053-S00 OAK	60-053-S00 MAP	Computer Station for Metal Shelving	84" x 24" x 12"	135	\$2,165	\$2,359	Co	omputer Station
		End of range units are standard type co The unit has a locking door on the botto ventilation. The top has two adjustable keyboard shelf. The back panel at the to	om for computer storage with shelves with pin and hole sy	h a perforat stem and a	ed metal fr djustable s	ont for heat slanted		0
60-012-S00 OAK	60-012-S00 MAP	OPAC Station	40-1/2" x 24" x 16"	110	\$1,318	\$1,438	End of Rang	ge OPAC Station
		End of range OPAC unit is designed for for computer monitor with a pull out key shelf. The work surface is HPL with solic	yboard shelf. It also has two	fixed flat sl	nelves belo		t	

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Newspaper Displayer	60-203-S00 OAK	60-203-S00 MAP	black plastic corner molding	67" x 28-3/16" x 28-3/16" 4" plywood using high-quality y on all vertical edges. Pocket has displayed items. The unit includes 1/4"W x 2-3/4"D).	100	\$4,143	\$4,516
Vertical Newpaper Rack	60-180-S00 OAK	60-180-S00 MAP	Vertical Newspaper Racks A-frame ends and cross-brac screwed together. J-hooks hi sticks which are included.		50	\$1,539	\$1,678
Wall-Mounted Newpaper Rack	60-969-S00 OAK	60-969-S00 MAP	Wall-Mounted Newspaper Racks Construction is solid hardwo holes to receive the sticks wl Fastening holes are drilled for	hich are included.	17	\$365	\$398
Magazine Rack	60-868-S00 OAK	60-868-S00 MAP	The unit is built with apron a	41-1/2" x 35-3/32" x 17-3/16 bed slots for magazine display. nd leg base construction. d oak or maple hardwood construction.		\$2,131	\$2,322

Oak Catalog No.	Maple Catalog No.	Description	Wt. H x W x D	Oak (lbs.)	Maple Price	Price	
S1-113-S00	1S-113-S00	Slatwall Shelving, Starter	60-1/2" x 36" x 12"	96	\$1,763	\$1,922	Slatwall Shelving
S2-113-S00	2S-113-S00	Slatwall Shelving, Adder	60-1/2" x 36" x 12"	81	\$1,327	\$1,446	
S1-112-S00 S2-112-S00	1S-112-S00 2S-112-S00	Slatwall Shelving, Starter Slatwall Shelving, Adder	82" x 36" x 12" 82" x 36" x 12"	112 92	\$1,883 \$1,475	\$2,053 \$1,608	
		This standard construction	shelving unit is fitted with a 3/4" t	hick slatwa	all inset panel.		
60-070-S00 OAK	60-070-S00 MAP	Constructed of 1-3/16" th	65-1/8" x 34-3/4" x 30-7/2" ick, 3-ply veneered particleboard Base is 8"H, usable slatwall anel).	300	\$3,026	\$3,299	Three-Sided Slatwall Kiosk
60-800-S00 OAK	60-800-S00 MAP	Three-Sided Multimedia Ki	osk65-1/8" x 42" x 47-7/8"	325	\$4,330	\$4,720	
		Each vertical support rail ha and attaches to the horizor are 54-1/4"H x 30-3/4"V slatwall display area is atta bolts fastened to internally	netal is ASTM A-513 type 2 steel and as a 2" diameter, self-leveling, adjutal top panel using 3/8" bolts. Verous with a surface of high-pressure lached to the top and bottom horizon and externally threaded bushings. bunded black plastic extrusion.	ustable flo rtical slatw minate. Tri ntal panels	or glide vall panels iangular s using 5/16"	I	
60-801-S00 OAK	60-801-S00 MAP		1/2" thick. A black metal hanger lly embedded "T" nuts is mounted be easily hung on slatwall.		\$319	\$348	Optional Bulletin Board
60-037-S00 OAK	60-037-S00 MAP		yer42" x 21-1/2" x 20-1/4"	90	\$2,925	\$3,188	Four-Sided Slatwall
60-038-S00 OAK	60-038-S00 MAP		yer42" x 21-1/2" x 20-1/4"	85	\$2,580	\$2,813	Dislapyer with Shelf
		•	o slatwall end panels and two ope elf depth is 9". Includes four 3/4'		ble		

	Oak Catalog No.	Maple Catalog No.	Description	HxD	Wt. (lbs.)	Oak Price	Maple Price
Specialty Shelving	S1-202-S00 S2-202-S00	1S-202-S00 2S-202-S00	FYI Reference Shelving, Starter FYI Reference Shelving, Adder	42" x 24" 42" x 24"	145 125	\$2,349 \$1,977	\$2,56 \$2,15
			Reference shelving is 42"H in the back and 39"H Tops have a 3/4" x 3/4" solid-wood retainer strip Units have 1/2" thick plywood backs. Shelves are	on the front edge.			
Serpentine	S1-197-S00 S1-186-S00	1S-197-S00 1S-186-S00	Serpentine with Wood Shelves Serpentine with Omega Flat Shelves	42"H 42"H	400 400	\$6,417 \$6,375	\$6,994 \$6,948
Design Flex Shelving	\$1-185-\$00 \$1-184-\$00	1S-185-S00 1S-184-S00	Serpentine with Omega Pixtorieves  Serpentine with Omega Divider Shelves  Serpentine with Omega Media Display Shelves	42"H 42"H 42"H	400 400 400	\$7,217 \$8,090	\$7,86° \$8,81°
Three Wing Design Flex Shelving	\$1-200-\$00 \$1-192-\$00	1S-200-S00 1S-192-S00	Three Wing with Wood Shelves Three Wing with Omega Flat Shelves	42"H 42"H	380 380	\$5,271 \$5,230	\$5,745 \$5,701
Design Flex Shelving	S1-191-S00 S1-190-S00	1S-191-S00 1S-190-S00	Three Wing with Omega Divider Shelves Three Wing with Omega Media Display Shelves	42"H 42"H	380 380	\$6,070 \$6,943	\$6,617 \$7,568
Horseshoe	\$1-199-\$00	1S-199-S00	Horseshoe with Wood Shelves	42"H	400	\$6,417	\$6,99
Design Flex Shelving	S1-189-S00 S1-188-S00	1S-189-S00 1S-188-S00	Horseshoe with Omega Flat Shelves Horseshoe with Omega Divider Shelves	42''H 42''H	400 400	\$6,375 \$7,212	\$6,94 \$7,86
	S1-187-S00	1S-187-S00	Horseshoe with Omega Media Display Shelves	42"H	400	\$8,090	\$8,81
90 Degree	\$1-196-\$00 \$1-195-\$00	1S-196-S00 1S-195-S00	90 Degree with Wood Shelves 90 Degree with Omega Flat Shelves	42"H 42"H	300 300	\$4,078 \$4,047	\$4,44! \$4,41
Design Flex Shelving	S1-194-S00	1S-194-S00	90 Degree with Omega Divider Shelves	42''H	300	\$4,609	\$5,02
	S1-193-S00	15-193-500	90 Degree with Omega Media Display Shelves	42"H	300	\$5,192	\$5,660

 $Please \ specify\ Wood\ Finish\ (Table\ 1)\ and\ High-Pressure\ Laminate; if\ applicable\ (Table\ 2).\ Details\ can\ be\ found\ on\ page\ GEN\ 4.$ 

Oak Catalog No.	Maple Catalog No.	Description	Wt. H x W x D	Oak (lbs.)	Maple Price	Price	
60-228-S00 OAK	60-228-S00 MAP	Large 3-Tier Displayer	51" x 47-1/2"x 47-1/2"	350	\$2,314	\$2,523	Miscellaneous Displayers
		This unit offers three disp from the floor and is 47-1 the floor and is 32" squa and is 16" square. A 10'	I veneered 3-ply particleboard. Ilay surfaces – the first is 16-5/8" I/2" square. Second is 34" from Ire. Third level is 51" from the floor square center column supports the each shelf is covered with high-pre	he	е		
60-239-S00 OAK 60-239-S07 OAK	60-239-S00 MAP 60-239-S07 MAP	Octagonal Displayer with Mobile Octagonal Displa	Riser 42" x 48" x 48" yer with Riser42" x 48" x 48"	200 175	\$4,109 \$4,817	\$4,479 \$5,251	
60-242-S00 OAK 60-242-S07 OAK	60-242-S00 MAP 60-242-S07 MAP	Octagonal Displayer with Mobile Octagonal Displa	out Riser30" x 48"x 48" yer without Riser30" x 48"x 48"	200 175	\$3,548 \$4,258	\$3,867 \$4,641	
		with inset 3/4" slatwall p covered with high-pressu hardwood edge banding. wood shelves adjustable and 12"H. This unit has a	or maple plywood and solids panels. The display surfaces are re laminate for added durability w The display cubes offer 3/4" soli in 32mm increments. The riser is 2 a 4"H black toe kick for increased /3" heavy-duty swivel casters.	d 24'' square			
60-899-S00 OAK	60-899-S00 MAP	Map Cabinet	23-1/4" x 48-1/2"x 28-3/8"	225	\$5,876	\$6,405	$\wedge$
		measuring 2-1/2"H x 44 screwed to the solid-woo mechanism and has stop and sides are 3/4" thick Cabinet back panel is 1/	d five drawers high. Drawers have I''W x 25-1/4"D inside. Drawer fro d drawer bodies. Drawer slides on os to prevent accidental removal. C , 7-ply veneer-core plywood with h 4" matching plywood. All exposed ick, solid hardwood. Cabinets may	onts are 3-7/8 hardwood slid abinet top, ba ardwood vene d edges of pand	d''H, le se, ers.		
60-900-800	N/A	Map Cabinet Base	4" x 47-1/4"x 27-3/8"	10	\$307	N/A	~
		Constructed of 3/4" thio 4"H recessed, ebonized	ck, 7-ply veneer-core plywood, the toe space.	base creates a			
60-303-S00 OAK	60-303-S00 MAP	Mobile Multimedia Kiosk	46-1/2" x 33" x 33"	175	\$3,483	\$3,797	Mobile Multimedia Displayers
		•	areas that are 11-7/8" wide by 42 /2" inside width x 42"H with 2-ad				
60-304-S00 OAK	60-304-S00 MAP		ire 11-7/8"W by 64-1/2"H. The f			\$4,813	
		are 8-1/2" inside width	x 64-1/2"H with 2 adjustable she	lves each area			
			ed of 3/4" thick, 7-ply hardwood v n alternating slatwall and adjustab		-		

Please specify Wood Finish (Table 1) and High-Pressure Laminate; if applicable (Table 2). Details can be found on page GEN 4.

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Mobile Pyramid Displayers	60-307-S00 OAK	60-307-S00 MAP	3-Sided Mobile Pyramid Displayer, Each Side is 38-	73" x 38-3/4"x 33-1/2"	195	\$2,942	\$3,207
	60-309-S00 OAK	60-309-S00 MAP	4-Sided Mobile Pyramid Displayer, Each Side is 39''	73" x 39"x 39"	245	\$3,754	\$4,092
			These units offers a unique	3-ply veneered particleboard. method of display. Available in tria with 2" dual-wheel, swivel locking			
Nobile Book Displayers	60-112-S00 OAK	60-112-S00 MAP	Double-Faced Browser with Casters	33-3/4" x 57-3/4" x 35-3/4"	200	\$5,643	\$6,151
	60-113-S00 OAK	60-113-S00 MAP	Single-Faced Browser with Casters	33-3/4" x 57-3/4"x 18-3/4"	175	\$4,025	\$4,387
	60-262-S00 OAK	60-262-S00 MAP	Double-Faced Browser - Sn	nall 23" x 25"x 25"	200	\$1,601	\$1,744
Wobile Bin Browsers	60-263-S00 OAK	60-263-S00 MAP	Single-Faced Mobile Browser with Seat	24-5/8" x 23-3/4" x 25"	140	\$1,850	\$2,017
	60-264-S00 OAK	60-264-S00 MAP	Double-Faced Mobile Browser with Seat	24-5/8" x 45"x 25"	190	\$2,607	\$2,842
Mobile Magazine/Book Displayer	60-017-S00 OAK	60-017-S00 MAP	Double-Faced Magazine/Book Displayer	60-1/2" x 37-3/16" x 24"	150	\$3,742	\$4,078

# Display Furniture


Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
60-072-S00 OAK 60-071-S00 OAK	60-072-S00 MAP 60-071-S00 MAP	CD Display Center, Starter CD Display Center, Adder	42" x 38-3/16"x 20" 42" x 37-3/16"x 20"	110 90	\$2,902 \$2,676	\$3,164 \$2,917	42"H CD Display Center
		Three drawers, approx. capacity Solid hardwood construction users 3/4" solid hardwood. Each single CD tray (multipack CD tray)	sing starter/adder configuration of drawer is fully extendable and				4 2 3 1

60-075-S00 OAK	60-075-S00 MAP	CD Display Center, Starter	61" x 38-3/16"x 20"	145	\$3,501	\$3,816	61"H CD Display Center
60-074-S00 OAK	60-074-S00 MAP	CD Display Center, Adder	61" x 37-3/16"x 20"	125	\$3,083	\$3,360	
		Four drawers, approx. capacity Solid hardwood construction urare 3/4" solid hardwood. Each single CD tray (multipack CD tra	sing starter/adder configuration on drawer is fully extendable and				

 60-751-S00 OAK
 60-751-S00 MAP
 CD Browser, Starter
 39-1/2" x 38-1/4" x 39-3/4" 175
 \$2,085
 \$2,273

 60-752-S00 OAK
 60-752-S00 MAP
 CD Browser, Adder
 39-1/2" x 37-3/8" x 39-3/4" 125
 \$1,738
 \$1,894

Constructed of 3/4" thick veneered 3-ply particleboard core with solid hardwood edge banding. Stretcher system is manufactured from solid hardwood. The display area is double-sided and holds approximately 300 CDs per unit in a double-sided black plastic display insert.



CD/DVD Drawer

CD/DVD Display

60-336-S00 OAK

60-336-S00 MAP

250

\$5,237

\$5,709

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
CD/DVD Displayer	60-580-S00 OAK	60-580-S00 MAP	CD/DVD Table	49" x 47-3/4"x 21-1/4"	125	\$1,426	\$1,554	
			0 ,	r with cascading stair step design and ' thick, 7-ply hardwood with 1.6mm e apron construction.				
	60-581-S00 OAK	60-581-S00 MAP	CD/DVD Cabinet	52" x 47-3/4"x 21-1/4"	125	\$3,307	\$3,604	
			Constructed of 3/4" The base is a storage	r with cascading stair step design and ' thick, 7-ply hardwood with 1.6mm e e cabinet on locking casters. Two side e. Each side has a fixed shelf that is 16	dge bands. d with four doo			
CD/DVD Units	64-771-S00 OAK	64-771-S00 MAP	CD/DVD Drawer Uni	it 49-5/8" x 34-1/2"x 23-1/8"	250	\$5,462	\$5,954	
2			This drawer unit feat Each drawer has five are constructed with	a. capacity is 850 CDs and 600 DVDs. ures five drawers installed using full e compartments with a metal follower a solid wood body and drawer front a media 8" tall. The cabinet is construc	xtension slides block. Drawers nd a black pull	handle.		

3-ply veneered particleboard.

CD/DVD Display Unit 49-5/8" x 34-1/2"x 23-1/8"


Five drawers, approx. capacity is 850 CDs and 600 DVDs.

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
60-194-S00	60-234-S00	4-Tier Revolving Displayer with 8-1/2"H Shelves	56-1/8" x 27" Diameter	110	\$4,148	\$4,521	Revolving Displayers
		Four tiers with four compartments or 368 DVDs up to 9"H. Each con			"D.		
60-195-S00	60-235-S00	4-Tier Revolving Displayer with 6-1/2"H Shelves	56-1/8" x 27" Diameter	110	\$3,860	\$4,207	
		Four tiers with four compartments Each compartment is 7"H x 11-3		7''Н.			
60-196-S00	60-236-S00	3-Tier Revolving Displayer with 12-1/2"H Shelves	56-1/8" x 27" Diameter	110	\$3,728	\$4,064	
		Three tiers with four compartment Each compartment is 13"H x 11-		to 13"H.			
		These durable displays are constr mounted on a five-prong base wit					
60-057-S00 OAK	60-057-S00 MAP	4-Sided Revolving Displayer Holds 272 paperbacks, 1,088 CD	48" x 27-1/4" x 27-1/4" 0s, 272 videocassettes or 544	299 DVDs.	\$3,137	\$3,419	4-Sided Revolving Displayers
60-058-S00 OAK	60-058-S00 MAP	4-Sided Revolving Displayer Holds 408 paperbacks, 1,632 CI	66" x 27-1/4" x 27-1/4" Os, 408 videocassettes or 816	325 DVDs.	\$3,820	\$4,163	
		These displayers are constructed with solid hardwood edge bandin The units revolve on a 1000# load	g. The adjustable shelves are 1				
60-854-S00 OAK	60-854-S00 MAP	S/F Revolving Dictionary Stand	5-3/4" x 21" x 12"	10	\$426	\$464	Revolving Dictionary Stand
		Rotates 360° for instant patron a 7-ply oak or maple hardwood ven edge band on 3-sides and a 1/2' edge. The bottom band has a rais hold the book in place.	eer plywood with a 1/4" thick ' thick x 3/4" W band on the b	solid oottom			

	Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price
Four Tower Island	60-415-S00 OAK	60-415-S00 MAP	Four Tower Island with Six (6) 8-1/4"H Shelves	68-1/4" x 38"x 38"	136	\$3,050	\$3,325
	60-215-S00 OAK	60-215-S00 MAP	Four Tower Island with Five (5) 10"H Shelves	68-1/4" x 38"x 38"	136	\$2,943	\$3,208
Six Tower Island	60-416-S00 OAK	60-416-S00 MAP	Six Tower Island with Six (6) 8-1/4"H Shelves	68-1/4" x 42-1/2"x 42-1/2"	210	\$4,882	\$5,321
	60-216-S00 OAK	60-216-S00 MAP	Six Tower Island with Five (5) 10"H Shelves	68-1/4" x 42-1/2" x 42-1/2"	210	\$4,736	\$5,163
Three Tower Wall	60-417-S00 OAK	60-417-S00 MAP	Three Tower Wall with Six (6) 8-1/4"H Shelves	68-1/4" x 43-7/8"x 17-1/4"	128	\$2,438	\$2,657
	60-217-S00 OAK	60-217-S00 MAP	Three Tower Wall with Five (5) 10"H Shelves	68-1/4" x 43-7/8" x 17-1/4"	128	\$2,368	\$2,581
Six Tower Aisle	60-418-S00 OAK	60-418-S00 MAP	Six Tower Aisle with Six (6) 8-1/4"H Shelves	68-1/4" x 43-7/8"x 34-1/2"	266	\$4,878	\$5,316
	60-218-S00 OAK	60-218-S00 MAP	Six Tower Aisle with Five (5) 10"H Shelves	68-1/4" x 43-7/8"x 34-1/2"	266	\$4,736	\$5,163

# Display Furniture

Catalog No.	Description	Overall H x W x D	Wt. (lbs.)	COM Price	Wood/G1 Price	Grade 2 Price	Grade 3 Price	Grade 4 Price	Grade 5 Price	
Shelving Be	ench, Oak Wood	d								Shelving Benches
S1-600-S00	12"D Starter	21"H x 12"D	45	\$923	\$917	\$1,132	\$1,182	\$1,340	\$1,416	
S2-600-S00	12"D Adder	21"H x 12"D	45	\$797	\$792	\$978	\$1,019	\$1,156	\$1,223	
S1-601-S00	16"D Starter	21"H x 16"D	50	\$997	\$991	\$1,224	\$1,274	\$1,447	\$1,530	
S2-601-S00	16"D Adder	21"Hx16"D	50	\$855	\$850	\$1,050	\$1,094	\$1,240	\$1,312	
Shelving Be	ench, Maple Wo	ood								
1S-600-S00	12"D Starter	21"H x 12"D	45	\$971	\$966	\$1,192	\$1,241	\$1,410	\$1,491	
2S-600-S00	12"D Adder	21"Hx12"D	45	\$843	\$838	\$1,034	\$1,078	\$1,224	\$1,295	
1S-601-S00	16"D Starter	21"H x 16"D	50	\$1,058	\$1,052	\$1,299	\$1,352	\$1,536	\$1,624	
2S-601-S00	16"D Adder	21"Hx16"D	50	\$917	\$912	\$1,127	\$1,173	\$1,334	\$1,410	-
Reader's R	oost, Oak Wood	d								Reader's Roost
60-274-S00	Reader's Roost	42" x 85"x 49-1/4"	375	\$6,065	\$6,054	\$7,472	\$7,790	\$8,840	\$9,349	
Reader's R	oost, Maple Wo	ood								
77-274-S00	Reader's Roost	42" x 85"x 49-1/4"	375	\$6,675	\$5,606	\$8,224	\$8,572	\$9,727	\$10,287	
	42"H, with a carpe	nsists of three sections of w eted platform 19"H. The she . Capacity: 600 children's b	elving is oak	,						



Hassock, Oak Wood									Hassocks
<b>60-864-S00</b> Hassock	15" x 15"x 15"	18	\$633	\$628	\$705	\$730	\$916	\$971	
Hassock, Maple Wood 77-864-S00 Hassock	15" x 15"x 15"	18	\$709	\$703	\$790	\$818	\$1,026	\$1,087	

 $Please\ specify\ Wood\ Finish\ (Table\ 1)\ and\ Upholstery\ (Table\ 5).\ Details\ can\ be\ found\ on\ pages\ GEN\ 4\ and\ GEN\ 5.$ 

**-DIS 16-** F11-1-19G-DIS

# Wood Book Trucks

# **General Specifications**

Construction is solid hardwood not less than 3/4" thick. Except when indicated, each truck is supplied with two fixed and two swivel carpet casters with 5" diameter tires. Each caster is attached with four lag screws, except as indicated. Caster forks are steel, heat treated, and bright nickel plated. Wheels are gray rubber, 1-9/32"W on ball bearings. Seals and O-rings are used to produce a quiet caster. Load capacity rated at 200# per caster.

	0ak	Maple			Wt.	0ak	Maple
	Catalog No.	Catalog No.	Description	HxWxD	(lbs.)	Price	Price
Large Book Truck with Flat Shelves	60-911-S01 OAK	60-911-S01 MAP	Large Book Truck with Flat Shelves	43" x 39-1/8" x 14-1/8"	82	\$1,688	\$1,840
	60-911-S02 OAK	60-911-S02 MAP	Large Book Truck with Flat Shelves and Ru	43" x 39-1/8" x 14-1/8" bber Bumpers	82	\$2,046	\$2,231
	60-911-S03 OAK	60-911-S03 MAP	Large Book Truck with Flat Shelves and All	43" x 39-1/8" x 14-1/8" Swivel Casters	82	\$1,738	\$1,894
	60-911-S04 OAK	60-911-S04 MAP	Large Book Truck with Flat Shelves, Rubbe	43" x 39-1/8" x 14-1/8" r Bumpers and All Swivel Casters	82	\$2,095	\$2,284
			Shelves are tenoned, glu 3/4" by 3/4" hardwood of both shelves. Trucks h	nder each			
Small Book Truck with Flat Shelves	60-912-S01 OAK	60-912-S01 MAP	Small Book Truck with Flat Shelves	43" x 32-1/2" x 14-1/8"	78	\$1,422	\$1,550
	60-912-S02 OAK	60-912-S02 MAP	Small Book Truck with Flat Shelves and Ru	43" x 32-1/2" x 14-1/8" bber Bumpers	78	\$1,782	\$1,942
	60-912-S03 OAK	60-912-S03 MAP	Small Book Truck 43" x 32-1/2" x 14-1/8" with Flat Shelves and All Swivel Casters		78	\$1,471	\$1,603
	60-912-S04 OAK	60-912-S04 MAP	Small Book Truck with Flat Shelves, Rubbe	43" x 32-1/2" x 14-1/8" r Bumpers and All Swivel Casters	78 S	\$1,830	\$1,995
			3/4" by 3/4" hardwood	ed and screwed into the ends. In d cleats are glued and screwed un ave 13-3/8" clearance between	nder each		
Utility Book Truck with All Swivel Casters	60-870-S01 OAK 60-870-S02 OAK	60-870-S01 MAP 60-870-S02 MAP	Utility Book Truck Utility Book Truck with Rubber Bumpers	31" x 31-9/16" x 13-3/16" 31" x 32-9/16" x 13-3/16"	40 40	\$1,164 \$1,523	\$1,268 \$1,661
			Unit has two sloped shelf and screwed into the end heavy-duty swivel casters		S.		

Oak Catalog No.	Maple Catalog No.	Description	HxWxD	Wt. (lbs.)	Oak Price	Maple Price	
60-917-S01 OAK	60-917-S01 MAP	Large Book Truck	43" x 39-1/8" x 17"	80	\$2,056	\$2,242	Large Book Truck with Double-Faced Display Shelves
60-917-S02 OAK	60-917-S02 MAP	with Double-Faced Display Large Book Truck	43" x 39-1/8" x 17"	80	\$2,417	\$2,635	with bouble-raced bisplay Shelves
60-917-S03 OAK	60-917-S03 MAP	Large Book Truck	Shelves and Rubber Bumper 43" x 39-1/8" x 17" Shelves and All Swivel Caste	80	\$2,106	\$2,295	
60-917-S04 OAK	60-917-S04 MAP	Large Book Truck	43" x 39-1/8" x 17" Shelves , Rubber Bumpers ar	80	\$2,464 vel Casters	\$2,686	
		_	and screwed into the ends. 'H x 5-3/4"D, double-faced flat.				
60-919-S01 OAK	60-919-S01 MAP	Small Book Truck	43" x 32-1/2" x 17"	75	\$1,792	\$1,953	Small Book Truck
60-919-S02 OAK	60-919-S02 MAP	with Double-Faced Display Small Book Truck	43" x 32-1/2" x 17"	75	\$2,151	\$2,344	with Double-Faced Display Shelves
60-919-S03 OAK	60-919-S03 MAP	Small Book Truck	Shelves and Rubber Bumper 43" x 32-1/2" x 17"	75	\$1,840	\$2,006	
60-919-S04 OAK	60-919-S04 MAP	Small Book Truck	Shelves and All Swivel Caste 43" x 32-1/2" x 17" Shelves , Rubber Bumpers ar	75	\$2,201	\$2,399	
		Shelves are tenoned, glued Top two shelves are 7-1/8' and sloped. Bottom shelf is	'H x 5-3/4"D, double-faced				
TO-915-S00	M0-915-S00	Large Depressible Book Receiving Truck	30-3/4" x 26" x 22"	100	\$1,812	\$1,975	Large Depressible Bool Receiving Trucl
T0-915-S02	M0-915-S02	Large Depressible Book Receiving Truck with Rubbe	30-3/4" x 26" x 22" r Bumpers	100	\$1,957	\$2,133	
		platform is plastic laminate and has nylon rollers moun and stability. The truck is su	lesk. Construction is 3/4" ush panel design. The depress d and mounted on a spring m ted into all four edges for ease pplied with four heavy-duty 3 d caster blocks. The unit holds	echanisr of opera '' swivel o	tion casters		
T0-914-S00	M0-914-S00	Small Depressible Book	23-3/4" x 26" x 22"	90	\$1,557	\$1,696	Small Depressible Book
ТО-914-S02	M0-914-S02	Receiving Truck for 32"H U Small Depressible Book Receiving Truck for 32"H U	23-3/4" x 26" x 22"	90	\$1,695	\$1,848	Receiving Truck
		platform is plastic laminate and has nylon rollers moun and stability. The truck is su	lesk. Construction is 3/4" ush panel design. The depress d and mounted on a spring m ted into all four edges for ease upplied with four heavy-duty 3 d caster blocks. The unit holds	echanisr of opera '' swivel o	ition asters		

**- WBT 4 -** F11-1-19G-WBT

# Electrical Accessories

# **General Specifications**

The Brodart power distribution system distributes power from the building's power supply to the furniture through the use of power-distribution channels which may be interconnected to allow multiple pieces to be shared from one power source. The components of the system are as follows:


A.) Power entry: Connects the building's power supply and feeds power to the furniture.

- A.) Power entry: Connects the building's power supply and feeds power to the furniture.
- B.) Power-distribution channel: Houses duplex electrical outlets to access power and serves as a wire management channel.
- C.) J-channel: An optional wire management tray, which may house data jacks. This channel is necessary when additional storage is required or when data lines are run in addition to electrical cords.

#### POWER-ENTRY ASSEMBLIES

Single-circuit power-entry assembly consist of a wood chase that is fastened to the unit with modular fasteners, a PVC plastic liner fastened to the wood chase, and the power-entry cable which is fastened inside of the PVC liner. The power entry cable has a 24" STO cord fitted with a 20-amp plug at the bottom of the assembly and a flexible metal conduit with a quick-connect coupling at the top. This power-entry assembly is used for single-circuit power distribution systems and provides access to circuit #1. The assembly can be plugged into any 20-amp outlet.

Multiple-circuit power-entry assembly is to be used if more than one circuit is required. The multiple-circuit power-entry assembly consists of a wood chase that is fastened to the unit with modular fasteners, a PVC plastic liner that is fastened to the wood chase and the power-entry cable which is fastened inside the PVC liner. The bottom of the power-entry has a 72" long liquid-tight conduit. Inside the conduit is an eight-wire harness that is wired to four building circuits: three sharing a common ground and one dedicated with an isolated ground.



The top of the power entry consists of a flexible metal conduit and a quick-connect coupling. This power entry is required when more than one circuit or when an isolated with a dedicated ground is required. This assembly must be installed by a qualified licensed electrician. A multiple-circuit system is required under the following conditions:

- 1.) The length of the wiring served by the power entry exceeds 30 feet.
- 2.) The total amperage served by the power entry exceeds 20 amps.
- 3.) A dedicated computer circuit is required. The dedicated computer circuit on system is circuit #4.
- 4.) More than thirteen (13) duplex receptacles are required.

Note: One power-entry assembly is required for each building power source accessed.

### PANEL-MOUNT, POWER-DISTRIBUTION CHANNEL

The panel-mount power-distribution channel is constructed of 20-gauge steel and is finished using a black electrostatically applied epoxy powder paint. The channel is open at the top to allow excess wire to be stored behind the power blocks and the duplex receptacles. Front of the channel has cutouts so two duplex outlets can be mounted. The duplex outlets are rated 15-amps at the receptacle with 20-amps though power. The duplex outlets are connected to each other and the power entry by means of 3/4" flexible metal conduit, which has a quick-connect coupling. The cable consists of an eight-wire, four-circuit system with three standard utility circuits and one isolated circuit with a dedicated ground (computer circuit). If a channel is ordered with one duplex outlet, a plastic cover is provided to cover the unused hole. Units mount to back panels or table keels.



# 15-AMP POWER-ENTRY LEGS

Power-entry legs are to be used with leg-base tables and computer-access stations. Power-entry legs are available in single circuit only. Power-entry legs are finished to match the other legs on the table.


Note: 15-amp power legs cannot accept power strips. Receptacles are for electrical device only.

## WIRE MANAGEMENT LEGS

Wire management legs are to be used with leg-base tables and computer-access stations. Wire management legs are finished to match the other legs on the table and allow wires to be run from the floor to the table inconspicuously.

## J-CHANNEL (OPTIONAL)

J-Channel is constructed using 18-gauge steel and is finished using a black electrostatically applied epoxy powder-paint. The J-Channel attaches to the bottom of the power-distribution channel with the same screws that attach the power-distribution channels to the unit. The channel is 3-1/8"H and 4"D; the front lip of the channel is 2"H. The J-Channel provides additional wire-storage capacity or a data wire-management channel when data lines are required. J-Channel has four square holes that hold either communication or data jacks. Unit uses modular insert data jacks, which must be ordered separately.





# **DUPLEX OUTLET RECEPTACLES (Multiple-Circuit System)**

Duplex outlets can be ordered to access any of the four circuits available in the power-distribution channel. You must specify the number of the circuit to be accessed for each duplex outlet ordered. Circuit IV outlets access the isolated circuit with the dedicated ground. If circuit numbers are not specified, your power-distribution channels are shipped with circuit one duplex outlet receptacles. Duplex outlets are easily interchanged within the power-distribution assembly by pushing the duplex receptacle sideways and then pulling it out.

When ordering duplex receptacles for circuits I, II, III, or IV, the following catalog numbers should be specified.

Description	Price
Circuit I	\$65
Circuit II	\$65
Circuit III	\$65
Circuit IV (Isolated Circuit)	\$65
	Circuit I Circuit II Circuit III





The following chart should be used to assist in the selection of eletrical components for circulation desks.

	grife of	cuit go tati	One Duplex Two Duplex Outlet		1000																
	Power	Ou	tlet Ci	hann	el		Cha	nnel			Ву	pass (	Chan	nels	& Ha	mess	es	Wire	Mgmt	Trays	
Single Wide Units	Inits										Bypass Channel						30"W 37"W 44"W				
XX-012/E12 [SW39/32 PL]	X	X	X		$\neg$	Т	X	П					0						1		
(X-014/E14 [SW39/32]	X	X	X		$\neg$		X	$\vdash$					0				$\vdash$		1		
XX-015/E15 [SW39/32 BR]	X	X	X		$\neg$		X	$\vdash$				$\Box$	0	$\neg$		$\top$	$\vdash$	П	1		
XX-E32 [SW32 ADA]					X				X						$\top$	0	-		7.		
XX-121/E21 [SW39/32 COS]	X	X	1	$\Box$	_	$\neg$		$\vdash$				П	$\neg$	$\neg$	$\neg$	_	$\vdash$				
XX-122 [SW39/32 FCD]	X	X																	- 38		
XX-123/E23 [SW39/32 CD]	X	X																			
(X-124/E24 [SW39/32 OSD]	X	X			$\neg$	$\top$								$\neg$		$\top$					
XX-131/E31 [ SW39/32 CSD]	X	X	X		$\neg$		X						0				$\vdash$		1		
XX-133 [SW39/32 F]	×	×	×		$\neg$	$\neg$	X						0	$\neg$	$\neg$	$\neg$	$\vdash$		1		
XX-135 [SW39/32 FC]	X	X	X		$\neg$		X					П	0						1	-	
XX-172/E72 [SW39/32 D]	х	X	X		$\neg$		X	$\Box$				П	0	$\neg$			$\vdash$	П	1		
(X-174/E74 [SW39/32 OS]	X	X	X		$\neg$		X						0	$\neg$			П		1		
XX-176/E76 (SW39/32 C)	X	X	X				X						0						1		
XX-134/E34 [5W39/32 FO5]	X	X	X		$\neg$	$\neg$	X						0			1	П		1		
XX-236/E36 [SW39/32 MS]					$\neg$								0	$\neg$			П				
Double Wide Desks																					
XX-009 [DWAH PL]	X	X	T	П	Т	$\top$	$\overline{}$	П				0	$\neg$	Т		$\top$	Т				
XX-011/E11[DW39/32 PL (35)]	X	X			$\neg$	×					-4	0							2		
XX-011-SEA [DW39 PL28]	X	×	T		$\neg$	×		$\Box$				0		$\neg$		$\neg$	$\Box$		2		
XX-013/E13 [DW39/32]	X	X			$\neg$	X						0							2		
XX-E37 [DW32 DP]	X	X	$\top$		$\neg$		$\top$					0		$\neg$		$\top$	$\Box$	П			
XX-138/E38 [DW39/32 SP]	X	X			$\neg$							0							- 7		
Corner Units					100	3 10			/2 23					31	-	0.0			7,1		
XX-010/E10 [9039/32 MC]	X	X	$\top$	X	$\neg$	$\neg$	$\overline{}$	X				$\Box$		- 10	0.1	$\top$	$\Box$				1
XX-016/E16 [9039/32 CC]					$\neg$									0			$\vdash$		- 5		
XX-017/E17 [9039/32 MCP]	X	X	T	X				X						-	0						1
XX-018/E18 [4539/32 CC]															-						
XX-040/E40 [9039/32 OCCP]	X	×				X				X							0		2		-
XX-041/E41 [9039/32 OCC]	X	X	T			X				X							0		2		
XX-047/E47 [6039/32 CCP]	X	X							1		Х							0	- 3	1	1
XX-048/E48 [6039/32 CC]	Х	X									Х							0		1	
XX-055/E55 [9039 CCC]														0							
XX-058/E58 [4539/32 CCC]															(				- 3		
XX-143/E43 [9039/32 OCS]																					
XX-150/E50 [9039 SC]														0							

X= Electrical Distribution Channel

O = Bypass Channel

### Notes:

If electrical distribution is not required in a given unit within a range of desks, and electric bypass channel can and must be used to continue the run of power to other units in the range.

Wire Management Trays are to be used to separate power from data.

XX-015-E15 Book Return Unit will receive a by-pass in most layout configurations.

All Closed Corner Units receive a factory installed PVC channel for by-pass (sold separately).

Catalog No.	Description	Price	
UL Listed Electric	for Circulation Desks, Oak Wood		
X3 100 S00 OAK	Power Entries, All Series, Cord and Plug (Single Circuit)	\$393	
X3 100 S02 OAK	Power Entries, All Series, Hardwired (Multiple Circuit)	\$465	0 0
UL Listed Electric	for Circulation Desks, Maple Wood		
X3 100 S00 MAP	Power Entries, All Series, Cord and Plug (Single Circuit)	\$393	
X3 100 S02 MAP	Power Entries, All Series, Hardwired (Multiple Circuit)	\$465	
	<b>Note:</b> Grommets are not always included on product as a standard item. If wires are to be passed through the work surface or from one unit to another, grommets may need to be ordered separately.		
			0
Power Distribution	n Channels for Circulation Desks, All Series		
One Duplex Outle	et Channel		
X3 012 S02	Circ Desk, One Outlet Channel, SW Unit	\$486	
X3 017 S02	Circ Desk, One Outlet Channel, Multipurpose Corner	\$825	
X3 032 S02	Circ Desk, One Outlet Channel, ADA Unit	\$605	
X3 040 S02	Circ Desk, One Outlet Channel, 90° Curved Corner	\$572	0 63 63 53
Two Duplex Outle	t Channel		
X3 011 S00	Circ Desk, Two Outlet Channel, DW Unit	\$608	
X3 012 S00	Circ Desk, Two Outlet Channel, SW Unit	\$576	
X3 017 S00	Circ Desk, Two Outlet Channel, Multipurpose Corner	\$906	
X3 032 S00	Circ Desk, Two Outlet Channel, ADA Unit	\$625	
X3 040 S00	Circ Desk, Two Outlet Channel, 90° Curved Corner	\$608	
X3 047 S00	Circ Desk, Two Outlet Channel, 60°g Nu-Curve Desk	\$689	0 [
Bypass Channels			
X3 311 S00	Circ Desk, Bypass Channel, DW Unit	\$573	
X3 312 S00	Circ Desk, Bypass Channel, SW Unit	\$447	
X3 316 S00	Circ Desk, Bypass Channel, 90° Closed Corner	\$441	
X3 317 S00	Circ Desk, Bypass Channel, Multipurpose Corner	\$575	
X3 318 S00	Circ Desk, Bypass Channel, 45° Closed Corner	\$441	
X3 332 S00	Circ Desk, Bypass Channel, ADA Unit	\$477	
X3 340 S00	Circ Desk, Bypass Channel, 90° Curved Corner	\$579	
X3 347 S00	Circ Desk, Bypass Channel, 60° Nu-Curve Desk	\$572	

**Note:** This asssembly is for units that do not require electrical access but need to have power passed through to the adjoining units.

Unit does not include any duplex outlets.

The following chart should be used to assist in the selection of eletrical components for carrels and media stations.

# Power Distribution and Wire Management for Carrels & MMS


Part Number	Gride Creat	/4	1000	2 480	3/3	8/5		13 450 S	A Henry	DE THEO	
		Multi Circuit	C	ne D	uplex		et	Two Dup Cha	lex Outlet nnel	Wire M	gmt Tray
Electrical for Carrels		relea.									
36"W Panel Based Carrel	X3 100 S00 (MAP)	X3 100 S02 (MAP)	х					X		0	
48"W Panel Based Carrel	X3 100 S00 (MAP)	X3 100 S02 (MAP)		X					х		0
36"W Panel & Post Carrel	X3 101 S02 (MAP)	X3-101-S02 (MAP)	х					×		0	
48"W Panel & Post Carrel	X3 101 S02 (MAP)	X3-101-S02 (MAP)		х					х		0
Electrical for MMS (LTS)											
36"W Stations	X3 300 500 (MAP)	X3 300 S02 (MAP)			х						
48"W Stations	X3 300 S00 (MAP)	X3 300 S02 (MAP)				х					
Functional Corner Unit	N/A	N/A					X				

X = Electrical Distribution Channel

Note: Wire Management Trays are to be used for separating data from power

O = Wire Management Tray

Catalog No.	Description	Price	
Power Entries for	r <u>Modular Media Stations, Oak Wood</u>		
X3 300 S00 OAK	Power Entry, Cord and Plug (Single Circuit)	\$385	
X3 300 S02 OAK	Power Entry, Hardwired (Multiple Circuit)	\$458	
Power Entries for	r Modular Media Stations, Maple Wood		
X3 300 S00 MAP	Power Entry, Cord and Plug (Single Circuit)	\$385	
X3 300 S02 MAP	Power Entry, Hardwired (Multiple Circuit)	\$458	
	<b>Note:</b> Grommets are not always included on product as a standard item. If wires are to be passed through the work surface or from one unit to another, grommets may need to be ordered separately.		
Power Distribution	on Channels for Modular Media Stations		
One Duplex Outle	<u>et</u>		Ļ
X3 354 S00	36" Wide Position	\$349	
X3 454 S00	48" Wide Position	\$377	u u
X3 554 S00	Functional Corner Unit	\$533	
	Note: This asssembly is for units that do not require electrical access		
	but need to have power passed through to the adjoining units.		



grommets may need to be ordered separately.



Catalog No.	Description	Price
Quorum 94 Serie	s Plate Style, 15-Amp Power-Outlet Leg, Oak Wood	d Veneer
X1 941 S00 OAK	Leg & Plate Type for 29"H Table	\$597
X1 941 S02 OAK	Leg & Plate Type for 27-1/2"H Table	\$593
X1 941 S03 OAK	Leg & Plate Type for 25"H Table	\$582
X1 941 S04 OAK	Leg & Plate Type for 32"H Table	\$638
Quorum 94 Serie	s Plate Style, 15-Amp Power-Outlet Leg, Maple Wo	ood Veneer
X1 941 S00 MAP	Leg & Plate Type for 29"H Table	\$650
X1 941 S02 MAP	Leg & Plate Type for 27-1/2"H Table	\$646
X1 941 S03 MAP	Leg & Plate Type for 25"H Table	\$634
X1 941 S04 MAP	Leg & Plate Type for 32"H Table	\$695
Quorum 94 Serie	s Apron Style, 15-Amp Power-Outlet Leg, Oak Woo	od Veneer
X1 942 S00 OAK	Leg & Apron Type for 29"H Table	\$556
X1 942 S04 OAK	Leg & Apron Type for 32"H Table	\$596
X1 942 S05 OAK	Leg & Apron Type for 39"H Table	\$636
Quorum 94 Serie	s Apron Style, 15-Amp Power-Outlet Leg, Maple W	lood Veneer
X1 942 S00 MAP	Leg & Apron Type for 29"H Table	\$606
X1 942 S04 MAP	Leg & Apron Type for 32"H Table	\$649
X1 942 S05 MAP	Leg & Apron Type for 39"H Table	\$693

Leg is 2-1/4" square, 1/8" thick wall, aluminum extrusion with 3/4" radius on the outside corners. Leg is oak beneer wrapped to match other legs on the table and has three receptacles for power outlet and a 2' SJT power cord. A Hi-Pot Test of insulation and connections of 1,200 volts is given to each leg.


Note: The use of grommets for wire passage through the work surface is recommended.

15-amp power legs cannot accept power strips. Receptacles are for electrical device only.

Catalog No.	Description	Price		
Chancellor's Serie	es Wire Management Leg			
Round Leg Style				
X3 CHR6 S00	Leg & Apron Type for 29"H Table	\$287	lifi.	
X3 CHR6 S02	Leg & Apron Type for 27-1/2"H Table	\$287		
X3 CHR6 S03	Leg & Apron Type for 25"H Table	\$287		
X3 CHR6 S04	Leg & Apron Type for 32"H Table	\$287		
Square Leg Style				
X3 CH25 S00	Leg & Plate Type for 29"H Table	\$287		IΠ
X3 CH25 S02	Leg & Plate Type for 27-1/2"H Table	\$287		
X3 CH26 S05	Leg & Apron Type for 39''H Table	\$287		
	Leg is constructed according to standard Chancellor Series Leg construction.  Leg is slotted 4" from the top and 2-1/2" from the bottom with a 1/2" W slot.  Slots receive a snap-on metal cover, which allows a 1" opening at the top and bottom of the slot for cord exit. Slot accepts two 3/8" power cords or four data cables.			

Epoch Series Wire	e Management Leg		
Powder-Coated Le	eg Style		-
59 945 S00	Powder-Coated Leg for 29"H Table	\$331	
59 945 S02	Powder-Coated Leg for 27-1/2"H Table	\$332	Powder-Coated
59 945 S03	Powder-Coated Leg for 25"H Table	\$331	
Chrome Leg Style			
59C 945 S00	Chrome Leg for 29"H Table	\$655	
59C 945 S02	Chrome Leg for 27-1/2"H Table	\$643	
59C 945 S03	Chrome Leg for 25"H Table	\$643	F-10
Oak Wood Leg Sty	<u>de</u>		
59W 945 S00 OAK	Wood Leg for 29"H Table	\$388	Chrome
59W 945 S02 OAK	Wood Leg for 27-1/2"H Table	\$388	
59W 945 S03 OAK	Wood Leg for 25"H Table	\$388	
Maple Wood Leg S	<u>Style</u>		Ų,
59W 945 S00 MAP	Wood Leg for 29"H Table	\$388	
59W 945 S02 MAP	Wood Leg for 27-1/2"H Table	\$388	
59W 945 S03 MAP	Wood Leg for 25"H Table	\$388	
	Leg is constructed according to standard Epoch leg construction	on. The leg will receive a 3/4" wide slot located	in the
	back of the leg underneath the angle bracket, 6-5/16" down	•	1 11
	the leg. A spring loaded cover of 1/8" bent metal will provide		1 11
	cover will provide a 1"D egress at the top and bottom of the sle		·

wraped in wood veneer according to the product specified.



Slots receive a snap-on veneer wrapped cover, which allows a 1" opening at the top and bottom of the slot for cord exit. Slot accepts two 3/8" power cords or four data cables.

Catalog No.	Description	Price				
Duplex Outle	t Receptacles					
X3 001 S00	Circuit I	\$65	<b>√08</b>	ACB.	~0	
X3 002 S00	Circuit II	\$65	/: <u>:</u>			
X3 003 S00	Circuit III	\$65	65/			
X3 004 S00	Circuit IV (Isolated Circuit)	\$65	1	Contract of the second		100
	Circuit I receptacles are supplied as standard. When ordering duplex receptacles for circuits II, III or IV, the following numbers should be specified.					

# **Data/Communication Terminal & Jacks**

X3 005 S00	RJ11 Telephone Jack	\$37
X3 007 S00	RJ45 Category Five Data Jack	\$40
X3 007 S02	RJ45 Category Five Data Jack w/9 ft Patch Cord	\$65
X3 007 S03	RJ45 Category Five Data Jack w/12 ft Patch Cord	\$69



Note: Data jacks are wired for TIA/EIA T568A.

# Horizontal Surface-Mount Data Outlet Box without Data Jacks & Cables

X1 700 074 Horizontal Data Outlet Box \$66

Constructed of black ABS plastic, box is designed for use in the horizontal mounting of data. This box inter-members with the X1 700 065 and X1 700 066 raceways. Capacity of two jacks.

Note: Data jacks not included.



### Vertical Date Outlet Box without Data Jacks

X1 700 070 Vertical Data Outlet Box \$99

Constructed of black ABS plastic, box is designed for use in the vertical mounting of data. This box inter-members with the X1 700 065 and X1 700 066

raceways. Capacity of two jacks.


Note: Data jacks not included.



# Power Strips


X1 700 112	Power Strip, 3 Outlet Power Strip with a 9' SJT Cord	\$65
73 200 S00	Electrical Interport w/2 outlets & 2 ports for data (purchase data separately)	\$267
73 258 S00	15-amp Power/Data Strip This unit consists of an outlet strip with four surge-protected electrical outlets and two RJ45 category 5 data jacks. Unit has two 9' patch cords for data and a 9' power cord. Unit has a resettable circuit breaker.	\$305

**Note:** Grommets are not always included on product as a standard item. If wires are to be passed through the work surface or from one unit to another, grommets may need to be ordered separately.




\$895

\$589



Catalog No.	Description	Price
<u>Tabletop/Worksurface Distribution</u> Corner Mounted Power/Communication Center		
73 560 S00	Corner Power Unit Constructed of black ABS plastic, the unit has four electrical outlets; three above the work surface, one below. The unit mounts in the corner of a carrel or PAC station. Unit comes with a nine foot SJT power cord.	\$258
73 559 S00	Corner Power and Communication Center without Patch Cords	\$436
73 559 S02	Corner Power and Communication Center with 9' Patch Cords Constructed of black ABS plastic, the unit has four electrical outlets; three above the work surface, one below. Unit also has a data module which allows for up to three data jacks. Unit comes standard with two RJ45 Category 5 data jacks. The unit mounts in the corner of a carrel or PAC station. Unit comes with a nine foot SJT power cord and can be ordered with or without nine foot data patch cords.  Note: Data jacks are wired for TIA/EIA T568A.	\$473



# <u>Tabletop/Worksurface Distribution</u> <u>OPAC Station Power Assembly</u>

**73 274 S00** Panel Power Assembly for 3-, 4- and 6-Position PAC Station

Overall dimensions: 14"H x 27-1/2"W x 2"D

Power assembly panel is constructed of 3/4" veneered particleboard with 2-1/2"D cleats on the end for mounting to the PAC unit. The assembly is installed in the well created in the center of the PAC stations. The power assembly has two six-outlet, 15-amp power strips. Each outlet strip has a 9' SJT power cord. Space is available on the panel for future data patch panel requirements.

Note: Outlets are for electrical devices only and are not for plugging in power strips.



# <u>Tabletop/Worksurface Distribution</u> <u>Panel Table Power and Data Outlet</u>

73 280 S00 Panel Mounted Power and Data Outlet

Overall dimensions: 2-3/4" x 8-1/2" x 3-3/8"D

Unit is constructed using the same species of wood and the same finish as the unit on which it is mounted. The unit has three 15-amp electrical outlets with resettable circuit breaker and is provided with a  $9^{\circ}$  SJT cord and two RJ45 category

5 data jacks with nine foot patch cords.

Note: Outlets are for electrical devices only and are not for plugging in power strips.

Catalog No. Description Price

# <u>Tabletop/Worksurface Distribution</u> <u>Single-Faced Tilt Up Power and Data Center</u>

73 268 S00 S/F Tilt Up Power and Data Center

\$572

Overall dimensions: 10"W x 5-3/4"D

Tilt up data and power center is constructed from 18-gauge steel painted black. The unit has three electrical outlets with resettable circuit breaker and comes standard with two RJ45 category 5 data jacks with 9' patch cords and a 9' SJT cord.

with two RJ45 category 5 data Jacks with 9° patch cords and a 9° SJ1 cord. The access door is spring loaded and opens to an approximate 42° angle.

The access door is held closed with a spring-loaded clasp. Unit mounts into the tabletop.

Door opening is 4-1/4"D x 8-3/8"W.

# <u>Tabletop/Worksurface Distribution</u> <u>Double-Faced Tilt Up Power and Data Center</u>

73 368 SOO D/F Tilt Up Power and Data Center \$1,195

Overall dimensions: 10"W x 10-3/4"D

Tilt up data and power center is constructed from 18-gauge steel painted black. The unit has six electrical outlets with resettable circuit breaker and comes standard with four RJ45 category 5 data jacks with 9' patch cords and two 9' SJT cords. The access doors are spring loaded and open to an approximate 42° angle.

The access door is held closed with a spring-loaded clasp. Unit mounts into the tabletop.

Door opening is 4-1/4"D x 8-3/8"W.

Note: Data jacks are wired for TIA/EIA T568A. For factory cutout to install the unit,

a sketch must be provided to show the unit in the work surface with dimensions noting the exact location.

# <u>Tabletop/Worksurface Distribution</u> <u>Table Power Tap, Round</u>

XSU PT4RD S Table Power Tap, Round

\$298

Unit is designed to allow hidden power and data access in a work surface. Constructed of black ABS plastic, the unit contains three (3) 15-amp outlets and two (2) Cat 5 Ethernet connections. Power cord is 8' in length. Unit fits into a 4-7/32" diameter hole and overall dimension is 4-3/8" diameter.

**Note:** For factory cutout to install the unit, a sketch must be provided to show the unit in the work surface with dimensions noting the exact location.



# Power Sphere (Fits into Standard 3" Grommet Hole) Two Outlets per sphere - 8 spheres can be linked off one plug (in sequential order)


XBE01640L1 S	Power Sphere Starter, Link 1, 10' Cord & Plug	\$312
XBE01640L2 S	Power Sphere Adder, Link 2, 5' Cord (Black/Red)	\$239
XBE01640L3 S	Power Sphere Adder, Link 3, 5' Cord (Red/Blue)	\$239
XBE01640L4 S	Power Sphere Adder, Link 4, 5' Cord (Blue/Orange)	\$239
XBE01640L5 S	Power Sphere Adder, Link 5, 5' Cord (Orange/Yellow)	\$239
XBE01640L6 S	Power Sphere Adder, Link 6, 5' Cord (Yellow/Green)	\$239
XBE01640L7 S	Power Sphere Adder, Link 7, 5' Cord (Green/White)	\$239
XBE01640L8 S	Power Sphere Adder, Link 8, 5' Cord (White)	\$239

Unit is designed to fit into a standard 3" grommet hole. This 15A system can link up to 8 duplex devices

(must be connected in sequence). Each module contains two outlets.

Note: For factory cutout to install the unit, a sketch must be provided to show the unit in the work surface

with dimensions noting the exact location.



# **General Specifications**

Have electrical power and data access conveniently located; where you need it and in the format required by your computer system and all other electrically powered equipment. Prevent wire clutter by storing excess cables and wires in wire-management channels. Based upon your specification, Brodart provides single or multi-circuit power systems with optional dedicated computer circuitry. Also, a choice of 15-amp or 20-amp systems, as you specify. Quick-connect cable couplings are utilized by Brodart to permit easy, on-site installations and to provide for rearrangement as changing needs dictate.

**NOTES:** Grommets are not always included as standard with the product. If wires are to be passed though work surfaces or from one unit to another you will need to order the grommets separately. For factory-cut holes to install grommets, a sketch must be provided to show the unit in the work surface with dimensions noting the exact location.

 Catalog No.	Description	Price
Grommet with a X1 700 001	Cap, 2" Round  Grommet with Cap, 2" Round  Constructed Black of ABS plastic, 2" round grommet  fits 1-3/4" diameter hole. Nominal 1-5/8" inside diameter.  Includes notched 5/8" W removable cap.	\$64
<u>Grommet with 1</u> X1 700 002	Cap, 3-1/2" Round  Grommet with Cap, 3-1/2" Round  Constructed Black of ABS plastic, 3-1/2" round grommet fits 3" diameter hole. Nominal 2-7/8" inside diameter.  Includes notched 5/8" W removable cap.	\$72



## Grommet with Paper Slot, 17" Long

X1 700 111 Grommet with Paper Slot, 17" Long

Constructed Black of ABS plastic. Inside dimensions are 17" x 1".

\$151

Catalog No. Description Price

# Plastic J-Channel Wire Manager

X1 700 020 Plastic J-Channel Wire Manager

Constructed of dark brown ABS plastic. Designed to be mounted by screwing or stapling to most surfaces. Front "J" is flexible for inserting cords. Inside dimensions: 1-1/2"H x 1"W x 72"L



# Data and Communication Raceway, 1/2"H x 1"W x 6'L

X1 700 065 Data and Communication Raceway, 1/2"Hx1"Wx6'L

One-piece, black, latching surface raceway for low voltage communications cabling applications. Supplied with preapplied adhesive-backed tape for trouble-free and permanent mounting. Will hold up to four data cables. Can be used with category 5 and fiber optic cabling applications.



## Power Data Raceway, 7/8"H x 1-1/2"W x 10'L

X1 700 066 Power Data Raceway, 7/8"H x 1-1/2"W x 10'L

One-piece, brown, latching surface raceway for data, voice, video, fiber optic and power cabling applications. Unit has two channels

that can route both power and data. Supplied with preapplied adhesive-backed tape for trouble-free and permanent mounting. Unit requires screw mounting when using for power applications.



\$107

\$164

\$72

\$92

\$145 \$145 \$164 \$175

## Wire Manager For Table Mounting

X1 700 030 22" J-Channel, 3-1/2"H x 22"W x 3-1/4"D X1 700 031 28" J-Channel, 3-1/2"H x 28"W x 3-1/4"D

Designed for electrical or data cables, unit is constructed of 18-gauge steel with electrostatically applied black powder-paint. Designed to be mounted to the underside of a tableton

to the underside of a tabletop.

**Note:** Grommets are not always included on product as a standard item. If wires are to be passed through the work surface or from one unit to another,

grommets may need to be ordered separately.



# Wire Manager For Panel Mounting

XJ 012 S00	30" J-Channel, 3-1/8"H x 30"W x 4"D
XJ 673 S00	32" J-Channel, 3-1/8"H x 32"W x 4"D
XJ 047 S00	38" J-Channel, 3-1/8"H x 38"W x 4"D
XJ 460 S00	44" J-Channel, 3-1/8"H x 44"W x 4"D

Designed for electrical or data cables, unit is constructed of 18-gauge steel with electrostatically applied black powder-paint. The front lip of the panel is 2"H.

Unit mounts to back panels or keels.

**Note:** Grommets are not always included on product as a standard item. If wires are to be passed through the work surface or from one unit to another, grommets may need to be ordered separately. Modular insert data jacks sold separately.





Catalog No.	Description	Price
<u>Vertical Wire Cha</u>	nse, Oak Wood	
X1 700 195 OAK	Wood Wire Chase for 25"H Work Surface, Actual height 22"	\$164
X1 700 197 OAK	Wood Wire Chase for 29"H Work Surface, Actual height 26"	\$205
X1 700 199 OAK	Wood Wire Chase for 39"H Work Surface, Actual height 36"	\$223
Vertical Wire Cha	nse, Maple Wood	
X1 700 195 MAP	Wood Wire Chase for 25"H Work Surface, Actual height 22"	\$164
X1 700 197 MAP	Wood Wire Chase for 29"H Work Surface, Actual height 26"	\$205
X1 700 199 MAP	Wood Wire Chase for 39"H Work Surface, Actual height 36"	\$223
	Designed to manage cords below the work surface, unit is constructed the woo species specified and finished to match. Inside Dimensions are 2-1/4" x 3"	od



# Flexible Wire Management Channels (Leg Style)

73 210 S00	32" for Sitting Height Tables	\$329
73 210 S01	39" for Standing Height Tables	\$362



# Metal Vertical Wire Manager

X1 700 050 Vertical Wire Manager for Table Mounting

Designed to be mounted underneath the work surface below a grommet. Unit is constructed of a 3-1/2" diameter steel tube and finished with black

electrostatically applied powder paint.

\$254